

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 015	Proposal: T4733	District:04
Counties:	ST LUCIE			
Road Name:	SR 9 (I-95)			
Limits:	FROM SR 9 (I-95) NB EXIT RAMP TO WB SR 68 (ORANGE AVE)			
Project(s):	44928115201(*)	Federal Aid No:	D425040B	
Total Roadway Length:	0.291 Miles	Contract Days:	133	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	0.291 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days	
Proposal Budget Estimate:	\$1,059,018.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, widening, asphalt (milling, resurfacing, miscellaneous), signing (single-post, multi-post, panel), pavement markings (thermoplastic, tubular delineator, reflective sign strip), lighting (conductors, pole), electrical (service, disconnect), and sod along State Road 9 (I-95) for 0.291 miles in St. Lucie County.

Call Order: 015 Proposal: T4733

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44928115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44928115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	30.000
	0102- 60-	WORK ZONE SIGN	ED	621.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,010.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	38.000
	0102-115-	TYPE III BARRICADE	ED	5.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,450.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	27.460
	0107- 2-	MOWING	AC	25.690
	0110- 1- 1	CLEARING & GRUBBING (44928115201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	112.900
	0120- 6-	EMBANKMENT	CY	671.300
	0160- 4-	TYPE B STABILIZATION	SY	860.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	619.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	2,633.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	1,002.000
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	TN	297.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,070.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	79.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.295
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.302
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	2,633.000

Call Order: 015 Proposal: T4733

ALT	Item	Description	Unit	Quantity
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44928115201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	26.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	16.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	33.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	110.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44928115201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.008
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	30.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	26.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	30.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.293
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.297
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,071.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	3,981.000
	0715- 61-400	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 0' ARM LENGTH	EA	7.000
	0715- 61-421	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 10' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	7.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	8.000
Section 0004 Intelligent Transportation System				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	133.000