

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	CT260325	Call Order: 014	Proposal: T2A70	District:02
Counties:	LEVY			
Road Name:	SR 121			
Limits:	FROM SR 55 (US 19) TO SR 45 (US 41 / SW 7TH ST)			
Project(s):	21028845201(*)	Federal Aid No: D225059B		
Total Roadway Length:	20.040 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	03/25/26	
Total Proposal Length:	20.040 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 DA	

Proposal Budget Estimate: \$14,649,680.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, highway signing, and other incidental construction on SR 121 from SR 55 (US 19) to SR 45 (US 41) (SW 7th Street) in Levy County.

Call Order: 014 Proposal: T2A70

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21028845201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21028845201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	25,960.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	45,216.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	4,493.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,524.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-115-	TYPE III BARRICADE	ED	40.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	45.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	829.000
	0104- 10- 3	SEDIMENT BARRIER	LF	22,604.000
	0107- 1-	LITTER REMOVAL	AC	1,438.700
	0107- 2-	MOWING	AC	1,244.300
	0110- 1- 1	CLEARING & GRUBBING (21028845201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	330.000
	0120- 1-	REGULAR EXCAVATION	CY	1,269.300
	0120- 6-	EMBANKMENT	CY	361.300
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	8,024.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	89.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	47,088.000

Call Order: 014 Proposal: T2A70

ALT	Item	Description	Unit	Quantity
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	4,123.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	227,212.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	136,988.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	1,749.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	11,775.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	40,689.200
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	63.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	23.600
	0530- 74-	BEDDING STONE	TN	16.900
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	82,905.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,472.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	40.649
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,461.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.459
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	54.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	19.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	21.670
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	506.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	12.367
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21028845201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	57.603
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	38.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	23.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	4.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	32.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,472.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21028845201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,461.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.459

Call Order: 014 Proposal: T2A70

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	54.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	19.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	506.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	40.649
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	21.670
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	12.367