

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260128	Call Order: 003	Proposal: T2A49	District:02
Counties:	DUVAL			
Road Name:	SR 228 (NORMANDY BLVD)			
Limits:	FROM S OF MEMORIAL PARK RD TO SR 103 (LANE AVE)			
Project(s):	20944865201(*)	Federal Aid No:	D225075B	
Total Roadway Length:	1.079 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	01/28/26	
Total Proposal Length:	1.079 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$3,239,739.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, curb & gutter, highway signing, sidewalks/bicycle path, and other incidental construction on SR 228/Normandy Blvd in Duval County south of Memorial Park Rd to SR 103 (Lane Ave).

Call Order: 003 Proposal: T2A49

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20944865201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20944865201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (20944865201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	64.000
	0102- 60-	WORK ZONE SIGN	ED	6,170.000
	0102- 61-	BUSINESS SIGN	EA	38.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,602.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	9,408.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	154.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	628.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	240.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	956.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	39.000
	0107- 1-	LITTER REMOVAL	AC	18.930
	0107- 2-	MOWING	AC	13.950
	0110- 1- 1	CLEARING & GRUBBING (20944865201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	42.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	34,838.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,876.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	3,832.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	4,018.800
	0425- 5-	MANHOLE, ADJUST	EA	7.000

Call Order: 003 Proposal: T2A49

ALT	Item	Description	Unit	Quantity
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	192.000
	0431- 1-124	PIPE LINER, CURED IN PLACE, 24"	LF	583.000
	0431- 1-130	PIPE LINER, CURED IN PLACE, 30"	LF	155.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	12.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	21.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	43.000
	0527- 2-	DETECTABLE WARNINGS	SF	202.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	11.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,022.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.673
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.056
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,458.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,224.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	309.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.973
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.386
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	51.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.961
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	41.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.301
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	16,960.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20944865201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,022.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	202.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20944865201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.056

Call Order: 003 Proposal: T2A49

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,458.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,224.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	309.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.386
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	3.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	51.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	41.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.301
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	768.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.673
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.973
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.961
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	490.000
Section 0003 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	120.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	18.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	9.000