

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 012	Proposal: T6614	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 817 (NW 27 AVE)			
Limits:	FROM SESAME ST TO DUNAD AVE			
Project(s):	44393725201(*)	Federal Aid No: D625045B		
Total Roadway Length:	0.132 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	12/03/25	
Total Proposal Length:	0.132 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$997,011.00			

Please read the full advertisement

Description:

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF PEDESTRIAN SAFETY IMPROVEMENT ALONG SR 817/NW 27 AVENUE FROM SESAME STREET TO DUNAD AVENUE IN MIAMI-DADE COUNTY.

Call Order: 012 Proposal: T6614

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44393725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44393725201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	136.000
	0102- 60-	WORK ZONE SIGN	ED	4,185.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	7,500.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,080.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-115-	TYPE III BARRICADE	ED	480.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	1.760
	0107- 2-	MOWING	AC	0.340
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44393725201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44393725201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	247.000
	0110- 21-	TREE PROTECTION BARRIER	LF	278.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	180.700
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44393725201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	54.000
	0285-702-	OPTIONAL BASE, BASE GROUP 02	SY	54.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	3,567.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4.400
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	245.200

Call Order: 012 Proposal: T6614

ALT	Item	Description	Unit	Quantity
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	1.600
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	26.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	520.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	113.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	70.000
	0527- 2-	DETECTABLE WARNINGS	SF	46.000
	0550- 10-228	FENCING, TYPE B, 5.1-6.0, RESET EXISTING	LF	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	250.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (44393725201)	LS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.236
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	130.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	65.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.252
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	1.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.164
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44393725201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	52.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44393725201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	130.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	65.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	1.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	140.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.236
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.252
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.164
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	853.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,925.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,652.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715- 62-311	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 40' MOUNTING HEIGHT, 8' ARM LENGTH	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	6.000

Call Order: 012 Proposal: T6614

ALT	Item	Description	Unit	Quantity
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	718.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	24.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	1.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	437.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0670- 5-180	TRAFFIC CONTROLLER ASSEMBLY, F&I, CALTRANS W/STANDARD LOCK	AS	1.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	1.000