

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 003	Proposal: T2A48	District:02
Counties:	DUVAL			
Road Name:	SR A1A (MAYPORT ROAD)			
Limits:	FROM ATLANTIC BLVD TO DUTTON ISLAND RD AND FROM ATLANTIC BLVD TO 7TH ST			
Project(s):	44350215201(*)	Federal Aid No:	D225102B	
Project(s):	44542815201	Federal Aid No:	D225051B	
Total Roadway Length:	1.596 Miles	Contract Days:	400	
Total Bridge Length:	0.000 Miles	Letting Date:	12/03/25	
Total Proposal Length:	1.596 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days	

Proposal Budget Estimate: \$11,246,351.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling, resurfacing, base work, drainage improvements, curb & gutters, traffic signals, lighting, highway signing, pavement markings, sidewalk/bicycle paths, bridge and MSE wall spall repair and cleaning and coating, and other incidental construction on SR A1A (Mayport Road) from Atlantic Blvd. to Dutton Island Road and SR A1A (Mayport Road) from Atlantic Blvd. to 7th Street in Duval County.

JEA Standards. Table A -- Schedule of Values is required to be submitted with the bid, as per Technical Special Provision T10007.

Please upload completed Table A as a zip file within your EBSx File using the "File Attachment Upload" tab before submitting your bid.

Award continent upon receipt of local funds

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
			SF	12,000.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5		
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	10.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	5,000.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44350215201)	LS	1.000
	0101- 1-	MOBILIZATION (44542815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44350215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44542815201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44542815201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44350215201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44542815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	316.000
	0102- 60-	WORK ZONE SIGN	ED	48,276.000
	0102- 61-	BUSINESS SIGN	EA	25.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	798.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	905.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	36,563.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	23,789.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	905.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,154.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,000.000

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,000.000
	0102-115-	TYPE III BARRICADE	ED	604.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,004.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	71.000
	0107- 1-	LITTER REMOVAL	AC	137.300
	0107- 2-	MOWING	AC	62.790
	0110- 1- 1	CLEARING & GRUBBING (44350215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	7,392.000
	0110- 21-	TREE PROTECTION BARRIER	LF	214.000
	0120- 1-	REGULAR EXCAVATION	CY	1,183.000
	0120- 6-	EMBANKMENT	CY	1,825.000
	0160- 4-	TYPE B STABILIZATION	SY	2,267.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	957.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	892.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	16,240.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	9,572.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	36,247.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2,855.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,264.600
	0350- 30- 13	CONCRETE PAVEMENT FOR ROUNDABOUT APRON, 12" DEPTH	SY	56.000
	0400- 0- 13	CONCRETE CLASS NS, STEPS	CY	7.200
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	46,450.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	16.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	10.000
	0425- 1-321	INLETS, CURB, TYPE P-2, <10'	EA	1.000
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	2.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	3.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	7.000
	0425- 1-523	INLETS, DT BOT, TYPE C, JBOT, <10'	EA	1.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	19.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	6.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-713	INLETS, GUTTER, TYPE V, J BOT, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	3.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	14.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	9.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0425- 5-	MANHOLE, ADJUST	EA	21.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	16.000
	0425- 6-	VALVE BOXES, ADJUST	EA	33.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	64.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	1,957.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	339.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	40.000
	0430-175-215	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 15"S/CD	LF	8.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	311.000
	0430-175-224	PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	LF	8.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	84.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	4,288.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	100.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	210.000
	0520- 2- 8	CONCRETE CURB, TYPE RA	LF	146.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	2,640.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	65.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	45.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	6,310.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	3,476.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,676.000
	0536- 73-	GUARDRAIL REMOVAL	LF	41.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	17,100.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,684.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,837.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.736
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.428
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,908.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	672.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,563.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.946
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.979
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	41.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	90.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	6.775
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	554.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.058

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	71.000
	0920-520-100	RAISED CROSSWALK, TYPE RC CURB WITH PLATE/GRATE	LF	84.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44350215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44542815201)	LS	1.000
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	31.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-400	SINGLE COLUMN GROUND SIGN ASSEMBLY, INSTALL	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	21.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	18.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	40.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	6.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	33.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	57.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	11.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,157.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	220.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44350215201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44542815201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.428
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,360.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	672.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	968.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.925
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	11.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	88.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	554.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.034
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,721.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	28.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	28.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.885

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.946
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.047
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.613
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.012
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	117.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	165.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	1.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	1.000
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	1.000
Section 0005 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	1.596
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	741.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	771.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	341.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	171.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	84.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	2.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	1.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	400.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	84.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0643-600-	STRAIN POLE, WOOD, REMOVE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	18.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	15.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	4.000

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	2.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	14.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	1.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	8.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	4.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	1.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	2.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	28.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	17.000
	0660- 5- 61	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, REMOVE CABINET EQUIPMENT	EA	3.000
	0660- 5- 62	VEHICLE DETECTION SYSTEM- WIRELESS MAGNETOMETER, REMOVE ABOVE GROUND EQUIPMENT	EA	3.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	2.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	29.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	4.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	18.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	3.000
	0682- 1-173	ITS CCTV CAMERA, NON-PRESSURIZED, IP, HIGH DEFINITION	EA	5.000
	0682- 1-500	ITS CCTV CAMERA, ADJUST/MODIFY	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000

Call Order: 003 Proposal: T2A48

ALT	Item	Description	Unit	Quantity
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	13.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
Section 0006 Utilities				
	1000- 7-	UTILITY WORK- JPA/UTILITY AGREEMENT, POWER (44350215201)	LS	1.000