

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 002	Proposal: T1929	District:01
Counties:	MANATEE			
Road Name:	SR 70 (15TH ST E)			
Limits:	FROM 30TH AVE E TO 26TH AVE E			
Project(s):	44965415201(*)	Federal Aid No:	D125049B	
Total Roadway Length:	0.252 Miles	Contract Days:	130	
Total Bridge Length:	0.000 Miles	Letting Date:	09/24/25	
Total Proposal Length:	0.252 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,186,494.00			

Please read the full advertisement

Description:

The improvements under this project consist of milling and resurfacing, sidewalk, drainage, lighting, and signalization on SR 70 (15th St E) from 30th Avenue E to 26th avenue E in Manatee County.

Call Order: 002 Proposal: T1929

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44965415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44965415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	96.000
	0102- 60-	WORK ZONE SIGN	ED	3,587.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	2,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	260.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	288.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-115-	TYPE III BARRICADE	ED	69.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,353.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	51.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	5.420
	0107- 2-	MOWING	AC	5.290
	0110- 1- 1	CLEARING & GRUBBING (44965415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	126.000
	0120- 1-	REGULAR EXCAVATION	CY	1,198.200
	0120- 6-	EMBANKMENT	CY	770.800
	0145- 3-	GEOSYNTHETIC REINFORCED EMBANKMENT	SY	88.000
	0160- 4-	TYPE B STABILIZATION	SY	367.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,313.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	273.400
	0425- 1-523	INLETS, DT BOT, TYPE C, JBOT, <10'	EA	1.000

Call Order: 002 Proposal: T1929

ALT	Item	Description	Unit	Quantity
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	59.000
	0430-524-120	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 30 DEGREES, ROUND	EA	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	506.000
	0527- 2-	DETECTABLE WARNINGS	SF	111.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,021.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44965415201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	33.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44965415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	996.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	235.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.027
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	870.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.181
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.084
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	364.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,584.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	15.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	6,770.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	4.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	6.000
	0715- 61-311	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 62-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	1.000
	0715- 68-000	LIGHT POLE COMPLETE, RELOCATE	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	10.000
Section 0004 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.252
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	500.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	25.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000

Call Order: 002 Proposal: T1929

ALT	Item	Description	Unit	Quantity
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	495.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	12.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	1.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	130.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	3.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	1.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	7.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	2.000
	0676- 1-500	TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	6.000