

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250326	Call Order: 015	Proposal: T4719	District:04
Counties:	PALM BEACH			
Road Name:	SR 15 (E MAIN ST)			
Limits:	FROM ANNONA ST TO S OF SR 700 (CONNERS HWY)			
Project(s):	44766415201(*)	Federal Aid No:	D424095B	
Project(s):	44766415202	Federal Aid No:	N/A	
Total Roadway Length:	3.342 Miles	Contract Days:	240	
Total Bridge Length:	0.000 Miles	Letting Date:	03/26/25	
Total Proposal Length:	3.342 Miles	Contract Execution Days:	10	
		Special Start Date:	03/02/26	
		Aquis/Flexible Start Time:		
Proposal Budget Estimate:	\$4,392,725.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, MOT (standard, pedestrian special detours, pedestrian longitudinal channelizing devices), erosion control (sediment barrier, turbidity barrier, inlet protection), monitor existing structures (inspection, settlement, vibration), concrete (removal, curb and gutter, sidewalk), earthwork (regular excavation, embankment), asphalt (repaved, base, milling, resurfacing, widening), utility adjustments (valves, manholes), pavement markings (painted, thermoplastic, raised marker), signing (single post, multi-post, removals, object marker, tubular marker) and sod along State Road 15 (East Main Street) northerly 3.342 miles from Annona Street to south of State Road 700 (Connors Highway) in the City of Pahokee, Palm Beach County

Call Order: 015 Proposal: T4719

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44766415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44766415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44766415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	29,760.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	143,900.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	254,942.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	508.000
	0102-115-	TYPE III BARRICADE	ED	1,739.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,287.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	56.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	56.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	27.000
	0107- 1-	LITTER REMOVAL	AC	150.580
	0107- 2-	MOWING	AC	123.480
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44766415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44766415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44766415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	661.000
	0120- 6-	EMBANKMENT	CY	80.300

Call Order: 015 Proposal: T4719

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44766415201)	LS	1.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	105.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	24.700
	0325- 70-	REPAVED ASPHALT CONCRETE	SY	45,411.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	20,410.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	20,145.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	24,998.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22	TN	5,429.700
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	8.000
	0425- 6-	VALVE BOXES, ADJUST	EA	63.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	286.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	161.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	131.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	751.000
	0527- 2-	DETECTABLE WARNINGS	SF	434.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	8,050.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,368.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.717
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.086
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,177.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	843.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	351.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.349
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	10.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.089
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,131.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.074
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.056
	0999- 16-	PARTNERING, DO NOT BID (44766415201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44766415201)	LS	1.000
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (43175255201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	72.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	22.000

Call Order: 015 Proposal: T4719

ALT	Item	Description	Unit	Quantity
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	85.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	4.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	30.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,465.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44766415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.108
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,100.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	807.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	421.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.673
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,127.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.113
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	130.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	63.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	57.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	80.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	1,361.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.348
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.982
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.074