

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250528	Call Order: 002	Proposal: T4575	District:04
Counties:	ST LUCIE			
Road Name:	PORT ST LUCIE BLVD			
Limits:	FROM S OF PAAR DR TO S OF ALCANTARRA BLVD			
Project(s):	43175255201(*)	Federal Aid No:	D425025B	
Project(s):	43175255202	Federal Aid No:	D425025B	
Project(s):	43175255601	Federal Aid No:	N/A	
Total Roadway Length:	1.076 Miles	Contract Days:	874	
Total Bridge Length:	0.000 Miles	Letting Date:	05/28/25	
Total Proposal Length:	1.076 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days	
Proposal Budget Estimate:	\$26,668,083.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of, but are not limited to, roadway reconstruction, milling resurfacing, widening, concrete (sidewalk, driveway, curb and gutter, patterned) earthwork, drainage, monitor existing structures (inspection and settlement), lighting, signalization, landscaping, irrigation, utility work, signage (single and multi-post), pavement markings (painted, thermoplastic) and sod along Port St. Lucie Boulevard from south of Paar Drive northerly 1.076 miles to south of Alcantarra Boulevard in the City of Port St. Lucie.

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43175255201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43175255201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43175255201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43175255201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	418.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	56.000
	0102- 60-	WORK ZONE SIGN	ED	292,501.000
	0102- 61-	BUSINESS SIGN	EA	3.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,463.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	809.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	506,710.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	42,065.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	322.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	2,405.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	15,880.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,748.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,748.000
	0102-115-	TYPE III BARRICADE	ED	55,344.000
	0104- 10- 3	SEDIMENT BARRIER	LF	10,827.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	429.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	49.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43175255201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43175255201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43175255201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	9,445.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	67.000
	0120- 1-	REGULAR EXCAVATION	CY	5,609.400
	0120- 6-	EMBANKMENT	CY	15,994.400
	0160- 4-	TYPE B STABILIZATION	SY	57,765.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	13,319.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	35,089.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	156.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	6,557.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	1,492.900
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	4,199.800
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	2,299.100
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	43.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	36.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	7.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	22.000
	0425- 1-455	INLETS, CURB, TYPE J-5, PARTIAL	EA	3.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	7.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	4.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	26.000
	0425- 1-543	INLETS, DITCH BOTTOM, TYPE D, J BOT, <10'	EA	6.000
	0425- 1-544	INLETS, DITCH BOTTOM, TYPE D, J BOT, >10'	EA	5.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	13.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 1-713	INLETS, GUTTER, TYPE V, J BOT, <10'	EA	10.000
	0425- 1-715	INLETS, GUTTER, TYPE V, PARTIAL	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	4.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	8.000
	0425- 10-	YARD DRAIN	EA	37.000
	0430-174-215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 15"SD	LF	916.000
	0430-175-112	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 12"S/CD	LF	673.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	5,071.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	2,056.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	1,394.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,373.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	1,424.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	307.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	40.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	116.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/CD	LF	180.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	LF	342.000
	0430-175-260	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 60"S/CD	LF	191.000
	0430-982-641	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 48" CD	EA	1.000
	0430-984-623	MITERED END SECTION, OPTIONAL OTHER - ELLIP/ARCH, 15" SD	EA	45.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	223.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	17,272.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	5,483.000
	0520- 2-100	CONCRETE CURB, RIBBON CURB	LF	114.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	231.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	8,248.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	8,056.000
	0523- 3-	PATTERNED PAVEMENT	SY	2,187.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	379.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	21.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,071.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	53.000
	0530- 74-	BEDDING STONE	TN	38.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	25,085.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (43175255202)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,646.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.775
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.808
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	186.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	266.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	926.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	19.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.085
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.106
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	666.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.071
	0999- 16-	PARTNERING, DO NOT BID (43175255201)	LS	1.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	28.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43175255201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43175255202)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	45.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	22.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	10.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	30.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	4.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	16.000
	0700-142-111	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, UP TO 12 SF OF STATIC SIGN PANELS	EA	1.000
	0700-142-802	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, RELOCATE - GROUND MOUNT	EA	4.000
	0700-142-902	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, REMOVE - GROUND MOUNT	EA	2.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	15.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,108.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	58.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43175255201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,606.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	731.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.385
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	64.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	470.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.284
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,162.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.911
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.024
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.032
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.521

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5,656.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,502.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	64.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	22,194.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	300.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 62-142	LIGHT POLE COMPLETE, F&I, STANDARD POLE SPECIAL FOUNDATION, 30' MOUNTING HEIGHT, 12' ARM LENGTH	EA	38.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	44.000
	0715-511-130	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30'	EA	6.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	2,070.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,594.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	480.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	6,560.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	500.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	306.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	3.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	3.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	874.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	1,165.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	71.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	21.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	311.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	16.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	2.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	2.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	3.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	17.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	4.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	16.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	1.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0680- 1-112	SYSTEM CONTROL EQUIPMENT, FURNISH & INSTALL, ADAPTIVE SIGNAL CONTROL SYSTEM- NEMA, CABINET EQUIPMENT	EA	2.000
	0680- 1-113	SYSTEM CONTROL EQUIPMENT, FURNISH & INSTALL, ADAPTIVE SIGNAL CONTROL SYSTEM- NEMA, ABOVE GROUND EQUIPMENT	EA	8.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	2.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	8.000
Section 0005 Landscape / Peripheral				
	0580- 1- 2	LANDSCAPE COMPLETE- LARGE PLANTS (43175255201)	LS	1.000
	0590- 70-	IRRIGATION SYSTEM (43175255201)	LS	1.000
Section 0006 Utilities				
	0999- 26-	LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) (43175255601)	LS	1.000
	1050- 10-103	UTILITY PIPE, F&I, PVC PIPE, 2.5", PROJECT 431752-5-56-01	LF	1,835.000
	1050- 16-002	UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	LF	4,872.000
	1050- 16-003	UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	LF	1,183.000
	1050- 16-004	UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	LF	6,172.000
	1050- 31-202	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 2"	LF	1,135.000
	1050- 31-203	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 3"	LF	690.000
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	1,186.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	1,202.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	1050- 31-208	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 8"	LF	2,126.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	1,850.000
	1050- 31-216	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 16"	LF	2,550.000
	1055- 51-108	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 8"	EA	84.000
	1055- 51-112	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 12"	EA	44.000
	1055- 51-116	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL ELBOW, 16"	EA	48.000
	1055- 51-208	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 8"	EA	1.000
	1055- 51-216	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL TEE, 16"	EA	7.000
	1055- 51-308	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL REDUCER, 8"	EA	6.000
	1055- 51-408	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 8"	EA	4.000
	1055- 51-412	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 12"	EA	8.000
	1055- 51-416	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL UNION, 16"	EA	21.000
	1055- 51-608	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL Y, 8"	EA	1.000
	1055- 51-808	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL CROSS, 8"	EA	2.000
	1055- 51-816	UTILITY FITTINGS, DUCTILE IRON/CAST IRON, FURNISH & INSTALL CROSS, 16"	EA	5.000
	1080- 21-100	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 1"	EA	4.000
	1080- 21-101	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 1.5"	EA	30.000
	1080- 21-102	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 2"	EA	3.000
	1080- 21-500	UTILITY FIXTURE, VALVE/METER BOX, ADJUST	EA	97.000
	1080- 23-108	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 8"	EA	1.000
	1080- 23-112	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 12"	EA	2.000
	1080- 23-116	UTILITY FIXTURE- TAPPING SADDLE/SLEEVE, FURNISH & INSTALL, 16"	EA	1.000
	1080- 24-102	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 2"	EA	6.000
	1080- 24-103	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 3"	EA	26.000
	1080- 24-104	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 4"	EA	8.000
	1080- 24-106	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 6"	EA	15.000
	1080- 24-108	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 8"	EA	8.000
	1080- 24-112	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 12"	EA	4.000
	1080- 24-116	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 16"	EA	13.000
	1080- 25-102	UTILITY FIXTURE- BLOWOFF ASSEMBLY, FURNISH AND INSTALL, 2"	EA	3.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	3.000
	1080- 27-108	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 8"	EA	5.000

Call Order: 002 Proposal: T4575

ALT	Item	Description	Unit	Quantity
	1080- 27-112	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 12"	EA	10.000
	1080- 27-116	UTILITY FIXTURE- LINE STOP ASSEMBLY, FURNISH AND INSTALL, 16"	EA	21.000
	1080- 32-106	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 6"	EA	20.000
	1080- 32-108	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 8"	EA	6.000
	1080- 32-112	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 12"	EA	8.000
	1080- 32-116	UTILITY FIXTURE- SAMPLE POINT, FURNISH & INSTALL, 16"	EA	20.000
	1644-112- 06	FIRE HYDRANT, F&I, STANDARD, 2 HOSE, 6"	EA	6.000