

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250924	Call Order: 012	Proposal: T7566	District:07
Counties:	PINELLAS			
Road Name:	SR 595 (ALT US 19 / BAYSHORE DR)			
Limits:	FROM WILSON ST TO CURLEW ST			
Project(s):	45107315201(*)	Federal Aid No:	D725023B	
Total Roadway Length:	1.869 Miles	Contract Days:	160	
Total Bridge Length:	0.052 Miles	Letting Date:	09/24/25	
Total Proposal Length:	1.921 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$1,362,037.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of traffic operations improvements along Alt US 19/SR 595/Bayshore Drive from Wilson Street to Curlew Road and includes roadway, drainage, signing and pavement markings, and signals in Pinellas County.

Call Order: 012 Proposal: T7566

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45107315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45107315201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	240.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	196.000
	0102- 60-	WORK ZONE SIGN	ED	2,616.000
	0102- 61-	BUSINESS SIGN	EA	1.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,230.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	84.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	314.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	160.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	160.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	160.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,722.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	1.890
	0107- 2-	MOWING	AC	0.150
	0110- 1- 1	CLEARING & GRUBBING (45107315201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.310
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	308.000
	0110- 23-	TREE REMOVAL	EA	1.000
	0120- 6-	EMBANKMENT	CY	14.300

Call Order: 012 Proposal: T7566

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	8,802.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	726.200
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	3.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	3.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	223.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	617.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	223.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	147.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	12.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	422.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	120.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	291.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	218.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	5.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	1.000
	0527- 2-	DETECTABLE WARNINGS	SF	199.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,533.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	492.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45107315201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	28.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	18.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	407.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	93.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45107315201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	964.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	232.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.106
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	20.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	18.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	230.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.071
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	904.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.867

Call Order: 012 Proposal: T7566

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.826
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.028
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	140.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	38.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	82.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	160.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	2.000
	0654- 2- 27	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- SINGLE DIR ACCESSIBLE DETECTOR	AS	12.000
	0654- 2- 28	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	4.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000