

Call Order: 006 Proposal: T2A68

ALT	Item	Description	Unit	Quantity
	0455- 15- 33	PREFORMED PILE HOLES GROUTING, 22" TO 26" DRILL/PUNCH SIZE	LF	1,186.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	60.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	2,002.000
	0455-115-	PILE REDRIVE	EA	46.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	106.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	12.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	624.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	172.000
	0460- 71- 1	METAL TRAFFIC RAILING, THRIE BEAM RETROFIT	LF	1,000.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	52.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	3,515.000
	0530- 74-	BEDDING STONE	TN	859.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43740215201)	LS	1.000
	0101- 1-	MOBILIZATION (43740315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43740215201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,480.000
	0102-115-	TYPE III BARRICADE	ED	1,080.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,451.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,769.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	483.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0110- 1- 1	CLEARING & GRUBBING (43740215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43740315201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	557.400
	0120- 6-	EMBANKMENT	CY	1,935.800
	0160- 4-	TYPE B STABILIZATION	SY	4,860.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	449.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	3,690.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	304.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	321.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	34.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	1,365.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	11.300
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,344.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	8.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,208.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,006.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43740215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43740315201)	LS	1.000

Call Order: 006 Proposal: T2A68

ALT	Item	Description	Unit	Quantity
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	71.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	118.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43740215201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43740315201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	77.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.534
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.534
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.197
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.197