

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 006	Proposal: T2A80	District:02
Counties:	LEVY			
Road Name:	SR 55 (US 19)			
Limits:	FROM N OF SR 121 TO S OF OTTER CREEK AND AT BULLFROG CREEK			
Project(s):	21042865201(*)	Federal Aid No:	D226061B	
Project(s):	21042895201	Federal Aid No:	N/A	
Total Roadway Length:	13.335 Miles	Contract Days:	330	
Total Bridge Length:	0.035 Miles	Letting Date:	09/30/26	
Total Proposal Length:	13.853 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$20,204,285.00			

Please read the full advertisement

Description:

The Improvements under this contract consists of milling & resurfacing, shoulder treatment, roadway reconstruction, drainage improvements, wildlife crossing and other incidental construction on SR 55 (US 19) From North of SR 121 to South of Otter Creek and at Bullfrog Creek in Levy County.

Call Order: 006 Proposal: T2A80

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (21042895201)	LS	1.000
	0400- 4- 1	CONCRETE CLASS IV, CULVERTS	CY	473.600
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21042865201)	LS	1.000
	0101- 1-	MOBILIZATION (21042895201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21042865201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21042895201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (21042895201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (21042895201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	42,170.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	7,452.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,476.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	3,372.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	557,660.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	4,030.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	19,691.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	9.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,835.000
	0102-115-	TYPE III BARRICADE	ED	7,180.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	160.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	2,800.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	154.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,115.000

Call Order: 006 Proposal: T2A80

ALT	Item	Description	Unit	Quantity
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	116.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	28.000
	0107- 1-	LITTER REMOVAL	AC	3,872.010
	0107- 2-	MOWING	AC	3,676.940
	0110- 1- 1	CLEARING & GRUBBING (21042865201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (21042895201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	33.000
	0120- 1-	REGULAR EXCAVATION	CY	1,104.900
	0120- 6-	EMBANKMENT	CY	7,100.300
	0160- 4-	TYPE B STABILIZATION	SY	10,494.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,482.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	6,136.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	293.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,370.000
	0327- 70- 9	MILLING EXISTING ASPHALT PAVEMENT, 5 1/4" AVG DEPTH	SY	1,051.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	288,710.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	24,293.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	182,676.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	35.600
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	58,182.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	19,217.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	43.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	54.500
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	4.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	1,685.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	352.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	52.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,381.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	1,217.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0550- 10-110	FENCING, TYPE A, 0.0-5.0', STANDARD	LF	105.000
	0550- 10-150	FENCING, TYPE A, 8.1-10.0', STANDARD	LF	9,412.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	116,773.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	12,938.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	33.055
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	201.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	26.145
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.578
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	104.000

Call Order: 006 Proposal: T2A80

ALT	Item	Description	Unit	Quantity
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	26.097
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.099
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21042865201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21042895201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	48.477
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	90.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	28.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	80.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	8.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	76.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	17,101.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21042865201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21042895201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	201.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.578
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	104.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	2.099
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	26.194
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	26.145
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	23.922
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.289
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.084
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.071
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.050
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.071
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.043
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	559.000