

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 020	Proposal: T6599	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 934 (NW 79 ST)			
Limits:	FROM NW 27 AVE TO NW 1 PL			
Project(s):	41064675201(*)	Federal Aid No:	D625014B	
Total Roadway Length:	2.800 Miles	Contract Days:	350	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	2.800 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$6,010,293.00			

Please read the full advertisement

Description: Incentive / Disincentive

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF SAFETY IMPROVEMENTS ALONG SR 934/NW 79 STREET FROM NW 27 AVENUE TO NW 1 PLACE IN MIAMI-DADE COUNTY.

Call Order: 020 Proposal: T6599

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (41064675201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (41064675201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	52.000
	0102- 60-	WORK ZONE SIGN	ED	19,790.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,600.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	27,639.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,035.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	810.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	27.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	924.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	801.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	801.000
	0102-115-	TYPE III BARRICADE	ED	1,332.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	51.000
	0107- 1-	LITTER REMOVAL	AC	79.920
	0107- 2-	MOWING	AC	28.800
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (41064675201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (41064675201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (41064675201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,796.000
	0110- 21-	TREE PROTECTION BARRIER	LF	81.000

Call Order: 020 Proposal: T6599

ALT	Item	Description	Unit	Quantity
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	358.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (41064675201)	LS	1.000
	0160- 4-	TYPE B STABILIZATION	SY	532.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	814.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	24,392.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	120.900
	0337- 7- 82	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22	TN	1,726.300
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-211	INLETS, CURB, TYPE 10, <10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	7.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	5.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	128.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	16.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	30.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	396.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	3,427.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	363.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	31.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	818.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	822.000
	0527- 2-	DETECTABLE WARNINGS	SF	434.000
	0550- 10-231	FENCING, TYPE B, 6.1-7.0, W/ BARB WIRE ATTMT	LF	30.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	695.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (41064675201)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	858.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.605
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.152
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,816.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	241.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	3,903.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.054
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.074
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	27.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	35.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.106

Call Order: 020 Proposal: T6599

ALT	Item	Description	Unit	Quantity
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	104.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.019
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.286
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	92.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (41064675201)	LS	1.000
Section 0002 Signing				
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	107.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	7.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	35.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	7.000
	0700-142-140	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	5.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	41.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	858.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	92.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (41064675201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.023
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,815.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	241.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	564.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.074
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	35.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	104.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.286
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,318.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	17.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.605
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.129
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.057

Call Order: 020 Proposal: T6599

ALT	Item	Description	Unit	Quantity
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.106
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.019
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,901.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	42.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	3.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	3.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	9,075.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,646.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	7,236.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	3.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	7.000
	0715- 61-352	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 15' ARM LENGTH	EA	6.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	26.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	4,272.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	11.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	7.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	223.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	11.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	11.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	11.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	8.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	2,404.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	650.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	11.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL-PEDESTAL/SERVICE POLE	EA	3.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	31.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	15.000

Call Order: 020 Proposal: T6599

ALT	Item	Description	Unit	Quantity
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 4	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 40'-30'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 7	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-30'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	3.000
	0649- 21- 21	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 78'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	33.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	38.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	26.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	9.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	2.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	21.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	21.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	54.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	7.000
	0670- 5-180	TRAFFIC CONTROLLER ASSEMBLY, F&I, CALTRANS W/STANDARD LOCK	AS	5.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 8- 1	CELLULAR MODEM, FURNISH AND INSTALL	EA	5.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	7.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	7.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	6.000
	0700-141-390	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN 12-16 SF	EA	4.000
Section 0005 Landscape / Peripheral				
	0581- 1-272	RELOCATE TREES AND PALMS, OTHER PALMS, <10.0" DBH, 14.0' OR GREATER OF CLEAR TRUNK	EA	1.000