

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251029	Call Order: 011	Proposal: T3984	District:03
Counties:	BAY			
Road Name:	SR 77			
Limits:	FROM 23RD ST TO CR 2312 (BALDWIN RD)			
Project(s):	44556435201(*)	Federal Aid No:	D325033B	
Total Roadway Length:	0.854 Miles	Contract Days:	350	
Total Bridge Length:	0.000 Miles	Letting Date:	10/29/25	
Total Proposal Length:	0.854 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	

Proposal Budget Estimate: \$3,806,272.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of resurfacing, base work, drainage improvements, curb & gutters, highway signing, gravity wall, sidewalks and other incidental construction on SR 77 from 23rd Street to CR 2312 Baldwin Road. All work to be done in Bay County.

Call Order: 011 Proposal: T3984

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44556435201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44556435201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	48.200
	0102- 60-	WORK ZONE SIGN	ED	20,300.000
	0102- 61-	BUSINESS SIGN	EA	22.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,074.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	10,950.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	700.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	700.000
	0102-115-	TYPE III BARRICADE	ED	1,400.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,336.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	22.400
	0107- 2-	MOWING	AC	22.400
	0110- 1- 1	CLEARING & GRUBBING (44556435201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,029.000
	0120- 1-	REGULAR EXCAVATION	CY	749.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	4,020.500
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,075.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	355.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	29.300
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	165.200
	0425- 1-910	INLETS, CLOSED FLUME	EA	41.000

Call Order: 011 Proposal: T3984

ALT	Item	Description	Unit	Quantity
	0425- 4-	INLETS, ADJUST	EA	10.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	4.000
	0425- 6-	VALVE BOXES, ADJUST	EA	3.000
	0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	890.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	5,920.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	5,495.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	3,572.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,305.000
	0527- 2-	DETECTABLE WARNINGS	SF	309.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	3.800
	0530- 74-	BEDDING STONE	TN	2.800
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,036.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	22.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	521.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	43.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	152.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44556435201)	LS	1.000