

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 022	Proposal: T6629	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 985 (NW 107 AVE)			
Limits:	FROM N OF FLAGLER ST TO N OF SR 836 (DOLPHIN EXPWY)			
Project(s):	45256015201(*)	Federal Aid No:	D625056B	
Project(s):	45256015601	Federal Aid No:	N/A	
Total Roadway Length:	0.777 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/26	
Total Proposal Length:	0.777 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$1,331,749.00			

Please read the full advertisement

Description: Incentive / Disincentive

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF RESURFACING ALONG SR 985/NW 107 AVENUE FROM NORTH OF FLAGLER STREET TO NORTH OF SR 836/DOLPHIN XWY IN MIAMI-DADE COUNTY.

Call Order: 022 Proposal: T6629

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45256015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45256015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	6,977.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	120.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	55,470.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,580.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	480.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	230.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	321.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	480.000
	0102-115-	TYPE III BARRICADE	ED	16.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	30.000
	0107- 1-	LITTER REMOVAL	AC	16.180
	0107- 2-	MOWING	AC	16.180
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45256015201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45256015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45256015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	128.000
	0210- 1- 9	REWORKING LIMEROCK BASE, 3"	SY	232.000

Call Order: 022 Proposal: T6629

ALT	Item	Description	Unit	Quantity
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	42,346.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	51.100
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	3,494.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.400
	0425- 5-	MANHOLE, ADJUST	EA	13.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	63.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	91.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	30.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	43.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	14.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	115.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-001, APPROACH TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	73.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	127.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.220
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.170
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45256015201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	7.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	7.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	18.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,039.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45256015201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.333
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.092
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,451.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	397.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	458.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.211
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	25.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	48.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	103.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.032

Call Order: 022 Proposal: T6629

ALT	Item	Description	Unit	Quantity
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	542.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.447
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.789
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.174
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.591
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.012
Section 0003 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	426.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	11.000
Section 0004 Utilities				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45256015601)	LS	1.000
	1060- 15-	UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	EA	1.000
	1080- 24-500	UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	EA	1.000