

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260930	Call Order: 012	Proposal: T3A46	District:03
Counties:	LEON			
Road Name:	SR 61 (THOMSVILLE HWY)			
Limits:	FROM N OF SR 63 (US 27 / MONROE ST) TO N OF 9TH AVE			
Project(s):	21966825201(*)	Federal Aid No:	D326069B	
Project(s):	21966825202	Federal Aid No:	N/A	
Project(s):	21966825601	Federal Aid No:	N/A	
Total Roadway Length:	0.766 Miles	Contract Days:	245	
Total Bridge Length:	0.000 Miles	Letting Date:	09/30/26	
Total Proposal Length:	0.766 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$2,386,527.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of providing the labor, material, and equipment necessary to complete the resurfacing, restoration, and rehabilitation of SR 61 (Thomasville Highway) from North of SR 63 (US 27) (Monroe Street) to North of 9th Avenue in Leon County. Proposed improvements under FPID: 219668-2-52-01 include, but are not limited to, milling and resurfacing, installation of new mast arms, minor drainage improvements, and signing and pavement markings. Proposed improvements under FPID: 219668-2-56-01 utility work by highway contractor (UWHC) include water service adjustments, sanitary sewer manhole adjustments, and valve and meter box adjustments. Details of this project are shown in the Contract Plans. A total of 245 Contract days will be allowed for the installation period.

Call Order: 012 Proposal: T3A46

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21966825201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21966825201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,416.000
	0102- 60-	WORK ZONE SIGN	ED	31,642.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	17,763.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	460.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	564.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	564.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,075.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	22.220
	0107- 2-	MOWING	AC	22.220
	0110- 1- 1	CLEARING & GRUBBING (21966825201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	770.000
	0110- 21-	TREE PROTECTION BARRIER	LF	676.000
	0120- 1-	REGULAR EXCAVATION	CY	9.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	93.100
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	16,205.000

Call Order: 012 Proposal: T3A46

ALT	Item	Description	Unit	Quantity
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	TN	1,336.900
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	1.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	30.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	499.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	49.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	363.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	126.000
	0527- 2-	DETECTABLE WARNINGS	SF	247.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	833.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	633.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.528
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.096
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,162.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	94.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	966.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.070
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.070
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.017
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	34.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	21.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.434
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	643.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.295
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.087
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21966825201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	27.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	19.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	30.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	28.000

Call Order: 012 Proposal: T3A46

ALT	Item	Description	Unit	Quantity
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	6.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	12.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	633.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21966825201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,038.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	94.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	240.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.017
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	34.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	21.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	643.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.087
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	609.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.528
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.096
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.060
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.070
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.434
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.295
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	521.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,944.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	3.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	46.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	1.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	6.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	7.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	5.000
	0649- 21- 4	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 40'-30'	EA	1.000

Call Order: 012 Proposal: T3A46

ALT	Item	Description	Unit	Quantity
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	EA	2.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	8.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	5.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0654- 2- 22	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSEMBLY- BACK TO BACK	AS	7.000
	0654- 2- 60	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, REMOVE COMPLETE SIGN ASSEMBLY	AS	7.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	11.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	18.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	20.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	11.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0671- 2- 17	TRAFFIC CONTROLLER WITHOUT CABINET, ATC, F&I IN EXISTING ATC CABINET	EA	1.000
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	2.000
	0923-676-205	ATC CABINET WITHOUT CONTROLLER, F&I, NEMA, SIZE 7, 44"-49" W x 24"-27" D	EA	1.000
Section 0004 Utilities				
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	11.000
	0425- 6-	VALVE BOXES, ADJUST	EA	26.000
	0425- 6- 1	METER BOXES, ADJUST	EA	1.000
	1050- 42-201	UTILITY PIPE- HIGH DENSITY POLYETHYLENE, FURNISH & INSTALL, WATER/SEWER, 1"	LF	38.000