

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 009	Proposal: T2A87	District:02
Counties:	ST JOHNS			
Road Name:	SR 13			
Limits:	FROM RAFTER TAIL LN TO MILL CREEK			
Project(s):	21022395201(*)	Federal Aid No:	D226036B	
Total Roadway Length:	7.172 Miles	Contract Days:	330	
Total Bridge Length:	0.026 Miles	Letting Date:	10/28/26	
Total Proposal Length:	7.504 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	

Proposal Budget Estimate: \$5,781,971.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, shoulder treatment, drainage improvements, curb & gutter, highway signing, guardrail, bridges, sidewalks and other incidental construction on SR 13 in St. Johns County from Rafter Tail Lane to Mill Creek.

Call Order: 009 Proposal: T2A87

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (21022395201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	64.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	12,428.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	115.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	6.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (21022395201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21022395201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	336.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,320.000
	0102- 60-	WORK ZONE SIGN	ED	8,678.000
	0102- 61-	BUSINESS SIGN	EA	1,320.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	310.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	416.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	310.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,282.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	6,484.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	660.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	410.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	688.000

Call Order: 009 Proposal: T2A87

ALT	Item	Description	Unit	Quantity
	0102-115-	TYPE III BARRICADE	ED	1,320.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	14.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	660.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,606.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	273.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0107- 1-	LITTER REMOVAL	AC	646.950
	0107- 2-	MOWING	AC	589.190
	0110- 1- 1	CLEARING & GRUBBING (21022395201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,218.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	73.000
	0120- 1-	REGULAR EXCAVATION	CY	635.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	659.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,020.000
	0285-707-	OPTIONAL BASE, BASE GROUP 07	SY	18.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	6,370.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	129,832.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	3,800.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	11,954.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	232.500
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	33.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	5.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	82.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	378.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	205.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	675.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	249.000
	0527- 2-	DETECTABLE WARNINGS	SF	83.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	5,371.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	23.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	3,342.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	11.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	46.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	32,250.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	3,586.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.258

Call Order: 009 Proposal: T2A87

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	23.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.515
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.947
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21022395201)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	2.420
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	37.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	36.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	19.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	19.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	20.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,935.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21022395201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	608.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	80.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	509.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.253
	0711- 11-144	THERMOPLASTIC, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE, 12" FOR ROUNDABOUT	GM	0.055
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	60.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,882.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.067
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	532.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	22.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	72.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.666
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.019
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	15.199
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.684

Call Order: 009 Proposal: T2A87

ALT	Item	Description	Unit	Quantity
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	280.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.053
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.053
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	49.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	149.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	4.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	4.000