

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 001	Proposal: T2A91	District:02
Counties:	DUVAL			
Road Name:	SR 115 (LEM TURNER RD)			
Limits:	AT TROUT RIVER, BRIDGE #720033			
Project(s):	43743725201(*)	Federal Aid No:	D226033B	
Total Roadway Length:	0.264 Miles	Contract Days:	1095	
Total Bridge Length:	0.145 Miles	Letting Date:	12/02/26	
Total Proposal Length:	0.406 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$40,307,607.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of structure removal, bridge construction, barrier walls, MSE walls, milling & resurfacing, base work, shoulder treatment, drainage improvements, curb & gutters, traffic signals, lighting, highway signing, guardrail, sidewalks, and incidental construction on SR 115 (Lem Turner Road) Trout River Bridge #720033 in Duval County.

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43743725201)	LS	1.000
	0400- 1- 30	CONCRETE, CLASS I (SEAL)	CY	308.100
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	230.400
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	1,942.700
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	219.400
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	1,487.100
	0400- 7- 1	BRIDGE DECK GROOVING	SY	6,191.000
	0400- 9- 1	BRIDGE DECK PLANING	SY	6,191.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	57.200
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	495,098.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	186,819.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	42,474.000
	0415- 2- 5	STAINLESS REINFORCING STEEL, SUBSTRUCTURE	LB	27,063.000
	0450- 1- 1	PRESTRESSED BEAMS, TYPE II	LF	6,672.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,139.000
	0455- 15- 15	PREFORMED PILE HOLES, 30" TO 34" DRILL/PUNCH SIZE	LF	10,159.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	200.000
	0455- 34- 25	PRESTRESSED CONCRETE PILING, 24" SQ W/FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	17,148.000
	0455-115-	PILE REDRIVE	EA	60.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	260.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	14.000
	0455-143- 25	TEST PILES-PRESTRESSED CONCRETE, 24" SQ W/ FRP OR STAINLESS STEEL STRAND AND REINFORCING	LF	1,498.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	390.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	1,666.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	1,666.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	1,666.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	46.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	2,658.800
	0530- 74-	BEDDING STONE	TN	989.900
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	8,992.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	74.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43743725201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43743725201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43743725201)	LS	1.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (43743725201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	45,180.000
	0102- 62- 12	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-012	ED	790.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,713.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	4,059.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	2,660.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,742.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	204,610.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	66,282.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,175.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	2,954.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	13.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,838.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	2,190.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	2,190.000
	0102-115-	TYPE III BARRICADE	ED	7,580.000
	0103- 1-100	TEMPORARY WORK STRUCTURE (43743725201)	LS	1.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	78.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,432.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	4,047.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	11.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	8.000
	0107- 1-	LITTER REMOVAL	AC	103.770
	0107- 2-	MOWING	AC	59.730
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43743725201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43743725201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43743725201)	LS	1.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,299.000
	0120- 1-	REGULAR EXCAVATION	CY	7,287.900
	0120- 6-	EMBANKMENT	CY	12,306.100
	0160- 4-	TYPE B STABILIZATION	SY	7,157.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	5,904.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	8,509.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	789.700
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,173.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.200
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	38.900
	0415- 1- 3	REINFORCING STEEL- RETAINING WALL	LB	1,046.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	7.000
	0425- 1-312	INLETS, CURB TYPE P-1, >10'	EA	1.000
	0425- 1-331	INLETS, CURB, TYPE P-3, <10'	EA	1.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	1.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	7.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	4.000
	0425- 2- 62	MANHOLES, P-8, >10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	3.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	2.000
	0425- 2-145	DRAINAGE MANHOLES, MODIFIED J-7, DIVERSION STRUCTURE	EA	3.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	2.000
	0425- 6-	VALVE BOXES, ADJUST	EA	3.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	881.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	906.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	298.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	435.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	136.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	5.200
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	6.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	2.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	148.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	274.000
	0515- 4- 2	BULLET RAIL, DOUBLE RAIL	LF	739.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,030.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,537.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	37.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	29.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,326.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	107.000
	0521- 6- 31	CONCRETE PARAPET, RETAINING WALL SYSTEM MOUNTED W/SIDEWALK, 27" HEIGHT	LF	742.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	99.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	600.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	90.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	54.000
	0527- 2-	DETECTABLE WARNINGS	SF	82.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	13.200
	0530- 74-	BEDDING STONE	TN	9.500
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	195.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	194.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	956.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	10,098.000
	0548- 13-	RETAINING WALL SYSTEM, TEMPORARY, EXCLUDING BARRIER	SF	1,000.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,528.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,372.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.055
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	550.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	129.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.805
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.269
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	6.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.752
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	67.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.037
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43743725201)	LS	1.000
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	20.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	13.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	3.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	5.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	249.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43743725201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	917.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	20.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	224.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.225
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	22.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	22.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.063
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	466.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	12.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.195
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.018
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.481
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.521
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	22.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.635
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.313
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.315
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.306
Section 0004 Lighting				
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (43743725201)	LS	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,025.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	228.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	13.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	1,331.000
	0715- 1- 70	LIGHTING CONDUCTORS, REMOVE & STOCKPILE, FDOT OR MAINT AGENCY OWNS	LF	1,596.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0715- 61-342	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 12' ARM LENGTH	EA	17.000
	0715- 65-366	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	7.000
	0715- 69-001	LIGHT POLE COMPLETE, REMOVE POLE, FOUNDATION REMAINS	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000
	0715-500- 3	POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT	EA	15.000
Section 0005 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.434
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	2.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	526.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,437.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	40.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 1-114	FIBER OPTIC CABLE, F&I, OVERHEAD,97-144 FIBERS	LF	808.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	240.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	2,371.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	2,290.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	312.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	2.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	26.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	22.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	9.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	2.000
	0639- 1-410	ELECTRICAL POWER SERVICE, REL OVERHEAD	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	4.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	2.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	3.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	4.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	5.000

Call Order: 001 Proposal: T2A91

ALT	Item	Description	Unit	Quantity
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	1.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	4.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	6.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0670- 5-710	TRAFFIC CONTROLLER ASSEMBLY, MODIFY ONLY - NO COMPONENTS ADDED	AS	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000