

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260225 Call Order: 002 Proposal: T1813 District:01
 Counties: DIST/ST-WIDE, MANATEE
 Road Name: SR 45 (US 41)
 Limits: FROM N OF EDWARDS DR TO N MAGELLAN DR, OVER BOWLESS CREEK, BRIDGE NO 130082
 AND FROM S OF GENERAL SPAATZ BLVD TO N OF EDWARDS DR

Project(s): 44461215201(*) Federal Aid No: D121031B
 Project(s): 44461215202 Federal Aid No: D121031B
 Project(s): 44461215203 Federal Aid No: D121031B
 Project(s): 45576915201 Federal Aid No: N/A
 Project(s): 45607515201 Federal Aid No: N/A

Total Roadway Length: 2.379 Miles Contract Days: 375
 Total Bridge Length: 0.028 Miles Letting Date: 02/25/26
 Total Proposal Length: 2.407 Miles Contract Execution Days:
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days

Proposal Budget Estimate: \$17,262,050.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, drainage improvements, curb and gutter, guardrail removal, signalization, lighting and signing and pavement markings on SR 45 from North of Edwards Drive to North Magellan Drive, SR 45 (US 41) over Bowless Creek Bridge # 130082, SR 45 (US 41) from South of General Spaatz Blvd to North of Edwards Drive in Manatee and Sarasota County.

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44461215201)	LS	1.000
	0101- 1-	MOBILIZATION (45576915201)	LS	1.000
	0101- 1-	MOBILIZATION (45607515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44461215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45576915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45607515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,213.000
	0102- 60-	WORK ZONE SIGN	ED	33,376.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	29,085.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	3,561.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	224,850.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	499,528.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	1,875.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,167.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	375.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	375.000
	0102-115-	TYPE III BARRICADE	ED	1,668.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	2.698
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.065
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	1.840
	0102-913- 32	REMOVABLE TAPE, YELLOW, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.043
	0104- 10- 3	SEDIMENT BARRIER	LF	530.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	4.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	93.000
	0107- 1-	LITTER REMOVAL	AC	136.050
	0107- 2-	MOWING	AC	80.400
	0110- 1- 1	CLEARING & GRUBBING (44461215202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44461215203)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,679.000
	0120- 1-	REGULAR EXCAVATION	CY	137.200
	0120- 6-	EMBANKMENT	CY	2,621.200
	0160- 4-	TYPE B STABILIZATION	SY	2,934.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	52.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	1,824.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	181.000
	0327- 70- 2	MILLING EXISTING ASPHALT PAVEMENT, 3 1/2" AVG DEPTH	SY	56,203.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	18,730.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	980.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	5,711.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	40,844.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	13,539.700
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,694.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	10,324.900
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.600
	0350- 3- 1	PLAIN CEMENT CONCRETE PAVEMENT, 6"	SY	1,157.000
	0350- 3- 13	PLAIN CEMENT CONCRETE PAVEMENT, 12"	SY	52.000
	0425- 1-311	INLETS, CURB, TYPE P-1, <10'	EA	8.000
	0425- 1-365	INLETS, CURB, TYPE P-6, PARTIAL	EA	1.000
	0425- 1-411	INLETS, CURB TYPE J-1, <10'	EA	1.000
	0425- 1-421	INLETS, CURB, TYPE J-2, <10'	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	3.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	3.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	143.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	38.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	32.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	32.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-175-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	LF	81.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	861.000
	0520- 2- 1	CONCRETE CURB, TYPE A	LF	11,139.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	134.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	1,247.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	985.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	793.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	370.000
	0527- 2-	DETECTABLE WARNINGS	SF	671.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	164.000
	0536- 73-	GUARDRAIL REMOVAL	LF	226.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,431.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID)	LS	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,092.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.240
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.326
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	12,060.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,035.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	9,903.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	25.569
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.565
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	165.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	598.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	13.945
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.005
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.173
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44461215201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44461215202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44461215203)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45576915201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45607515201)	LS	1.000
Section 0002 Signing				
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	2.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	96.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	19.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	5.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	51.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0700- 1-912	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-913	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 20.1-30.0 SF	EA	4.000
	0700- 1-914	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 30.1+ SF	EA	2.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	29.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	46.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	9.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	27.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,712.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	105.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44461215201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45576915201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45607515201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,020.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	345.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	861.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.855
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	5.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	152.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.391
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,440.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	50.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	48.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.078
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.132
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.005
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.054
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.442
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	8.479
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.689
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	330.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,038.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	16,281.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	108.000
	0639- 1-500	ELECTRICAL POWER SERVICE, ADJUST/MODIFY	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	8.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	88,308.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	12,545.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	51,925.000
	0715- 5- 40	LUMINAIRE & BRACKET ARM, RELOCATE	EA	1.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	25.000
	0715- 61-111	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 8' ARM LENGTH	EA	3.000
	0715- 61-152	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 15' ARM LENGTH	EA	25.000
	0715- 61-211	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 8' ARM LENGTH	EA	4.000
	0715- 61-252	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 15' ARM LENGTH	EA	2.000
	0715- 61-411	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 8' ARM LENGTH	EA	1.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	41.000
	0715- 65-166	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 16' ARM LENGTH	EA	9.000
	0715- 65-266	LIGHT POLE COMPLETE, F&I, UTILITY CONFLICT POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 16' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	39.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	118.000
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,036.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,776.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	4.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,804.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	68.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	8.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	48.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	4.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	4.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	375.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	118.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	5.000
	0635- 2- 14	PULL & SPLICE BOX, F&I, 17" X 30" COVER SIZE	EA	102.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	4.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	574.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	30.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	19.000
	0649- 21- 1	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 30'	EA	1.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	2.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	5.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	40.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	8.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	30.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	30.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	3.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	10.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	6.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	4.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	24.000
	0660- 6-121	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, CABINET EQUIPMENT	EA	1.000
	0660- 6-122	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	1.000
	0660- 6-421	VEHICLE DETECTION SYSTEM- AVI, BLUETOOTH RELOCATE, CABINET EQUIPMENT	EA	1.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	4.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	4.000
	0663- 1-600	SIGNAL PRIORITY & PREEMPTION SYSTEM, REMOVE	EA	3.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	30.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	3.000

Call Order: 002 Proposal: T1813

ALT	Item	Description	Unit	Quantity
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	4.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	4.000
	0676- 1-112	TRAFFIC SIGNAL CONTROLLER CABINET, FURNISH & INSTALL WITHOUT CONTROLLER, TYPE/SIZE 2, 20" W x 32" H x 14" D	EA	3.000
	0676- 1-600	TRAFFIC SIGNAL CONTROLLER CABINET, REMOVE	EA	3.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	2.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	3.000
	0682- 1-600	ITS CCTV CAMERA, REMOVE & DISPOSAL	EA	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	4.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	4.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	4.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	16.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	11.000
	0700-141-360	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN <12 SF	EA	2.000