

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 010	Proposal: T3A01	District:03
Counties:	WALTON			
Road Name:	SR 83 (US 331)			
Limits:	AT ROCK HILL RD			
Project(s):	45490915201(*)	Federal Aid No:	D325075B	
Total Roadway Length:	0.006 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	12/03/25	
Total Proposal Length:	0.006 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	

Proposal Budget Estimate: \$1,134,583.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of new strain pole signal installation and signing and marking improvements at the intersection of SR 83 (US 331) at Rock Hill Road in Walton County.

Call Order: 010 Proposal: T3A01

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45490915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45490915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	24.000
	0102- 60-	WORK ZONE SIGN	ED	2,340.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,440.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	520.000
	0102-115-	TYPE III BARRICADE	ED	40.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	72.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	28.280
	0107- 2-	MOWING	AC	28.280
	0110- 1- 1	CLEARING & GRUBBING (45490915201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	1.870
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,586.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45490915201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700-142-122	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/2 BEACONS, 12-20 SF OF STATIC SIGN PANELS	EA	4.000

Call Order: 010 Proposal: T3A01

ALT	Item	Description	Unit	Quantity
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	52.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	83.000
	0710- 17- 1	PAINTED PAVEMENT MARKINGS, REMOVAL OF NON-CONFLICTING	SF	83.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	145.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.042
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.050
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.047
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	366.000
Section 0003 Signalization				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.441
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,127.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	261.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	LF	405.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	4.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	8.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	1.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	1.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	12.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	90.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	3.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	88.000
	0639- 3- 12	ELECTRICAL SERVICE DISCONNECT, F&I, CABINET	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0649- 1- 14	STEEL STRAIN POLE, F&I, TYPE PS- VII	EA	4.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	6.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	2.000

Call Order: 010 Proposal: T3A01

ALT	Item	Description	Unit	Quantity
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	10.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	4.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	1.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	1.000
	0670- 5-161	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA W/STANDARD LOCK, 1 PREEMPTION	AS	1.000
	0682- 1-163	ITS CCTV CAMERA, PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0684- 6- 3	WIRELESS COMMUNICATION SYSTEM DEVICE, INSTALL	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000