

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260225	Call Order: 015	Proposal: T6619	District:06
Counties:	MIAMI-DADE			
Road Name:	SR 969 (NW 72 AVE) AND SR 826			
Limits:	AT SR 948 (NW 36 ST) AND FROM SB OFF RAMP TO EB SW 8 ST			
Project(s):	45103315201(*)	Federal Aid No:	D625050B	
Project(s):	45103915201	Federal Aid No:	D624062B	
Total Roadway Length:	0.587 Miles	Contract Days:	180	
Total Bridge Length:	0.070 Miles	Letting Date:	02/25/26	
Total Proposal Length:	0.657 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$2,066,346.00			

Please read the full advertisement

Description: Incentive / Disincentive

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIST OF INTERSECTION IMPROVEMENT ALONG SR 969/NW 72 AVENUE AT SR 948/NW 36 STREET AND SAFETY PROJECT ALONG SR 826 SOUTHBOUND OFF RAMP TO EASTBOUND SW 8 STREET IN MIAMI-DADE COUNTY.

Call Order: 015 Proposal: T6619

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45103315201)	LS	1.000
	0101- 1-	MOBILIZATION (45103915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45103315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45103915201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	17.800
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45103315201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	480.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	480.000
	0102- 60-	WORK ZONE SIGN	ED	2,075.000
	0102- 62- 12	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-012	ED	572.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	580.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,465.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	26,502.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	310.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	1.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	338.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	482.000
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.400
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000

Call Order: 015 Proposal: T6619

ALT	Item	Description	Unit	Quantity
	0107- 1-	LITTER REMOVAL	AC	18.660
	0107- 2-	MOWING	AC	14.100
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45103315201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (45103315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45103315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45103915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	807.000
	0110- 21-	TREE PROTECTION BARRIER	LF	231.000
	0120- 1-	REGULAR EXCAVATION	CY	346.600
	0120- 6-	EMBANKMENT	CY	178.000
	0160- 4-	TYPE B STABILIZATION	SY	443.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	442.000
	0285-774-	COMPOSITE BASE, SPECIAL DESIGN, 6.5" OF B-12 & 6" GRANULAR SUB-BASE	SY	1.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,053.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	2,235.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	61.200
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	499.800
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	230.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	63.400
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425-100- 41	SPECIAL DRAINAGE, UTILITY AVOIDANCE STRUCTURE	EA	4.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	143.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	316.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	693.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	210.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	280.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	343.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	844.000
	0536- 7- 1	SPECIAL GUARDRAIL POST- DEEP POST FOR SLOPE BREAK CONDITION- TIMBER OR STEEL	EA	88.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	30.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0570- 1- 1	PERFORMANCE TURF	SY	117.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	370.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (45103315201)	LS	1.000
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	2,792.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45103315201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45103915201)	LS	1.000

Call Order: 015 Proposal: T6619

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	1.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	4.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	11.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	1.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	2.000
	0700-142-141	ENHANCED HWY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/HIGHLIGHTED SIGN <12 SF, UP TO 12 SF OF STATIC PANELS	EA	5.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	10.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	158.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45103315201)	LS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45103915201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.044
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	973.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	190.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.244
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	4.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	888.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.392
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.198
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.267
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,362.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000

Call Order: 015 Proposal: T6619

ALT	Item	Description	Unit	Quantity
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	4,642.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	40.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	4,113.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	1.000
	0715- 11-211	LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	EA	2.000
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	1.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	3.000
Section 0004 Signalization				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	494.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	7.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	494.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	494.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
Section 0005 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.127
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	1.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	888.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	100.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	6.000
	0635- 2- 30	PULL & SPLICE BOX, INSTALL	EA	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	888.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	896.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	1.000