

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT260225	Call Order: 004	Proposal: T2A33	District:02
Counties:	PUTNAM			
Road Name:	SR 15 (US 17 / REID ST) AND SR 20 (CRILL AVE)			
Limits:	FROM MEMORIAL BRIDGE TO SR 19 AND FROM E OF OSCEOLA ST TO S OF CARR ST			
Project(s):	21002625201(*)	Federal Aid No: D224094B		
Project(s):	42879735201	Federal Aid No: N/A		
Total Roadway Length:	3.008 Miles	Contract Days:	350	
Total Bridge Length:	0.000 Miles	Letting Date:	02/25/26	
Total Proposal Length:	3.008 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$7,536,047.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, base work, shoulder treatment, drainage improvements, curb & gutters, traffic signals, highway signing, sidewalks/bicycle path, concrete pavement rehabilitation, and other incidental construction on SR 15 (US 17) Reid Street from Memorial Bridge to SR 19 and SR 20 (Crill Avenue) from East of Osceola St. to South of Carr St. in Putnam County.

RR Insurance Required

Call Order: 004 Proposal: T2A33

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (21002625201)	LS	1.000
	0101- 1-	MOBILIZATION (42879735201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (21002625201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42879735201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (42879735201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	644.000
	0102- 60-	WORK ZONE SIGN	ED	41,525.000
	0102- 62- 13	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-013	ED	1,813.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	406.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	24,572.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,610.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	900.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	180.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,199.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	3,500.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	3,500.000
	0102-115-	TYPE III BARRICADE	ED	1,826.000
	0102-913- 12	REMOVABLE TAPE, BLACK, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP	GM	0.055
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.414
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.055

Call Order: 004 Proposal: T2A33

ALT	Item	Description	Unit	Quantity
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	108.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	493.000
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	3.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.288
	0104- 10- 3	SEDIMENT BARRIER	LF	4,476.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	155.000
	0107- 1-	LITTER REMOVAL	AC	264.250
	0107- 2-	MOWING	AC	206.480
	0110- 1- 1	CLEARING & GRUBBING (21002625201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (42879735201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,168.000
	0120- 1-	REGULAR EXCAVATION	CY	16.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	97.900
	0120- 6-	EMBANKMENT	CY	54.400
	0121- 70-	FLOWABLE FILL	CY	13.800
	0162- 1-100	PREPARED SOIL LAYER, 24" DEPTH	SY	54.000
	0285-708-	OPTIONAL BASE, BASE GROUP 08	SY	15.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	87,532.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	39,135.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	2.400
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	7,221.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1.200
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	10,450.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	5,074.000
	0350- 6-	CLEANING & SEALING RANDOM CRACKS- CONCRETE PAVEMENT	LF	80.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	2,970.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	176.900
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	22.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	20.000
	0425- 6-	VALVE BOXES, ADJUST	EA	34.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	14.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	16.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	18.000
	0431- 1-118	PIPE LINER, CURED IN PLACE, 18"	LF	84.000
	0432- 3- 2	CHEMICAL GROUT REPAIR, PIPE, NON-TEST, 18"	EA	1.000
	0433- 1-	CHEMICAL GROUT REPAIR, MANHOLE / INLET	EA	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	95.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,928.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	172.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	10.000
	0520- 4-	CURB-CONCRETE PAVEMENT JOINT	LF	72.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	88.000

Call Order: 004 Proposal: T2A33

ALT	Item	Description	Unit	Quantity
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	172.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	797.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	13.000
	0527- 2-	DETECTABLE WARNINGS	SF	1,727.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,137.000
	0591- 1-200	IRRIGATION SLEEVE, 2" DIAMETER	LF	50.000
	0591- 1-400	IRRIGATION SLEEVE, 4" DIAMETER	LF	50.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	4,796.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.485
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.268
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	7,308.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,219.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,907.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.194
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.103
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	2.736
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	131.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.710
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	654.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	1.059
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	16,540.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (21002625201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42879735201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	166.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	42.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	74.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	15.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	88.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	75.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	58.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	7.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,868.000

Call Order: 004 Proposal: T2A33

ALT	Item	Description	Unit	Quantity
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	935.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (21002625201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,308.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,143.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,930.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	2.695
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	19.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	132.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	717.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.059
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,598.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.061
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	76.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	74.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	61.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	357.000
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.061
	0711- 14-526	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 32"	LF	426.000
	0711- 14-527	THERMOPLASTIC, PREFORMED, 24" WHITE WITH 4" BLACK CONTRAST FOR STOP LINE ON CONCRETE PAVEMENT, 32"	LF	108.000
	0711- 14-528	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" BLACK CONTRAST FOR CROSSWALK ON CONCRETE PAVEMENT, 20"	LF	439.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	4.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	8.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	6.922
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	1.220
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.194
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.103
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.605
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	3,971.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.161

Call Order: 004 Proposal: T2A33

ALT	Item	Description	Unit	Quantity
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.096
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.213
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.161
	0713-103-381	PERMANENT TAPE, BLACK, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.213
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	180.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	146.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	8.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	68.000