

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 011	Proposal: T3A13	District:03
Counties:	OKALOOSA			
Road Name:	CR 118 (AIRPORT RD)			
Limits:	AT BUCKHORN DR			
Project(s):	45099715201(*)	Federal Aid No:	D326029B	
Total Roadway Length:	0.590 Miles	Contract Days:	140	
Total Bridge Length:	0.000 Miles	Letting Date:	12/02/26	
Total Proposal Length:	0.590 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Flexible	
Proposal Budget Estimate:		\$294,528.00		

Please read the full advertisement

Description:

The Improvements under this Contract consist of high friction course treatment and signing and pavement marking updates for rural curve safety improvements at CR 188 (Airport Road) and Buckhorn Drive in Okaloosa County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 011 Proposal: T3A13				
ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45099715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45099715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,640.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,796.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	353.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	308.000
	0104- 10- 3	SEDIMENT BARRIER	LF	589.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.418
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.409
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	2,995.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	0.623
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	9.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	9.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	22.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	353.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45099715201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	19.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.418
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.409
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	2,185.000