

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 007	Proposal: T3969	District:03
Counties:	BAY			
Road Name:	SR 20			
Limits:	FROM SR 75 (US 231) TO CALHOUN CO LINE			
Project(s):	44560115201	Federal Aid No:	D325034B	
Project(s):	45080515201(*)	Federal Aid No:	D325047B	
Total Roadway Length:	2.366 Miles	Contract Days:	170	
Total Bridge Length:	0.025 Miles	Letting Date:	12/03/25	
Total Proposal Length:	2.391 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days	
Proposal Budget Estimate:	\$1,669,533.00			

Please read the full advertisement

Description:

The Improvements under this Contract for Financial Project ID 450805-1-52-01 consist of milling and resurfacing SR 20 FROM SR 75 (US 231) TO CALHOUN COUNTY LINE. This project also includes minor drainage improvements, shoulder widening, loop replacement, and pavement marking improvements. FPID 450805-1-52-01 is the Lead Project. The Goes With project FPID 445601-1-52-01 SR 75 (US 231) AT SR 20 INTERSECTION SAFETY IMPROVEMENTS consists of adding backplates to the signal heads and adding signing to intersection approaches. All work is to be done in Bay County.

Call Order: 007 Proposal: T3969

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45080515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45080515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	29.700
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	12.000
	0102- 60-	WORK ZONE SIGN	ED	7,382.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	50,124.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	100.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,016.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	170.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	170.000
	0102-115-	TYPE III BARRICADE	ED	12.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	140.000
	0104- 10- 3	SEDIMENT BARRIER	LF	120.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	46.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	52.000
	0107- 1-	LITTER REMOVAL	AC	109.480
	0107- 2-	MOWING	AC	93.150
	0110- 1- 1	CLEARING & GRUBBING (45080515201)	LS	1.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	8.700
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (45080515201)	LS	1.000

Call Order: 007 Proposal: T3969

ALT	Item	Description	Unit	Quantity
	0160- 4-	TYPE B STABILIZATION	SY	867.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	704.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	401.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	33,176.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	15,142.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	125.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	23.800
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,054.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	9.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	80.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	100.000
	0536- 73-	GUARDRAIL REMOVAL	LF	100.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,696.000
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	32.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	459.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.286
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	2.252
	0906-173-100	SINGLE COMPONENT POLYURETHANE INJECTION	GA	692.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45080515201)	LS	1.000
Section 0002 Signing				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	4.000
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	6.836
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	11.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	24.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	459.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	26.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45080515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	313.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	269.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID, 6"	LF	41.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	22.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	158.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.706
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.286

Call Order: 007 Proposal: T3969

ALT	Item	Description	Unit	Quantity
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	2.252
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.049
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.025
Section 0003 Signalization				
	0101- 1-	MOBILIZATION (44560115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44560115201)	LS	1.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,321.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	520.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,671.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	9.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	1.000
	0700-142-112	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/BEACON, 12-20 SF OF STATIC SIGN PANELS	EA	4.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44560115201)	LS	1.000