

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261202	Call Order: 012	Proposal: T3A31	District:03
Counties:	WALTON			
Road Name:	SR 20			
Limits:	FROM W OF BUS 331 (MADISON ST) TO SR 81			
Project(s):	45315015201(*)	Federal Aid No:	D326046B	
Project(s):	45315015202	Federal Aid No:	D326046B	
Project(s):	45315015203	Federal Aid No:	N/A	
Project(s):	45315015205	Federal Aid No:	D326046B	
Total Roadway Length:	10.455 Miles	Contract Days:	475	
Total Bridge Length:	0.109 Miles	Letting Date:	12/02/26	
Total Proposal Length:	10.564 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Flexible	
Proposal Budget Estimate:	\$11,121,180.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling & resurfacing, curb & gutter, sidewalk, drainage, signing & pavement marking, temporary traffic control, signalization, gravity wall and utility adjustment on FPID 453150-1-52-01; widening, temporary traffic control, drainage, and signing & pavement marking on FPID 453150-1-52-02; bridge joint replacement on FPID 453150-1-52-03; widening, temporary traffic control, drainage, and signing & pavement marking on FPID 453150-1-52-05, State Road 20 from West of Business 331 (Madison Street) to State Road 81, approximately 10.564 miles in Walton County.

Call Order: 012 Proposal: T3A31

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	552.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	185.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (45315015201)	LS	1.000
	0101- 1-	MOBILIZATION (45315015202)	LS	1.000
	0101- 1-	MOBILIZATION (45315015203)	LS	1.000
	0101- 1-	MOBILIZATION (45315015205)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45315015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45315015202)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45315015203)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45315015205)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45315015201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45315015202)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45315015205)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45315015201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45315015202)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45315015205)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	800.200
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45315015201)	LS	1.000

Call Order: 012 Proposal: T3A31

ALT	Item	Description	Unit	Quantity
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	1,232.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	112.000
	0102- 60-	WORK ZONE SIGN	ED	30,763.000
	0102- 61-	BUSINESS SIGN	EA	5.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,148.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	4,463.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	1,426.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	57,762.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	10,363.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	4,634.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	20.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	978.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	950.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	950.000
	0102-115-	TYPE III BARRICADE	ED	100.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	80.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,957.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	33.000
	0107- 1-	LITTER REMOVAL	AC	2,064.000
	0107- 2-	MOWING	AC	1,920.000
	0110- 1- 1	CLEARING & GRUBBING (45315015201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45315015202)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45315015205)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	1,740.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	12.000
	0120- 1-	REGULAR EXCAVATION	CY	4,176.700
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	3,256.900
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	14,318.000
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	677.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	15,550.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	148,959.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	577.000
	0327- 70- 12	MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	SY	2,055.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	16,139.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	19,852.400
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	41.500
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	174.300
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	3.000
	0425- 1-481	INLETS, CURB, TYPE 8, <10'	EA	3.000
	0425- 1-521	INLETS, DT BOT, TYPE C, <10'	EA	1.000

Call Order: 012 Proposal: T3A31

ALT	Item	Description	Unit	Quantity
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	2.000
	0425- 1-561	INLETS, DT BOT, TYPE F, <10'	EA	1.000
	0425- 2- 43	MANHOLES, P-7, PARTIAL	EA	3.000
	0425- 2- 73	MANHOLES, J-7, PARTIAL	EA	1.000
	0425- 4-	INLETS, ADJUST	EA	2.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	431.000
	0430-174-218	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	LF	170.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	183.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	34.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	65.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	343.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	3.500
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	20.000
	0430-984-625	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	EA	7.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	637.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	34.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,217.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	109.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	186.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	762.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	427.000
	0526- 1-101	PAVERS, ARCHITECTURAL, REMOVE EXISTING AND REINSTALL	SY	203.000
	0527- 2-	DETECTABLE WARNINGS	SF	188.000
	0530- 5- 12	GABION, MATTRESS 1 FOOT AND GREATER THICKNESS	SY	444.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	438.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	387.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	45,633.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	104.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	24.744
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.081
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,133.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	149.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	774.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.297

Call Order: 012 Proposal: T3A31

ALT	Item	Description	Unit	Quantity
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.481
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	17.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	97.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	15.176
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	6.435
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.116
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45315015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45315015202)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45315015203)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45315015205)	LS	1.000
Section 0003 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	27.049
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	15.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	7.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	12.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	1.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	128.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	21.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3,098.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45315015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,782.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	149.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	664.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.474
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	82.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,700.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.116
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	945.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	15.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	15.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.467
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.081
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.427
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	13.072

Call Order: 012 Proposal: T3A31

ALT	Item	Description	Unit	Quantity
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.435
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	85.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.095
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.047
Section 0004 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,165.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,422.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	2.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	475.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	43.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	13.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	2.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	13.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	4.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	15.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	12.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	10.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	11.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000