

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 021	Proposal: T5914	District:05
Counties:	BREVARD			
Road Name:	SR 9 (I-95)			
Limits:	FROM VIERA BLVD TO SR 519 (FISKE BLVD)			
Project(s):	45805715201(*)	Federal Aid No: D526075B		
Total Roadway Length:	1.782 Miles	Contract Days:	110	
Total Bridge Length:	0.000 Miles	Letting Date:	10/28/26	
Total Proposal Length:	1.782 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$20,636,951.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of constructing auxiliary lanes in both the northbound and southbound directions, widening the outside shoulders, installing guardrail, constructing a noise wall, modifying roadside ditches for stormwater treatment, and making signing, pavement marking, and lighting improvements on I-95 from Viera Blvd. to Fiske Blvd., approximately 1.782 miles in Brevard County.

Call Order: 021 Proposal: T5914

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45805715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45805715201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (45805715201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (45805715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,080.000
	0102- 60-	WORK ZONE SIGN	ED	2,640.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	804.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	384.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	22,440.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	583.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY (PCMS WILL BE PLACED 14 DAYS PRIOR TO CONSTRUCTION)	ED	248.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	440.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	440.000
	0104- 10- 3	SEDIMENT BARRIER	LF	11,643.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	98.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	5,913.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	52.000
	0107- 1-	LITTER REMOVAL	AC	123.860
	0107- 2-	MOWING	AC	123.860
	0110- 1- 1	CLEARING & GRUBBING (45805715201)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	8,284.300

Call Order: 021 Proposal: T5914

ALT	Item	Description	Unit	Quantity
	0120- 4-	SUBSOIL EXCAVATION	CY	10,455.600
	0120- 6-	EMBANKMENT	CY	46,943.500
	0160- 4-	TYPE B STABILIZATION	SY	39,057.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	16,818.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	18,488.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,774.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	182.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	5,365.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	2,682.200
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	3,905.900
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	3,254.300
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,050.600
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	58.600
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	11.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0430-174-224	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 24"SD	LF	26.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	722.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	399.000
	0430-524-100	STRAIGHT CONCRETE ENDWALLS, 24", SINGLE, 0 DEGREES, ROUND	EA	5.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	7.600
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	6.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	5.000
	0430-984-629	MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 24" SD	EA	4.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	238.500
	0534- 72-101	SOUND/NOISE BARRIER-INC FOUNDATION, PERMANENT	SF	190,075.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	1,122.000
	0536- 7- 3	SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	EA	10.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	495.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	3.000
	0563- 3-	ANTI-GRAFFITI COATING, SACRIFICIAL	SF	172,795.000
	0570- 1- 1	PERFORMANCE TURF	SY	101,668.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	947.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	947.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.758
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.252
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	7.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	2.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45805715201)	LS	1.000

Call Order: 021 Proposal: T5914

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	2.795
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	4.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	3.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	1.000
	0700- 2-500	MULTI-COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	2.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	6.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	3.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	5.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	3.000
	0700- 3-607	SIGN PANEL, REMOVE, 201-300 SF	EA	1.000
	0700- 4-113	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 31-40 FT	EA	2.000
	0700- 4-612	OVERHEAD STATIC SIGN STRUCTURE, DEEP FOUNDATION REMOVAL, CANTILEVER	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	598.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45805715201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.114
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.802
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.627
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	1.000
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.252
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	642.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5,536.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	170.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	26.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	23,165.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	5,850.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	21.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	21.000

Call Order: 021 Proposal: T5914

ALT	Item	Description	Unit	Quantity
	0715- 61-442	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 12' ARM LENGTH	EA	26.000
	0715- 69-000	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	21.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	47.000