

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT261028	Call Order: 011	Proposal: T2B08	District:02
Counties:	COLUMBIA			
Road Name:	SR 247 (BRANFORD HWY)			
Limits:	FROM SUWANNEE COUNTY LINE TO SR 93 (I-75)			
Project(s):	20841195201(*)	Federal Aid No:	D226050B	
Total Roadway Length:	10.029 Miles	Contract Days:	180	
Total Bridge Length:	0.045 Miles	Letting Date:	10/28/26	
Total Proposal Length:	10.074 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$8,714,075.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, shoulder treatment, drainage improvements, highway signing, guardrail, and other incidental construction on SR 247 in Columbia County from the Suwannee County Line to I-75 (SR 93).

Call Order: 011 Proposal: T2B08

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (20841195201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20841195201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	10.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	728.000
	0102- 60-	WORK ZONE SIGN	ED	18,180.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	235.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	223.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	157,072.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	5,794.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	388.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	540.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	360.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	180.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.089
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.089
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	425.000
	0104- 6-	TEMPORARY SLOPE DRAIN / RUNOFF CONTROL STRUCTURE	LF	84.000
	0104- 10- 3	SEDIMENT BARRIER	LF	228.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0107- 1-	LITTER REMOVAL	AC	1,127.200
	0107- 2-	MOWING	AC	1,041.290

Call Order: 011 Proposal: T2B08

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (20841195201)	LS	1.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	5,798.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	80,389.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	145,168.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	19,960.600
	0337- 7- 91	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, HIGH POLYMER	TN	18,689.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	8.500
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	12.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	35.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	7.900
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	143.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	22.700
	0530- 74-	BEDDING STONE	TN	16.300
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	144.000
	0536- 73-	GUARDRAIL REMOVAL	LF	112.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	42,532.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	5,107.700
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	45.526
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.122
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	894.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	590.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	2,044.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.132
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	118.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	25.198
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	2,462.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	11.562
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.284
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20841195201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	28.256
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	37.000

Call Order: 011 Proposal: T2B08

ALT	Item	Description	Unit	Quantity
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	36.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	36.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	12.000
	0705- 10- 3	OBJECT MARKER, TYPE 3	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,897.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20841195201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	447.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	295.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,022.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.566
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	59.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,231.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.142
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	375.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	22.763
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.061
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	12.599
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	5.781
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	370.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.089
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	120.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	2.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	8.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	8.000