

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT251203	Call Order: 009	Proposal: T3994	District:03
Counties:	CALHOUN			
Road Name:	SR 69			
Limits:	FROM S OF NE VAN LEROP RD TO JACKSON CO LINE			
Project(s):	45081615201(*)	Federal Aid No:	D325053B	
Total Roadway Length:	7.941 Miles	Contract Days:	280	
Total Bridge Length:	0.084 Miles	Letting Date:	12/03/25	
Total Proposal Length:	8.025 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$3,550,599.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing of SR 69 from S of NE Van Lerop RD to Jackson County line in Calhoun County. Other improvements include the installation of a traffic monitoring site, drainage, and signing and pavement marking.

Call Order: 009 Proposal: T3994

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45081615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45081615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	40.000
	0102- 60-	WORK ZONE SIGN	ED	8,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	48,736.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	574.000
	0102-115-	TYPE III BARRICADE	ED	540.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	280.000
	0104- 10- 3	SEDIMENT BARRIER	LF	234.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	70.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	14.000
	0107- 1-	LITTER REMOVAL	AC	850.850
	0107- 2-	MOWING	AC	771.210
	0110- 1- 1	CLEARING & GRUBBING (45081615201)	LS	1.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	108,001.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	39,100.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	2,483.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	409.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	15,379.300
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	176.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	24.000
	0430-548-200	STRAIGHT CONCRETE ENDWALLS, 48", DOUBLE, 0 DEGREES, ROUND	EA	1.000

Call Order: 009 Proposal: T3994

ALT	Item	Description	Unit	Quantity
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	23,018.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	79.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-141	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 4, BASE MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,753.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.550
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.059
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	6.093
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45081615201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	23.342
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,753.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45081615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	15.550
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.059
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	6.093
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.174
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.046
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.087