

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT260128 Call Order: 006 Proposal: T3954 District:03
 Counties: ESCAMBIA
 Road Name: KLONDIKE RD
 Limits: OVER UNNAMED BRANCH BRIDGE NO 484060
 Project(s): 44905415201(*) Federal Aid No: D325042B
 Total Roadway Length: 0.152 Miles Contract Days: 500
 Total Bridge Length: 0.018 Miles Letting Date: 01/28/26
 Total Proposal Length: 0.170 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 60 Days

Proposal Budget Estimate: \$2,814,046.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of 449054-1-52-01 Bridge Replacement for Klondike Rd over Unnamed Branch Bridge No 484060 in Escambia County, including roadway approach rehabilitation, signing and marking, drainage, and a special detour.

Call Order: 006 Proposal: T3954

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44905415201)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	62.100
	0400- 2- 47	CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	CY	68.400
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	32.800
	0400- 7- 1	BRIDGE DECK GROOVING	SY	256.000
	0400-148-	PLAIN NEOPRENE BEARING PADS	CF	3.300
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	15,005.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	5,396.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	11,358.000
	0450- 8- 33	PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 18" CARBON STEEL, WIDTH 55-57"	LF	469.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	456.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE, 18" SQ	LF	144.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	78.000
	0521- 5- 13	CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	LF	200.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	20.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	727.400
	0530- 74-	BEDDING STONE	TN	259.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	407.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	8.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44905415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44905415201)	LS	1.000

Call Order: 006 Proposal: T3954

ALT	Item	Description	Unit	Quantity
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44905415201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44905415201)	LS	1.000
	0102- 2-400	SPECIAL DETOUR- TEMPORARY BRIDGE (44905415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	27.500
	0102- 60-	WORK ZONE SIGN	ED	10,970.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	590.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	37,712.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,028.000
	0102-115-	TYPE III BARRICADE	ED	2,560.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	548.000
	0104- 6-	TEMPORARY SLOPE DRAIN / RUNOFF CONTROL STRUCTURE	LF	73.000
	0104- 10- 3	SEDIMENT BARRIER	LF	883.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44905415201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44905415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44905415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	278.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	10.000
	0120- 1-	REGULAR EXCAVATION	CY	1,578.100
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	530.200
	0160- 4-	TYPE B STABILIZATION	SY	2,862.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,011.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	459.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,365.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	43.100
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	207.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	16.800
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	38.000
	0430-174-215	PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 15"SD	LF	65.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-623	MITERED END SECTION, OPTIONAL OTHER - ELLIP/ARCH, 15" SD	EA	8.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	174.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	177.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	3.000
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	319.000
	0536- 8-111	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2	EA	2.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	2.000
	0536- 73-	GUARDRAIL REMOVAL	LF	102.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000

Call Order: 006 Proposal: T3954

ALT	Item	Description	Unit	Quantity
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	7,464.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	692.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.327
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.327
Section 0003 Signing				
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	33.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44905415201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.329
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.062
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.165
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.023
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.011
	0713-103-281	PERMANENT TAPE, YELLOW, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	0.011