

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	CT250730	Call Order: 013	Proposal: T4720	District:04
Counties:	PALM BEACH			
Road Name:	I-95 RAMP			
Limits:	AT SR 704 (OKEECHOBEE BLVD), SR 786 (PGA BLVD) AND SR 706 (INDIANTTOWN RD)			
Project(s):	44928015201(*)	Federal Aid No: D424089B		
Total Roadway Length:	0.902 Miles	Contract Days:	118	
Total Bridge Length:	0.000 Miles	Letting Date:	07/30/25	
Total Proposal Length:	0.902 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days	
Proposal Budget Estimate:	\$1,576,133.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of , but are not limited to, MOT (standard, traffic officer), erosion control (sediment barrier, inlet protection), clearing (tree protection), earthwork (slope regrading), asphalt (milling, resurfacing), guardrail (installation, end treatments, removal), pavement markings (painted, thermoplastic, raised marker), high friction surface course, signing (single post, removals), enhanced sign assembly (solar powered, barrier mounted, beacon), lighting (luminaire, bracket arm, pole complete, conductors, cable distribution), electrical power service (meter, service wire, disconnect, concrete pole), load center (rework), conduit, pull/splice box, and sod along I-95 Loop Ramps at SR-704 (Okeechobee Blvd.), SR-786 (PGA Blvd.) and SR-706 (Indiantown Road), for 0.902 miles in Palm Beach County.

Call Order: 013 Proposal: T4720

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44928015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44928015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	260.000
	0102- 60-	WORK ZONE SIGN	ED	2,820.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20,688.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	4,500.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	168.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	488.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	472.000
	0102-115-	TYPE III BARRICADE	ED	376.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,841.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000
	0107- 1-	LITTER REMOVAL	AC	141.690
	0107- 2-	MOWING	AC	111.280
	0110- 1- 1	CLEARING & GRUBBING (44928015201)	LS	1.000
	0110- 21-	TREE PROTECTION BARRIER	LF	44.000
	0120- 6-	EMBANKMENT	CY	5.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	3,613.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	6,453.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76	TN	929.800
	-22			

Call Order: 013 Proposal: T4720

ALT	Item	Description	Unit	Quantity
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	19.900
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	213.000
	0536- 73-	GUARDRAIL REMOVAL	LF	251.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	604.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.872
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.107
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	68.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	16.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	14.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	6.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.818
	0908-333-100	HIGH FRICTION SURFACE COURSE	SY	10,066.000
	0999- 16-	PARTNERING, DO NOT BID (44928015201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44928015201)	LS	1.000
Section 0002 Signing				
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	2.000
	0700-142-472	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I BARRIER SIDE MOUNT, W/EDS AND BEACON, 12-20 SF OF STATIC SIGN PANELS	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	343.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44928015201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.107
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	68.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	16.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	15.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	8.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	48.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.872
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.818
Section 0003 Lighting				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	613.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000

Call Order: 013 Proposal: T4720

ALT	Item	Description	Unit	Quantity
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	150.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	2,061.000
	0715- 5- 21	LUMINAIRE & BRACKET ARM, REPLACE LUMINAIRE AND ARM ON EXISTING POLE	EA	4.000
	0715- 7- 21	LOAD CENTER, REWORK, SECONDARY VOLTAGE	EA	1.000
	0715- 61-252	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 35' MOUNTING HEIGHT, 15' ARM LENGTH	EA	1.000
	0715- 61-452	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 45' MOUNTING HEIGHT, 15' ARM LENGTH	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	7.000
Section 0004 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	118.000