Vendor Ranking

Letting: CT210127 January 27, 2021 10:30 AM **Call Order:** 027 **Contract:** T5715
District: District 5 **Counties:** OSCEOLA **Fed Aid No:** D520034B
Contract Time: 430 AVAILABLE DAYS **Project(s):** 44418715201 (*)
Contract Desc: CR 532

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	ATLANTIC CIVIL CONSTRUCTORS CORP	Responsive	Winning bid	$8,989,132.71	100.00%
2	SOUTHLAND CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$9,307,777.77	103.54%
3	WATSON CIVIL CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$9,405,491.00	104.63%
4	HUBBARD CONSTRUCTION COMPANY	Responsive	Non-Winning Bid	$9,491,219.56	105.59%
5	RANGER CONSTRUCTION INDUSTRIES, INC.	Responsive	Non-Winning Bid	$10,210,320.48	113.59%
6	SEMA CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$10,438,691.32	116.13%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

District: District 5 **Counties:** OSCEOLA **Fed Aid No:** D520034B

Contract Time: 430 AVAILABLE DAYS **Project(s):** 44418715201 (*)

Contract Descr: CR 532

The improvements under this contract consist of reconstruction of the interchange at CR 532 to convert the existing diamond interchange to a
diverging diamond interchange (DDI). The ramps in all quadrants will be modified to accommodate future traffic demand and to tie to the proposed DDI geometry. Additionally, closed drainage will be added to the curb and gutter sections, and the stormwater ponds will be modified as necessary for the proposed roadway improvements. The I-4 bridge over CR 532 will remain, however, the slope abutment will be cut back to accommodate the proposed sidewalk. Lighting, ITS and signalization improvements will also be provided to facilitate the DDI operational requirements. Lastly, a directional median opening will be constructed at the intersection of CR 532 and Goodman Rd.

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0005 0101 1 MOBILIZATION 44418715201 (1.000) LS	738,683.02000	738,683.02	920,000.00000	920,000.00	940,000.00000	940,000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 44418715201 (430.000) DA (LS)	635,322.74000	635,322.74	591,000.00000	591,000.00	300,000.00000	300,000.00
0015 0102 2200 SPECIAL DETOUR- TEMPORARY PAVEMENT 44418715201 (2649.000) SY (LS)	119,725.68000	119,725.68	70,000.00000	70,000.00	120,000.00000	120,000.00
0017 0102 2300 SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (883.000) CY (LS)	233,123.54000	233,123.54	58,000.00000	58,000.00	197,502.27000	197,502.27
0020 0102 14 TRAFFIC CONTROL OFFICER 32.000 HR	65.32000	2,090.24	88.00000	2,816.00	67.00000	2,144.00
0025 0102 60 WORK ZONE SIGN 151,494.000 ED	0.18000	27,268.92	0.21000	31,813.74	0.26000	39,388.44

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Roadway						
0030 0102 71 13 — 1,220.000 LF TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	24.12000	29,426.40	26.60000	32,452.00	30.00000	36,600.00
0035 0102 71 15 — 4,900.000 LF TEMPORARY BARRIER, F&I, ANCHORED	18.09000	88,641.00	19.95000	97,755.00	25.00000	122,500.00
0040 0102 74 1 — 97,737.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.90000	87,963.30	0.11000	10,751.07	0.15000	14,660.55
0041 0102 78 — 862.000 EA TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	2.86000	2,465.32	3.55000	3,060.10	5.00000	4,310.00
0045 0102 89 1 — 5.000 LO TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	954.71000	4,773.55	752.48000	3,762.40	1,000.00000	5,000.00
0050 0102 99 — 7,776.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	8.79000	68,351.04	8.87000	68,973.12	10.00000	77,760.00
0055 0102104 — 648.000 ED TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	35.84000	23,224.32	165.12000	106,997.76	22.00000	14,256.00
0060 0102107 1 — 648.000 ED TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	22.17000	14,366.16	1.11000	719.28	20.00000	12,960.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0065 0104 10 3 SEDIMENT BARRIER 10,983.000 LF	1.27000	13,948.41	0.72000	7,907.76	1.50000	16,474.50
0070 0104 11 FLOATING TURBIDITY BARRIER 388.000 LF	8.70000	3,375.60	9.40000	3,647.20	10.50000	4,074.00
0075 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC 429.000 LF	4.78000	2,050.62	3.80000	1,630.20	4.50000	1,930.50
0080 0104 18 INLET PROTECTION SYSTEM 41.000 EA	79.54000	3,261.14	160.00000	6,560.00	100.00000	4,100.00
0085 0107 1 LITTER REMOVAL 466.720 AC	82.99000	38,733.09	29.00000	13,534.88	88.00000	41,071.36
0090 0107 2 MOWING 163.450 AC	163.45000	26,715.90	73.00000	11,931.85	95.00000	15,527.75
0095 0110 1 1 CLEARING & GRUBBING 44418715201 (15.560) AC (LS)	325,718.62000	325,718.62	141,344.60000	141,344.60	180,000.00000	180,000.00
0100 0110 4 10 REMOVAL OF EXISTING CONCRETE 1,268.000 SY	19.49000	24,713.32	17.00000	21,556.00	15.00000	19,020.00
0105 0120 1 REGULAR EXCAVATION 37,920.100 CY	6.72000	254,823.07	5.00000	189,600.50	16.50000	625,681.65

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0110 0120 4 SUBSOIL EXCAVATION 767.200 CY	28.51000	21,872.87	17.20000	13,195.84	28.00000	21,481.60
0115 0120 6 EMBANKMENT 13,588.400 CY	8.06000	109,522.50	9.40000	127,730.96	5.00000	67,942.00
0120 0160 4 TYPE B STABILIZATION 21,659.000 SY	11.51000	249,295.09	18.90000	409,355.10	9.00000	194,931.00
0125 0285701 OPTIONAL BASE, BASE GROUP 01 TYPE B 12.5 ONLY 2,768.000 SY	20.98000	58,072.64	26.70000	73,905.60	25.00000	69,200.00
0130 0285707 OPTIONAL BASE, BASE GROUP 07 TYPE B 12.5 ONLY 1,830.000 SY	28.63000	52,392.90	32.10000	58,743.00	38.50000	70,455.00
0135 0285709 OPTIONAL BASE, BASE GROUP 09 TYPE B 12.5 ONLY 9,180.000 SY	29.81000	273,655.80	36.35000	333,693.00	33.50000	307,530.00
0140 0285710 OPTIONAL BASE, BASE GROUP 10 TYPE B 12.5 ONLY 2,382.000 SY	33.14000	78,939.48	42.50000	101,235.00	42.00000	100,044.00
0145 0285713 OPTIONAL BASE, BASE GROUP 13 TYPE B 12.5 ONLY 1,158.000 SY	42.77000	49,527.66	48.40000	56,047.20	47.00000	54,426.00
0150 0285715 OPTIONAL BASE, BASE GROUP 15 TYPE B 12.5 ONLY 3,967.000 SY	44.77000	177,602.59	57.90000	229,689.30	60.20000	238,813.40

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0155 0327 70 3 MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH 1,371.000 SY	10.05000	13,778.55	6.65000	9,117.15	8.50000	11,653.50
0160 0327 70 4 MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH 5,495.000 SY	10.05000	55,224.75	3.77000	20,716.15	6.00000	32,970.00
0165 0327 70 6 MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH 3,846.000 SY	10.05000	38,652.30	4.32000	16,614.72	6.50000	24,999.00
0170 0327 70 7 MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH 2,519.000 SY	10.05000	25,315.95	4.32000	10,882.08	8.75000	22,041.25
0175 0327 70 10 MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH 1,415.000 SY	10.05000	14,220.75	6.87000	9,721.05	9.00000	12,735.00
0180 0327 70 17 MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH 546.000 SY	10.05000	5,487.30	13.85000	7,562.10	15.00000	8,190.00
0185 0327 70 18 MILLING EXISTING ASPHALT PAVEMENT, 5 1/2" AVG DEPTH 3,674.000 SY	10.05000	36,923.70	4.10000	15,063.40	9.60000	35,270.40
0190 0327 70 27 MILLING EXISTING ASPHALT PAVEMENT, 5 3/4" AVG DEPTH 1,486.000 SY	10.05000	14,934.30	6.87000	10,208.82	8.50000	12,631.00
0195 0334 1 11 SUPERPAVE ASPHALTIC CONC, TRAFFIC A 74.800 TN	150.74000	11,275.35	230.50000	17,241.40	151.65000	11,343.42

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0200 0334 1 13 — 4,822.800 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	135.67000	654,309.28	127.40000	614,424.72	96.65000	466,123.62
0205 0334 1 54 — 1,153.400 TN SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	155.77000	179,665.12	145.00000	167,243.00	116.70000	134,601.78
0210 0337 7 81 — 263.900 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22	165.82000	43,759.90	182.80000	48,240.92	131.20000	34,623.68
0215 0337 7 83 — 2,364.700 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	123.53000	292,111.39	149.00000	352,340.30	112.60000	266,265.22
0220 0337 7 85 — 2,364.700 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22	102.39000	242,121.63	145.00000	342,881.50	112.60000	266,265.22
0225 0339 1 — 9.700 TN MISCELLANEOUS ASPHALT PAVEMENT	189.58000	1,838.93	785.00000	7,614.50	285.00000	2,764.50
0230 0400 0 11 — 140.000 CY CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	1,399.60000	195,944.00	1,500.00000	210,000.00	920.00000	128,800.00
0235 0425 1311 — 6.000 EA INLETS, CURB, TYPE P-1, <10'	7,461.57000	44,769.42	5,919.20000	35,515.20	6,500.00000	39,000.00
0240 0425 1312 — 1.000 EA INLETS, CURB TYPE P-1, >10'	10,658.59000	10,658.59	6,594.94000	6,594.94	9,500.00000	9,500.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0245 0425 1351 INLETS, CURB, TYPE P-5, <10' 1.000 EA	5,103.90000	5,103.90	4,708.58000	4,708.58	5,000.00000	5,000.00
0250 0425 1412 INLETS, CURB, TYPE J-1, >10' 2.000 EA	10,086.24000	20,172.48	7,439.26000	14,878.52	11,500.00000	23,000.00
0255 0425 1451 INLETS, CURB, TYPE J-5, <10' 4.000 EA	8,974.13000	35,896.52	11,490.11000	45,960.44	11,000.00000	44,000.00
0260 0425 1461 INLETS, CURB, TYPE J-6, <10' 2.000 EA	8,644.67000	17,289.34	10,117.78000	20,235.56	7,800.00000	15,600.00
0265 0425 1521 INLETS, DT BOT, TYPE C,<10' 6.000 EA	4,492.64000	26,955.84	5,241.71000	31,450.26	3,500.00000	21,000.00
0270 0425 1541 INLETS, DT BOT, TYPE D, <10' 3.000 EA	4,801.99000	14,405.97	5,561.44000	16,684.32	3,900.00000	11,700.00
0275 0425 1549 INLETS, DT BOT, TYPE D, MODIFY 1.000 EA	3,799.88000	3,799.88	6,960.32000	6,960.32	5,500.00000	5,500.00
0280 0425 1711 INLETS, GUTTER, TYPE V, <10' 1.000 EA	5,043.82000	5,043.82	5,596.51000	5,596.51	4,000.00000	4,000.00
0285 0425 2 43 MANHOLES, P-7, PARTIAL 1.000 EA	3,286.20000	3,286.20	2,910.24000	2,910.24	3,000.00000	3,000.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0290 0425 2 62 MANHOLES, P-8, >10' 2.000 EA	5,640.90000	11,281.80	3,887.59000	7,775.18	5,000.00000	10,000.00
0295 0425 2 63 MANHOLES, P-8, PARTIAL 2.000 EA	3,357.00000	6,714.00	2,910.21000	5,820.42	3,000.00000	6,000.00
0300 0425 2 91 MANHOLES, J-8, <10' 3.000 EA	6,059.81000	18,179.43	4,949.29000	14,847.87	7,000.00000	21,000.00
0305 0425 2 92 MANHOLES, J-8, >10' 2.000 EA	8,827.35000	17,654.70	5,434.08000	10,868.16	8,500.00000	17,000.00
0310 0425 5 1 MANHOLE, ADJUST, UTILITIES 1.000 EA	1,052.83000	1,052.83	1,400.00000	1,400.00	1,000.00000	1,000.00
0315 0425 6 VALVE BOXES, ADJUST 6.000 EA	512.73000	3,076.38	600.00000	3,600.00	750.00000	4,500.00
0320 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD 17.000 LF	162.54000	2,763.18	234.16000	3,980.72	150.00000	2,550.00
0325 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD 713.000 LF	172.11000	122,714.43	155.25000	110,693.25	105.00000	74,865.00
0330 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD 734.000 LF	270.22000	198,341.48	317.47000	233,022.98	110.00000	80,740.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0335 0430175130 498.000 LF PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	293.91000	146,367.18	188.99000	94,117.02	170.00000	84,660.00
0340 0430175136 47.000 LF PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	330.03000	15,511.41	322.49000	15,157.03	285.00000	13,395.00
0345 0430175218 54.000 LF PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	250.90000	13,548.60	176.56000	9,534.24	180.00000	9,720.00
0346 0430830 32.200 CY PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	352.77000	11,359.19	419.00000	13,491.80	330.00000	10,626.00
0350 0430982123 1.000 EA MITERED END SECTION, OPTIONAL ROUND, 15" CD	1,402.73000	1,402.73	1,220.00000	1,220.00	1,100.00000	1,100.00
0355 0430982125 3.000 EA MITERED END SECTION, OPTIONAL ROUND, 18" CD	1,456.67000	4,370.01	1,180.00000	3,540.00	1,150.00000	3,450.00
0360 0430982129 5.000 EA MITERED END SECTION, OPTIONAL ROUND, 24" CD	1,647.07000	8,235.35	1,395.00000	6,975.00	1,315.00000	6,575.00
0365 0430982133 2.000 EA MITERED END SECTION, OPTIONAL ROUND, 30" CD	2,323.22000	4,646.44	2,450.00000	4,900.00	2,500.00000	5,000.00
0370 0515 1 1 276.000 LF PIPE HANDRAIL - GUIDERAIL, STEEL	50.25000	13,869.00	55.00000	15,180.00	56.50000	15,594.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0375 0520 1 7 CONCRETE CURB & GUTTER, TYPE E 816.000 LF	34.65000	28,274.40	20.50000	16,728.00	64.50000	52,632.00
0380 0520 1 10 CONCRETE CURB & GUTTER, TYPE F 4,629.000 LF	27.93000	129,287.97	20.90000	96,746.10	45.00000	208,305.00
0385 0520 2 1 CONCRETE CURB, TYPE A 1,311.000 LF	23.48000	30,782.28	20.60000	27,006.60	54.00000	70,794.00
0390 0520 2 4 CONCRETE CURB, TYPE D 276.000 LF	19.82000	5,470.32	18.80000	5,188.80	57.00000	15,732.00
0395 0520 6 SHOULDER GUTTER- CONCRETE 155.000 LF	24.46000	3,791.30	18.80000	2,914.00	55.00000	8,525.00
0400 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH 1,112.000 SY	55.95000	62,216.40	46.50000	51,708.00	130.00000	144,560.00
0401 0521 1 11 MEDIAN CONCRETE BARRIER, 38" HEIGHT 205.000 LF	121.76000	24,960.80	345.00000	70,725.00	280.00000	57,400.00
0402 0521 72 43 SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER 10.000 LF	284.07000	2,840.70	350.00000	3,500.00	440.00000	4,400.00
0405 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 2,490.000 SY	32.65000	81,298.50	35.40000	88,146.00	60.00000	149,400.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0410 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 109.000 SY	97.84000	10,664.56	48.70000	5,308.30	95.00000	10,355.00
0415 0527 2 DETECTABLE WARNINGS 291.000 SF	17.95000	5,223.45	39.00000	11,349.00	25.00000	7,275.00
0420 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING 6.000 TN	260.44000	1,562.64	153.00000	918.00	625.00000	3,750.00
0425 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 92.000 LF	16.08000	1,479.36	17.70000	1,628.40	18.70000	1,720.40
0430 0536 1 1 GUARDRAIL -ROADWAY, GENERAL TL-3 182.000 LF	20.10000	3,658.20	22.10000	4,022.20	23.50000	4,277.00
0435 0536 8111 GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2 2.000 EA	2,411.90000	4,823.80	2,650.00000	5,300.00	2,800.00000	5,600.00
0440 0536 73 GUARDRAIL REMOVAL 193.000 LF	2.01000	387.93	2.20000	424.60	2.40000	463.20
0445 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 1.000 EA	1,205.95000	1,205.95	1,320.00000	1,320.00	1,400.00000	1,400.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0450 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 3.000 EA	3,014.88000	9,044.64	3,320.00000	9,960.00	3,500.00000	10,500.00
0455 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD 805.000 LF	8.04000	6,472.20	8.87000	7,140.35	9.00000	7,245.00
0460 0570 1 1 PERFORMANCE TURF 20,331.000 SY	3.60000	73,191.60	1.00000	20,331.00	4.00000	81,324.00
0465 0570 1 2 PERFORMANCE TURF, SOD 23,919.000 SY	3.87000	92,566.53	4.40000	105,243.60	6.00000	143,514.00
0470 0591 1600 IRRIGATION SLEEVE, 6" DIAMETER 579.000 LF	28.38000	16,432.02	21.10000	12,216.90	30.00000	17,370.00
0475 0710 11101 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" 7.342 GM	1,004.96000	7,378.42	1,384.90000	10,167.94	1,100.00000	8,076.20
0480 0710 11103 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12" 0.103 GM	2,411.90000	248.43	2,689.90000	277.06	2,500.00000	257.50
0485 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" 583.000 LF	1.09000	635.47	2.44000	1,422.52	1.15000	670.45

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0490 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE 1.298 GM	401.98000	521.77	605.76000	786.28	435.00000	564.63
0495 0710 11180 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE 143.000 LF	2.01000	287.43	5.54000	792.22	2.15000	307.45
0500 0710 11201 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" 5.010 GM	1,004.96000	5,034.85	1,385.28000	6,940.25	1,100.00000	5,511.00
0505 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 44418715201 (1.000) LS	78,000.00000	78,000.00	78,000.00000	78,000.00	78,000.00000	78,000.00
0001 Roadway Section Totals:		**$7,141,421.75**		**$7,053,109.95**		**$7,040,065.44**
SECTION: 0002 Signing						
0510 0634 4151 SPAN WIRE ASSEMBLY, F&I, TWO POINT, PERPENDICULAR 1.000 PI	5,062.98000	5,062.98	3,517.49000	3,517.49	6,700.00000	6,700.00
0520 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF 44.000 AS	343.70000	15,122.80	332.47000	14,628.68	500.00000	22,000.00
0525 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF 17.000 AS	1,031.09000	17,528.53	997.40000	16,955.80	1,500.00000	25,500.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0530 0700 1 14 SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF 2.000 AS	1,947.61000	3,895.22	1,883.98000	3,767.96	2,500.00000	5,000.00
0535 0700 1 21 SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF 1.000 AS	1,718.48000	1,718.48	1,662.33000	1,662.33	1,675.00000	1,675.00
0540 0700 1 50 SINGLE POST SIGN, RELOCATE 4.000 AS	859.24000	3,436.96	831.17000	3,324.68	850.00000	3,400.00
0545 0700 1 60 SINGLE POST SIGN, REMOVE 36.000 AS	28.64000	1,031.04	27.71000	997.56	97.00000	3,492.00
0550 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF 2.000 AS	4,009.78000	8,019.56	3,878.77000	7,757.54	6,200.00000	12,400.00
0555 0700 2 15 MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF 2.000 AS	4,582.61000	9,165.22	4,432.88000	8,865.76	6,000.00000	12,000.00
0560 0700 2 16 MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF 2.000 AS	8,019.57000	16,039.14	7,757.54000	15,515.08	9,800.00000	19,600.00
0565 0700 2 50 MULTI- POST SIGN, GROUND MOUNT, RELOCATE 2.000 AS	5,728.26000	11,456.52	5,541.10000	11,082.20	6,200.00000	12,400.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0570 0700 2 60 MULTI- POST SIGN, REMOVE 2.000 AS	916.52000	1,833.04	886.58000	1,773.16	890.00000	1,780.00
0575 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF 5.000 EA	499.50000	2,497.50	526.41000	2,632.05	670.00000	3,350.00
0580 0700 3202 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF 1.000 EA	515.54000	515.54	1,055.03000	1,055.03	1,030.00000	1,030.00
0585 0700 3206 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF 4.000 EA	4,238.92000	16,955.68	4,580.27000	18,321.08	4,200.00000	16,800.00
0590 0700 4114 OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT 2.000 EA	67,042.80000	134,085.60	85,000.00000	170,000.00	85,000.00000	170,000.00
0595 0700 13 12 RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 2' 16.000 EA	57.28000	916.48	64.83000	1,037.28	60.00000	960.00
0600 0705 10 3 OBJECT MARKER, TYPE 3 4.000 EA	103.11000	412.44	99.74000	398.96	320.00000	1,280.00
0605 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR 4.000 EA	63.01000	252.04	60.95000	243.80	61.50000	246.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0610 0710 11190 — 19.000 SF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	1.96000	37.24	2.22000	42.18	2.15000	40.85
0615 0710 11290 — 114.000 SF PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	1.96000	223.44	2.22000	253.08	2.15000	245.10
0620 0710 90 — (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44418715201	14,225.19000	14,225.19	18,285.63000	18,285.63	15,000.00000	15,000.00
0625 0711 11124 — 1,113.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	2.51000	2,793.63	3.32000	3,695.16	2.55000	2,838.15
0630 0711 11125 — 263.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	3.52000	925.76	4.65000	1,222.95	3.55000	933.65
0635 0711 11141 — 0.640 GM THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	1,748.81000	1,119.24	1,773.14000	1,134.81	1,800.00000	1,152.00
0640 0711 11160 — 15.000 EA THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	150.74000	2,261.10	193.94000	2,909.10	151.60000	2,274.00
0645 0711 11170 — 89.000 EA THERMOPLASTIC, STANDARD, WHITE, ARROW	59.29000	5,276.81	57.63000	5,129.07	59.60000	5,304.40

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0650 0711 11180 THERMOPLASTIC, STANDARD, WHITE, YIELD LINE 30.000 LF	15.07000	452.10	6.65000	199.50	15.16000	454.80
0655 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON 627.000 LF	2.51000	1,573.77	3.32000	2,081.64	2.55000	1,598.85
0660 0711 14123 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK 801.000 LF	6.78000	5,430.78	7.76000	6,215.76	6.85000	5,486.85
0665 0711 14125 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK 543.000 LF	13.57000	7,368.51	15.52000	8,427.36	13.65000	7,411.95
0670 0711 14660 THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD 4.000 EA	1,934.55000	7,738.20	720.34000	2,881.36	1,945.00000	7,780.00
0675 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 2.402 GM	3,517.35000	8,448.67	5,259.66000	12,633.70	3,532.50000	8,485.07
0680 0711 16102 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" 0.617 GM	4,723.31000	2,914.28	7,417.52000	4,576.61	4,695.00000	2,896.82
0685 0711 16131 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP 0.993 GM	1,256.20000	1,247.41	1,381.09000	1,371.42	1,260.00000	1,251.18

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0690 0711 16201 — 1.487 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	3,517.35000	5,230.30	5,239.26000	7,790.78	3,520.00000	5,234.24
0695 0711 16202 — 0.199 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	4,683.11000	931.94	7,163.37000	1,425.51	4,500.00000	895.50
0002 Signing Section Totals:		**$318,143.14**		**$363,812.06**		**$388,896.41**
SECTION: 0003 Lighting						
0700 0630 2 11 — 3,362.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	7.74000	26,021.88	9.75000	32,779.50	13.00000	43,706.00
0705 0630 2 12 — 1,930.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	18.79000	36,264.70	18.29000	35,299.70	23.00000	44,390.00
0710 0635 2 11 — 40.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	760.22000	30,408.80	1,419.63000	56,785.20	1,500.00000	60,000.00
0715 0639 2 1 — 25.000 LF ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	21.10000	527.50	25.49000	637.25	9.50000	237.50
0720 0715 1 12 — 19,234.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	1.31000	25,196.54	1.88000	36,159.92	1.40000	26,927.60

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Lighting						
0725 0715 1 13 LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2 3,429.000 LF	2.13000	7,303.77	2.38000	8,161.02	2.65000	9,086.85
0730 0715 1 60 LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS 2,372.000 LF	0.66000	1,565.52	0.94000	2,229.68	0.75000	1,779.00
0735 0715 4 13 LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT 27.000 EA	5,080.30000	137,168.10	6,400.00000	172,800.00	6,000.00000	162,000.00
0740 0715 7 21 LOAD CENTER, REWORK, SECONDARY VOLTAGE 1.000 EA	2,394.25000	2,394.25	2,600.00000	2,600.00	2,300.00000	2,300.00
0745 0715 19 13 HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120' 1.000 EA	78,820.21000	78,820.21	94,000.00000	94,000.00	88,000.00000	88,000.00
0750 0715 19 60 HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION 1.000 EA	8,578.33000	8,578.33	9,500.00000	9,500.00	16,000.00000	16,000.00
0755 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL 27.000 EA	403.44000	10,892.88	674.91000	18,222.57	600.00000	16,200.00
0760 0715500 2 POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST 1.000 EA	287.42000	287.42	518.65000	518.65	1,200.00000	1,200.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Lighting						
0003 Lighting Section Totals:		**$365,429.90**		**$469,693.49**		**$471,826.95**
SECTION: 0004 Signalization						
0765 0630 2 11 855.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	17.18000	14,688.90	31.58000	27,000.90	27.00000	23,085.00
0770 0630 2 12 940.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	43.53000	40,918.20	64.83000	60,940.20	53.00000	49,820.00
0775 0632 7 1 2.000 PI SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	7,148.87000	14,297.74	11,200.00000	22,400.00	18,500.00000	37,000.00
0780 0632 7 6 2.000 PI SIGNAL CABLE, REMOVE-INTERSECTION	989.84000	1,979.68	1,636.84000	3,273.68	870.00000	1,740.00
0785 0633 2 32 12.000 EA FIBER OPTIC CONNECTION, INSTALL, TERMINATION	52.13000	625.56	93.64000	1,123.68	100.00000	1,200.00
0790 0633 3 12 1.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	148.93000	148.93	62.62000	62.62	67.00000	67.00
0795 0633 3 16 1.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	2,577.72000	2,577.72	1,530.45000	1,530.45	1,625.00000	1,625.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0800 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE 43.000 EA	746.97000	32,119.71	739.18000	31,784.74	1,435.00000	61,705.00
0805 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE 1.000 EA	1,461.85000	1,461.85	1,798.64000	1,798.64	2,100.00000	2,100.00
0810 0639 2 1 ELECTRICAL SERVICE WIRE, FURNISH & INSTALL 170.000 LF	3.12000	530.40	5.54000	941.80	7.50000	1,275.00
0815 0639 2 6 ELECTRICAL SERVICE WIRE, REMOVE 250.000 LF	0.74000	185.00	3.71000	927.50	1.00000	250.00
0820 0639 3 11 ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT 1.000 EA	902.77000	902.77	1,100.00000	1,100.00	2,300.00000	2,300.00
0825 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE 1.000 EA	737.80000	737.80	1,500.00000	1,500.00	1,830.00000	1,830.00
0826 0641 2 18 PRESTRESSED CONCRETE POLE, F&I, TYPE P-VIII 2.000 EA	9,165.22000	18,330.44	23,000.00000	46,000.00	31,000.00000	62,000.00
0830 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL 12.000 EA	1,981.98000	23,783.76	1,550.00000	18,600.00	1,400.00000	16,800.00
0835 0646 1 60 ALUMINUM SIGNALS POLE, REMOVE 1.000 EA	164.97000	164.97	287.00000	287.00	280.00000	280.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0840 0649 21 3 — 1.000 EA STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	35,102.80000	35,102.80	36,000.00000	36,000.00	40,000.00000	40,000.00
0845 0649 21 6 — 2.000 EA STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	40,258.24000	80,516.48	42,000.00000	84,000.00	46,000.00000	92,000.00
0850 0649 21 10 — 3.000 EA STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	42,549.54000	127,648.62	49,000.00000	147,000.00	48,000.00000	144,000.00
0855 0649 21 15 — 1.000 EA STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	46,903.02000	46,903.02	56,000.00000	56,000.00	54,000.00000	54,000.00
0860 0649 26 3 — 4.000 EA STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT	5,247.09000	20,988.36	2,540.00000	10,160.00	4,250.00000	17,000.00
0865 0650 1 14 — 15.000 AS VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	934.85000	14,022.75	1,026.21000	15,393.15	1,500.00000	22,500.00
0870 0653 1 11 — 12.000 AS PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	600.32000	7,203.84	650.53000	7,806.36	575.00000	6,900.00
0875 0660 4 11 — 1.000 EA VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	25,291.43000	25,291.43	26,900.00000	26,900.00	15,200.00000	15,200.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0880 0660 4 12 — 7.000 EA VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	3,528.61000	24,700.27	3,800.00000	26,600.00	6,750.00000	47,250.00
0885 0663 1121 — 1.000 EA SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	5,127.94000	5,127.94	7,126.96000	7,126.96	5,700.00000	5,700.00
0890 0663 1122 — 1.000 EA SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	4,096.85000	4,096.85	6,648.21000	6,648.21	8,000.00000	8,000.00
0895 0665 1 12 — 12.000 EA PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	1,748.27000	20,979.24	111.93000	1,343.16	1,263.00000	15,156.00
0900 0670 5141 — 1.000 AS TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL, MODEL 2070, 1 PREEMPTION	27,426.93000	27,426.93	31,000.00000	31,000.00	31,100.00000	31,100.00
0905 0670 5600 — 1.000 AS TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	824.87000	824.87	1,500.00000	1,500.00	2,025.00000	2,025.00
0910 0682 1113 — 2.000 EA ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	7,240.53000	14,481.06	7,400.00000	14,800.00	7,500.00000	15,000.00
0915 0684 1 1 — 1.000 EA MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	2,577.72000	2,577.72	3,100.00000	3,100.00	3,500.00000	3,500.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0920 0684 5 1 MEDIA CONVERTER, FURNISH & INSTALL 1.000 EA	400.98000	400.98	812.32000	812.32	900.00000	900.00
0925 0685 1 12 UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION 1.000 EA	6,159.03000	6,159.03	11,000.00000	11,000.00	3,250.00000	3,250.00
0930 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF 12.000 EA	508.67000	6,104.04	584.03000	7,008.36	915.00000	10,980.00
0935 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF 3.000 EA	3,519.45000	10,558.35	3,700.00000	11,100.00	6,500.00000	19,500.00
0004 Signalization Section Totals:		**$634,568.01**		**$724,569.73**		**$817,038.00**
SECTION: 0005 Intelligent Transportation System						
0940 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH 6,895.000 LF	6.87000	47,368.65	13.30000	91,703.50	12.00000	82,740.00
0945 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE 780.000 LF	16.04000	12,511.20	24.93000	19,445.40	22.00000	17,160.00
0950 0630 2 14 CONDUIT, FURNISH & INSTALL, ABOVEGROUND 210.000 LF	22.00000	4,620.00	25.49000	5,352.90	33.00000	6,930.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
0955 0633 1121 2,334.000 LF FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	2.23000	5,204.82	2.94000	6,861.96	3.15000	7,352.10
0960 0633 1122 135.000 LF FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	2.37000	319.95	3.10000	418.50	3.35000	452.25
0965 0633 1123 11,034.000 LF FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	2.46000	27,143.64	3.32000	36,632.88	3.65000	40,274.10
0970 0633 1620 1,679.000 LF FIBER OPTIC CABLE, REMOVE, UNDERGROUND	1.32000	2,216.28	0.94000	1,578.26	1.05000	1,762.95
0975 0633 2 31 108.000 EA FIBER OPTIC CONNECTION, INSTALL, SPLICE	40.10000	4,330.80	43.77000	4,727.16	47.00000	5,076.00
0980 0633 3 11 5.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	1,134.20000	5,671.00	905.42000	4,527.10	975.00000	4,875.00
0985 0633 3 12 2.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	1,444.35000	2,888.70	62.61000	125.22	67.00000	134.00
0990 0633 3 13 24.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	28.64000	687.36	68.71000	1,649.04	73.00000	1,752.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
0995 0633 3 15 — 6.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	1,718.48000	10,310.88	2,966.70000	17,800.20	3,200.00000	19,200.00
1000 0633 3 17 — 2.000 EA FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	114.57000	229.14	106.39000	212.78	115.00000	230.00
1005 0633 3 52 — 1.000 EA FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	144.35000	144.35	12.74000	12.74	155.00000	155.00
1010 0633 8 1 — 981.000 LF MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	4.87000	4,777.47	2.77000	2,717.37	6.80000	6,670.80
1015 0635 2 11 — 19.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	719.47000	13,669.93	739.18000	14,044.42	1,600.00000	30,400.00
1020 0635 2 12 — 19.000 EA PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	1,425.19000	27,078.61	1,840.75000	34,974.25	2,300.00000	43,700.00
1025 0635 2 13 — 5.000 EA PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	2,153.83000	10,769.15	3,704.78000	18,523.90	3,700.00000	18,500.00
1030 0635 3 40 — 1.000 EA JUNCTION BOX, RELOCATE	719.47000	719.47	2,489.06000	2,489.06	1,200.00000	1,200.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
1035 0639 2 1 — 3,260.000 LF ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	10.43000	34,001.80	15.52000	50,595.20	11.50000	37,490.00
1040 0639 3 11 — 5.000 EA ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	941.73000	4,708.65	1,189.12000	5,945.60	1,750.00000	8,750.00
1045 0641 2 12 — 2.000 EA PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	728.64000	1,457.28	1,507.18000	3,014.36	1,780.00000	3,560.00
1050 0660 7 12 — 2.000 EA VEHICLE DETECTION SYSTEM-WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES	64,408.00000	128,816.00	92,780.14000	185,560.28	83,000.00000	166,000.00
1055 0676 2122 — 2.000 EA ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	6,301.09000	12,602.18	7,795.22000	15,590.44	7,000.00000	14,000.00
1060 0676 2142 — 1.000 EA ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	7,698.79000	7,698.79	11,792.56000	11,792.56	8,500.00000	8,500.00
1065 0676 3 60 — 1.000 EA SMALL EQUIPMENT ENCLOSURE, REMOVE- POST/CABINET TO REMAIN	3,111.62000	3,111.62	654.96000	654.96	650.00000	650.00
1070 0682 1113 — 8.000 EA ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	7,240.53000	57,924.24	7,426.00000	59,408.00	7,500.00000	60,000.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
1075 0682 1600 — 1.000 EA — ITS CCTV CAMERA, REMOVE & DISPOSAL	973.80000	973.80	312.50000	312.50	350.00000	350.00
1080 0684 1 1 — 7.000 EA — MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	4,009.78000	28,068.46	3,179.00000	22,253.00	3,500.00000	24,500.00
1085 0684 6 60 — 1.000 EA — WIRELESS COMMUNICATION DEVICE, REMOVE	155.81000	155.81	312.00000	312.00	450.00000	450.00
1090 0685 1 11 — 3.000 EA — UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	2,456.28000	7,368.84	11,695.00000	35,085.00	5,800.00000	17,400.00
1095 0685 2 1 — 2.000 EA — REMOTE POWER MANAGEMENT UNIT-RPMU, FURNISH AND INSTALL	1,613.08000	3,226.16	1,200.00000	2,400.00	950.00000	1,900.00
1100 0700 6 11 — 6.000 AS — HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, UP TO 12 SF	7,263.44000	43,580.64	4,900.00000	29,400.00	6,980.00000	41,880.00
1105 0700 6 12 — 2.000 AS — HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, 12-20 SF	7,263.44000	14,526.88	4,980.00000	9,960.00	6,375.00000	12,750.00
1110 0700 13 12 — 8.000 EA — RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 2'	85.92000	687.36	64.00000	512.00	115.00000	920.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID Item Description *( ) indicates item is bid as Lump Sum*	Alternate	Quantity Units	(1) ATLANTIC CIVIL CONSTRUCTORS CORP		(2) SOUTHLAND CONSTRUCTION, INC.		(3) WATSON CIVIL CONSTRUCTION, INC.	
			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System								
0005 Intelligent Transportation System Section Totals:				**$529,569.91**		**$696,592.54**		**$687,664.20**
Contract Grand Totals:				**$8,989,132.71**		**$9,307,777.77**		**9,405,491.00**

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0005 0101 1 MOBILIZATION 44418715201 (1.000) LS	940,000.00000	940,000.00	1,269,000.00000	1,269,000.00	950,000.00000	950,000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 44418715201 (430.000) DA (LS)	738,000.00000	738,000.00	614,000.00000	614,000.00	250,000.00000	250,000.00
0015 0102 2200 SPECIAL DETOUR- TEMPORARY PAVEMENT 44418715201 (2649.000) SY (LS)	194,000.00000	194,000.00	72,000.00000	72,000.00	250,000.00000	250,000.00
0017 0102 2300 SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (883.000) CY (LS)	29,000.00000	29,000.00	64,200.00000	64,200.00	35,000.00000	35,000.00
0020 0102 14 TRAFFIC CONTROL OFFICER 32.000 HR	75.00000	2,400.00	93.80000	3,001.60	80.00000	2,560.00
0025 0102 60 WORK ZONE SIGN 151,494.000 ED	0.18000	27,268.92	0.20000	30,298.80	0.20000	30,298.80
0030 0102 71 13 TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE 1,220.000 LF	24.43000	29,804.60	30.00000	36,600.00	25.00000	30,500.00
0035 0102 71 15 TEMPORARY BARRIER, F&I, ANCHORED 4,900.000 LF	18.32000	89,768.00	22.50000	110,250.00	19.00000	93,100.00
0040 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 97,737.000 ED	0.09000	8,796.33	0.10000	9,773.70	0.10000	9,773.70

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0041 0102 78 TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER 862.000 EA	2.99000	2,577.38	3.55000	3,060.10	5.00000	4,310.00
0045 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION 5.000 LO	966.92000	4,834.60	4,190.00000	20,950.00	820.00000	4,100.00
0050 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 7,776.000 ED	8.91000	69,284.16	10.95000	85,147.20	8.50000	66,096.00
0055 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION 648.000 ED	10.06000	6,518.88	100.00000	64,800.00	11.00000	7,128.00
0060 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION 648.000 ED	9.86000	6,389.28	62.50000	40,500.00	10.00000	6,480.00
0065 0104 10 3 SEDIMENT BARRIER 10,983.000 LF	0.65000	7,138.95	1.35000	14,827.05	0.80000	8,786.40
0070 0104 11 FLOATING TURBIDITY BARRIER 388.000 LF	8.50000	3,298.00	13.35000	5,179.80	8.00000	3,104.00
0075 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC 429.000 LF	3.50000	1,501.50	5.35000	2,295.15	3.90000	1,673.10

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0080 0104 18 INLET PROTECTION SYSTEM 41.000 EA	65.00000	2,665.00	156.20000	6,404.20	68.00000	2,788.00
0085 0107 1 LITTER REMOVAL 466.720 AC	25.00000	11,668.00	28.25000	13,184.84	88.00000	41,071.36
0090 0107 2 MOWING 163.450 AC	90.00000	14,710.50	59.50000	9,725.28	350.00000	57,207.50
0095 0110 1 1 CLEARING & GRUBBING 44418715201 (15.560) AC (LS)	398,000.00000	398,000.00	100,000.00000	100,000.00	1,400,050.00000	1,400,050.00
0100 0110 4 10 REMOVAL OF EXISTING CONCRETE 1,268.000 SY	33.27000	42,186.36	27.65000	35,060.20	9.50000	12,046.00
0105 0120 1 REGULAR EXCAVATION 37,920.100 CY	11.05000	419,017.11	3.70000	140,304.37	5.00000	189,600.50
0110 0120 4 SUBSOIL EXCAVATION 767.200 CY	25.56000	19,609.63	24.05000	18,451.16	25.00000	19,180.00
0115 0120 6 EMBANKMENT 13,588.400 CY	18.00000	244,591.20	1.65000	22,420.86	25.00000	339,710.00
0120 0160 4 TYPE B STABILIZATION 21,659.000 SY	9.31000	201,645.29	8.60000	186,267.40	9.00000	194,931.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0125 0285701 OPTIONAL BASE, BASE GROUP 01 TYPE B 12.5 ONLY 2,768.000 SY	25.60000	70,860.80	26.00000	71,968.00	28.00000	77,504.00
0130 0285707 OPTIONAL BASE, BASE GROUP 07 TYPE B 12.5 ONLY 1,830.000 SY	31.10000	56,913.00	40.15000	73,474.50	42.00000	76,860.00
0135 0285709 OPTIONAL BASE, BASE GROUP 09 TYPE B 12.5 ONLY 9,180.000 SY	35.10000	322,218.00	34.85000	319,923.00	37.00000	339,660.00
0140 0285710 OPTIONAL BASE, BASE GROUP 10 TYPE B 12.5 ONLY 2,382.000 SY	40.90000	97,423.80	43.95000	104,688.90	46.00000	109,572.00
0145 0285713 OPTIONAL BASE, BASE GROUP 13 TYPE B 12.5 ONLY 1,158.000 SY	46.70000	54,078.60	49.20000	56,973.60	51.00000	59,058.00
0150 0285715 OPTIONAL BASE, BASE GROUP 15 TYPE B 12.5 ONLY 3,967.000 SY	55.70000	220,961.90	63.50000	251,904.50	65.00000	257,855.00
0155 0327 70 3 MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH 1,371.000 SY	6.00000	8,226.00	8.30000	11,379.30	8.00000	10,968.00
0160 0327 70 4 MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH 5,495.000 SY	3.40000	18,683.00	6.25000	34,343.75	6.00000	32,970.00
0165 0327 70 6 MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH 3,846.000 SY	3.90000	14,999.40	6.65000	25,575.90	6.50000	24,999.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0170 0327 70 7 MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH 2,519.000 SY	3.90000	9,824.10	9.05000	22,796.95	9.00000	22,671.00
0175 0327 70 10 MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH 1,415.000 SY	6.10000	8,631.50	8.75000	12,381.25	8.50000	12,027.50
0180 0327 70 17 MILLING EXISTING ASPHALT PAVEMENT, 3 1/4" AVG DEPTH 546.000 SY	12.40000	6,770.40	15.60000	8,517.60	15.00000	8,190.00
0185 0327 70 18 MILLING EXISTING ASPHALT PAVEMENT, 5 1/2" AVG DEPTH 3,674.000 SY	3.70000	13,593.80	10.10000	37,107.40	10.00000	36,740.00
0190 0327 70 27 MILLING EXISTING ASPHALT PAVEMENT, 5 3/4" AVG DEPTH 1,486.000 SY	6.20000	9,213.20	8.95000	13,299.70	9.00000	13,374.00
0195 0334 1 11 SUPERPAVE ASPHALTIC CONC, TRAFFIC A 74.800 TN	215.00000	16,082.00	161.10000	12,050.28	160.00000	11,968.00
0200 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C 4,822.800 TN	122.00000	588,381.60	102.60000	494,819.28	100.00000	482,280.00
0205 0334 1 54 SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22 1,153.400 TN	138.00000	159,169.20	123.90000	142,906.26	120.00000	138,408.00
0210 0337 7 81 ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-12.5, PG 76-22 263.900 TN	172.00000	45,390.80	139.10000	36,708.49	140.00000	36,946.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0215 0337 7 83 2,364.700 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	142.00000	335,787.40	119.50000	282,581.65	120.00000	283,764.00
0220 0337 7 85 2,364.700 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC D, FC-12.5, PG 76-22	118.00000	279,034.60	119.50000	282,581.65	120.00000	283,764.00
0225 0339 1 9.700 TN MISCELLANEOUS ASPHALT PAVEMENT	715.00000	6,935.50	289.20000	2,805.24	270.00000	2,619.00
0230 0400 0 11 140.000 CY CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	1,909.00000	267,260.00	1,110.00000	155,400.00	840.00000	117,600.00
0235 0425 1311 6.000 EA INLETS, CURB, TYPE P-1, <10'	5,831.73000	34,990.38	10,600.00000	63,600.00	11,200.00000	67,200.00
0240 0425 1312 1.000 EA INLETS, CURB TYPE P-1, >10'	12,079.97000	12,079.97	15,300.00000	15,300.00	11,900.00000	11,900.00
0245 0425 1351 1.000 EA INLETS, CURB, TYPE P-5, <10'	4,709.70000	4,709.70	8,500.00000	8,500.00	10,900.00000	10,900.00
0250 0425 1412 2.000 EA INLETS, CURB, TYPE J-1, >10'	11,440.46000	22,880.92	20,000.00000	40,000.00	13,800.00000	27,600.00
0255 0425 1451 4.000 EA INLETS, CURB, TYPE J-5, <10'	8,857.16000	35,428.64	18,800.00000	75,200.00	16,400.00000	65,600.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0260 0425 1461 2.000 EA INLETS, CURB, TYPE J-6, <10'	7,432.20000	14,864.40	13,800.00000	27,600.00	13,500.00000	27,000.00
0265 0425 1521 6.000 EA INLETS, DT BOT, TYPE C,<10'	4,559.41000	27,356.46	5,750.00000	34,500.00	8,100.00000	48,600.00
0270 0425 1541 3.000 EA INLETS, DT BOT, TYPE D, <10'	4,745.92000	14,237.76	7,000.00000	21,000.00	8,700.00000	26,100.00
0275 0425 1549 1.000 EA INLETS, DT BOT, TYPE D, MODIFY	7,235.27000	7,235.27	9,250.00000	9,250.00	9,900.00000	9,900.00
0280 0425 1711 1.000 EA INLETS, GUTTER, TYPE V, <10'	3,615.39000	3,615.39	6,880.00000	6,880.00	9,000.00000	9,000.00
0285 0425 2 43 1.000 EA MANHOLES, P-7, PARTIAL	3,077.78000	3,077.78	5,000.00000	5,000.00	6,100.00000	6,100.00
0290 0425 2 62 2.000 EA MANHOLES, P-8, >10'	5,893.65000	11,787.30	8,880.00000	17,760.00	11,900.00000	23,800.00
0295 0425 2 63 2.000 EA MANHOLES, P-8, PARTIAL	3,217.21000	6,434.42	5,350.00000	10,700.00	6,100.00000	12,200.00
0300 0425 2 91 3.000 EA MANHOLES, J-8, <10'	6,181.90000	18,545.70	12,000.00000	36,000.00	9,900.00000	29,700.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0305 0425 2 92 MANHOLES, J-8, >10' 2.000 EA	7,750.98000	15,501.96	15,000.00000	30,000.00	15,600.00000	31,200.00
0310 0425 5 1 MANHOLE, ADJUST, UTILITIES 1.000 EA	836.61000	836.61	1,070.00000	1,070.00	2,200.00000	2,200.00
0315 0425 6 VALVE BOXES, ADJUST 6.000 EA	274.15000	1,644.90	615.50000	3,693.00	1,400.00000	8,400.00
0320 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD 17.000 LF	262.20000	4,457.40	225.00000	3,825.00	380.00000	6,460.00
0325 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD 713.000 LF	160.24000	114,251.12	187.50000	133,687.50	240.00000	171,120.00
0330 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD 734.000 LF	262.34000	192,557.56	193.80000	142,249.20	360.00000	264,240.00
0335 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD 498.000 LF	220.25000	109,684.50	250.00000	124,500.00	390.00000	194,220.00
0340 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD 47.000 LF	454.96000	21,383.12	437.50000	20,562.50	540.00000	25,380.00
0345 0430175218 PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD 54.000 LF	194.28000	10,491.12	312.50000	16,875.00	480.00000	25,920.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0346 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE 32.200 CY	540.06000	17,389.93	625.00000	20,125.00	590.00000	18,998.00
0350 0430982123 MITERED END SECTION, OPTIONAL ROUND, 15" CD 1.000 EA	1,603.55000	1,603.55	1,750.00000	1,750.00	2,200.00000	2,200.00
0355 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD 3.000 EA	1,950.22000	5,850.66	1,880.00000	5,640.00	2,300.00000	6,900.00
0360 0430982129 MITERED END SECTION, OPTIONAL ROUND, 24" CD 5.000 EA	2,327.37000	11,636.85	2,000.00000	10,000.00	3,400.00000	17,000.00
0365 0430982133 MITERED END SECTION, OPTIONAL ROUND, 30" CD 2.000 EA	3,131.68000	6,263.36	3,500.00000	7,000.00	4,300.00000	8,600.00
0370 0515 1 1 PIPE HANDRAIL - GUIDERAIL, STEEL 276.000 LF	66.07000	18,235.32	62.50000	17,250.00	52.00000	14,352.00
0375 0520 1 7 CONCRETE CURB & GUTTER, TYPE E 816.000 LF	27.18000	22,178.88	55.00000	44,880.00	40.00000	32,640.00
0380 0520 1 10 CONCRETE CURB & GUTTER, TYPE F 4,629.000 LF	27.18000	125,816.22	42.15000	195,112.35	40.00000	185,160.00
0385 0520 2 1 CONCRETE CURB, TYPE A 1,311.000 LF	27.18000	35,632.98	48.85000	64,042.35	40.00000	52,440.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0390 0520 2 4 CONCRETE CURB, TYPE D 276.000 LF	27.18000	7,501.68	53.00000	14,628.00	32.00000	8,832.00
0395 0520 6 SHOULDER GUTTER- CONCRETE 155.000 LF	27.18000	4,212.90	57.60000	8,928.00	32.00000	4,960.00
0400 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH 1,112.000 SY	71.73000	79,763.76	134.20000	149,230.40	62.00000	68,944.00
0401 0521 1 11 MEDIAN CONCRETE BARRIER, 38" HEIGHT 205.000 LF	324.01000	66,422.05	314.50000	64,472.50	310.00000	63,550.00
0402 0521 72 43 SHOULDER CONCRETE BARRIER, CURB AND GUTTER BARRIER 10.000 LF	326.13000	3,261.30	481.50000	4,815.00	310.00000	3,100.00
0405 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 2,490.000 SY	48.92000	121,810.80	68.70000	171,063.00	57.00000	141,930.00
0410 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 109.000 SY	70.66000	7,701.94	114.00000	12,426.00	76.00000	8,284.00
0415 0527 2 DETECTABLE WARNINGS 291.000 SF	43.48000	12,652.68	34.35000	9,995.85	42.00000	12,222.00
0420 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING 6.000 TN	163.94000	983.64	250.00000	1,500.00	480.00000	2,880.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0425 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 92.000 LF	16.00000	1,472.00	25.20000	2,318.40	16.00000	1,472.00
0430 0536 1 1 GUARDRAIL -ROADWAY, GENERAL TL-3 182.000 LF	20.00000	3,640.00	29.40000	5,350.80	21.00000	3,822.00
0435 0536 8111 GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-2 2.000 EA	2,400.00000	4,800.00	3,160.00000	6,320.00	2,000.00000	4,000.00
0440 0536 73 GUARDRAIL REMOVAL 193.000 LF	2.00000	386.00	2.50000	482.50	1.80000	347.40
0445 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 1.000 EA	1,200.00000	1,200.00	1,500.00000	1,500.00	1,400.00000	1,400.00
0450 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 3.000 EA	3,000.00000	9,000.00	3,750.00000	11,250.00	2,500.00000	7,500.00
0455 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD 805.000 LF	8.00000	6,440.00	10.00000	8,050.00	8.50000	6,842.50
0460 0570 1 1 PERFORMANCE TURF 20,331.000 SY	3.17000	64,449.27	3.10000	63,026.10	3.40000	69,125.40

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0465 0570 1 2 23,919.000 SY PERFORMANCE TURF, SOD	3.17000	75,823.23	3.15000	75,344.85	4.00000	95,676.00
0470 0591 1600 579.000 LF IRRIGATION SLEEVE, 6" DIAMETER	54.54000	31,578.66	50.00000	28,950.00	77.00000	44,583.00
0475 0710 11101 7.342 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1,050.54000	7,713.06	1,250.00000	9,177.50	1,000.00000	7,342.00
0480 0710 11103 0.103 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	2,448.54000	252.20	2,910.00000	299.73	2,050.00000	211.15
0485 0710 11125 583.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	1.13000	658.79	1.35000	787.05	0.75000	437.25
0490 0710 11131 1.298 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	420.98000	546.43	497.00000	645.11	370.00000	480.26
0495 0710 11180 143.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	2.10000	300.30	2.50000	357.50	2.10000	300.30
0500 0710 11201 5.010 GM PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1,050.83000	5,264.66	1,250.00000	6,262.50	1,000.00000	5,010.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0505 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 44418715201	78,000.00000	78,000.00	78,000.00000	78,000.00	78,000.00000	78,000.00
0001 Roadway Section Totals:		**$7,653,607.77**		**$7,380,621.60**		**$8,533,573.12**
SECTION: 0002 Signing						
0510 0634 4151 1.000 PI SPAN WIRE ASSEMBLY, F&I, TWO POINT, PERPENDICULAR	6,008.31000	6,008.31	3,020.00000	3,020.00	6,300.00000	6,300.00
0520 0700 1 11 44.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	449.58000	19,781.52	756.50000	33,286.00	440.00000	19,360.00
0525 0700 1 12 17.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	1,418.98000	24,122.66	909.00000	15,453.00	790.00000	13,430.00
0530 0700 1 14 2.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	2,298.04000	4,596.08	3,930.00000	7,860.00	2,400.00000	4,800.00
0535 0700 1 21 1.000 AS SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	1,216.36000	1,216.36	2,530.00000	2,530.00	2,900.00000	2,900.00
0540 0700 1 50 4.000 AS SINGLE POST SIGN, RELOCATE	569.22000	2,276.88	185.00000	740.00	260.00000	1,040.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0545 0700 1 60 SINGLE POST SIGN, REMOVE 36.000 AS	87.33000	3,143.88	31.25000	1,125.00	16.00000	576.00
0550 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF 2.000 AS	5,543.28000	11,086.56	6,100.00000	12,200.00	5,600.00000	11,200.00
0555 0700 2 15 MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF 2.000 AS	5,935.16000	11,870.32	6,820.00000	13,640.00	6,300.00000	12,600.00
0560 0700 2 16 MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF 2.000 AS	8,885.44000	17,770.88	9,710.00000	19,420.00	8,400.00000	16,800.00
0565 0700 2 50 MULTI- POST SIGN, GROUND MOUNT, RELOCATE 2.000 AS	6,113.58000	12,227.16	8,460.00000	16,920.00	3,800.00000	7,600.00
0570 0700 2 60 MULTI- POST SIGN, REMOVE 2.000 AS	578.02000	1,156.04	1,110.00000	2,220.00	470.00000	940.00
0575 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF 5.000 EA	391.33000	1,956.65	1,540.00000	7,700.00	790.00000	3,950.00
0580 0700 3202 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF 1.000 EA	602.03000	602.03	3,100.00000	3,100.00	1,700.00000	1,700.00
0585 0700 3206 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF 4.000 EA	4,065.33000	16,261.32	10,300.00000	41,200.00	3,100.00000	12,400.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0590 0700 4114 2.000 EA OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	68,895.68000	137,791.36	193,000.00000	386,000.00	72,200.00000	144,400.00
0595 0700 13 12 16.000 EA RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 2'	41.53000	664.48	146.30000	2,340.80	76.00000	1,216.00
0600 0705 10 3 4.000 EA OBJECT MARKER, TYPE 3	290.89000	1,163.56	75.00000	300.00	140.00000	560.00
0605 0705 11 1 4.000 EA DELINEATOR, FLEXIBLE TUBULAR	100.00000	400.00	190.00000	760.00	100.00000	400.00
0610 0710 11190 19.000 SF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	2.05000	38.95	2.45000	46.55	2.10000	39.90
0615 0710 11290 114.000 SF PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	2.05000	233.70	2.45000	279.30	2.10000	239.40
0620 0710 90 (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44418715201	14,874.51000	14,874.51	17,700.00000	17,700.00	22,800.00000	22,800.00
0625 0711 11124 1,113.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	2.63000	2,927.19	3.10000	3,450.30	2.30000	2,559.90

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0630 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 263.000 LF	3.68000	967.84	4.35000	1,144.05	3.20000	841.60
0635 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.640 GM	1,866.28000	1,194.42	2,220.00000	1,420.80	1,050.00000	672.00
0640 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL 15.000 EA	157.62000	2,364.30	187.50000	2,812.50	52.00000	780.00
0645 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW 89.000 EA	62.00000	5,518.00	73.80000	6,568.20	42.00000	3,738.00
0650 0711 11180 THERMOPLASTIC, STANDARD, WHITE, YIELD LINE 30.000 LF	15.76000	472.80	18.75000	562.50	2.10000	63.00
0655 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON 627.000 LF	2.63000	1,649.01	3.15000	1,975.05	2.30000	1,442.10
0660 0711 14123 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK 801.000 LF	7.09000	5,679.09	8.45000	6,768.45	6.00000	4,806.00
0665 0711 14125 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK 543.000 LF	14.19000	7,705.17	16.85000	9,149.55	12.00000	6,516.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0670 0711 14660 4.000 EA THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	2,022.85000	8,091.40	2,410.00000	9,640.00	1,900.00000	7,600.00
0675 0711 16101 2.402 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	3,674.85000	8,826.99	4,370.00000	10,496.74	4,000.00000	9,608.00
0680 0711 16102 0.617 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	4,962.92000	3,062.12	5,810.00000	3,584.77	5,400.00000	3,331.80
0685 0711 16131 0.993 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	1,309.57000	1,300.40	1,560.00000	1,549.08	1,000.00000	993.00
0690 0711 16201 1.487 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	3,685.33000	5,480.09	4,350.00000	6,468.45	4,000.00000	5,948.00
0695 0711 16202 0.199 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	4,921.46000	979.37	5,560.00000	1,106.44	5,200.00000	1,034.80
0002 Signing Section Totals:		**$345,461.40**		**$654,537.53**		**$335,185.50**
SECTION: 0003 Lighting						
0700 0630 2 11 3,362.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	7.03000	23,634.86	7.80000	26,223.60	7.50000	25,215.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Lighting						
0705 0630 2 12 1,930.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	19.40000	37,442.00	21.25000	41,012.50	20.00000	38,600.00
0710 0635 2 11 40.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	772.55000	30,902.00	1,230.00000	49,200.00	810.00000	32,400.00
0715 0639 2 1 25.000 LF ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	9.23000	230.75	15.60000	390.00	9.50000	237.50
0720 0715 1 12 19,234.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	1.12000	21,542.08	3.10000	59,625.40	1.20000	23,080.80
0725 0715 1 13 3,429.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	2.50000	8,572.50	4.40000	15,087.60	2.60000	8,915.40
0730 0715 1 60 2,372.000 LF LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	0.57000	1,352.04	1.55000	3,676.60	0.60000	1,423.20
0735 0715 4 13 27.000 EA LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	5,156.69000	139,230.63	7,290.00000	196,830.00	5,400.00000	145,800.00
0740 0715 7 21 1.000 EA LOAD CENTER, REWORK, SECONDARY VOLTAGE	1,953.15000	1,953.15	8,140.00000	8,140.00	2,000.00000	2,000.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Lighting						
0745 0715 19 13 HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120' 1.000 EA	86,657.09000	86,657.09	104,000.00000	104,000.00	90,900.00000	90,900.00
0750 0715 19 60 HIGH MAST LIGHT POLE, REMOVE POLE AND FOUNDATION 1.000 EA	4,977.69000	4,977.69	9,060.00000	9,060.00	5,200.00000	5,200.00
0755 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL 27.000 EA	451.56000	12,192.12	869.00000	23,463.00	470.00000	12,690.00
0760 0715500 2 POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST 1.000 EA	444.07000	444.07	1,580.00000	1,580.00	46.00000	46.00
0003 Lighting Section Totals:		**$369,130.98**		**$538,288.70**		**$386,507.90**
SECTION: 0004 Signalization						
0765 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH 855.000 LF	14.82000	12,671.10	27.50000	23,512.50	16.00000	13,680.00
0770 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE 940.000 LF	48.74000	45,815.60	48.75000	45,825.00	51.00000	47,940.00
0775 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL 2.000 PI	16,522.11000	33,044.22	19,400.00000	38,800.00	17,300.00000	34,600.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0780 0632 7 6 SIGNAL CABLE, REMOVE-INTERSECTION 2.000 PI	629.43000	1,258.86	1,380.00000	2,760.00	660.00000	1,320.00
0785 0633 2 32 FIBER OPTIC CONNECTION, INSTALL, TERMINATION 12.000 EA	28.45000	341.40	106.30000	1,275.60	30.00000	360.00
0790 0633 3 12 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY 1.000 EA	40.06000	40.06	68.70000	68.70	42.00000	42.00
0795 0633 3 16 FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED 1.000 EA	766.93000	766.93	1,680.00000	1,680.00	800.00000	800.00
0800 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE 43.000 EA	687.98000	29,583.14	906.50000	38,979.50	720.00000	30,960.00
0805 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE 1.000 EA	1,488.03000	1,488.03	1,680.00000	1,680.00	1,600.00000	1,600.00
0810 0639 2 1 ELECTRICAL SERVICE WIRE, FURNISH & INSTALL 170.000 LF	4.02000	683.40	6.85000	1,164.50	4.20000	714.00
0815 0639 2 6 ELECTRICAL SERVICE WIRE, REMOVE 250.000 LF	0.05000	12.50	1.25000	312.50	0.05000	12.50

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0820 0639 3 11 ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT 1.000 EA	1,815.22000	1,815.22	1,260.00000	1,260.00	1,900.00000	1,900.00
0825 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE 1.000 EA	1,811.39000	1,811.39	2,340.00000	2,340.00	1,900.00000	1,900.00
0826 0641 2 18 PRESTRESSED CONCRETE POLE, F&I, TYPE P-VIII 2.000 EA	30,252.63000	60,505.26	31,300.00000	62,600.00	31,700.00000	63,400.00
0830 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL 12.000 EA	1,264.80000	15,177.60	2,160.00000	25,920.00	1,300.00000	15,600.00
0835 0646 1 60 ALUMINUM SIGNALS POLE, REMOVE 1.000 EA	167.07000	167.07	1,000.00000	1,000.00	180.00000	180.00
0840 0649 21 3 STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40' 1.000 EA	32,607.64000	32,607.64	46,300.00000	46,300.00	34,200.00000	34,200.00
0845 0649 21 6 STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50' 2.000 EA	35,658.65000	71,317.30	52,400.00000	104,800.00	37,400.00000	74,800.00
0850 0649 21 10 STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60' 3.000 EA	41,778.52000	125,335.56	60,700.00000	182,100.00	43,800.00000	131,400.00
0855 0649 21 15 STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70' 1.000 EA	47,308.89000	47,308.89	67,800.00000	67,800.00	49,600.00000	49,600.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0860 0649 26 3 STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION-BOLT ON ATTACHMENT 4.000 EA	3,203.14000	12,812.56	5,040.00000	20,160.00	3,400.00000	13,600.00
0865 0650 1 14 VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY 15.000 AS	905.47000	13,582.05	1,260.00000	18,900.00	950.00000	14,250.00
0870 0653 1 11 PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY 12.000 AS	564.16000	6,769.92	875.00000	10,500.00	590.00000	7,080.00
0875 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT 1.000 EA	3,580.57000	3,580.57	34,900.00000	34,900.00	3,800.00000	3,800.00
0880 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT 7.000 EA	6,107.19000	42,750.33	5,090.00000	35,630.00	6,400.00000	44,800.00
0885 0663 1121 SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS 1.000 EA	3,570.12000	3,570.12	7,630.00000	7,630.00	3,700.00000	3,700.00
0890 0663 1122 SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR 1.000 EA	7,264.33000	7,264.33	5,480.00000	5,480.00	7,600.00000	7,600.00
0895 0665 1 12 PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE 12.000 EA	1,141.85000	13,702.20	1,750.00000	21,000.00	1,500.00000	18,000.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization						
0900 0670 5141 TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL, MODEL 2070, 1 PREEMPTION 1.000 AS	25,632.83000	25,632.83	38,700.00000	38,700.00	26,900.00000	26,900.00
0905 0670 5600 TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET 1.000 AS	486.18000	486.18	593.50000	593.50	510.00000	510.00
0910 0682 1113 ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION 2.000 EA	4,850.36000	9,700.72	9,180.00000	18,360.00	5,100.00000	10,200.00
0915 0684 1 1 MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL 1.000 EA	2,866.70000	2,866.70	4,760.00000	4,760.00	3,000.00000	3,000.00
0920 0684 5 1 MEDIA CONVERTER, FURNISH & INSTALL 1.000 EA	854.19000	854.19	893.50000	893.50	900.00000	900.00
0925 0685 1 12 UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION 1.000 EA	3,184.77000	3,184.77	8,750.00000	8,750.00	3,300.00000	3,300.00
0930 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF 12.000 EA	606.36000	7,276.32	2,110.00000	25,320.00	640.00000	7,680.00
0935 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF 3.000 EA	5,808.46000	17,425.38	6,460.00000	19,380.00	6,100.00000	18,300.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units			(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum			Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Signalization								
0004 Signalization Section Totals:				**$653,210.34**		**$921,135.30**		**$688,628.50**
SECTION: 0005 Intelligent Transportation System								
0940	0630 2 11	6,895.000 LF	9.41000	64,881.95	13.15000	90,669.25	10.00000	68,950.00
CONDUIT, FURNISH & INSTALL, OPEN TRENCH								
0945	0630 2 12	780.000 LF	18.60000	14,508.00	25.00000	19,500.00	20.00000	15,600.00
CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE								
0950	0630 2 14	210.000 LF	22.54000	4,733.40	25.00000	5,250.00	24.00000	5,040.00
CONDUIT, FURNISH & INSTALL, ABOVEGROUND								
0955	0633 1121	2,334.000 LF	1.57000	3,664.38	4.35000	10,152.90	1.70000	3,967.80
FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS								
0960	0633 1122	135.000 LF	1.71000	230.85	4.70000	634.50	1.80000	243.00
FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS								
0965	0633 1123	11,034.000 LF	2.38000	26,260.92	5.00000	55,170.00	2.50000	27,585.00
FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS								
0970	0633 1620	1,679.000 LF	0.75000	1,259.25	1.25000	2,098.75	0.80000	1,343.20
FIBER OPTIC CABLE, REMOVE, UNDERGROUND								

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
0975 0633 2 31 FIBER OPTIC CONNECTION, INSTALL, SPLICE 108.000 EA	28.45000	3,072.60	50.00000	5,400.00	30.00000	3,240.00
0980 0633 3 11 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE 5.000 EA	766.93000	3,834.65	994.00000	4,970.00	800.00000	4,000.00
0985 0633 3 12 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY 2.000 EA	40.06000	80.12	68.80000	137.60	42.00000	84.00
0990 0633 3 13 FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY 24.000 EA	29.61000	710.64	75.00000	1,800.00	31.00000	744.00
0995 0633 3 15 FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL 6.000 EA	766.93000	4,601.58	3,250.00000	19,500.00	800.00000	4,800.00
1000 0633 3 17 FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL 2.000 EA	93.47000	186.94	118.80000	237.60	98.00000	196.00
1005 0633 3 52 FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY 1.000 EA	139.34000	139.34	13.75000	13.75	150.00000	150.00
1010 0633 8 1 MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL 981.000 LF	3.10000	3,041.10	3.10000	3,041.10	3.30000	3,237.30

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
1015 0635 2 11 19.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	728.19000	13,835.61	831.50000	15,798.50	760.00000	14,440.00
1020 0635 2 12 19.000 EA PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	1,339.32000	25,447.08	1,960.00000	37,240.00	1,400.00000	26,600.00
1025 0635 2 13 5.000 EA PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	3,367.82000	16,839.10	2,710.00000	13,550.00	3,500.00000	17,500.00
1030 0635 3 40 1.000 EA JUNCTION BOX, RELOCATE	1,106.66000	1,106.66	731.00000	731.00	1,200.00000	1,200.00
1035 0639 2 1 3,260.000 LF ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	7.41000	24,156.60	8.75000	28,525.00	8.00000	26,080.00
1040 0639 3 11 5.000 EA ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	1,266.30000	6,331.50	1,260.00000	6,300.00	1,300.00000	6,500.00
1045 0641 2 12 2.000 EA PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1,502.27000	3,004.54	3,790.00000	7,580.00	1,600.00000	3,200.00
1050 0660 7 12 2.000 EA VEHICLE DETECTION SYSTEM-WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES	60,516.11000	121,032.22	79,600.00000	159,200.00	63,500.00000	127,000.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
1055 0676 2122 2.000 EA ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	6,872.55000	13,745.10	10,500.00000	21,000.00	7,200.00000	14,400.00
1060 0676 2142 1.000 EA ITS CABINET, FURNISH & INSTALL, BASE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	7,232.31000	7,232.31	12,400.00000	12,400.00	7,600.00000	7,600.00
1065 0676 3 60 1.000 EA SMALL EQUIPMENT ENCLOSURE, REMOVE- POST/CABINET TO REMAIN	532.15000	532.15	393.50000	393.50	560.00000	560.00
1070 0682 1113 8.000 EA ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	4,851.36000	38,810.88	10,100.00000	80,800.00	5,100.00000	40,800.00
1075 0682 1600 1.000 EA ITS CCTV CAMERA, REMOVE & DISPOSAL	273.89000	273.89	650.00000	650.00	290.00000	290.00
1080 0684 1 1 7.000 EA MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	2,867.27000	20,070.89	4,760.00000	33,320.00	3,000.00000	21,000.00
1085 0684 6 60 1.000 EA WIRELESS COMMUNICATION DEVICE, REMOVE	199.86000	199.86	343.50000	343.50	210.00000	210.00
1090 0685 1 11 3.000 EA UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	3,186.10000	9,558.30	5,380.00000	16,140.00	3,300.00000	9,900.00

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) HUBBARD CONSTRUCTION COMPANY		(5) RANGER CONSTRUCTION INDUSTRIES, INC.		(6) SEMA CONSTRUCTION, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Intelligent Transportation System						
1095 0685 2 1 — 2.000 EA REMOTE POWER MANAGEMENT UNIT-RPMU, FURNISH AND INSTALL	917.47000	1,834.94	2,160.00000	4,320.00	960.00000	1,920.00
1100 0700 6 11 — 6.000 AS HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, UP TO 12 SF	4,270.03000	25,620.18	7,240.00000	43,440.00	4,500.00000	27,000.00
1105 0700 6 12 — 2.000 AS HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, 12-20 SF	4,319.65000	8,639.30	7,240.00000	14,480.00	4,500.00000	9,000.00
1110 0700 13 12 — 8.000 EA RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 2'	41.53000	332.24	118.80000	950.40	52.00000	416.00
0005 Intelligent Transportation System Section Totals:		**$469,809.07**		**$715,737.35**		**$494,796.30**
Contract Grand Totals:		**$9,491,219.56**		**$10,210,320.48**		**10,438,691.32**

Letting: CT210127 January 27, 2021 **Call Order:** 027 **Contract:** T5715

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

Alan D. Autry 02/09/2021

Manager, Contracts Administration Office