Vendor Ranking

Letting: CT250129 January 29, 2025 10:30 AM **Call Order:** 020 **Contract:** T6610

District: District 6 **Counties:** MIAMI-DADE **Fed Aid No:** D623026B

Contract Time: 360 AVAILABLE DAYS **Project(s):** 44393115201 (*)
44618915201
44393115601
44618915601

Contract Desc: SR A1A (COLLINS AVE / INDIAN CREEK DR) AND SR 112 FROM 44...

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	FLORIDA ENGINEERING & DEVELOPMENT CORP	Responsive	Winning bid	$9,176,265.71	100.00%
2	STRONGCORE GROUP, LLC	Responsive	Non-Winning Bid	$10,160,693.92	110.73%
3	SOUTHERN ROAD & BRIDGE, LLC	Responsive	Non-Winning Bid	$13,510,695.40	147.24%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

District: District 6 **Counties:** MIAMI-DADE **Fed Aid No:** D623026B

Contract Time: 360 AVAILABLE DAYS **Project(s):** 44393115201 (*), 44618915201, 44393115601, 44618915601

Contract Descr: SR A1A (COLLINS AVE / INDIAN CREEK DR) AND SR 112 FROM 44...

THE IMPROVEMENTS UNDER THIS CONTRACT CONSIT OF RESURFACING ALONG SR A1A/COLLINS AVENUE FROM 44 ST TO 4700 BLK & INDIAN CREEK FROM 41 STREET TO 44 STREET AND BRIDGE-REPAIR/REHABILITATION ALONG SR 112 - WEST 41ST STREET OVER INDIAN CREEK WATERWAY - BRIDGE NO. 870055 IN MIAMI-DADE COUNTY.

Line No / Item ID / Item Description / Alternate	Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures							
0005 0400 4 8 CONC CLASS IV, BULKHEAD	3.900 CY	13,560.00000	52,884.00	10,300.00000	40,170.00	9,500.00000	37,050.00
0010 0401 70 3 RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	1,087.600 CF	904.00000	983,190.40	1,530.00000	1,664,028.00	1,180.00000	1,283,368.00
0015 0411 1 EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	3.000 GA	282.50000	847.50	545.00000	1,635.00	50.00000	150.00
0020 0411 2 CRACKS INJECT & SEAL- STRUCTURES REHAB	61.000 LF	2,034.00000	124,074.00	363.00000	22,143.00	248.00000	15,128.00
0025 0413149 PENETRANT SEALER	251.000 GA	226.00000	56,726.00	132.00000	33,132.00	110.00000	27,610.00
0030 0413154 CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	38,789.000 SF	3.39000	131,494.71	3.10000	120,245.90	18.00000	698,202.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0035 0458 1 21 BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD 401.000 LF	113.00000	45,313.00	77.00000	30,877.00	125.00000	50,125.00
0040 0458 2 POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT 32.000 CF	904.00000	28,928.00	1,050.00000	33,600.00	1,850.00000	59,200.00
0045 0460 1 1 STRUCT STEEL- REHAB, CARBON 2,433.000 LB	67.80000	164,957.40	69.50000	169,093.50	135.00000	328,455.00
0050 0460 1 13 STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES 426.000 LB	36.16000	15,404.16	56.50000	24,069.00	150.00000	63,900.00
0055 0460 94 STRUCTURAL STEEL REPAIR- WELDS 6.000 LF	565.00000	3,390.00	3,080.00000	18,480.00	325.00000	1,950.00
0060 0561 1 COATING EXISTING STRUCTURAL STEEL 44618915201 870055 (60.600) TN (LS)	650,000.00000	650,000.00	282,800.00000	282,800.00	1,250,000.00000	1,250,000.00
0001 Structures Section Totals:		**$2,257,209.17**		**$2,440,273.40**		**$3,815,138.00**
SECTION: 0002 Roadway						
0065 0101 1 MOBILIZATION 44393115201 (1.000) LS	450,000.00000	450,000.00	850,000.00000	850,000.00	650,000.00000	650,000.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0070 0101 1 (1.000) LS MOBILIZATION 44618915201	450,000.00000	450,000.00	850,000.00000	850,000.00	650,000.00000	650,000.00
0075 0102 1 (280.000) DA (LS) MAINTENANCE OF TRAFFIC 44393115201	400,000.00000	400,000.00	272,400.00000	272,400.00	500,000.00000	500,000.00
0080 0102 1 (330.000) DA (LS) MAINTENANCE OF TRAFFIC 44618915201	400,000.00000	400,000.00	44,100.00000	44,100.00	500,000.00000	500,000.00
0085 0102 14 1,792.000 HR TRAFFIC CONTROL OFFICER	108.82000	195,005.44	90.00000	161,280.00	85.00000	152,320.00
0090 0102 60 29,180.000 ED WORK ZONE SIGN	0.24000	7,003.20	0.30000	8,754.00	0.30000	8,754.00
0095 0102 71 13 131.000 LF TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	76.07000	9,965.17	116.00000	15,196.00	125.00000	16,375.00
0100 0102 74 1 31,690.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.14000	4,436.60	0.20000	6,338.00	0.20000	6,338.00
0105 0102 74 8 10,560.000 FD CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	0.07000	739.20	0.10000	1,056.00	0.15000	1,584.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0110 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL 510.000 ED	5.93000	3,024.30	6.90000	3,519.00	7.00000	3,570.00
0115 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 1,276.000 ED	11.87000	15,146.12	14.00000	17,864.00	15.00000	19,140.00
0120 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION 2,520.000 ED	13.56000	34,171.20	14.50000	36,540.00	29.00000	73,080.00
0125 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION 2,520.000 ED	13.56000	34,171.20	14.50000	36,540.00	3.00000	7,560.00
0130 0102115 TYPE III BARRICADE 1,900.000 ED	0.32000	608.00	0.40000	760.00	0.50000	950.00
0135 0104 11 FLOATING TURBIDITY BARRIER 278.000 LF	80.00000	22,240.00	274.00000	76,172.00	12.00000	3,336.00
0140 0104 18 INLET PROTECTION SYSTEM 23.000 EA	97.98000	2,253.54	279.00000	6,417.00	125.00000	2,875.00
0145 0107 1 LITTER REMOVAL 42.770 AC	245.51000	10,500.46	412.00000	17,621.24	75.00000	3,207.75
0150 0107 2 MOWING 22.360 AC	561.58000	12,556.93	3,090.00000	69,092.40	75.00000	1,677.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0002 Roadway						
0155 0108 1 (1.000) LS MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 44393115201	8,000.00000	8,000.00	9,630.00000	9,630.00	78,000.00000	78,000.00
0160 0110 1 1 (0.410) AC (LS) CLEARING & GRUBBING 44393115201	310,000.00000	310,000.00	133,200.00000	133,200.00	185,000.00000	185,000.00
0165 0110 4 10 3,237.000 SY REMOVAL OF EXISTING CONCRETE	68.21000	220,795.77	58.00000	187,746.00	65.00000	210,405.00
0170 0110 21 318.000 LF TREE PROTECTION BARRIER	7.55000	2,400.90	23.00000	7,314.00	25.00000	7,950.00
0175 0120 1 42.000 CY REGULAR EXCAVATION	131.02000	5,502.84	1,000.00000	42,000.00	145.00000	6,090.00
0180 0120 6 3.000 CY EMBANKMENT	175.12000	525.36	7,330.00000	21,990.00	650.00000	1,950.00
0185 0285715 1,402.000 SY OPTIONAL BASE, BASE GROUP 15	175.00000	245,350.00	231.00000	323,862.00	145.00000	203,290.00
0190 0327 70 6 35,466.000 SY MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	5.09000	180,521.94	5.50000	195,063.00	14.00000	496,524.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0195 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C 1,043.200 TN	314.23000	327,804.74	457.00000	476,742.40	295.00000	307,744.00
0200 0337 7 83 ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22 3,009.800 TN	264.42000	795,851.32	289.00000	869,832.20	405.00000	1,218,969.00
0205 0425 1351 INLETS, CURB, TYPE P-5, <10' 1.000 EA	14,475.09000	14,475.09	32,500.00000	32,500.00	14,000.00000	14,000.00
0210 0425 1461 INLETS, CURB, TYPE J-6, <10' 1.000 EA	16,197.07000	16,197.07	35,700.00000	35,700.00	14,000.00000	14,000.00
0215 0425 5 MANHOLE, ADJUST 21.000 EA	1,250.00000	26,250.00	2,840.00000	59,640.00	2,500.00000	52,500.00
0220 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD 24.000 LF	750.00000	18,000.00	1,820.00000	43,680.00	900.00000	21,600.00
0225 0520 1 22 CONCRETE CURB & GUTTER, TYPE F VARIABLE GUTTER PAN WITH REINFORCING, PROJECTS 443931-1-52-01, ETC. 3,011.000 LF	92.18000	277,553.98	96.50000	290,561.50	145.00000	436,595.00
0230 0520 1 23 CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE, VARIABLE GUTTER PAN WITH REINFORCING, PROJECT 443931-1-52-01 281.000 LF	94.25000	26,484.25	134.00000	37,654.00	145.00000	40,745.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0235 0520 2 4 CONCRETE CURB, TYPE D 162.000 LF	73.93000	11,976.66	59.50000	9,639.00	145.00000	23,490.00
0240 0520 2114 CONCRETE CURB, TYPE D WITH REINFORCING 119.000 LF	71.48000	8,506.12	61.50000	7,318.50	150.00000	17,850.00
0245 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH 145.000 SY	268.33000	38,907.85	197.00000	28,565.00	285.00000	41,325.00
0250 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 1,280.000 SY	94.80000	121,344.00	113.00000	144,640.00	120.00000	153,600.00
0255 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 1,123.000 SY	121.17000	136,073.91	119.00000	133,637.00	140.00000	157,220.00
0260 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK 5.000 SY	242.98000	1,214.90	1,000.00000	5,000.00	950.00000	4,750.00
0265 0527 2 DETECTABLE WARNINGS 626.000 SF	46.96000	29,396.96	34.50000	21,597.00	80.00000	50,080.00
0270 0570 1 2 PERFORMANCE TURF, SOD 286.000 SY	12.46000	3,563.56	159.00000	45,474.00	12.00000	3,432.00
0275 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE 5.000 LF	45.20000	226.00	49.00000	245.00	285.00000	1,425.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0280 0635 2 11 1.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	2,203.50000	2,203.50	3,000.00000	3,000.00	2,900.00000	2,900.00
0285 0639 8130 (1.000) LS ELECTRICAL POWER SERVICE-CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) 44393115201	1,000.00000	1,000.00	1,000.00000	1,000.00	1,000.00000	1,000.00
0290 0695 1 1 6.000 EA TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	2,034.00000	12,204.00	2,210.00000	13,260.00	3,400.00000	20,400.00
0295 0695 6 12 6.000 EA TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	1,808.00000	10,848.00	1,960.00000	11,760.00	3,400.00000	20,400.00
0300 0695 7162 1.000 EA TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	16,950.00000	16,950.00	18,400.00000	18,400.00	19,500.00000	19,500.00
0305 0695 7600 1.000 EA TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	1,356.00000	1,356.00	1,470.00000	1,470.00	1,400.00000	1,400.00
0310 0710 11101 3.164 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1,915.35000	6,060.17	2,080.00000	6,581.12	2,025.00000	6,407.10

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0315 0710 11102 — 0.183 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	2,028.36000	371.19	2,170.00000	397.11	2,160.00000	395.28
0320 0710 11123 — 2,067.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	1.13000	2,335.71	1.20000	2,480.40	1.35000	2,790.45
0325 0710 11124 — 996.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	1.70000	1,693.20	1.80000	1,792.80	2.70000	2,689.20
0330 0710 11125 — 665.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	2.26000	1,502.90	2.50000	1,662.50	4.05000	2,693.25
0335 0710 11131 — 1.625 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	745.80000	1,211.93	813.00000	1,321.13	1,080.00000	1,755.00
0340 0710 11133 — 0.100 GM PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	2,141.30000	214.13	2,330.00000	233.00	2,160.00000	216.00
0345 0710 11141 — 0.475 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	745.79000	354.25	819.00000	389.03	1,080.00000	513.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0002 Roadway						
0350 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL 40.000 EA	67.80000	2,712.00	73.50000	2,940.00	114.75000	4,590.00
0355 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS 54.000 EA	45.20000	2,440.80	49.00000	2,646.00	60.75000	3,280.50
0360 0710 11201 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" 1.417 GM	1,915.35000	2,714.05	2,090.00000	2,961.53	2,025.00000	2,869.43
0365 0710 11224 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18" 51.000 LF	1.69000	86.19	1.80000	91.80	2.70000	137.70
0370 0710 11241 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" 0.011 GM	746.36000	8.21	736.00000	8.10	1,080.00000	11.88
0375 0710 11421 PAINTED PAVEMENT MARKINGS, STANDARD, BLUE, SOLID FOR PARKING LOT- ACCESSIBLE MARKINGS, 6" 95.000 LF	1.02000	96.90	1.10000	104.50	6.75000	641.25
0380 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 44393115201 (1.000) LS	51,097.00000	51,097.00	51,097.00000	51,097.00	51,097.00000	51,097.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0385 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 44618915201	31,020.00000	31,020.00	31,020.00000	31,020.00	31,020.00000	31,020.00
0002 Roadway Section Totals:		**$5,027,224.71**		**$5,791,496.26**		**$6,526,007.79**
SECTION: 0003 Signing						
0390 0700 1111 102.000 EA SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	559.35000	57,053.70	608.00000	62,016.00	648.00000	66,096.00
0395 0700 1112 3.000 EA SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	2,655.50000	7,966.50	2,890.00000	8,670.00	2,970.00000	8,910.00
0400 0700 1113 1.000 EA SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	3,107.50000	3,107.50	3,380.00000	3,380.00	4,050.00000	4,050.00
0405 0700 1311 2.000 EA SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	2,141.35000	4,282.70	2,330.00000	4,660.00	4,050.00000	8,100.00
0410 0700 1600 60.000 EA SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	11.30000	678.00	12.50000	750.00	47.25000	2,835.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0415 0700 3501 SIGN PANEL, RELOCATE, UP TO 12 SF 23.000 EA	423.75000	9,746.25	460.00000	10,580.00	101.25000	2,328.75
0420 0700 3601 SIGN PANEL, REMOVE, UP TO 12 SF 9.000 EA	79.10000	711.90	86.00000	774.00	27.00000	243.00
0425 0704 1 1 TUBULAR MARKER, DURABLE, 36" WHITE POST 29.000 EA	107.35000	3,113.15	117.00000	3,393.00	303.75000	8,808.75
0430 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR 10.000 EA	101.70000	1,017.00	12.50000	125.00	135.00000	1,350.00
0435 0706 1 3 RAISED PAVEMENT MARKER, TYPE B 1,142.000 EA	5.65000	6,452.30	6.10000	6,966.20	6.75000	7,708.50
0440 0710 12290 PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE 1,373.000 SF	2.26000	3,102.98	2.50000	3,432.50	6.75000	9,267.75
0445 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44393115201 (1.000) LS	31,351.07000	31,351.07	34,100.00000	34,100.00	43,875.00000	43,875.00
0450 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT 2,067.000 LF	2.71000	5,601.57	3.00000	6,201.00	6.75000	13,952.25

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0455 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS 982.000 LF	4.07000	3,996.74	4.40000	4,320.80	9.45000	9,279.90
0460 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 655.000 LF	5.42000	3,550.10	5.90000	3,864.50	12.15000	7,958.25
0465 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.475 GM	1,789.92000	850.21	1,970.00000	935.75	6,075.00000	2,885.63
0470 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL 40.000 EA	135.60000	5,424.00	147.00000	5,880.00	303.75000	12,150.00
0475 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW 54.000 EA	90.40000	4,881.60	98.00000	5,292.00	121.50000	6,561.00
0480 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON 51.000 LF	4.07000	207.57	4.40000	224.40	9.45000	481.95
0485 0711 11241 THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" 0.011 GM	1,789.09000	19.68	1,770.00000	19.47	6,075.00000	66.83
0490 0711 11421 THERMOPLASTIC, STANDARD, BLUE, SOLID,6" 95.000 LF	0.68000	64.60	0.70000	66.50	13.50000	1,282.50

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0495 0711 14125 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK 1,943.000 LF	20.34000	39,520.62	22.00000	42,746.00	27.00000	52,461.00
0500 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAGE 24.000 EA	293.80000	7,051.20	319.00000	7,656.00	472.50000	11,340.00
0505 0711 14170 THERMOPLASTIC, PREFORMED, WHITE, ARROW 10.000 EA	169.50000	1,695.00	184.00000	1,840.00	168.75000	1,687.50
0510 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 3.164 GM	7,159.68000	22,653.23	7,770.00000	24,584.28	7,020.00000	22,211.28
0515 0711 16102 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" 0.183 GM	7,457.98000	1,364.81	7,970.00000	1,458.51	8,100.00000	1,482.30
0520 0711 16131 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP 1.625 GM	1,789.92000	2,908.62	1,950.00000	3,168.75	4,725.00000	7,678.13
0525 0711 16133 THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP 0.100 GM	3,579.80000	357.98	3,890.00000	389.00	9,450.00000	945.00
0530 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 1.417 GM	7,159.68000	10,145.27	7,800.00000	11,052.60	7,020.00000	9,947.34

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0535 0714 10 1,782.000 SF GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	11.30000	20,136.60	12.50000	22,275.00	13.50000	24,057.00
0003 Signing Section Totals:		**$259,012.45**		**$280,821.26**		**$350,000.61**
SECTION: 0004 Lighting						
0540 0635 2 11 5.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	2,203.50000	11,017.50	2,200.00000	11,000.00	2,600.00000	13,000.00
0545 0715 11211 5.000 EA LUMINAIRE, F&I- REPLACE EXISTING LUMINAIRE ON EXISTING POLE/ARM, ROADWAY, COBRA HEAD	2,034.00000	10,170.00	2,000.00000	10,000.00	3,025.00000	15,125.00
0550 0715500 1 5.000 EA POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	847.50000	4,237.50	800.00000	4,000.00	4,700.00000	23,500.00
0004 Lighting Section Totals:		**$25,425.00**		**$25,000.00**		**$51,625.00**
SECTION: 0005 Signalization						
0555 0630 2 12 4,176.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	45.20000	188,755.20	40.00000	167,040.00	98.00000	409,248.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Signalization						
0560 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL 7.000 PI	13,560.00000	94,920.00	12,300.00000	86,100.00	22,500.00000	157,500.00
0565 0632 7 6 SIGNAL CABLE, REMOVE- INTERSECTION 7.000 PI	565.00000	3,955.00	520.00000	3,640.00	2,800.00000	19,600.00
0570 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE 182.000 EA	2,203.50000	401,037.00	2,200.00000	400,400.00	2,600.00000	473,200.00
0575 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE 7.000 EA	3,955.00000	27,685.00	3,750.00000	26,250.00	4,200.00000	29,400.00
0580 0635 2 30 PULL & SPLICE BOX, INSTALL 6.000 EA	904.00000	5,424.00	985.00000	5,910.00	1,850.00000	11,100.00
0585 0639 1122 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR 7.000 AS	8,475.00000	59,325.00	7,700.00000	53,900.00	11,325.00000	79,275.00
0590 0639 2 1 ELECTRICAL SERVICE WIRE, FURNISH & INSTALL 2,384.000 LF	6.78000	16,163.52	6.50000	15,496.00	17.00000	40,528.00
0595 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE 7.000 EA	2,825.00000	19,775.00	2,550.00000	17,850.00	6,100.00000	42,700.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Signalization						
0600 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL 27.000 EA	2,260.00000	61,020.00	2,050.00000	55,350.00	4,200.00000	113,400.00
0605 0646 1 60 ALUMINUM SIGNALS POLE, REMOVE 13.000 EA	282.50000	3,672.50	255.00000	3,315.00	1,050.00000	13,650.00
0610 0649 21 6 STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50' 1.000 EA	141,250.00000	141,250.00	127,500.00000	127,500.00	148,500.00000	148,500.00
0615 0650 1 14 VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY 6.000 AS	2,034.00000	12,204.00	1,900.00000	11,400.00	2,650.00000	15,900.00
0620 0650 2109 VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED 2.000 EA	734.50000	1,469.00	670.00000	1,340.00	2,000.00000	4,000.00
0625 0653 1 11 PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY 25.000 AS	2,034.00000	50,850.00	1,850.00000	46,250.00	1,605.00000	40,125.00
0630 0653 1 12 PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS 2.000 AS	2,486.00000	4,972.00	2,300.00000	4,600.00	3,000.00000	6,000.00
0635 0653 1 60 PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN 3.000 AS	282.50000	847.50	260.00000	780.00	350.00000	1,050.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Signalization						
0640 0654 2 60 MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, REMOVE COMPLETE SIGN ASSEMBLY 2.000 AS	1,695.00000	3,390.00	1,540.00000	3,080.00	48,500.00000	97,000.00
0645 0660 1110 LOOP DETECTOR INDUCTIVE, F&I, TYPE 10 10.000 EA	282.50000	2,825.00	260.00000	2,600.00	800.00000	8,000.00
0650 0660 2106 LOOP ASSEMBLY, F&I, TYPE F 13.000 AS	2,260.00000	29,380.00	2,100.00000	27,300.00	3,500.00000	45,500.00
0655 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT 1.000 EA	6,215.00000	6,215.00	5,700.00000	5,700.00	14,000.00000	14,000.00
0660 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT 1.000 EA	4,520.00000	4,520.00	4,200.00000	4,200.00	7,700.00000	7,700.00
0665 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD 22.000 EA	565.00000	12,430.00	520.00000	11,440.00	710.00000	15,620.00
0670 0665 1 12 PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE 12.000 EA	2,825.00000	33,900.00	2,600.00000	31,200.00	3,700.00000	44,400.00
0675 0665 1 60 PEDESTRIAN DETECTOR, REMOVE-POLE/PEDESTAL TO REMAIN 8.000 EA	56.50000	452.00	55.00000	440.00	178.00000	1,424.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Signalization						
0680 0670 5140 1.000 AS TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 2070	56,500.00000	56,500.00	52,000.00000	52,000.00	95,000.00000	95,000.00
0685 0670 5600 1.000 AS TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	1,130.00000	1,130.00	1,050.00000	1,050.00	4,200.00000	4,200.00
0690 0684 90102 1.000 EA NETWORK DEVICE, CELLULAR MODEM	3,390.00000	3,390.00	3,100.00000	3,100.00	4,300.00000	4,300.00
0695 0700 3201 5.000 EA SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	1,356.00000	6,780.00	1,230.00000	6,150.00	2,500.00000	12,500.00
0700 0700 3601 7.000 EA SIGN PANEL, REMOVE, UP TO 12 SF	361.60000	2,531.20	260.00000	1,820.00	700.00000	4,900.00
0705 0700 5 22 1.000 EA INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	4,520.00000	4,520.00	4,100.00000	4,100.00	7,425.00000	7,425.00
0005 Signalization Section Totals:		**$1,261,287.92**		**$1,181,301.00**		**$1,967,145.00**
SECTION: 0006 Landscape / Peripheral						
0710 0581 1 2 14.000 EA RELOCATE TREES AND PALMS, PALM, >=14' OF CLEAR TRUNK	5,650.00000	79,100.00	6,140.00000	85,960.00	8,650.00000	121,100.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Landscape / Peripheral						
0715 0590 70 5 (1.000) LS IRRIGATION SYSTEM- MODIFY EXISTING SYSTEM 44393115201	48,025.00000	48,025.00	85,000.00000	85,000.00	185,000.00000	185,000.00
0006 Landscape / Peripheral Section Totals:		**$127,125.00**		**$170,960.00**		**$306,100.00**
SECTION: 0007 Utilities						
0720 0999 26 (1.000) LS LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) 44393115601	16,300.00000	16,300.00	16,300.00000	16,300.00	16,300.00000	16,300.00
0725 0999 26 (1.000) LS LOCAL AGENCY INITIAL CONTINGENCY AMOUNT (DO NOT BID) 44618915601	6,704.00000	6,704.00	6,704.00000	6,704.00	6,704.00000	6,704.00
0730 1050 16004 331.000 LF UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	226.00000	74,806.00	168.00000	55,608.00	625.00000	206,875.00
0735 1060 15 21.000 EA UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	1,813.18000	38,076.78	1,630.00000	34,230.00	3,500.00000	73,500.00
0740 1080 21300 25.000 EA UTILITY FIXTURE, VALVE/METER BOX, INSTALL- BOX FURNISHED BY UTILITY	534.72000	13,368.00	1,940.00000	48,500.00	2,250.00000	56,250.00
0745 1080 24500 73.000 EA UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	955.16000	69,726.68	1,500.00000	109,500.00	1,850.00000	135,050.00

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) FLORIDA ENGINEERING & DEVELOPMENT CORP		(2) STRONGCORE GROUP, LLC		(3) SOUTHERN ROAD & BRIDGE, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0007 Utilities						
0007 Utilities Section Totals:		**$218,981.46**		**$270,842.00**		**$494,679.00**
Contract Grand Totals:		**$9,176,265.71**		**$10,160,693.92**		**13,510,695.40**

Letting: CT250129 January 29, 2025 **Call Order:** 020 **Contract:** T6610

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

A Mirza Rezazadeh 02/11/2025

Manager, Contracts Administration Office