Vendor Ranking

Letting: CT230927 September 27, 2023 10:30 AM **Call Order:** 006 **Contract:** T3854

District: District 3 **Counties:** ESCAMBIA **Fed Aid No:** D323055B

Contract Time: 1365 AVAILABLE DAYS **Project(s):** 44274915201 (*) 44274915601 44274915602

Contract Desc: SR 8 (I-10) OVER SR 10 (US 90A) (NINE MILE RD), BRIDGE NOS.

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	WEBBER, LLC	Responsive	Winning bid	$55,462,468.17	100.00%
2	ANDERSON COLUMBIA CO., INC.	Responsive	Non-Winning Bid	$65,895,914.66	118.81%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

District: District 3 **Counties:** ESCAMBIA **Fed Aid No:** D323055B

Contract Time: 1365 AVAILABLE DAYS **Project(s):** 44274915201 (*)
44274915601
44274915602

Contract Descr: SR 8 (I-10) OVER SR 10 (US 90A) (NINE MILE RD), BRIDGE NOS.

The Improvements under this Contract consist of replacing SR 8 (I-10) OVER SR 10 (US 90A) NINE MILE RD BR NO. 480061 & 480066 in Escambia County with proposed Bridge No. 480305. Also included in this Contract is excavation, embankment, stabilization, base construction, pilings, permanent and temporary walls, approach slabs, bridge substructure and superstructure, asphalt placement, milling and resurfacing, safety and drainage improvements, guardrail, barrier wall, crash cushions, lighting, intelligent transportation systems, signing and pavement markings. Included in this Contract under FPID 442749-1-56-01 is buried electric and buried fiber conduit construction. Included in this Contract under FPID 442749-1-56-02 is water main construction. The summary of pay items for this project is listed in the Plans.

Table "A" to be submitted with the bid.

For projects in excess of $50 million, in addition to meeting all other qualification requirements of Section 337.14, Florida Statutes, and Rule Chapter 14-22, Florida Administrative Code, any Contractor who is not prequalified and in good standing with the Department as of January 1, 2019, must submit evidence which demonstrates satisfactory completion of at least two projects, each in excess of $15 million, for the Florida Department of Transportation or for any other state department of transportation. Acceptability of the evidence related to the two projects is at the sole discretion of the Department.

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (24310.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 44274915201	2,000,000.00000	2,000,000.00	3,600,000.00000	3,600,000.00		
0010 0400 0 11 5.000 CY CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	1,000.00000	5,000.00	6,000.00000	30,000.00		
0015 0400 2 10 506.800 CY CONCRETE CLASS II, APPROACH SLABS	623.36000	315,918.85	1,050.00000	532,140.00		
0020 0400 4 4 1,339.100 CY CONCRETE CLASS IV, SUPERSTRUCTURE	1,023.97000	1,371,198.23	1,350.00000	1,807,785.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0025 0400 4 5 CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE 218.200 CY	1,622.55000	354,040.41	3,500.00000	763,700.00		
0030 0400 4 25 CONCRETE CLASS IV, MASS, SUBSTRUCTURE 969.800 CY	1,141.87000	1,107,385.53	1,700.00000	1,648,660.00		
0035 0400 7 1 BRIDGE DECK GROOVING 5,022.000 SY	3.00000	15,066.00	10.00000	50,220.00		
0040 0400 9 1 BRIDGE DECK PLANING 5,022.000 SY	6.24000	31,337.28	14.00000	70,308.00		
0045 0400147 COMPOSITE NEOPRENE PADS 34.200 CF	1,191.34000	40,743.83	2,500.00000	85,500.00		
0050 0415 1 4 REINFORCING STEEL - BRIDGE SUPERSTRUCTURE 266,260.000 LB	1.22000	324,837.20	1.90000	505,894.00		
0055 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 227,870.000 LB	1.66000	378,264.20	2.15000	489,920.50		
0060 0415 1 9 REINFORCING STEEL- APPROACH SLABS 96,560.000 LB	1.27000	122,631.20	2.00000	193,120.00		
0065 0450 2 72 PREST BEAMS: FLORIDA-I BEAM 72" 8,056.000 LF	400.98000	3,230,294.88	725.00000	5,840,600.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0070 0451 70 162.000 EA PREST SOIL ANCHORS	7,585.98000	1,228,928.76	8,650.00000	1,401,300.00		
0075 0455 34 5 10,140.000 LF PRESTRESSED CONCRETE PILING, 24" SQ	164.55000	1,668,537.00	420.00000	4,258,800.00		
0080 0455133 2 51,212.000 SF SHEET PILING STEEL, TEMPORARY-CRITICAL	32.98000	1,688,971.76	54.00000	2,765,448.00		
0085 0455143 5 755.000 LF TEST PILES-PRESTRESSED CONCRETE,24" SQ	301.15000	227,368.25	650.00000	490,750.00		
0090 0458 1 11 444.000 LF BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	91.41000	40,586.04	100.00000	44,400.00		
0095 0459 71 802.000 SY PILES, POLYETHYLENE SHEETING	18.81000	15,085.62	40.00000	32,080.00		
0100 0521 5 12 442.000 LF CONCRETE TRAFFIC RAILING- BRIDGE, 36" MEDIAN SINGLE SLOPE	115.04000	50,847.68	450.00000	198,900.00		
0105 0521 5 13 882.000 LF CONCRETE TRAFFIC RAILING- BRIDGE, 36" SINGLE-SLOPE	117.92000	104,005.44	300.00000	264,600.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0110 0548 12	13,900.000	92.62000	1,287,418.00	135.00000	1,876,500.00	
RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF					
0115 0548 13	23,716.000	26.13000	619,699.08	50.00000	1,185,800.00	
RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	SF					
0120 0630 2 16	2,961.000	20.00000	59,220.00	25.00000	74,025.00	
CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF					
0125 0635 3 13	6.000	975.88000	5,855.28	4,500.00000	27,000.00	
JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA					
0001 Structures Section Totals:			**$16,293,240.52**		**$28,237,450.50**	
SECTION: 0002 Roadway						
0130 0101 1	(1.000)	5,500,000.00000	5,500,000.00	6,700,000.00000	6,700,000.00	
MOBILIZATION 44274915201	LS					
0135 0102 1	(1365.000)	5,380,000.00000	5,380,000.00	2,700,000.00000	2,700,000.00	
MAINTENANCE OF TRAFFIC 44274915201	DA (LS)					
0140 0102 2200	(23995.000)	3,000,000.00000	3,000,000.00	1,800,000.00000	1,800,000.00	
SPECIAL DETOUR- TEMPORARY PAVEMENT 44274915201	SY (LS)					

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0145 0102 2300 (39005.000) CY (LS) SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE 44274915201	6,000,000.00000	6,000,000.00	6,050,000.00000	6,050,000.00		
0150 0102 14 669.000 HR TRAFFIC CONTROL OFFICER	90.00000	60,210.00	100.00000	66,900.00		
0155 0102 60 97,900.000 ED WORK ZONE SIGN	0.39000	38,181.00	0.44000	43,076.00		
0160 0102 71 13 3,090.000 LF TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	75.00000	231,750.00	85.00000	262,650.00		
0165 0102 71 15 7,350.000 LF TEMPORARY BARRIER, F&I, ANCHORED	60.00000	441,000.00	68.00000	499,800.00		
0170 0102 71 16 5,747.000 LF TEMPORARY BARRIER, F&I, FREE STANDING	55.00000	316,085.00	60.00000	344,820.00		
0175 0102 71 23 2,364.000 LF TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	25.00000	59,100.00	30.00000	70,920.00		
0180 0102 71 25 29,751.000 LF TEMPORARY BARRIER, RELOCATE, ANCHORED	25.00000	743,775.00	29.00000	862,779.00		
0185 0102 71 26 20,760.000 LF TEMPORARY BARRIER, RELOCATE, FREE STANDING	25.00000	519,000.00	29.00000	602,040.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0190 0102 74 1 374,815.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.17000	63,718.55	0.19000	71,214.85		
0195 0102 89 1 15.000 LO TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	1,500.00000	22,500.00	2,950.00000	44,250.00		
0200 0102 99 5,460.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	15.75000	85,995.00	17.85000	97,461.00		
0205 0102104 2,730.000 ED TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	20.00000	54,600.00	22.66000	61,861.80		
0210 0102107 1 2,730.000 ED TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	20.00000	54,600.00	22.66000	61,861.80		
0215 0102115 2,160.000 ED TYPE III BARRICADE	0.75000	1,620.00	0.85000	1,836.00		
0220 0104 1 591.000 SY ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	6.88000	4,066.08	10.20000	6,028.20		
0225 0104 10 3 3,914.000 LF SEDIMENT BARRIER	2.35000	9,197.90	11.33000	44,345.62		
0230 0104 15 10.000 EA SOIL TRACKING PREVENTION DEVICE	4,571.88000	45,718.80	12,126.04000	121,260.40		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0235 0104 18 8.000 EA INLET PROTECTION SYSTEM	198.02000	1,584.16	1,133.28000	9,066.24		
0240 0107 1 1,140.150 AC LITTER REMOVAL	75.00000	85,511.25	198.33000	226,125.95		
0245 0107 2 1,055.220 AC MOWING	66.77000	70,457.04	198.33000	209,281.78		
0250 0108 1 (1.000) LS MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 44274915201	70,000.00000	70,000.00	130,000.00000	130,000.00		
0255 0108 2 (1.000) LS MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 44274915201	70,000.00000	70,000.00	245,000.00000	245,000.00		
0260 0110 1 1 (20.400) AC (LS) CLEARING & GRUBBING 44274915201	4,000,000.00000	4,000,000.00	2,500,000.00000	2,500,000.00		
0265 0110 4 10 5,372.000 SY REMOVAL OF EXISTING CONCRETE	44.52000	239,161.44	25.00000	134,300.00		
0270 0110 21 2,000.000 LF TREE PROTECTION BARRIER	7.31000	14,620.00	1.70000	3,400.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate *( ) indicates item is bid as Lump Sum*	Quantity Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway							
0275 0120 1 REGULAR EXCAVATION	24,297.000 CY	15.03000	365,183.91	28.00000	680,316.00		
0280 0120 4 SUBSOIL EXCAVATION	4,795.000 CY	40.15000	192,519.25	35.00000	167,825.00		
0285 0120 6 EMBANKMENT	77,797.000 CY	32.85000	2,555,631.45	28.50000	2,217,214.50		
0290 0160 4 TYPE B STABILIZATION	44,443.000 SY	7.48000	332,433.64	13.65000	606,646.95		
0295 0285709 OPTIONAL BASE, BASE GROUP 09	15,173.000 SY	53.00000	804,169.00	45.00000	682,785.00		
0300 0285711 OPTIONAL BASE, BASE GROUP 11	23,753.000 SY	52.50000	1,247,032.50	51.00000	1,211,403.00		
0305 0285759 OPTIONAL BASE- GRADED AGGREGATE, 18" FOR PROJECT 442749-1-52-01	1,153.000 SY	145.00000	167,185.00	130.00000	149,890.00		
0310 0327 70 6 MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	3,634.000 SY	15.00000	54,510.00	4.50000	16,353.00		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0315 0327 70 11 — 11,345.000 SY MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	14.00000	158,830.00	4.50000	51,052.50		
0320 0327 70 12 — 10,094.000 SY MILLING EXISTING ASPHALT PAVEMENT, 1 1/4" AVG DEPTH	6.50000	65,611.00	4.50000	45,423.00		
0325 0334 1 53 — 96.600 TN SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	390.54000	37,726.16	375.00000	36,225.00		
0330 0334 1 55 — 10,133.200 TN SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	163.68000	1,658,602.18	190.00000	1,925,308.00		
0335 0337 7 25 — 1,554.000 TN ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	302.10000	469,463.40	420.00000	652,680.00		
0340 0337 7 82 — 742.300 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	252.96000	187,772.21	268.00000	198,936.40		
0345 0339 1 — 423.000 TN MISCELLANEOUS ASPHALT PAVEMENT	310.96000	131,536.08	385.00000	162,855.00		
0350 0425 1521 — 1.000 EA INLETS, DT BOT, TYPE C,<10'	6,822.98000	6,822.98	10,543.98000	10,543.98		
0355 0425 1541 — 6.000 EA INLETS, DT BOT, TYPE D, <10'	7,020.42000	42,122.52	14,112.67000	84,676.02		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0360 0425 1701 INLETS, GUTTER, TYPE S, <10' 5.000 EA	7,174.79000	35,873.95	13,002.06000	65,010.30		
0365 0425 1702 INLETS, GUTTER, TYPE S, >10' 3.000 EA	9,475.92000	28,427.76	20,895.32000	62,685.96		
0370 0425 2 61 MANHOLES, P-8, <10' 4.000 EA	5,051.81000	20,207.24	12,974.86000	51,899.44		
0375 0425 2 62 MANHOLES, P-8, >10' 3.000 EA	5,862.80000	17,588.40	18,975.55000	56,926.65		
0380 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD 1,125.000 LF	95.61000	107,561.25	228.92000	257,535.00		
0385 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD 834.000 LF	128.22000	106,935.48	273.12000	227,782.08		
0390 0430611125 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE 1.000 EA	6,008.90000	6,008.90	7,405.94000	7,405.94		
0395 0430611325 U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE 5.000 EA	6,119.59000	30,597.95	7,513.61000	37,568.05		
0400 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD 1.000 EA	2,965.37000	2,965.37	3,829.34000	3,829.34		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0405 0430982129 MITERED END SECTION, OPTIONAL ROUND, 24" CD 1.000 EA	3,412.15000	3,412.15	4,193.12000	4,193.12		
0410 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM 20.000 LF	90.00000	1,800.00	283.32000	5,666.40		
0415 0520 1 7 CONCRETE CURB & GUTTER, TYPE E 451.000 LF	72.00000	32,472.00	57.80000	26,067.80		
0420 0520 5 11 TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE 716.000 LF	80.00000	57,280.00	67.99000	48,680.84		
0425 0520 6 SHOULDER GUTTER- CONCRETE 2,008.000 LF	57.00000	114,456.00	62.33000	125,158.64		
0430 0521 1 11 MEDIAN CONCRETE BARRIER, 38" HEIGHT 442.000 LF	122.46000	54,127.32	750.00000	331,500.00		
0435 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 407.000 SY	80.00000	32,560.00	93.38000	38,005.66		
0440 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 16.000 SY	105.00000	1,680.00	128.01000	2,048.16		
0445 0524 1 2 CONCRETE DITCH PAVEMENT, NON REINFORCED, 4" 1,746.000 SY	146.90000	256,487.40	128.06000	223,592.76		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0450 0536 1 1 — 3,275.000 LF GUARDRAIL -ROADWAY, GENERAL TL-3	28.66000	93,861.50	32.30000	105,782.50		
0455 0536 8112 — 4.000 EA GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	3,570.19000	14,280.76	4,023.13000	16,092.52		
0460 0536 8113 — 2.000 EA GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	2,262.80000	4,525.60	2,549.87000	5,099.74		
0465 0536 73 — 6,183.000 LF GUARDRAIL REMOVAL	2.97000	18,363.51	3.97000	24,546.51		
0470 0536 85 20 — 6.000 EA GUARDRAIL END TREATMENT-TRAILING ANCHORAGE	2,463.93000	14,783.58	2,776.53000	16,659.18		
0475 0536 85 24 — 5.000 EA GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL	4,274.17000	21,370.85	4,816.41000	24,082.05		
0480 0544 3 1 — 2.000 EA CRASH CUSHION, TL-3, NARROW	25,695.29000	51,390.58	43,858.38000	87,716.76		
0485 0570 1 1 — 42,897.000 SY PERFORMANCE TURF	1.69000	72,495.93	1.42000	60,913.74		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0490 0570 1 2 PERFORMANCE TURF, SOD 26,811.000 SY	3.96000	106,171.56	3.06000	82,041.66		
0495 0571 1 11 PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1 8,639.000 SY	11.23000	97,015.97	11.26000	97,275.14		
0500 0706 1 3 RAISED PAVEMENT MARKER, TYPE B 17,925.000 EA	4.62000	82,813.50	4.70000	84,247.50		
0505 0710 11101 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" 9.478 GM	1,200.00000	11,373.60	1,699.90000	16,111.65		
0510 0710 11102 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" 1.264 GM	1,500.00000	1,896.00	1,905.15000	2,408.11		
0515 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" 147.000 LF	6.00000	882.00	2.83000	416.01		
0520 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE 6.939 GM	950.00000	6,592.05	1,359.93000	9,436.55		
0525 0710 11141 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" 0.131 GM	950.00000	124.45	1,359.93000	178.15		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0530 0710 11170 14.000 EA PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	50.00000	700.00	56.66000	793.24		
0535 0710 11201 8.207 GM PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1,200.00000	9,848.40	1,699.90000	13,951.08		
0540 0999 20 1 14.000 DA DISPUTES REVIEW BOARD, MEETING-DO NOT BID	3,900.00000	54,600.00	3,900.00000	54,600.00		
0545 0999 20 2 2.000 EA DISPUTES REVIEW BOARD, HEARING-DO NOT BID	4,500.00000	9,000.00	4,500.00000	9,000.00		
0550 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 44274915201	150,000.00000	150,000.00	150,000.00000	150,000.00		
0002 Roadway Section Totals:		**$37,392,133.51**		**$35,307,320.22**		
SECTION: 0003 Signing						
0555 0546 72 1 2.452 GM GROUND-IN RUMBLE STRIPS, 16"	1,351.00000	3,312.65	8,781.49000	21,532.21		
0560 0700 1 11 8.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	500.00000	4,000.00	566.64000	4,533.12		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0565 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF 4.000 AS	2,000.00000	8,000.00	2,266.55000	9,066.20		
0570 0700 1 50 SINGLE POST SIGN, RELOCATE 4.000 AS	200.00000	800.00	226.66000	906.64		
0575 0700 1 60 SINGLE POST SIGN, REMOVE 19.000 AS	50.00000	950.00	56.66000	1,076.54		
0580 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF 2.000 AS	7,800.00000	15,600.00	8,839.55000	17,679.10		
0585 0700 2 15 MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF 1.000 AS	10,000.00000	10,000.00	11,332.75000	11,332.75		
0590 0700 2 17 MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF 2.000 AS	22,800.00000	45,600.00	25,838.66000	51,677.32		
0595 0700 2 50 MULTI- POST SIGN, GROUND MOUNT, RELOCATE 1.000 AS	12,000.00000	12,000.00	13,599.30000	13,599.30		
0600 0700 2 60 MULTI- POST SIGN, REMOVE 4.000 AS	1,200.00000	4,800.00	1,359.93000	5,439.72		
0605 0700 13 12 RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 2' 2.000 EA	75.00000	150.00	84.99000	169.98		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0610 0700 13 15 RETROREFLECTIVE SIGN STRIP-FURNISH AND INSTALL, 5' 4.000 EA	85.00000	340.00	96.33000	385.32		
0615 0704 1 2 TUBULAR MARKER, DURABLE, 36" YELLOW POST 2.000 EA	165.00000	330.00	186.99000	373.98		
0620 0705 11 2 DELINEATOR, NON-FLEXIBLE 71.000 EA	75.00000	5,325.00	84.99000	6,034.29		
0625 0706 1 3 RAISED PAVEMENT MARKER, TYPE B 976.000 EA	4.62000	4,509.12	5.67000	5,533.92		
0630 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE 7.000 SF	20.00000	140.00	11.33000	79.31		
0635 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 44274915201 (1.000) LS	16,943.30000	16,943.30	28,331.87000	28,331.87		
0640 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS 710.000 LF	7.00000	4,970.00	6.80000	4,828.00		
0645 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 86.000 LF	9.00000	774.00	11.33000	974.38		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0650 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.041 GM	6,000.00000	246.00	4,533.09000	185.86		
0655 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL 10.000 EA	140.00000	1,400.00	283.32000	2,833.20		
0660 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW 31.000 EA	80.00000	2,480.00	113.32000	3,512.92		
0665 0711 11241 THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" 0.048 GM	6,000.00000	288.00	4,533.09000	217.59		
0670 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAGE 3.000 EA	250.00000	750.00	283.32000	849.96		
0675 0711 14170 THERMOPLASTIC, PREFORMED, WHITE, ARROW 2.000 EA	200.00000	400.00	226.66000	453.32		
0680 0711 15101 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6" 2.407 GM	4,400.00000	10,590.80	8,499.56000	20,458.44		
0685 0711 15102 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8" 0.518 GM	8,000.00000	4,144.00	10,199.47000	5,283.33		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0690 0711 15131 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP 2.043 GM	4,400.00000	8,989.20	3,399.83000	6,945.85		
0695 0711 15201 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6" 2.268 GM	4,400.00000	9,979.20	8,499.56000	19,277.00		
0700 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.955 GM	4,400.00000	4,202.00	6,233.02000	5,952.53		
0705 0711 16102 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8" 0.243 GM	8,000.00000	1,944.00	8,499.56000	2,065.39		
0710 0711 16131 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP 0.404 GM	4,400.00000	1,777.60	2,833.19000	1,144.61		
0715 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 0.438 GM	4,400.00000	1,927.20	6,233.02000	2,730.06		
0720 0713103101 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES 0.129 GM	28,000.00000	3,612.00	45,330.98000	5,847.70		
0725 0713103131 PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES 0.129 GM	14,000.00000	1,806.00	22,665.49000	2,923.85		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0730 0713103201 0.129 GM PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	28,000.00000	3,612.00	45,330.98000	5,847.70		
0735 0713103331 0.129 GM PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	12,000.00000	1,548.00	9,689.50000	1,249.95		
0003 Signing Section Totals:		**$198,240.07**		**$271,333.21**		
SECTION: 0004 Lighting						
0740 0630 2 11 2,167.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	13.00000	28,171.00	14.73000	31,919.91		
0745 0630 2 12 1,768.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	33.00000	58,344.00	37.40000	66,123.20		
0750 0630 2 15 802.000 LF CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	30.00000	24,060.00	34.00000	27,268.00		
0755 0630 2 65 803.000 LF CONDUIT, REMOVE, BRIDGE MOUNT	12.00000	9,636.00	13.60000	10,920.80		
0760 0635 2 11 14.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	2,255.00000	31,570.00	2,555.54000	35,777.56		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Lighting						
0765 0635 3 12 — 17.000 EA JUNCTION BOX, FURNISH & INSTALL, MOUNTED	760.00000	12,920.00	861.29000	14,641.93		
0770 0635 3 13 — 9.000 EA JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	375.00000	3,375.00	424.98000	3,824.82		
0775 0715 1 12 — 6,429.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	5.38000	34,588.02	6.10000	39,216.90		
0780 0715 1 13 — 13,924.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	5.10000	71,012.40	5.78000	80,480.72		
0785 0715 1 14 — 7,934.000 LF LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	6.65000	52,761.10	7.54000	59,822.36		
0790 0715 1 60 — 25,973.000 LF LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	1.00000	25,973.00	1.13000	29,349.49		
0795 0715 7 21 — 1.000 EA LOAD CENTER, REWORK, SECONDARY VOLTAGE	5,500.00000	5,500.00	6,233.02000	6,233.02		
0800 0715 11125 — 12.000 EA LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	1,800.00000	21,600.00	2,039.89000	24,478.68		
0805 0715 11500 — 8.000 EA LUMINAIRE, REMOVE	300.00000	2,400.00	339.98000	2,719.84		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0004 Lighting						
0004 Lighting Section Totals:		**$381,910.52**		**$432,777.23**		
SECTION: 0005 Utilities						
0810 0630 2 11 1,140.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	17.27000	19,687.80	38.67000	44,083.80		
0815 0630 2 12 855.000 LF CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	37.85000	32,361.75	211.74000	181,037.70		
0820 1000 6 (1.000) LS UTILITY WORK- JPA/UTILITY AGREEMENT, WATER 44274915602	275,820.00000	275,820.00	437,007.75000	437,007.75		
0005 Utilities Section Totals:		**$327,869.55**		**$662,129.25**		
SECTION: 0006 Intelligent Transportation System						
0825 0611 1 1 1.120 MI ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	10,000.00000	11,200.00	11,332.75000	12,692.68		
0830 0611 2 2 3.000 EA ITSFM LOCATION DOCUMENTATION- ITS SITE	5,500.00000	16,500.00	6,233.02000	18,699.06		
0835 0630 2 11 904.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	17.00000	15,368.00	19.27000	17,420.08		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate *( ) indicates item is bid as Lump Sum*	Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Intelligent Transportation System							
0840 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	1,648.000 LF	33.00000	54,384.00	37.40000	61,635.20		
0845 0630 2 14 CONDUIT, FURNISH & INSTALL, ABOVEGROUND	50.000 LF	15.00000	750.00	17.00000	850.00		
0850 0633 1122 FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	2,676.000 LF	7.50000	20,070.00	8.50000	22,746.00		
0855 0633 1420 FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	255.000 LF	20.00000	5,100.00	22.66000	5,778.30		
0860 0633 1620 FIBER OPTIC CABLE, REMOVE, UNDERGROUND	495.000 LF	2.00000	990.00	2.27000	1,123.65		
0865 0633 2 31 FIBER OPTIC CONNECTION, INSTALL, SPLICE	8.000 EA	100.00000	800.00	113.32000	906.56		
0870 0633 2 32 FIBER OPTIC CONNECTION, INSTALL, TERMINATION	96.000 EA	100.00000	9,600.00	113.32000	10,878.72		
0875 0633 3 14 FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	8.000 EA	355.00000	2,840.00	402.32000	3,218.56		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Intelligent Transportation System						
0880 0633 3 16 FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED 5.000 EA	3,500.00000	17,500.00	3,966.46000	19,832.30		
0885 0633 8 1 MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL 283.000 LF	13.00000	3,679.00	14.73000	4,168.59		
0890 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE 20.000 EA	2,100.00000	42,000.00	2,379.87000	47,597.40		
0895 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE 8.000 EA	3,800.00000	30,400.00	4,306.45000	34,451.60		
0900 0639 2 1 ELECTRICAL SERVICE WIRE, FURNISH & INSTALL 2,369.000 LF	6.00000	14,214.00	6.80000	16,109.20		
0905 0639 2 4 ELECTRICAL SERVICE WIRE, RELOCATE 241.000 LF	10.00000	2,410.00	11.33000	2,730.53		
0910 0639 2 6 ELECTRICAL SERVICE WIRE, REMOVE 819.000 LF	1.00000	819.00	1.13000	925.47		
0915 0639 3 11 ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT 4.000 EA	600.00000	2,400.00	679.97000	2,719.88		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Intelligent Transportation System						
0920 0639 6121 4.000 EA ELECTRICAL POWER SERVICE-TRANSFORMER, F&I, 5-10 KVA, SINGLE PHASE, COPPER WINDINGS	9,000.00000	36,000.00	10,199.47000	40,797.88		
0925 0641 2 12 2.000 EA PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	3,500.00000	7,000.00	3,966.46000	7,932.92		
0930 0641 2 80 2.000 EA PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	9,000.00000	18,000.00	10,199.47000	20,398.94		
0935 0641 3169 2.000 EA CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	37,000.00000	74,000.00	41,931.17000	83,862.34		
0940 0660 3 11 1.000 EA VEHICLE DETECTION SYSTEM-MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	2,500.00000	2,500.00	2,833.19000	2,833.19		
0945 0660 3 12 1.000 EA VEHICLE DETECTION SYSTEM-MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	12,000.00000	12,000.00	13,599.30000	13,599.30		
0950 0660 3 41 2.000 EA VEHICLE DETECTION SYSTEM-MICROWAVE, RELOCATE CABINET EQUIPMENT	2,000.00000	4,000.00	2,266.55000	4,533.10		
0955 0660 3 42 2.000 EA VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	550.00000	1,100.00	623.30000	1,246.60		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Intelligent Transportation System						
0960 0660 7 22 VEHICLE DETECTION SYSTEM-WRONG WAY FOR EXIT RAMP, 3 OR MORE LANES, AC POWERED 2.000 EA	190,000.00000	380,000.00	215,322.22000	430,644.44		
0965 0676 2122 ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D 1.000 EA	8,500.00000	8,500.00	9,632.84000	9,632.84		
0970 0676 2143 ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D 2.000 EA	13,000.00000	26,000.00	14,732.57000	29,465.14		
0975 0676 2400 ITS CABINET, RELOCATE 1.000 EA	2,000.00000	2,000.00	2,266.55000	2,266.55		
0980 0682 1133 ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION 1.000 EA	8,000.00000	8,000.00	9,066.19000	9,066.19		
0985 0682 1400 ITS CCTV CAMERA, RELOCATE 1.000 EA	1,000.00000	1,000.00	1,133.28000	1,133.28		
0990 0684 1 1 MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL 3.000 EA	4,500.00000	13,500.00	5,099.73000	15,299.19		
0995 0684 2 1 DEVICE SERVER, FURNISH & INSTALL 1.000 EA	950.00000	950.00	1,076.61000	1,076.61		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) WEBBER, LLC		(2) ANDERSON COLUMBIA CO., INC.			
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0006 Intelligent Transportation System						
1000 0685 1 11 3.000 EA UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	7,500.00000	22,500.00	8,499.56000	25,498.68		
1005 0685 2 1 1.000 EA REMOTE POWER MANAGEMENT UNIT-RPMU, FURNISH AND INSTALL	1,000.00000	1,000.00	1,133.28000	1,133.28		
0006 Intelligent Transportation System Section Totals:		**$869,074.00**		**$984,904.25**		
Contract Grand Totals:		**$55,462,468.17**		**$65,895,914.66**		

Letting: CT230927 September 27, 2023 **Call Order:** 006 **Contract:** T3854

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

A Mirza Rezazadeh 10/5/2023

Manager, Contracts Administration Office