LBTHEAD VENDOR RANKING

CALL ORDER : 019 PROPOSAL ID : T6047 PROPOSAL DESC :
LETTING DATE : 04/28/04 10:30 A.M. DISTRICT : 06
SET-ASIDE : U/R CODE : The improvements under this contract consist of access and transit improvements to the Miami Intermodal Center, located on SR 953.
CONTRACT TIME : 1100 CALENDAR DAYS

FINPROJ(S) :	24993725201	F.A. NO. :	N/A
	25023425201		N/A
	25023445201		N/A
	25023455601		N/A
	40832015201		N/A
	40883415201 (*)		N/A

COUNTIES : MIAMI-DADE

LOCAL NAME(*) : MIAMI INTERMODAL CTR S.R. NO.(*) : SR 953 US NO.(*) :
PROJ LIMITS(*): (MIC) MIC/MIA INTERCHANGE

A+B BREAKOUT

LBTABAB

RANK	VENDOR NAME	CALENDAR DAYS	STANDARD BID (A)	TIME BID (B)	TOTAL BID (A+B)
1	GILBERT SOUTHERN CORP.	1100	$ 71,642,526.49	$ 11,000,000.00	$ 82,642,526.49
2	DE MOYA GROUP INC. (THE)	1400	$ 77,979,734.07	$ 14,000,000.00	$ 91,979,734.07
3	AMEC CIVIL, LLC	1600	$ 77,496,203.08	$ 16,000,000.00	$ 93,496,203.08
4	ASTALDI CONSTRUCTION CORPORATION	1550	$ 81,024,195.68	$ 15,500,000.00	$ 96,524,195.68

LBTAVR1 VENDOR RANKING

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	GILBERT SOUTHERN CORP.	Responsive	Winning bid	$ 82,642,526.49	0.000%
2	DE MOYA GROUP INC. (THE)	Responsive		$ 91,979,734.07	11.298%
3	AMEC CIVIL, LLC	Responsive		$ 93,496,203.08	13.133%
4	ASTALDI CONSTRUCTION CORPORATION	Responsive		$ 96,524,195.68	16.797%

LBTHEAD TABULATION OF BIDS

CALL ORDER : 019 PROPOSAL ID : T6047 PROPOSAL DESC :
LETTING DATE : 04/28/04 10:30 A.M. DISTRICT : 06
SET-ASIDE : U/R CODE : The improvements under this contract consist of access and
CONTRACT TIME : 1100 CALENDAR DAYS transit improvements to the Miami Intermodal Center, located on SR 953.

FINPROJ(S) : 24993725201 F.A. NO. : N/A COUNTIES : MIAMI-DADE
25023425201 N/A
25023445201 N/A
25023455601 N/A
40832015201 N/A
40883415201 (*) N/A

LOCAL NAME(*) : MIAMI INTERMODAL CTR S.R. NO.(*) : SR 953 US NO.(*) :
PROJ LIMITS(*): (MIC) MIC/MIA INTERCHANGE

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0101 1 MOBILIZATION 40832015201	LUMP	50000.00000	50000.00	250000.00000	250000.00	400000.00000	400000.00
0010 0101 1 MOBILIZATION 24993725201	LUMP	250000.00000	250000.00	575000.00000	575000.00	3800000.00000	3800000.00
0015 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	9292.000 LS	140000.00000	140000.00	250000.00000	250000.00	380000.00000	380000.00
0020 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	8596.000 LS	190000.00000	190000.00	250000.00000	250000.00	380000.00000	380000.00
0025 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	9292.000 LS	160000.00000	160000.00	250000.00000	250000.00	290000.00000	290000.00
0030 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	8596.000 LS	220000.00000	220000.00	250000.00000	250000.00	290000.00000	290000.00
0035 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	7100.000 LS	190000.00000	190000.00	250000.00000	250000.00	195000.00000	195000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0040 0110 3 STRUCTURE REMOVAL OF EXISTING 25023445201	10473.000 LS	220000.00000	220000.00	250000.00000	250000.00	290000.00000	290000.00
0045 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	13362.000 LS	140000.00000	140000.00	250000.00000	250000.00	190000.00000	190000.00
0050 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	5260.000 LS	110000.00000	110000.00	250000.00000	250000.00	195000.00000	195000.00
0055 0121 70 FLOWABLE FILL	103.000 CY	260.00000	26780.00	300.00000	30900.00	250.00000	25750.00
0060 0400 2 4 CONC CLASS II(SUPERSTRUCTURE)	6458.470 CY	920.00000	5941792.40	600.00000	3875082.00	850.00000	5489699.50
0065 0400 2 10 CONC CLASS II (APPROACH SLABS)	1428.920 CY	320.00000	457254.40	375.00000	535845.00	288.00000	411528.96
0070 0400 3 20 CONC CLASS III (SEAL)	1359.100 CY	400.00000	543640.00	225.00000	305797.50	800.00000	1087280.00
0075 0400 4 5 CONC CLASS IV (SUBSTRUCTURE)	1349.580 CY	920.00000	1241613.60	850.00000	1147143.00	1400.00000	1889412.00
0080 0400 4 8 CONC CLASS IV (BULKHEAD)	205.170 CY	750.00000	153877.50	1000.00000	205170.00	1100.00000	225687.00
0085 0400 4 11 CONC CLASS IV (RETAINING WALLS)	22.000 CY	1100.00000	24200.00	1000.00000	22000.00	1100.00000	24200.00
0090 0400 4 25 CONC CLASS IV (MASS)(SUBSTRUCTURE)	5301.530 CY	700.00000	3711071.00	425.00000	2253150.25	800.00000	4241224.00
0095 0400 7 BRIDGE FLOOR GROOVING	23296.000 SY	2.25000	52416.00	5.00000	116480.00	1.60000	37273.60
0096 0400 95 COFFERDAM	5.000 EA	180000.00000	900000.00	20000.00000	100000.00	70000.00000	350000.00
0100 0400147 COMPOSITE NEOPRENE PADS	67.220 CF	450.00000	30249.00	1200.00000	80664.00	700.00000	47054.00
0105 0415 1 3 REINF STEEL (RETAINING WALL)	3450.000 LB	0.90000	3105.00	2.00000	6900.00	0.49000	1690.50

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0110 0415 1 4 REINF STEEL (SUPERSTRUCTURE)	1933746.000 LB	0.90000	1740371.40	0.90000	1740371.40	0.49000	947535.54
0115 0415 1 5 REINF STEEL (SUBSTRUCTURE)	1294447.000 LB	0.90000	1165002.30	0.90000	1165002.30	0.52000	673112.44
0120 0415 1 8 REINF STEEL (BULKHEAD)	16954.000 LB	0.90000	15258.60	0.90000	15258.60	0.49000	8307.46
0125 0415 1 9 REINF STEEL (APPROACH SLABS)	272156.000 LB	0.90000	244940.40	0.90000	244940.40	0.49000	133356.44
0130 0450 1 1 PREST BEAMS (TYPE II)	2799.330 LF	85.00000	237943.05	90.00000	251939.70	71.00000	198752.43
0135 0450 1 2 PREST BEAMS (TYPE III)	5817.330 LF	105.00000	610819.65	110.00000	639906.30	84.00000	488655.72
0140 0451 70 PREST SOIL ANCHORS	43.000 EA	1200.00000	51600.00	1.00000	43.00	2040.00000	87720.00
0145 0451 70 1 PREST SOIL ANCHOR (PERFORMANCE TEST)	9.000 EA	100.00000	900.00	1.00000	9.00	200.00000	1800.00
0150 0451 70 2 PREST SOIL ANCHOR (CREEP TEST)	2.000 EA	400.00000	800.00	1.00000	2.00	500.00000	1000.00
0155 0455 34 3 CONCRETE PILING PRESTRESSED (18" SQ.)	46703.900 LF	0.01000	467.04	20.00000	934078.00	34.00000	1587932.60
0160 0455 34 5 CONCRETE PILING PRESTRESSED (24" SQ.)	4317.500 LF	0.01000	43.18	40.00000	172700.00	60.00000	259050.00
0165 0455 87 ANCHOR BAR STEEL	25.000 EA	2000.00000	50000.00	2000.00000	50000.00	2000.00000	50000.00
0170 0455 88 7 DRILLED SHAFT (72" DIA)	1789.000 LF	430.00000	769270.00	250.00000	447250.00	300.00000	536700.00
0175 0455103130 TEST LOAD (STATNAMIC)(COMPRESSION)(3000 TONS)	2.000 EA	63000.00000	126000.00	75000.00000	150000.00	160000.00000	320000.00
0180 0455107 7 CASING (72" DIA)	180.000 LF	300.00000	54000.00	300.00000	54000.00	360.00000	64800.00
0185 0455122 7 EXCAVATION UNCLASSIFIED SHAFT (72" DIA)	1789.000 LF	200.00000	357800.00	250.00000	447250.00	460.00000	822940.00
0190 0455133 SHEET PILING STEEL	22891.000 SF	18.00000	412038.00	20.00000	457820.00	18.00000	412038.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0195 0455133 1 SHEET PILING STEEL (TEMPORARY)	37545.000 SF	11.00000	412995.00	0.01000	375.45	12.00000	450540.00
0200 0455137 TEST LOAD(DYNAMIC)	47.000 EA	1250.00000	58750.00	2500.00000	117500.00	750.00000	35250.00
0205 0455142 CROSSHOLE SONIC LOGGING	14.000 EA	2200.00000	30800.00	3500.00000	49000.00	4500.00000	63000.00
0206 0521 5 20 CNC TRAF RAIL BARRIER BRG(F-SHAPED W/ SNB BAR WALL 8' HT	134.000 LF	300.00000	40200.00	300.00000	40200.00	500.00000	67000.00
0210 0455143 3 TEST PILES (PRESTRESSED CONCRETE) (18" SQ.)	3829.100 LF	0.01000	38.29	50.00000	191455.00	65.00000	248891.50
0215 0455143 5 TEST PILES (PRESTRESSED CONCRETE) (24" SQ.)	430.500 LF	0.01000	4.31	100.00000	43050.00	140.00000	60270.00
0220 0459 71 POLYETHYLENE SHEETING ON CONCRETE PILES	2413.530 SY	3.00000	7240.59	9.00000	21721.77	14.00000	33789.42
0225 0460 2 1 STRUCT STEEL (CARBON) 24993725201	79950.000 LS	570000.00000	570000.00	1400000.00000	1400000.00	132000.00000	132000.00
0230 0460 2 1 STRUCT STEEL (CARBON) 40883415201	14733.000 LS	60000.00000	60000.00	800000.00000	800000.00	91300.00000	91300.00
0235 0460 2 1 STRUCT STEEL (CARBON) 40883415201	53300.000 LS	110000.00000	110000.00	600000.00000	600000.00	60500.00000	60500.00
0240 0460 2 1 STRUCT STEEL (CARBON) 40883415201	60300.000 LS	570000.00000	570000.00	600000.00000	600000.00	110000.00000	110000.00
0245 0460 2 1 STRUCT STEEL (CARBON) 25023445201	188884.000 LS	70000.00000	70000.00	1670000.00000	1670000.00	176000.00000	176000.00
0250 0460 2 1 STRUCT STEEL (CARBON) 40883415201	175900.000 LS	100000.00000	100000.00	280000.00000	280000.00	38500.00000	38500.00
0255 0460 2 1 STRUCT STEEL (CARBON) 40883415201	19523.000 LS	570000.00000	570000.00	280000.00000	280000.00	100000.00000	100000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0260 0460 2 2 STRUCT STEEL (LOW ALLOY) 24993725201	1724374.000 LS	1300000.00000	1300000.00	1400000.00000	1400000.00	2750000.00000	2750000.00
0265 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	1044000.000 LS	550000.00000	550000.00	800000.00000	800000.00	2020000.00000	2020000.00
0270 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	385897.000 LS	1800000.00000	1800000.00	600000.00000	600000.00	900000.00000	900000.00
0275 0460 2 2 STRUCT STEEL (LOW ALLOY) 25023445201	2094767.000 LS	3000000.00000	3000000.00	1670000.00000	1670000.00	4250000.00000	4250000.00
0280 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	791400.000 LS	3600000.00000	3600000.00	600000.00000	600000.00	1300000.00000	1300000.00
0285 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	333314.000 LS	650000.00000	650000.00	280000.00000	280000.00	510000.00000	510000.00
0290 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	703600.000 LS	1300000.00000	1300000.00	1280000.00000	1280000.00	590000.00000	590000.00
0295 0460 2 13 STRUCT STEEL (BOLTS, NUTS, WASHERS & PLATES) 24993725201	67707.000 LS	75000.00000	75000.00	100000.00000	100000.00	450000.00000	450000.00
0300 0460 7 4 EXPANSION JOINT SEAL (STRIP ELAST)	380.000 LF	150.00000	57000.00	160.00000	60800.00	90.00000	34200.00
0305 0461113 12 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(251-500 KIPS)	6.000 EA	2800.00000	16800.00	6000.00000	36000.00	2500.00000	15000.00
0310 0461113 14 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(751-1000 KIPS)	3.000 EA	4100.00000	12300.00	6000.00000	18000.00	4500.00000	13500.00
0315 0461113 15 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(1000-1250 KIPS)	4.000 EA	4800.00000	19200.00	6000.00000	24000.00	5200.00000	20800.00
0320 0461113 17 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(1501-1750 KIPS)	2.000 EA	6300.00000	12600.00	6000.00000	12000.00	6500.00000	13000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0325 0461114 12 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(251-500 KIPS)	18.000 EA	2900.00000	52200.00	6000.00000	108000.00	2500.00000	45000.00
0330 0461114 13 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(501-750 KIPS)	4.000 EA	3500.00000	14000.00	6000.00000	24000.00	3500.00000	14000.00
0335 0461114 14 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(751-1000 KIPS)	4.000 EA	3500.00000	14000.00	6000.00000	24000.00	4600.00000	18400.00
0340 0461114 15 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1001-1250 KIPS)	2.000 EA	5100.00000	10200.00	6000.00000	12000.00	5200.00000	10400.00
0345 0461114 16 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1251-1500 KIPS)	4.000 EA	5500.00000	22000.00	6000.00000	24000.00	6200.00000	24800.00
0350 0461114 17 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1501-1750 KIPS)	2.000 EA	13500.00000	27000.00	6000.00000	12000.00	7200.00000	14400.00
0355 0506 2 BRIDGE DRAINAGE PIPING	1687.000 LF	30.00000	50610.00	100.00000	168700.00	35.00000	59045.00
0360 0506 3 BRIDGE DRAINS	15.000 EA	1000.00000	15000.00	5000.00000	75000.00	650.00000	9750.00
0365 0521 5 1 CONCRETE TRAFFIC RAILING BARRIER BRIDGE (32" F)	9989.000 LF	70.00000	699230.00	65.00000	649285.00	48.00000	479472.00
0370 0521 8 1 CONC TRAF RAIL BARRIER(RET WALL SYSTEM)32" F SHAPE	370.000 LF	110.00000	40700.00	205.00000	75850.00	180.00000	66600.00
0375 0521 72 4 BARRIER WALL CONC (RIGID-RETAINING)	48.000 LF	160.00000	7680.00	120.00000	5760.00	105.00000	5040.00
0380 0547 70 1 RIPRAP FABRIC-FORMED CONCRETE (8" FILTER POINTS)	270.000 SY	35.00000	9450.00	100.00000	27000.00	40.00000	10800.00
0385 0548 12 RETAINING WALL SYSTEM(PERMANENT)(EXCLUDING BARRIER)	11625.000 SF	19.00000	220875.00	24.00000	279000.00	24.00000	279000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0390 0548 13 RETAINING WALL SYSTEM(TEMPORARY)(EXCLUDING BARRIER)	1715.000 SF	12.00000	20580.00	10.00000	17150.00	11.00000	18865.00
0395 0750 71 ELECTRICAL WORK 24993725201	LUMP	40000.00000	40000.00	66248.00000	66248.00	20000.00000	20000.00
0396 0750 71 ELECTRICAL WORK	LUMP	40000.00000	40000.00	66248.00000	66248.00	20000.00000	20000.00
0400 0750 71 ELECTRICAL WORK 40883415201	LUMP	40000.00000	40000.00	66248.00000	66248.00	20000.00000	20000.00
SECTION 0001 TOTALS			$ 36,909,705.71		$ 32,949,293.67		$ 42,483,613.11
SECTION 0002 ROADWAY							
0405 0101 1 MOBILIZATION 25023445201	LUMP	1300000.00000	1300000.00	2300000.00000	2300000.00	400000.00000	400000.00
0410 0101 1 MOBILIZATION 40883415201	LUMP	2400000.00000	2400000.00	2300000.00000	2300000.00	1718748.00000	1718748.00
0415 0101 1 MOBILIZATION 25023425201	LUMP	1500000.00000	1500000.00	2300000.00000	2300000.00	523600.00000	523600.00
0420 0102 1 MAINTENANCE OF TRAFFIC 25023425201	700.000 LS	700000.00000	700000.00	1900000.00000	1900000.00	500000.00000	500000.00
0425 0102 1 MAINTENANCE OF TRAFFIC 25023445201	1337.000 LS	200000.00000	200000.00	1900000.00000	1900000.00	850000.00000	850000.00
0430 0102 1 MAINTENANCE OF TRAFFIC 40883415201	1800.000 LS	800000.00000	800000.00	1900000.00000	1900000.00	1500000.00000	1500000.00
0435 0102 2 1 SPECIAL DETOUR (DETOUR 1) 40883415201	LUMP	25000.00000	25000.00	200000.00000	200000.00	145200.00000	145200.00
0440 0102 2 2 SPECIAL DETOUR (DETOUR 2) 40883415201	LUMP	12000.00000	12000.00	200000.00000	200000.00	109200.00000	109200.00
0445 0102 2 3 SPECIAL DETOUR (DETOUR 3) 40883415201	LUMP	20000.00000	20000.00	200000.00000	200000.00	210000.00000	210000.00
0450 0102 2 4 SPECIAL DETOUR (DETOUR 4) 40883415201	LUMP	14000.00000	14000.00	200000.00000	200000.00	167000.00000	167000.00
0455 0102 2 5 SPECIAL DETOUR (DETOUR 5) 40883415201	LUMP	20000.00000	20000.00	200000.00000	200000.00	117900.00000	117900.00
0460 0102 2 6 SPECIAL DETOUR (DETOUR 6) 40883415201	LUMP	34000.00000	34000.00	200000.00000	200000.00	152000.00000	152000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0465 0102 2 7 SPECIAL DETOUR (DETOUR 7) 40883415201	LUMP	40000.00000	40000.00	200000.00000	200000.00	109000.00000	109000.00
0470 0102 2 8 SPECIAL DETOUR (DETOUR 8) 40883415201	LUMP	30000.00000	30000.00	200000.00000	200000.00	110000.00000	110000.00
0475 0102 2 9 SPECIAL DETOUR (DETOUR 9) 40883415201	LUMP	20000.00000	20000.00	200000.00000	200000.00	45000.00000	45000.00
0480 0102 2 10 SPECIAL DETOUR (DETOUR 10) 40883415201	LUMP	10000.00000	10000.00	200000.00000	200000.00	12000.00000	12000.00
0485 0102 2 11 SPECIAL DETOUR (DETOUR 11) 40883415201	LUMP	7000.00000	7000.00	200000.00000	200000.00	8000.00000	8000.00
0490 0102 2 12 SPECIAL DETOUR (DETOUR 12) 40883415201	LUMP	24000.00000	24000.00	200000.00000	200000.00	34000.00000	34000.00
0495 0102 2 13 SPECIAL DETOUR (DETOUR 13) 25023445201	LUMP	30000.00000	30000.00	200000.00000	200000.00	138000.00000	138000.00
0500 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	691.000 CY	35.00000	24185.00	10.00000	6910.00	47.00000	32477.00
0505 0102 14 TRAFFIC CONTROL OFFICER	2346.000 MH	38.00000	89148.00	40.00000	93840.00	43.00000	100878.00
0510 0102 60 WORK ZONE SIGNS	429195.000 ED	0.20000	85839.00	0.20000	85839.00	1.00000	429195.00
0515 0102 61 BUSINESS SIGNS	12.000 EA	100.00000	1200.00	100.00000	1200.00	100.00000	1200.00
0520 0102 71 11 BARRIER WALL (TEMPORARY) (F&I)(CONCRETE	15375.000 LF	23.00000	353625.00	12.00000	184500.00	37.00000	568875.00
0525 0102 71 14 BARRIER WALL (TEMPORARY) (F&I)(TYPE K)	10367.000 LF	25.00000	259175.00	12.00000	124404.00	72.00000	746424.00
0530 0102 71 21 BARRIER WALL (TEMPORARY) (RELOCATE)(CONCRETE)	31471.000 LF	3.00000	94413.00	12.00000	377652.00	12.00000	377652.00
0535 0102 71 24 BARRIER WALL (TEMPORARY) (RELOCATE)(TYPE K)	16129.000 LF	3.00000	48387.00	12.00000	193548.00	20.00000	322580.00
0540 0102 74 1 BARRICADE (TEMPORARY)(TYPES I,II,VP & DRUM)	581809.000 ED	0.18000	104725.62	0.23000	133816.07	0.18000	104725.62
0545 0102 74 2 BARRICADE (TEMPORARY)(TYPE III) (6')	38329.000 ED	0.40000	15331.60	0.45000	17248.05	0.48000	18397.92

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(1) GILBERT SOUTHERN CORP. UNIT PRICE	(1) GILBERT SOUTHERN CORP. AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	(2) DE MOYA GROUP INC. (THE) AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	(3) AMEC CIVIL, LLC AMOUNT
0550 0102 76 PANELS ARROW ADVANCE WARNING	5187.000	ED	7.00000	36309.00	7.00000	36309.00	7.25000	37605.75
0555 0102 77 HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	60035.000	ED	0.40000	24014.00	0.40000	24014.00	0.50000	30017.50
0560 0102 78 MARKER PAVT REFLECTIVE (TEMPORARY)	13375.000	EA	3.00000	40125.00	2.50000	33437.50	3.00000	40125.00
0565 0102 79 LIGHTS(TEMP-BARR. WALL MOUNT)(TYPE C STEADY BURN)	212211.000	ED	0.15000	31831.65	0.16000	33953.76	0.14000	29709.54
0570 0102 89 7 IMPACT ATTENUATOR (REDIRECTIVE OPTION)(TEMPORARY)	265.000	LO	1250.00000	331250.00	250.00000	66250.00	1200.00000	318000.00
0575 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	12523.000	ED	18.00000	225414.00	1.00000	12523.00	23.00000	288029.00
0580 0104 1 ARTIFICIAL COVERINGS	1389.000	SY	1.50000	2083.50	5.00000	6945.00	7.00000	9723.00
0585 0104 4 MOWING	204.400	AC	50.00000	10220.00	150.00000	30660.00	180.00000	36792.00
0590 0104 7 SEDIMENT BASINS	14.000	EA	500.00000	7000.00	3000.00000	42000.00	850.00000	11900.00
0595 0104 9 SEDIMENT BASIN CLEANOUTS	14.000	CO	500.00000	7000.00	1000.00000	14000.00	600.00000	8400.00
0600 0104 11 1 TURBIDITY BARRIER FLOATING (SPECIAL)	1719.000	LF	10.00000	17190.00	15.00000	25785.00	27.00000	46413.00
0605 0104 13 1 SILT FENCE STAKED (TYPE III)	5195.000	LF	1.00000	5195.00	1.50000	7792.50	8.00000	41560.00
0610 0104 13 2 STAKED SILT FENCE (TYPE IV)	1521.000	LF	0.50000	760.50	5.00000	7605.00	9.00000	13689.00
0615 0104 15 PREVENTION DEVICE SOIL TRACKING	18.000	EA	600.00000	10800.00	1000.00000	18000.00	1800.00000	32400.00
0620 0104 16 ROCK BAGS	2940.000	EA	5.00000	14700.00	1.00000	2940.00	21.00000	61740.00
0625 0109 71 2 FIELD OFFICE (600 SQ FT)	1800.000	DA	21.00000	37800.00	10.00000	18000.00	34.00000	61200.00
0630 0109 71 5 FIELD OFFICE (1500 SQ FT)	1800.000	DA	41.00000	73800.00	10.00000	18000.00	58.00000	104400.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0635 0110 1 1 CLEARING & GRUBBING 40883415201	32.010 LS	500000.00000	500000.00	2000000.00000	2000000.00	200000.00000	200000.00
0640 0110 1 1 CLEARING & GRUBBING 25023425201	24.360 LS	500000.00000	500000.00	2000000.00000	2000000.00	75000.00000	75000.00
0645 0110 1 1 CLEARING & GRUBBING 25023445201	2.010 LS	150000.00000	150000.00	2000000.00000	2000000.00	35000.00000	35000.00
0650 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	61314.000 LS	40000.00000	40000.00	1000.00000	1000.00	6500.00000	6500.00
0655 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 25023425201	LUMP	1400.00000	1400.00	1000.00000	1000.00	1000.00000	1000.00
0660 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 40883415201	LUMP	1400.00000	1400.00	1000.00000	1000.00	1000.00000	1000.00
0665 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 25023445201	LUMP	1400.00000	1400.00	1000.00000	1000.00	1000.00000	1000.00
0670 0120 1 EXCAVATION REGULAR	158757.000 CY	4.50000	714406.50	9.60000	1524067.20	2.70000	428643.90
0675 0120 4 EXCAVATION SUBSOIL	23774.000 CY	10.00000	237740.00	9.50000	225853.00	7.00000	166418.00
0676 0120 5 EXCAVATION CHANNEL	15624.000 CY	23.00000	359352.00	15.00000	234360.00	6.50000	101556.00
0680 0120 6 EMBANKMENT	192802.000 CY	9.00000	1735218.00	13.60000	2622107.20	3.50000	674807.00
0685 0121 70 FLOWABLE FILL	70.000 CY	60.00000	4200.00	400.00000	28000.00	160.00000	11200.00
0690 0160 4 STABILIZATION TYPE B	125602.200 SY	2.50000	314005.50	0.25000	31400.55	2.00000	251204.40
0695 0162 3101 FINISH SOIL LAYER(GRASSING OPERATIONS) (6")	142490.000 SY	1.80000	256482.00	0.05000	7124.50	5.00000	712450.00
0700 0285704 BASE OPTIONAL (BASE GROUP 04)	11654.600 SY	15.00000	174819.00	10.00000	116546.00	14.00000	163164.40
0705 0285706 BASE OPTIONAL (BASE GROUP 06)	191.000 SY	16.00000	3056.00	15.00000	2865.00	116.00000	22156.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0710 0285709 BASE OPTIONAL (BASE GROUP 09)	2992.600 SY	15.00000	44889.00	17.50000	52370.50	25.00000	74815.00
0715 0285710 BASE OPTIONAL (BASE GROUP 10)	95521.900 SY	14.00000	1337306.60	17.50000	1671633.25	22.00000	2101481.80
0720 0285715 BASE OPTIONAL (BASE GROUP 15)	1268.000 SY	45.00000	57060.00	33.00000	41844.00	35.00000	44380.00
0725 0327 70 6 MILLING EXIST ASPH PAVT (1 1/2" AVG DEPTH)	44656.000 SY	2.50000	111640.00	3.00000	133968.00	4.00000	178624.00
0730 0327 70 13 MILLING EXIST ASPH PAVT (1 3/4" AVG DEPTH)	277.000 SY	10.00000	2770.00	10.00000	2770.00	8.70000	2409.90
0735 0334 1 11 SUPERPAVE ASPHALTIC CONC (TRAFFIC A)	1815.800 TN	71.00000	128921.80	100.00000	181580.00	73.00000	132553.40
0740 0334 1 13 SUPERPAVE ASPHALTIC CONC (TRAFFIC C)	14579.700 TN	71.00000	1035158.70	68.00000	991419.60	70.00000	1020579.00
0745 0334 1 14 SUPERPAVE ASPHALTIC CONC (TRAFFIC D)	2158.000 TN	71.00000	153218.00	75.00000	161850.00	78.00000	168324.00
0750 0337 7 6 ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(FC-6)	12170.400 TN	78.00000	949291.20	83.00000	1010143.20	87.00000	1058824.80
0755 0337 7 7 ASPH CONC FRICTION COURSE(INC BIT / RUBBER) (FC-9.5)	1393.200 TN	88.00000	122601.60	94.00000	130960.80	98.00000	136533.60
0760 0339 1 ASPHALT PAVEMENT MISCELLANEOUS	431.000 TN	150.00000	64650.00	80.00000	34480.00	79.00000	34049.00
0765 0400 1 2 CONC CLASS I(ENDWALLS)	352.690 CY	0.01000	3.53	200.00000	70538.00	180.00000	63484.20
0770 0400 1 11 CONC CLASS I(RETAINING WALLS)	22.800 CY	975.00000	22230.00	600.00000	13680.00	700.00000	15960.00
0775 0400 1 15 CONC CLASS I(MISCELLANEOUS)	768.900 CY	450.00000	346005.00	265.00000	203758.50	550.00000	422895.00
0780 0400 4 11 CONC CLASS IV (RETAINING WALLS)	144.000 CY	600.00000	86400.00	1000.00000	144000.00	700.00000	100800.00
0785 0410 70 64 PRECAST CONC BOX CULVERT (F&I) (6' SPAN)(4' HT)	25.000 LF	1000.00000	25000.00	500.00000	12500.00	800.00000	20000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0790 0415 1 1 REINF STEEL (ROADWAY)	1573.000 LB	0.90000	1415.70	3.00000	4719.00	0.70000	1101.10
0795 0415 1 3 REINF STEEL (RETAINING WALL)	20425.000 LB	0.90000	18382.50	1.50000	30637.50	0.50000	10212.50
0800 0425 1311 INLETS (CURB) (TYPE P-1) (<10')	2.000 EA	3000.00000	6000.00	3500.00000	7000.00	2622.00000	5244.00
0805 0425 1341 INLETS (CURB) (TYPE P-4) (<10')	3.000 EA	3100.00000	9300.00	3500.00000	10500.00	2580.00000	7740.00
0810 0425 1351 INLETS (CURB) (TYPE P-5) (<10')	26.000 EA	3600.00000	93600.00	3500.00000	91000.00	2730.00000	70980.00
0815 0425 1352 INLETS (CURB) (TYPE P-5) (>10')	2.000 EA	4700.00000	9400.00	5000.00000	10000.00	3390.00000	6780.00
0820 0425 1361 INLETS (CURB) (TYPE P-6) (<10')	9.000 EA	3900.00000	35100.00	4000.00000	36000.00	2260.00000	20340.00
0825 0425 1451 INLETS (CURB) (TYPE J-5) (<10')	6.000 EA	7400.00000	44400.00	7000.00000	42000.00	3300.00000	19800.00
0830 0425 1452 INLETS (CURB) (TYPE J-5) (>10')	2.000 EA	9700.00000	19400.00	9000.00000	18000.00	6000.00000	12000.00
0835 0425 1461 INLETS (CURB) (TYPE J-6) (<10')	2.000 EA	7800.00000	15600.00	7000.00000	14000.00	3750.00000	7500.00
0840 0425 1481 INLETS (CURB) (TYPE 8) (<10')	2.000 EA	3200.00000	6400.00	3500.00000	7000.00	4300.00000	8600.00
0845 0425 1501 INLETS (DT BOT) (TYPE A) (<10')	3.000 EA	3400.00000	10200.00	3500.00000	10500.00	3760.00000	11280.00
0850 0425 1541 INLETS (DT BOT) (TYPE D) (<10')	27.000 EA	4100.00000	110700.00	3500.00000	94500.00	2920.00000	78840.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0855 0425 1561 INLETS (DT BOT) (TYPE F) (<10')	1.000 EA	3700.00000	3700.00	3500.00000	3500.00	3690.00000	3690.00
0860 0425 1571 INLETS (DT BOT) (TYPE G) (<10')	9.000 EA	4700.00000	42300.00	3500.00000	31500.00	3760.00000	33840.00
0865 0425 1701 INLETS (GUTTER) (TYPE S) (<10')	9.000 EA	3500.00000	31500.00	3500.00000	31500.00	2910.00000	26190.00
0870 0425 1702 INLETS (GUTTER) (TYPE S) (>10')	3.000 EA	4900.00000	14700.00	4500.00000	13500.00	3050.00000	9150.00
0875 0425 1703 INLETS (GUTTER) (TYPE S) (J BOT, <10')	1.000 EA	5900.00000	5900.00	6000.00000	6000.00	2970.00000	2970.00
0880 0425 1705 INLETS (GUTTER) (TYPE S) (PARTIAL)	2.000 EA	3100.00000	6200.00	2500.00000	5000.00	2830.00000	5660.00
0885 0425 1711 INLETS (GUTTER) (TYPE V) (<10')	1.000 EA	3600.00000	3600.00	4000.00000	4000.00	4490.00000	4490.00
0890 0425 1713 INLETS (GUTTER) (TYPE V) (J BOT, <10')	1.000 EA	6300.00000	6300.00	6000.00000	6000.00	4410.00000	4410.00
0895 0425 1881 INLETS (BARRIER WALL,RIGID,CURB & GUTTER) (<10')	3.000 EA	3400.00000	10200.00	4000.00000	12000.00	3437.00000	10311.00
0900 0425 1891 INLETS (BARRIER WALL) (<10')	15.000 EA	3700.00000	55500.00	4000.00000	60000.00	3437.00000	51555.00
0905 0425 1892 INLETS (BARRIER WALL) (>10')	3.000 EA	5500.00000	16500.00	6000.00000	18000.00	3600.00000	10800.00
0910 0425 1910 INLETS (CLOSED FLUME)(N/A)	25.000 EA	2500.00000	62500.00	2500.00000	62500.00	3800.00000	95000.00
0915 0425 2 41 MANHOLES (P-7) (<10')	15.000 EA	3500.00000	52500.00	5000.00000	75000.00	2860.00000	42900.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0920 0425 2 42 MANHOLES (P-7) (>10')	2.000 EA	6200.00000	12400.00	5000.00000	10000.00	3240.00000	6480.00
0925 0425 2 43 MANHOLES (P-7) (PARTIAL)	8.000 EA	2100.00000	16800.00	2000.00000	16000.00	2860.00000	22880.00
0930 0425 2 71 MANHOLES (J-7) (<10')	5.000 EA	4800.00000	24000.00	6000.00000	30000.00	3280.00000	16400.00
0935 0425 2 72 MANHOLES (J-7) (>10')	6.000 EA	10300.00000	61800.00	12000.00000	72000.00	3940.00000	23640.00
0940 0425 2101 MANHOLES (SPECIAL) (<10')	3.000 EA	6600.00000	19800.00	10000.00000	30000.00	4300.00000	12900.00
0945 0425 2102 MANHOLES (SPECIAL) (>10')	4.000 EA	9300.00000	37200.00	10000.00000	40000.00	5110.00000	20440.00
0950 0425 2103 MANHOLES (SPECIAL) (PARTIAL)	1.000 EA	3000.00000	3000.00	3000.00000	3000.00	3920.00000	3920.00
0955 0425 3 83 JUNCTION BOXES (SPECIAL) (PARTIAL)	1.000 EA	2600.00000	2600.00	5000.00000	5000.00	2475.00000	2475.00
0960 0425 5 MANHOLE (ADJUST)	13.000 EA	1300.00000	16900.00	500.00000	6500.00	2300.00000	29900.00
0965 0426733023 SLOTTED DRAIN PIPE (OPTIONAL) (GA 16)(15")	30.000 LF	275.00000	8250.00	300.00000	9000.00	200.00000	6000.00
0970 0430171125 PIPE CULV(OPT MATL)(ROUND)(18"SS)	7334.000 LF	92.00000	674728.00	45.00000	330030.00	48.00000	352032.00
0975 0430171129 PIPE CULV(OPT MATL)(ROUND)(24"SS)	1756.000 LF	95.00000	166820.00	55.00000	96580.00	62.00000	108872.00
0980 0430171133 PIPE CULV(OPT MATL)(ROUND)(30"SS)	101.000 LF	113.00000	11413.00	70.00000	7070.00	125.00000	12625.00
0985 0430171138 PIPE CULV(OPT MATL)(ROUND)(36"SS)	99.000 LF	120.00000	11880.00	100.00000	9900.00	145.00000	14355.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
0990 0430171140 PIPE CULV(OPT MATL)(ROUND)(42"SS)	425.000 LF	125.00000	53125.00	110.00000	46750.00	100.00000	42500.00
0995 0430171141 PIPE CULV(OPT MATL)(ROUND)(48"SS)	644.000 LF	140.00000	90160.00	120.00000	77280.00	200.00000	128800.00
1000 0430171223 PIPE CULV(OPT MATL)(OTHER)(15"SS)	2.000 LF	400.00000	800.00	300.00000	600.00	500.00000	1000.00
1005 0430172133 PIPE CULV(OPT MAT)(ROUND)(30"CD)	537.000 LF	100.00000	53700.00	70.00000	37590.00	82.00000	44034.00
1010 0430172138 PIPE CULV(OPT MATL)(ROUND)(36"CD)	45.000 LF	112.00000	5040.00	100.00000	4500.00	220.00000	9900.00
1015 0430173125 PIPE CULV(OPT MATL)(ROUND)(18"GD)	578.000 LF	90.00000	52020.00	45.00000	26010.00	60.00000	34680.00
1020 0430173129 PIPE CULV(OPT MATL)(ROUND)(24"GD)	12.000 LF	110.00000	1320.00	100.00000	1200.00	290.00000	3480.00
1025 0430173133 PIPE CULV(OPT MATL)(ROUND)(30"GD)	42.000 LF	118.00000	4956.00	70.00000	2940.00	150.00000	6300.00
1030 0430610 25 U-ENDWALL WITH GRATE (18")	1.000 EA	1500.00000	1500.00	5000.00000	5000.00	1500.00000	1500.00
1035 0430941 02 PIPE ELLIP DESILTING (14" X 23" SS)	4.000 LF	4.00000	16.00	100.00000	400.00	30.00000	120.00
1040 0430941 23 PIPE DESILTING (15" SS)	416.500 LF	3.00000	1249.50	2.90000	1207.85	4.00000	1666.00
1045 0430941 25 PIPE DESILTING (18" SS)	472.100 LF	3.50000	1652.35	3.35000	1581.54	5.00000	2360.50
1050 0430941 29 PIPE DESILTING (24" SS)	161.000 LF	4.50000	724.50	4.35000	700.35	6.00000	966.00
1055 0430941 33 PIPE DESILTING (30" SS)	1695.000 LF	6.50000	11017.50	6.25000	10593.75	6.00000	10170.00
1060 0430941 38 PIPE DESILTING (36" SS)	347.000 LF	8.50000	2949.50	8.40000	2914.80	8.00000	2776.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1065 0430941 40 PIPE DESILTING (42" SS)	153.000 LF	10.50000	1606.50	10.50000	1606.50	11.00000	1683.00
1070 0430941 41 PIPE DESILTING (48" SS)	216.000 LF	13.00000	2808.00	12.85000	2775.60	14.00000	3024.00
1075 0430941 43 PIPE DESILTING (60" SS)	1112.000 LF	19.00000	21128.00	18.85000	20961.20	22.00000	24464.00
1080 0430982125 MITERED END SECTION (OPTIONAL ROUND) (18" CD)	27.000 EA	975.00000	26325.00	1500.00000	40500.00	980.00000	26460.00
1085 0430982129 MITERED END SECTION (OPTIONAL ROUND) (24" CD)	8.000 EA	1200.00000	9600.00	2000.00000	16000.00	1040.00000	8320.00
1090 0443 70 3 FRENCH DRAINS (18")	160.000 LF	150.00000	24000.00	150.00000	24000.00	95.00000	15200.00
1095 0443 70 4 FRENCH DRAINS (24")	1926.000 LF	130.00000	250380.00	150.00000	288900.00	100.00000	192600.00
1100 0451 70 PREST SOIL ANCHORS	518.000 EA	1200.00000	621600.00	1.00000	518.00	2050.00000	1061900.00
1105 0451 70 1 PREST SOIL ANCHOR (PERFORMANCE TEST)	52.000 EA	100.00000	5200.00	1.00000	52.00	150.00000	7800.00
1110 0451 70 2 PREST SOIL ANCHOR (CREEP TEST)	26.000 EA	400.00000	10400.00	1.00000	26.00	400.00000	10400.00
1115 0455133 1 SHEET PILING STEEL (TEMPORARY)	173650.000 SF	11.00000	1910150.00	0.01000	1736.50	7.60000	1319740.00
1120 0460 5 ENDWALL GRATE	326.000 LB	5.00000	1630.00	30.00000	9780.00	8.00000	2608.00
1125 0520 1 10 CURB & GUTTER CONC (TYPE F)	31271.000 LF	12.00000	375252.00	10.00000	312710.00	9.00000	281439.00
1130 0520 5 41 TRAF SEP CONC (TYPE IV) (4' WIDE)	1014.000 LF	20.00000	20280.00	40.00000	40560.00	18.00000	18252.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1135 0520 5 46 TRAF SEP CONC (TYPE IV) (8.5' WIDE)	239.000 LF	43.00000	10277.00	70.00000	16730.00	30.00000	7170.00
1140 0520 6 GUTTER SHLDR CONC	2912.000 LF	17.00000	49504.00	12.00000	34944.00	9.00000	26208.00
1145 0521 1 BARRIER WALL CONC	550.000 LF	250.00000	137500.00	165.00000	90750.00	39.00000	21450.00
1150 0521 8 1 CONC TRAF RAIL BARRIER(RET WALL SYSTEM)32" F SHAPE	3539.000 LF	195.00000	690105.00	205.00000	725495.00	200.00000	707800.00
1155 0521 72 3 BARRIER WALL CONC (RIGID-SHOULDER)	751.000 LF	180.00000	135180.00	120.00000	90120.00	109.00000	81859.00
1160 0521 72 5 BARRIER WALL CONC (RIGID-CURB & GUTTER)	50.000 LF	160.00000	8000.00	120.00000	6000.00	95.00000	4750.00
1165 0521 72 6 BARRIER WALL CONC (PLAIN-SHOULDER)	2615.000 LF	120.00000	313800.00	75.00000	196125.00	90.00000	235350.00
1170 0521 73 BARRIER WALL REMOVAL (CONCRETE)	1543.000 LF	45.00000	69435.00	50.00000	77150.00	11.00000	16973.00
1175 0522 1 SIDEWALK CONC (4" THICK)	1738.000 SY	25.00000	43450.00	35.00000	60830.00	18.00000	31284.00
1180 0522 2 SIDEWALK CONC (6" THICK)	433.000 SY	33.00000	14289.00	45.00000	19485.00	26.00000	11258.00
1185 0524 1 1 DITCH PAVT CONC (3")	515.400 SY	40.00000	20616.00	70.00000	36078.00	28.00000	14431.20
1190 0524 2 2 SLOPE PAVT CONC (4")	92.000 SY	48.00000	4416.00	100.00000	9200.00	85.00000	7820.00
1195 0536 1 1 GUARDRAIL (ROADWAY)	6168.000 LF	15.00000	92520.00	16.80000	103622.40	16.80000	103622.40
1200 0536 2 GUARDRAIL (SHOP-BENT PANELS)	488.000 LF	16.00000	7808.00	18.90000	9223.20	19.00000	9272.00
1205 0536 7 GUARDRAIL POST SPECIAL	4.000 EA	150.00000	600.00	156.00000	624.00	160.00000	640.00
1210 0536 8 GUARDRAIL BRIDGE ANCHORAGE ASSEM	2.000 EA	1600.00000	3200.00	2350.00000	4700.00	2400.00000	4800.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1215 0536 73 GUARDRAIL REMOVAL	10363.800 LF	2.50000	25909.50	2.00000	20727.60	2.20000	22800.36
1220 0536 82 GUARDRAIL ANCHORAGE (CONCRETE BARRIER WALL)	17.000 EA	1600.00000	27200.00	2653.00000	45101.00	2700.00000	45900.00
1225 0536 85 22 GUARDRAIL END ANCHORAGE ASSEMBLY FLARED	8.000 EA	1600.00000	12800.00	2196.00000	17568.00	2200.00000	17600.00
1230 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY PARALLEL	11.000 EA	2000.00000	22000.00	2690.00000	29590.00	2700.00000	29700.00
1235 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY TYPE I	11.000 EA	400.00000	4400.00	509.00000	5599.00	510.00000	5610.00
1240 0544 75 14 IMPACT ATTENUATOR VEHICULAR (QUADGURD)	4.000 EA	30000.00000	120000.00	17341.00000	69364.00	17400.00000	69600.00
1245 0546 72 51 RUMBLE STRIP (GROUND-IN) (16" MIN. WIDTH)	0.644 PM	1200.00000	772.80	13000.00000	8372.00	5500.00000	3542.00
1250 0548 12 RETAINING WALL SYSTEM(PERMANENT)(EXCLUDING BARRIER)	87129.000 SF	27.00000	2352483.00	24.00000	2091096.00	30.00000	2613870.00
1255 0548 13 RETAINING WALL SYSTEM(TEMPORARY)(EXCLUDING BARRIER)	40410.000 SF	11.00000	444510.00	10.00000	404100.00	11.00000	444510.00
1260 0550 2 5 FENCING, TYPE B (5' HEIGHT)	142.000 LF	6.00000	852.00	10.00000	1420.00	12.00000	1704.00
1261 0550 2 7 FENCING, TYPE B (8' HEIGHT)	2038.000 LF	12.00000	24456.00	15.00000	30570.00	14.00000	28532.00
1265 0550 2 7 FENCING, TYPE B (8' HEIGHT)	905.500 LF	8.00000	7244.00	12.00000	10866.00	14.00000	12677.00
1270 0550 3 2 FENCE CORNER POST ASSEM (TYPE B)	2.000 EA	100.00000	200.00	300.00000	600.00	100.00000	200.00
1275 0550 3 4 FENCE CORNER POST ASSEM (SPECIAL)	2.000 EA	150.00000	300.00	500.00000	1000.00	250.00000	500.00
1285 0550 4 4 FENCE PULL & END POST ASSEM (SPECIAL	4.000 EA	150.00000	600.00	500.00000	2000.00	100.00000	400.00
1286 0550 5 3 FENCE PULL POST ASSEMBLY (TYPE B) (SPECIAL)	8.000 EA	150.00000	1200.00	500.00000	4000.00	100.00000	800.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1288 0550 6 3 FENCE END POST ASSEMBLY (TYPE B) (SPECIAL)	6.000 EA	150.00000	900.00	500.00000	3000.00	150.00000	900.00
1315 0550 76121 FENCE GATE (TYPE B) (SINGLE 12')(12' OPENING)	1.000 EA	800.00000	800.00	2000.00000	2000.00	700.00000	700.00
1320 0556 1 2 JACK AND BORE CASING DIAMETER(6" TO <12")	232.000 LF	60.00000	13920.00	200.00000	46400.00	210.00000	48720.00
1325 0556 1 5 JACK AND BORE CASING DIAMETER(24" TO <36")	245.000 LF	200.00000	49000.00	400.00000	98000.00	610.00000	149450.00
1330 0570 2 SEED & MULCH	98714.000 SY	0.50000	49357.00	0.47000	46395.58	1.00000	98714.00
1335 0570 3 1 SEED GRASS (PERM TYPE, ARGEN BAHIA)	2023.000 LB	7.00000	14161.00	7.28000	14727.44	3.20000	6473.60
1340 0570 4 MULCH MATL	77.100 TN	550.00000	42405.00	550.00000	42405.00	85.00000	6553.50
1345 0570 10 SEED GRASS (QUICK-GROWING TYPE)	145.000 LB	7.00000	1015.00	7.25000	1051.25	2.20000	319.00
1350 0571 1 12 PLASTIC EROSION MAT (TRM)(TYPE 2)	4218.720 SY	5.00000	21093.60	2.00000	8437.44	6.00000	25312.32
1355 0575 1 3 SODDING (ARGENTINE BAHIA)	43776.000 SY	1.85000	80985.60	1.85000	80985.60	1.00000	43776.00
1360 0580340 1 TREE PROTECTION (BATTERBOARD)	260.000 LF	6.00000	1560.00	10.00000	2600.00	10.00000	2600.00
1365 0710 5 1 GUIDE LINES (PAINT) (WHITE)	2391.000 LF	0.25000	597.75	0.25000	597.75	0.25000	597.75
1370 0710 5 2 GUIDE LINES (PAINT) (YELLOW)	1650.212 LF	0.25000	412.55	0.25000	412.55	0.80000	1320.17
1375 0710 6 DIRECTIONAL ARROWS, PAINTED	116.000 EA	20.00000	2320.00	20.00000	2320.00	20.00000	2320.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1380 0710 7 PAVT MESSAGE, PAINTED	118.000 EA	50.00000	5900.00	50.00000	5900.00	50.00000	5900.00
1385 0710 11 MARKINGS (PAINT) REMOVAL	84744.000 SF	1.25000	105930.00	1.25000	105930.00	1.25000	105930.00
1390 0710 21 TRAFFIC STRIPE SKIP (WHITE/BLACK)	20.940 GM	375.00000	7852.50	375.00000	7852.50	375.00000	7852.50
1395 0710 22 TRAFFIC STRIPE SKIP (YELLOW)	0.280 GM	375.00000	105.00	375.00000	105.00	375.00000	105.00
1400 0710 23 61 TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	33.620 NM	700.00000	23534.00	690.00000	23197.80	690.00000	23197.80
1405 0710 23 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	1.626 NM	1750.00000	2845.50	1750.00000	2845.50	1745.00000	2837.37
1410 0710 24 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	22.949 NM	700.00000	16064.30	690.00000	15834.81	700.00000	16064.30
1415 0710 24 81 TRAFFIC STRIPE SOLID (YELLOW) (8")	0.106 NM	1750.00000	185.50	1750.00000	185.50	1750.00000	185.50
1420 0710 25 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	6808.400 LF	0.35000	2382.94	0.33000	2246.77	0.35000	2382.94
1425 0710 25121 TRAFFIC STRIPE SOLID (WHITE/BLACK) (12")	3104.000 LF	1.00000	3104.00	1.00000	3104.00	1.00000	3104.00
1430 0710 25181 TRAFFIC STRIPE SOLID (WHITE/BLACK) (18")	3115.000 LF	1.45000	4516.75	1.45000	4516.75	1.50000	4672.50
1435 0710 25241 TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	1796.000 LF	1.50000	2694.00	1.50000	2694.00	1.50000	2694.00
1440 0710 26 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	3051.800 LF	0.15000	457.77	0.13000	396.73	0.20000	610.36

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1445 0710 26181 TRAFFIC STRIPE SOLID (YELLOW) (18")	1447.000 LF	1.45000	2098.15	1.45000	2098.15	1.40000	2025.80
1450 0710 27 TRAFFIC STRIPE SKIP (WHITE/BLACK)	1860.000 LF	0.45000	837.00	0.45000	837.00	0.45000	837.00
1455 0710 30 REFLECTIVE PAINT (ISLAND NOSE) (YELLOW)	6.000 SY	25.00000	150.00	20.00000	120.00	20.00000	120.00
1460 0711 7 PAVT MARKING REMOVE THERMOPLASTIC	28012.000 SF	1.25000	35015.00	1.25000	35015.00	1.25000	35015.00
1465 0715 2112 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (1")	68784.000 LF	4.20000	288892.80	4.10000	282014.40	4.11000	282702.24
1470 0715 2115 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (2")	12559.000 LF	4.50000	56515.50	4.40000	55259.60	4.45000	55887.55
1475 0715 2117 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (4")	25457.000 LF	5.20000	132376.40	5.20000	132376.40	5.25000	133649.25
1480 0715 2215 CONDUIT (F&I UNDERPAVEMENT) (PVC SCH 40) (2")	95.000 LF	18.00000	1710.00	18.00000	1710.00	18.00000	1710.00
1485 0715 2335 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (2")	420.000 LF	20.00000	8400.00	19.00000	7980.00	19.10000	8022.00
1490 0715 2337 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (4")	420.000 LF	35.00000	14700.00	31.00000	13020.00	31.00000	13020.00
1495 0715 14 11 PULL BOX (F&I) (ROADSIDE)	40.000 EA	310.00000	12400.00	310.00000	12400.00	310.00000	12400.00
1500 0715 14 14 PULL BOX (F&I) (SURFACE MOUNT)	29.000 EA	130.00000	3770.00	126.00000	3654.00	127.00000	3683.00
1505 0736 72 11 UTILITY RELOCATION (WATER) (PERMANENT) 25023445201	LUMP	70000.00000	70000.00	100000.00000	100000.00	50000.00000	50000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1510 0999 10 CALENDAR DAYS	10000.000 DD (TIME BID)	1100.00000	11000000.00	1400.00000	14000000.00	1600.00000	16000000.00
1515 0999 16 PARTNERING 25023445201	LUMP (DO NOT BID)	30000.00000	30000.00	30000.00000	30000.00	30000.00000	30000.00
1520 0999 16 PARTNERING 40883415201	LUMP (DO NOT BID)	30000.00000	30000.00	30000.00000	30000.00	30000.00000	30000.00
1525 0999 20 DISPUTES REVIEW BOARD	15.000 DA (DO NOT BID)	3000.00000	45000.00	3000.00000	45000.00	3000.00000	45000.00
1530 0999 25 INITIAL CONTINGENCY AMOUNT 25023425201	LUMP (DO NOT BID)	150000.00000	150000.00	150000.00000	150000.00	150000.00000	150000.00
1535 0999 25 INITIAL CONTINGENCY AMOUNT 25023445201	LUMP (DO NOT BID)	100000.00000	100000.00	100000.00000	100000.00	100000.00000	100000.00
1540 0999 25 INITIAL CONTINGENCY AMOUNT 40883415201	LUMP (DO NOT BID)	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0002 TOTALS			$ 41,069,217.26		$ 54,618,498.49		$ 45,759,012.24
SECTION 0003 SIGNING							
1545 0700 40 1 SIGN SINGLE POST (LESS THAN 12)	115.000 AS	250.00000	28750.00	244.00000	28060.00	245.00000	28175.00
1550 0700 40 4 SIGN SINGLE POST GORE SIGN)	5.000 AS (SPECIAL-EXIT	950.00000	4750.00	933.00000	4665.00	935.00000	4675.00
1555 0700 41 10 SIGN MULTI POST (50 OR LESS)	11.000 AS	2500.00000	27500.00	2516.00000	27676.00	2520.00000	27720.00
1560 0700 41 12 SIGN MULTI-POST - 150 SF)	1.000 AS (101	4800.00000	4800.00	4782.00000	4782.00	4800.00000	4800.00
1565 0700 41 14 SIGN MULTI-POST - 250 SF)	1.000 AS (201	6500.00000	6500.00	6347.00000	6347.00	6400.00000	6400.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1570 0700 44033 SIGN LT'D OVHD TRUSS (T 41 TO 60,S 201 TO 300)	1.000 AS	48000.00000	48000.00	47983.00000	47983.00	48000.00000	48000.00
1575 0700 44034 SIGN LT'D OVHD TRUSS (T 41 TO 60,S 301 TO 400)	1.000 AS	43000.00000	43000.00	42890.00000	42890.00	43000.00000	43000.00
1580 0700 44043 SIGN LT'D OVHD TRUSS (T 61 TO 80,S 201 TO 300)	1.000 AS	40000.00000	40000.00	40006.00000	40006.00	40000.00000	40000.00
1585 0700 44053 SIGN LT'D OVHD TRUSS (T 81 TO 100,S 201 TO 300)	1.000 AS	60000.00000	60000.00	56146.00000	56146.00	56200.00000	56200.00
1590 0700 44056 SIGN LT'D OVHD TRUSS (T 81 TO 100,S 501 TO 600)	1.000 AS	80000.00000	80000.00	80027.00000	80027.00	80100.00000	80100.00
1595 0700 44076 SIGN LT'D OVHD TRUSS (T 121 TO 140,S 501 TO 600)	1.000 AS	75000.00000	75000.00	75576.00000	75576.00	75600.00000	75600.00
1600 0700 44084 SIGN LT'D OVHD TRUSS (T 141 TO 160,S 301 TO 400)	1.000 AS	64000.00000	64000.00	63331.00000	63331.00	63400.00000	63400.00
1605 0700 45 12 SIGN LT'D OVHD CTLVR(C 20 OR <, S 51 TO 100)	2.000 AS	15000.00000	30000.00	14524.00000	29048.00	14550.00000	29100.00
1610 0700 45 23 SIGN LT'D OVHD CTLVR(C 21 TO 30, S 101 TO 150)	5.000 AS	17000.00000	85000.00	17295.00000	86475.00	17300.00000	86500.00
1615 0700 45 24 SIGN LT'D OVHD CTLVR(C 21 TO 30, S 151 TO 200)	1.000 AS	23000.00000	23000.00	23134.00000	23134.00	23200.00000	23200.00
1620 0700 45 34 SIGN LT'D OVHD CTLVR(C 31 TO 40, S 151 TO 200)	1.000 AS	26000.00000	26000.00	25443.00000	25443.00	25500.00000	25500.00
1625 0700 45 35 SIGN LT'D OVHD CTLVR(C 31 TO 40, S 201 TO 250)	1.000 AS	30000.00000	30000.00	29429.00000	29429.00	29500.00000	29500.00
1630 0700 46 11 SIGN EXISTING (REMOVAL) (SINGLE POST)	175.000 AS	40.00000	7000.00	40.00000	7000.00	40.00000	7000.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1635 0700 46 12 SIGN EXISTING (REMOVAL) (MULTI - POST)	13.000 AS	320.00000	4160.00	313.00000	4069.00	320.00000	4160.00
1640 0700 46 13 SIGN EXISTING (REMOVAL) (OVERHEAD TRUSS)	5.000 AS	2000.00000	10000.00	1952.00000	9760.00	2000.00000	10000.00
1645 0700 46 14 SIGN EXISTING (REMOVAL) (OVERHEAD CANTILEVER)	13.000 AS	950.00000	12350.00	937.00000	12181.00	1000.00000	13000.00
1650 0700 46 16 SIGN EXISTING (REMOVAL) (BRIDGE MOUNTED)	9.000 AS	1850.00000	16650.00	1849.00000	16641.00	1900.00000	17100.00
1655 0700 48 60 SIGN PANELS (REMOVE)	17.000 EA	100.00000	1700.00	79.00000	1343.00	80.00000	1360.00
1660 0700 83 SIGN OVHD (BRIDGE MOUNTED)	9.000 AS	4500.00000	40500.00	4535.00000	40815.00	4600.00000	41400.00
1665 0705 10 11 MARKER OBJECT (POST MOUNT) (TYPE 1)	24.000 EA	120.00000	2880.00	118.00000	2832.00	120.00000	2880.00
1670 0705 71 DELINEATOR TUBULAR (FLEXIBLE)	15.000 EA	100.00000	1500.00	82.00000	1230.00	84.00000	1260.00
1675 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 25023425201	LUMP	18000.00000	18000.00	17570.00000	17570.00	18000.00000	18000.00
1680 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 25023445201	LUMP	45000.00000	45000.00	11162.00000	11162.00	50000.00000	50000.00
1685 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 40883415201	LUMP	11000.00000	11000.00	45500.00000	45500.00	12000.00000	12000.00
SECTION 0003 TOTALS		$	847,040.00	$	841,121.00	$	850,030.00
SECTION 0004 LIGHTING							
1690 0400 1 15 CONC CLASS I(MISCELLANEOUS)	100.440 CY	275.00000	27621.00	265.00000	26616.60	270.00000	27118.80

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1695 0715 1111 CONDUCTORS (F&I)(INSULATED) (NO 10)	4453.000 LF	0.50000	2226.50	0.50000	2226.50	0.50000	2226.50
1700 0715 1113 CONDUCTORS (F&I)(INSULATED) (NO 6)	79856.000 LF	0.70000	55899.20	0.70000	55899.20	0.71000	56697.76
1705 0715 1114 CONDUCTORS (F&I)(INSULATED) (NO 4)	6370.000 LF	1.00000	6370.00	1.00000	6370.00	1.00000	6370.00
1710 0715 1115 CONDUCTORS (F&I)(INSULATED) (NO 2)	1516.000 LF	1.10000	1667.60	1.10000	1667.60	1.11000	1682.76
1715 0715 1119 CONDUCTORS (F&I)(INSULATED) (1/0 TO 3/0)	1952.000 LF	2.00000	3904.00	2.00000	3904.00	2.00000	3904.00
1720 0715 2111 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (3/4")	264.000 LF	5.00000	1320.00	5.00000	1320.00	5.00000	1320.00
1725 0715 2115 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (2")	16497.000 LF	4.25000	70112.25	4.20000	69287.40	4.30000	70937.10
1730 0715 2215 CONDUIT (F&I UNDERPAVEMENT) (PVC SCH 40) (2")	5669.000 LF	15.00000	85035.00	14.40000	81633.60	14.50000	82200.50
1735 0715 2332 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (1")	1636.000 LF	14.50000	23722.00	14.30000	23394.80	14.40000	23558.40
1740 0715 2335 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (2")	1192.000 LF	13.50000	16092.00	13.40000	15972.80	13.50000	16092.00
1745 0715 7 11 LOAD CENTER (F&I) (SECONDARY VOLTAGE)	2.000 EA	5500.00000	11000.00	5441.00000	10882.00	5500.00000	11000.00
1750 0715 7 21 LOAD CENTER (REWORK) (SECONDARY VOLTAGE)	1.000 EA	6500.00000	6500.00	6594.00000	6594.00	6600.00000	6600.00
1755 0715 10 2 LIGHT POLE FOUNDATION (F&I)	4.000 EA	550.00000	2200.00	541.00000	2164.00	545.00000	2180.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1760 0715 11125 LUMINAIRE (F&I)(UNDERDECK WALL MOUNT)	19.000 EA	640.00000	12160.00	638.00000	12122.00	640.00000	12160.00
1765 0715 14 11 PULL BOX (F&I) (ROADSIDE)	97.000 EA	320.00000	31040.00	310.00000	30070.00	312.00000	30264.00
1770 0715 14 12 PULL BOX (F&I) (SIDEWALK)	13.000 EA	400.00000	5200.00	388.00000	5044.00	390.00000	5070.00
1775 0715 14 14 PULL BOX (F&I) (SURFACE MOUNT)	87.000 EA	100.00000	8700.00	94.00000	8178.00	95.00000	8265.00
1780 0715191100 LIGHT POLE COMPLETE HIGH MAST (F&I)(100')	12.000 EA	20000.00000	240000.00	19724.00000	236688.00	19800.00000	237600.00
1785 0715500 1 POLE CABLE DISTRIBUTION SYSTEM (CONVENTIONAL)	108.000 EA	1000.00000	108000.00	977.00000	105516.00	980.00000	105840.00
1790 0715500 2 POLE CABLE DISTRIBUTION SYSTEM (HIGH MAST)	12.000 EA	1050.00000	12600.00	1031.00000	12372.00	1050.00000	12600.00
1795 0715500 3 POLE CABLE DISTRIBUTION SYSTEM (WALL MOUNTED)	18.000 EA	1050.00000	18900.00	1031.00000	18558.00	1040.00000	18720.00
1800 0715511130 LIGHT POLE COMP(F&I)(SGL ARM SHLDR MNT-ALUM)(30')	104.000 EA	4350.00000	452400.00	4339.00000	451256.00	4400.00000	457600.00
1805 0715512130 LIGHT POLE COMPLETE(F&I)(DBL ARM SHLDR MNT-ALUM)(30')	4.000 EA	6650.00000	26600.00	6638.00000	26552.00	6640.00000	26560.00
1810 0715513130 LIGHT POLE COMP(F&I)(SGL ARM WALL MNT-ALUM)(30')	3.000 EA	4400.00000	13200.00	4367.00000	13101.00	4400.00000	13200.00
1820 0715540000 LIGHT POLE COMP(RELOCATE)	4.000 EA	1100.00000	4400.00	1097.00000	4388.00	1100.00000	4400.00
1825 0715550000 LIGHT POLE COMP(REMOVE)	137.000 EA	225.00000	30825.00	222.00000	30414.00	230.00000	31510.00
SECTION 0004 TOTALS			$ 1,277,694.55		$ 1,262,191.50		$ 1,275,676.82
SECTION 0005 SIGNALIZATION							

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1830 0630 1 12 CONDUIT (FURNISH & INSTALL)(UNDERGROUND	9060.000 LF	5.00000	45300.00	5.00000	45300.00	5.00000	45300.00
1835 0630 1 13 CONDUIT (FURNISH & INSTALL)(UNDER PAVEMENT)	2586.000 LF	15.00000	38790.00	15.00000	38790.00	15.00000	38790.00
1840 0632 7 1 CABLE (SIGNAL) (FURNISH & INSTALL)	5.000 PI	2100.00000	10500.00	2121.00000	10605.00	2130.00000	10650.00
1845 0632 8112 CABLE (INTERCONNECT)(F&I) (UNDER-GRND)	2100.000 LF	2.00000	4200.00	2.00000	4200.00	2.00000	4200.00
1850 0635 1 11 PULL & JUNCTION BOXES (F&I) (PULL BOX)	98.000 EA	310.00000	30380.00	310.00000	30380.00	312.00000	30576.00
1855 0635 1 15 PULL & JUNCTION BOXES (F&I) (FIBER OPTICS)	12.000 EA	800.00000	9600.00	802.00000	9624.00	805.00000	9660.00
1860 0639 1 13 ELECTRICAL POWER SERVICE (OVERHEAD)	4.000 AS	600.00000	2400.00	573.00000	2292.00	580.00000	2320.00
1865 0639 2 1 ELECTRICAL SERVICE WIRE	3492.000 LF	1.00000	3492.00	1.00000	3492.00	1.00000	3492.00
1870 0649411001 M/ARM (F&I/HL)(SGL ARM W/O LUM(1ST ARM TYPE B1(2ND 0(Q1	2.000 EA	8800.00000	17600.00	8803.00000	17606.00	8810.00000	17620.00
1875 0649413002 M/ARM(F&I/HL)(SGL ARM W/O LUM)(1ST ARM(B3) 2ND ARM(0)POLE(Q2)	2.000 EA	10000.00000	20000.00	9973.00000	19946.00	10000.00000	20000.00
1880 0649415003 M/ARM (F&I/HL)(SGL ARM W/O LUM)1ST ARM(B5) 2ND ARM(0)POLE(Q3)	5.000 EA	13000.00000	65000.00	12945.00000	64725.00	13000.00000	65000.00
1885 0649416004 M/ARM (F&I/HL)(SGL ARM W/O LUM)(1ST ARM(B6)2ND(0)POLE(Q4)	4.000 EA	15500.00000	62000.00	15515.00000	62060.00	15600.00000	62400.00
1890 0649435009 M/ARM(F&I/HL)(SI ARM W/ LUM)(1ST ARM(B5) 2NDARM(0)POLE(Q23LU)	1.000 EA	16000.00000	16000.00	16017.00000	16017.00	16100.00000	16100.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1895 0650 51111 SIGNAL TRAFFIC(F&I)(1 SECT 1 WAY)(STD)	2.000 AS	225.00000	450.00	224.00000	448.00	225.00000	450.00
1900 0650 51311 SIGNAL TRAFFIC(F&I)(3 SECT 1 WAY)(STD)	29.000 AS	500.00000	14500.00	474.00000	13746.00	480.00000	13920.00
1905 0650 51511 SIGNAL TRAFFIC(F&I)(5 SECT 1 WAY)(STD)	8.000 AS	700.00000	5600.00	669.00000	5352.00	670.00000	5360.00
1910 0653171 SIGNAL PEDESTRIAN(NEON INTERNATIONAL SYM LOW WATT (1 WAY)	10.000 AS	525.00000	5250.00	522.00000	5220.00	525.00000	5250.00
1915 0653172 SIGNAL PEDESTRIAN (NEON INT SYM LOW WATT)	4.000 AS	910.00000	3640.00	910.00000	3640.00	920.00000	3680.00
1920 0659107 SIGNAL HEAD AUXILIARIES (ALUMINUM PEDESTAL)	4.000 EA	700.00000	2800.00	681.00000	2724.00	685.00000	2740.00
1925 0660 1109 LOOP DETECTOR INDUCTIVE (F&I) (TYPE 9)	19.000 EA	135.00000	2565.00	133.00000	2527.00	135.00000	2565.00
1930 0660 2101 LOOP ASSEMBLY (F&I) (TYPE A)	35.000 AS	640.00000	22400.00	637.00000	22295.00	640.00000	22400.00
1935 0665 11 DETECTOR PEDEST(F&I)(DET STA POLE OR CABINET MTD)	10.000 EA	100.00000	1000.00	102.00000	1020.00	105.00000	1050.00
1940 0670 5120 CNTL ASSEM ACT SS F&I 170 PRE(NONE)	3.000 AS	12000.00000	36000.00	12104.00000	36312.00	12200.00000	36600.00
1945 0670 5121 CNTL ASSEM ACT SS F&I 170 PRE(ONE)	1.000 AS	13000.00000	13000.00	13103.00000	13103.00	13100.00000	13100.00
1950 0671 2 42 TRAFFIC CONTROLLER(MOD)(TYPE 170)	1.000 EA	1000.00000	1000.00	937.00000	937.00	940.00000	940.00
1955 0685120 SYSTEM AUXILIARIES (TELEMETRY TRANSCEIVER)	4.000 EA	1300.00000	5200.00	1297.00000	5188.00	1300.00000	5200.00
1960 0685124 SYSTEM AUXILIARIES (UNIVERSAL ADAPTER)	4.000 EA	1300.00000	5200.00	1297.00000	5188.00	1300.00000	5200.00
1965 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	39.000 EA	40.00000	1560.00	40.00000	1560.00	41.00000	1599.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
1970 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	2.000 EA	40.00000	80.00	40.00000	80.00	41.00000	82.00
1975 0690 31 SIGNAL PEDESTAL REMOVAL	1.000 EA	40.00000	40.00	40.00000	40.00	41.00000	41.00
1980 0690 33 1 POLE REMOVAL (DEEP DIRECT BURIAL)	226.000 LF	220.00000	49720.00	220.00000	49720.00	222.00000	50172.00
1985 0690 50 CNTRL ASSEM REMOVE	5.000 EA	160.00000	800.00	157.00000	785.00	160.00000	800.00
1990 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	2.000 EA	40.00000	80.00	40.00000	80.00	41.00000	82.00
1995 0690 80 SPAN WIRE ASSEMBLY REMOVE	3.000 EA	350.00000	1050.00	313.00000	939.00	315.00000	945.00
2000 0690 90 CONDUIT & CABLING REMOVE	5.000 PI	1250.00000	6250.00	1249.00000	6245.00	1250.00000	6250.00
2005 0690 91 SIGNAL INTERCONNECT CABLE REMOVE	1915.000 LF	1.50000	2872.50	1.20000	2298.00	1.25000	2393.75
2010 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	5.000 PI	1250.00000	6250.00	1249.00000	6245.00	1250.00000	6250.00
2015 0700 40 1 SIGN SINGLE POST (LESS THAN 12)	1.000 AS	275.00000	275.00	258.00000	258.00	260.00000	260.00
2020 0700 48 18 SIGN PANELS (F & I) (15 OR <)	21.000 EA	225.00000	4725.00	223.00000	4683.00	225.00000	4725.00
2025 0700 48 60 SIGN PANELS (REMOVE)	12.000 EA	80.00000	960.00	79.00000	948.00	80.00000	960.00
2030 0715 2112 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (1")	77404.000 LF	4.10000	317356.40	0.41000	31735.64	4.15000	321226.60
2035 0715 2117 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (4")	19351.000 LF	5.10000	98690.10	5.10000	98690.10	5.15000	99657.65
2040 0730 76113 CASING STEEL (F&I) (24")	120.000 LF	75.00000	9000.00	300.00000	36000.00	20.00000	2400.00
2045 0745 70 12 TMS INDUCTIVE LOOP ASSEM(F&I)(2 LOOPS/LN)	9.000 AS	1100.00000	9900.00	1093.00000	9837.00	1100.00000	9900.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
2050 0746 71111 TMS CABINET(F&I)(TYPE III)(BASE MNT)(1 BACKPLANE)	1.000 EA	2400.00000	2400.00	2427.00000	2427.00	2430.00000	2430.00
2055 0746 71112 TMS CABINET(F&I)(TYPE III)(BASE MNT)(2 BACKPLANE)	1.000 EA	2700.00000	2700.00	2678.00000	2678.00	2700.00000	2700.00
SECTION 0005 TOTALS		$	958,576.00	$	697,985.74	$	957,437.00
SECTION 0006 LANDSCAPE / PERIPHERAL							
2060 0430961211 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (3")	183.900 LF	8.00000	1471.20	10.00000	1839.00	3.50000	643.65
2065 0430961213 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (4")	1274.600 LF	10.00000	12746.00	10.00000	12746.00	3.50000	4461.10
2070 0430961216 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (6")	2473.800 LF	12.00000	29685.60	15.00000	37107.00	4.00000	9895.20
SECTION 0006 TOTALS		$	43,902.80	$	51,692.00	$	14,999.95
SECTION 0007 UTILITIES							
0076 0556 1 5 JACK AND BORE CASING DIAMETER(24" TO <36")	114.000 LF	200.00000	22800.00	300.00000	34200.00	2700.00000	307800.00
2075 0101 1 MOBILIZATION 25023455601	LUMP	30000.00000	30000.00	100000.00000	100000.00	125000.00000	125000.00
2080 0102 1 MAINTENANCE OF TRAFFIC 25023455601	120.000 LS	10000.00000	10000.00	200000.00000	200000.00	250000.00000	250000.00
2085 0102 14 TRAFFIC CONTROL OFFICER	160.000 MH	38.00000	6080.00	40.00000	6400.00	43.00000	6880.00
2090 0102 60 WORK ZONE SIGNS	1879.000 ED	0.20000	375.80	0.20000	375.80	1.00000	1879.00
2095 0102 71 11 BARRIER WALL (TEMPORARY) (F&I)(CONCRETE	1250.000 LF	15.00000	18750.00	12.00000	15000.00	37.00000	46250.00
2100 0102 71 21 BARRIER WALL (TEMPORARY) (RELOCATE)(CONCRETE)	1120.000 LF	8.00000	8960.00	12.00000	13440.00	12.00000	13440.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
2105 0102 74 1 BARRICADE (TEMPORARY)(TYPES I,II,VP & DRUM)	8852.000 ED	0.18000	1593.36	0.23000	2035.96	0.18000	1593.36
2110 0102 74 2 BARRICADE (TEMPORARY)(TYPE III) (6')	949.000 ED	0.40000	379.60	0.45000	427.05	0.48000	455.52
2115 0102 76 PANELS ARROW ADVANCE WARNING	188.000 ED	7.00000	1316.00	7.00000	1316.00	7.25000	1363.00
2120 0102 77 HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	717.000 ED	0.40000	286.80	0.40000	286.80	0.50000	358.50
2125 0102 78 MARKER PAVT REFLECTIVE (TEMPORARY)	160.000 EA	3.00000	480.00	2.50000	400.00	3.00000	480.00
2130 0102 79 LIGHTS(TEMP-BARR. WALL MOUNT)(TYPE C STEADY BURN)	2790.000 ED	0.15000	418.50	0.16000	446.40	0.15000	418.50
2135 0102 89 7 IMPACT ATTENUATOR (REDIRECTIVE OPTION)(TEMPORARY)	4.000 LO	1250.00000	5000.00	250.00000	1000.00	1200.00000	4800.00
2140 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	6.000 ED	18.00000	108.00	1.00000	6.00	30.00000	180.00
2145 0125 1 EXCAVATION FOR STRUCTURES	67.000 CY	0.03000	2.01	20.00000	1340.00	35.00000	2345.00
2150 0710 6 DIRECTIONAL ARROWS, PAINTED	10.000 EA	20.00000	200.00	20.00000	200.00	20.00000	200.00
2155 0710 7 PAVT MESSAGE, PAINTED	1.000 EA	50.00000	50.00	50.00000	50.00	50.00000	50.00
2160 0710 25 61 TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	1720.000 LF	0.15000	258.00	0.13000	223.60	0.14000	240.80
2165 0710 25 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	42.000 LF	0.40000	16.80	0.33000	13.86	0.34000	14.28
2170 0710 25121 TRAFFIC STRIPE SOLID (WHITE/BLACK) (12")	248.000 LF	1.00000	248.00	1.00000	248.00	1.00000	248.00
2175 0710 25181 TRAFFIC STRIPE SOLID (WHITE/BLACK) (18")	6.000 LF	1.50000	9.00	1.45000	8.70	5.00000	30.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
2180 0710 25241 TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	124.000 LF	1.80000	223.20	1.50000	186.00	1.50000	186.00
2185 0710 26 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	3880.000 LF	0.15000	582.00	0.13000	504.40	0.15000	582.00
2190 0710 27 TRAFFIC STRIPE SKIP (WHITE/BLACK)	143.000 LF	0.45000	64.35	0.45000	64.35	0.50000	71.50
2195 0711 7 PAVT MARKING REMOVE THERMOPLASTIC	1991.000 SF	1.25000	2488.75	1.25000	2488.75	1.50000	2986.50
2200 0730 76116 CASING STEEL (F&I) (30")	373.000 LF	200.00000	74600.00	270.00000	100710.00	225.00000	83925.00
2205 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 25023455601	LUMP	150000.00000	150000.00	150000.00000	150000.00	150000.00000	150000.00
2210 1010 1 PIPE(PLUG & PLACE OUT OF SERVICE)(8" OR LESS)	3.000 EA	1250.00000	3750.00	100.00000	300.00	800.00000	2400.00
2215 1010 3 PIPE(PLUG & PLACE OUT OF SERVICE)(9" OR MORE)	25.000 LF	300.00000	7500.00	100.00000	2500.00	210.00000	5250.00
2220 1060144 51 UTILITY STRUCT(F&I)(SPECIAL)METERING SYSTEM(CONT OPT)0-6'	1.000 EA	23000.00000	23000.00	45000.00000	45000.00	46000.00000	46000.00
2225 1070111113 VALVE ASSEMBLY GATE (F&I)(CI) (150 PSI)(16")	13.000 EA	3000.00000	39000.00	6000.00000	78000.00	6200.00000	80600.00
2230 1070111208 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(6")	1.000 EA	900.00000	900.00	3000.00000	3000.00	1800.00000	1800.00
2235 1070111209 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(8")	1.000 EA	1300.00000	1300.00	4000.00000	4000.00	2100.00000	2100.00
2240 1070111211 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(12")	4.000 EA	1900.00000	7600.00	5000.00000	20000.00	2900.00000	11600.00

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GILBERT SOUTHERN CORP. UNIT PRICE	 AMOUNT	(2) DE MOYA GROUP INC. (THE) UNIT PRICE	 AMOUNT	(3) AMEC CIVIL, LLC UNIT PRICE	 AMOUNT
2245 1070116205 VALVE ASSEMBLY(BLOWOFF ASSEMBLY)(F&I)(CI)(250 PSI)(2")	4.000 EA	1900.00000	7600.00	1000.00000	4000.00	1300.00000	5200.00
2250 1070118205 VALVE ASSEMBLY(F&I)(CAST IRON)(AIR RELEASE ASSEMBLY) (250PSI)(2")	11.000 EA	1500.00000	16500.00	1000.00000	11000.00	1350.00000	14850.00
2255 1100111813 PIPE(CAST/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(250PSI)(16")	6492.000 LF	150.00000	973800.00	80.00000	519360.00	110.00000	714120.00
2260 1100111908 PIPE(CASTI/DUCTILE IRON)CEMENT LINED(F&I)(PUSH ON)(350P)(6")	36.000 LF	130.00000	4680.00	80.00000	2880.00	55.00000	1980.00
2265 1100111909 PIPE(CASTI/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(350P)(8")	60.000 LF	180.00000	10800.00	80.00000	4800.00	70.00000	4200.00
2270 1100111911 PIPE(CAST/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(350PSI)(12")	323.000 LF	105.00000	33915.00	80.00000	25840.00	160.00000	51680.00
2275 1110132213 PIPE(STEEL)(COATED)(F&I)(FLANGE JOINT)(CLASS 5/16)(16")	228.000 LF	110.00000	25080.00	400.00000	91200.00	400.00000	91200.00
2280 1610140 FITTINGS WATER(FURNISH&INSTALL)(DI-CEMENT LINED)	6.900 TN	5000.00000	34500.00	12000.00000	82800.00	13500.00000	93150.00
2285 1637131106 VLV BOX,TAP CROSS&VALVE,WITH SLV&VALVE(F&I)(8"X 8")	1.000 EA	2800.00000	2800.00	5000.00000	5000.00	5100.00000	5100.00
2290 1637131134 VALV BOX,TAP CROSS&VALVE(2PC)W/SLEEVE&VALV(F&I)(DI)(24"X16")	1.000 EA	5000.00000	5000.00	20000.00000	20000.00	16000.00000	16000.00
2295 1644900 FIRE HYDRANT(REMOVE)	4.000 EA	600.00000	2400.00	1000.00000	4000.00	700.00000	2800.00
2300 1698170 02 WATER SERVICE COPPER(FURNISH & INSTALL)(1")	39.000 LF	25.00000	975.00	100.00000	3900.00	93.00000	3627.00
SECTION 0007 TOTALS			$ 1,536,390.17		$ 1,558,951.67		$ 2,155,433.96
CONTRACT TOTALS			$ 82,642,526.49		$ 91,979,734.07		$ 93,496,203.08

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0101 1 MOBILIZATION 40832015201	LUMP	106000.00000	106000.00				
0010 0101 1 MOBILIZATION 24993725201	LUMP	264000.00000	264000.00				
0015 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	9292.000 LS	207000.00000	207000.00				
0020 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	8596.000 LS	332000.00000	332000.00				
0025 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	9292.000 LS	193000.00000	193000.00				
0030 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	8596.000 LS	277000.00000	277000.00				
0035 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	7100.000 LS	242000.00000	242000.00				
0040 0110 3 STRUCTURE REMOVAL OF EXISTING 25023445201	10473.000 LS	232000.00000	232000.00				
0045 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	13362.000 LS	223000.00000	223000.00				
0050 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	5260.000 LS	246000.00000	246000.00				
0055 0121 70 FLOWABLE FILL	103.000 CY	490.00000	50470.00				
0060 0400 2 4 CONC CLASS II(SUPERSTRUCTURE)	6458.470 CY	645.00000	4165713.15				
0065 0400 2 10 CONC CLASS II (APPROACH SLABS)	1428.920 CY	250.00000	357230.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0070 0400 3 20 CONC CLASS III	1359.100 CY (SEAL)	270.00000	366957.00				
0075 0400 4 5 CONC CLASS IV	1349.580 CY (SUBSTRUCTURE)	985.00000	1329336.30				
0080 0400 4 8 CONC CLASS IV	205.170 CY (BULKHEAD)	800.00000	164136.00				
0085 0400 4 11 CONC CLASS IV WALLS)	22.000 CY (RETAINING	1165.00000	25630.00				
0090 0400 4 25 CONC CLASS IV (MASS)(SUBSTRUCTURE)	5301.530 CY	470.00000	2491719.10				
0095 0400 7 BRIDGE FLOOR GROOVING	23296.000 SY	1.80000	41932.80				
0096 0400 95 COFFERDAM	5.000 EA	131000.00000	655000.00				
0100 0400147 COMPOSITE NEOPRENE PADS	67.220 CF	1260.00000	84697.20				
0105 0415 1 3 REINF STEEL WALL)	3450.000 LB (RETAINING	1.10000	3795.00				
0110 0415 1 4 REINF STEEL (SUPERSTRUCTURE)	1933746.000 LB	0.90000	1740371.40				
0115 0415 1 5 REINF STEEL	1294447.000 LB (SUBSTRUCTURE)	0.95000	1229724.65				
0120 0415 1 8 REINF STEEL	16954.000 LB (BULKHEAD)	0.98000	16614.92				
0125 0415 1 9 REINF STEEL SLABS)	272156.000 LB (APPROACH	0.88000	239497.28				
0130 0450 1 1 PREST BEAMS	2799.330 LF (TYPE II)	86.00000	240742.38				
0135 0450 1 2 PREST BEAMS	5817.330 LF (TYPE III)	127.00000	738800.91				
0140 0451 70 PREST SOIL ANCHORS	43.000 EA	1997.00000	85871.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0145 0451 70 1 PREST SOIL ANCHOR (PERFORMANCE TEST)	9.000 EA	667.00000	6003.00				
0150 0451 70 2 PREST SOIL ANCHOR (CREEP TEST)	2.000 EA	2001.00000	4002.00				
0155 0455 34 3 CONCRETE PILING PRESTRESSED (18" SQ.)	46703.900 LF	75.00000	3502792.50				
0160 0455 34 5 CONCRETE PILING PRESTRESSED (24" SQ.)	4317.500 LF	92.00000	397210.00				
0165 0455 87 ANCHOR BAR STEEL	25.000 EA	538.00000	13450.00				
0170 0455 88 7 DRILLED SHAFT (72" DIA)	1789.000 LF	280.00000	500920.00				
0175 0455103130 TEST LOAD (STATNAMIC)(COMPRESSION)(3000 TONS)	2.000 EA	150452.00000	300904.00				
0180 0455107 7 CASING (72" DIA)	180.000 LF	385.00000	69300.00				
0185 0455122 7 EXCAVATION UNCLASSIFIED SHAFT (72" DIA)	1789.000 LF	500.00000	894500.00				
0190 0455133 SHEET PILING STEEL	22891.000 SF	27.00000	618057.00				
0195 0455133 1 SHEET PILING STEEL (TEMPORARY)	37545.000 SF	13.50000	506857.50				
0200 0455137 TEST LOAD(DYNAMIC)	47.000 EA	1700.00000	79900.00				
0205 0455142 CROSSHOLE SONIC LOGGING	14.000 EA	3890.00000	54460.00				
0206 0521 5 20 CNC TRAF RAIL BARRIER BRG(F-SHAPED W/ SNB BAR WALL 8' HT	134.000 LF	578.00000	77452.00				
0210 0455143 3 TEST PILES (PRESTRESSED CONCRETE) (18" SQ.)	3829.100 LF	145.00000	555219.50				
0215 0455143 5 TEST PILES (PRESTRESSED CONCRETE) (24" SQ.)	430.500 LF	210.00000	90405.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0220 0459 71 POLYETHYLENE SHEETING ON CONCRETE PILES	2413.530 SY	3.50000	8447.36				
0225 0460 2 1 STRUCT STEEL (CARBON) 24993725201	79950.000 LS	304000.00000	304000.00				
0230 0460 2 1 STRUCT STEEL (CARBON) 40883415201	14733.000 LS	272000.00000	272000.00				
0235 0460 2 1 STRUCT STEEL (CARBON) 40883415201	53300.000 LS	197000.00000	197000.00				
0240 0460 2 1 STRUCT STEEL (CARBON) 40883415201	60300.000 LS	121000.00000	121000.00				
0245 0460 2 1 STRUCT STEEL (CARBON) 25023445201	188884.000 LS	121000.00000	121000.00				
0250 0460 2 1 STRUCT STEEL (CARBON) 40883415201	175900.000 LS	56000.00000	56000.00				
0255 0460 2 1 STRUCT STEEL (CARBON) 40883415201	19523.000 LS	56000.00000	56000.00				
0260 0460 2 2 STRUCT STEEL (LOW ALLOY) 24993725201	1724374.000 LS	3350000.00000	3350000.00				
0265 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	1044000.000 LS	2900000.00000	2900000.00				
0270 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	385897.000 LS	1790000.00000	1790000.00				
0275 0460 2 2 STRUCT STEEL (LOW ALLOY) 25023445201	2094767.000 LS	1200000.00000	1200000.00				
0280 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	791400.000 LS	1200000.00000	1200000.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0285 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	333314.000 LS	554000.00000	554000.00				
0290 0460 2 2 STRUCT STEEL (LOW ALLOY) 40883415201	703600.000 LS	554000.00000	554000.00				
0295 0460 2 13 STRUCT STEEL (BOLTS, NUTS, WASHERS & PLATES) 24993725201	67707.000 LS	171000.00000	171000.00				
0300 0460 7 4 EXPANSION JOINT SEAL (STRIP ELAST)	380.000 LF	155.00000	58900.00				
0305 0461113 12 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(251-500 KIPS)	6.000 EA	3590.00000	21540.00				
0310 0461113 14 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(751-1000 KIPS)	3.000 EA	6100.00000	18300.00				
0315 0461113 15 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(1000-1250 KIPS)	4.000 EA	9780.00000	39120.00				
0320 0461113 17 MULTIROTATIONAL BEARING ASSEM-FIXED(F&I)(1501-1750 KIPS)	2.000 EA	14760.00000	29520.00				
0325 0461114 12 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(251-500 KIPS)	18.000 EA	4060.00000	73080.00				
0330 0461114 13 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(501-750 KIPS)	4.000 EA	5600.00000	22400.00				
0335 0461114 14 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(751-1000 KIPS)	4.000 EA	8500.00000	34000.00				
0340 0461114 15 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1001-1250 KIPS)	2.000 EA	11345.00000	22690.00				
0345 0461114 16 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1251-1500 KIPS)	4.000 EA	10200.00000	40800.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0350 0461114 17 MULTIROTATIONAL BEARING ASSEM EXP(F&I)(1501-1750 KIPS)	2.000 EA	15235.00000	30470.00				
0355 0506 2 BRIDGE DRAINAGE PIPING	1687.000 LF	39.00000	65793.00				
0360 0506 3 BRIDGE DRAINS	15.000 EA	1535.00000	23025.00				
0365 0521 5 1 CONCRETE TRAFFIC RAILING BARRIER BRIDGE (32" F)	9989.000 LF	70.00000	699230.00				
0370 0521 8 1 CONC TRAF RAIL BARRIER(RET WALL SYSTEM)32" F SHAPE	370.000 LF	186.00000	68820.00				
0375 0521 72 4 BARRIER WALL CONC (RIGID-RETAINING)	48.000 LF	89.00000	4272.00				
0380 0547 70 1 RIPRAP FABRIC-FORMED CONCRETE (8" FILTER POINTS)	270.000 SY	46.00000	12420.00				
0385 0548 12 RETAINING WALL SYSTEM(PERMANENT)(EXCLUDING BARRIER)	11625.000 SF	25.00000	290625.00				
0390 0548 13 RETAINING WALL SYSTEM(TEMPORARY)(EXCLUDING BARRIER)	1715.000 SF	21.00000	36015.00				
0395 0750 71 ELECTRICAL WORK 24993725201	LUMP	25000.00000	25000.00				
0396 0750 71 ELECTRICAL WORK	LUMP	25000.00000	25000.00				
0400 0750 71 ELECTRICAL WORK 40883415201	LUMP	25000.00000	25000.00				
SECTION 0001 TOTALS			$ 38,542,138.95		$		$
SECTION 0002 ROADWAY							
0405 0101 1 MOBILIZATION 25023445201	LUMP	600000.00000	600000.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0410 0101 1 MOBILIZATION 40883415201	LUMP	582014.00000	582014.00				
0415 0101 1 MOBILIZATION 25023425201	LUMP	6988548.00000	6988548.00				
0420 0102 1 MAINTENANCE OF TRAFFIC 25023425201	700.000 LS	306000.00000	306000.00				
0425 0102 1 MAINTENANCE OF TRAFFIC 25023445201	1337.000 LS	2400000.00000	2400000.00				
0430 0102 1 MAINTENANCE OF TRAFFIC 40883415201	1800.000 LS	313000.00000	313000.00				
0435 0102 2 1 SPECIAL DETOUR (DETOUR 1) 40883415201	LUMP	123000.00000	123000.00				
0440 0102 2 2 SPECIAL DETOUR (DETOUR 2) 40883415201	LUMP	87000.00000	87000.00				
0445 0102 2 3 SPECIAL DETOUR (DETOUR 3) 40883415201	LUMP	205000.00000	205000.00				
0450 0102 2 4 SPECIAL DETOUR (DETOUR 4) 40883415201	LUMP	187000.00000	187000.00				
0455 0102 2 5 SPECIAL DETOUR (DETOUR 5) 40883415201	LUMP	128000.00000	128000.00				
0460 0102 2 6 SPECIAL DETOUR (DETOUR 6) 40883415201	LUMP	94000.00000	94000.00				
0465 0102 2 7 SPECIAL DETOUR (DETOUR 7) 40883415201	LUMP	127000.00000	127000.00				
0470 0102 2 8 SPECIAL DETOUR (DETOUR 8) 40883415201	LUMP	177000.00000	177000.00				
0475 0102 2 9 SPECIAL DETOUR (DETOUR 9) 40883415201	LUMP	100000.00000	100000.00				
0480 0102 2 10 SPECIAL DETOUR (DETOUR 10) 40883415201	LUMP	74000.00000	74000.00				
0485 0102 2 11 SPECIAL DETOUR (DETOUR 11) 40883415201	LUMP	71000.00000	71000.00				
0490 0102 2 12 SPECIAL DETOUR (DETOUR 12) 40883415201	LUMP	91000.00000	91000.00				
0495 0102 2 13 SPECIAL DETOUR (DETOUR 13) 25023445201	LUMP	156000.00000	156000.00				
0500 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	691.000 CY	60.00000	41460.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0505 0102 14 TRAFFIC CONTROL OFFICER	2346.000 MH	39.00000	91494.00				
0510 0102 60 WORK ZONE SIGNS	429195.000 ED	0.22000	94422.90				
0515 0102 61 BUSINESS SIGNS	12.000 EA	110.00000	1320.00				
0520 0102 71 11 BARRIER WALL (TEMPORARY) (F&I)(CONCRETE	15375.000 LF	16.00000	246000.00				
0525 0102 71 14 BARRIER WALL (TEMPORARY) (F&I)(TYPE K)	10367.000 LF	56.00000	580552.00				
0530 0102 71 21 BARRIER WALL (TEMPORARY) (RELOCATE)(CONCRETE)	31471.000 LF	4.50000	141619.50				
0535 0102 71 24 BARRIER WALL (TEMPORARY) (RELOCATE)(TYPE K)	16129.000 LF	9.35000	150806.15				
0540 0102 74 1 BARRICADE (TEMPORARY)(TYPES I,II,VP & DRUM)	581809.000 ED	0.20000	116361.80				
0545 0102 74 2 BARRICADE (TEMPORARY)(TYPE III) (6')	38329.000 ED	0.44000	16864.76				
0550 0102 76 PANELS ARROW ADVANCE WARNING	5187.000 ED	7.50000	38902.50				
0555 0102 77 HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	60035.000 ED	0.44000	26415.40				
0560 0102 78 MARKER PAVT REFLECTIVE (TEMPORARY)	13375.000 EA	2.75000	36781.25				
0565 0102 79 LIGHTS(TEMP-BARR. WALL MOUNT)(TYPE C STEADY BURN)	212211.000 ED	0.17000	36075.87				
0570 0102 89 7 IMPACT ATTENUATOR (REDIRECTIVE OPTION)(TEMPORARY)	265.000 LO	1400.00000	371000.00				
0575 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	12523.000 ED	20.00000	250460.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0580 0104 1 ARTIFICIAL COVERINGS	1389.000	SY	2.70000	3750.30				
0585 0104 4 MOWING	204.400	AC	645.00000	131838.00				
0590 0104 7 SEDIMENT BASINS	14.000	EA	2580.00000	36120.00				
0595 0104 9 SEDIMENT BASIN CLEANOUTS	14.000	CO	1025.00000	14350.00				
0600 0104 11 1 TURBIDITY BARRIER FLOATING (SPECIAL)	1719.000	LF	9.00000	15471.00				
0605 0104 13 1 SILT FENCE STAKED (TYPE III)	5195.000	LF	0.70000	3636.50				
0610 0104 13 2 STAKED SILT FENCE (TYPE IV)	1521.000	LF	2.70000	4106.70				
0615 0104 15 PREVENTION DEVICE SOIL TRACKING	18.000	EA	4000.00000	72000.00				
0620 0104 16 ROCK BAGS	2940.000	EA	5.00000	14700.00				
0625 0109 71 2 FIELD OFFICE (600 SQ FT)	1800.000	DA	44.00000	79200.00				
0630 0109 71 5 FIELD OFFICE (1500 SQ FT)	1800.000	DA	66.00000	118800.00				
0635 0110 1 1 CLEARING & GRUBBING 40883415201	32.010	LS	363000.00000	363000.00				
0640 0110 1 1 CLEARING & GRUBBING 25023425201	24.360	LS	365000.00000	365000.00				
0645 0110 1 1 CLEARING & GRUBBING 25023445201	2.010	LS	553000.00000	553000.00				
0650 0110 3 STRUCTURE REMOVAL OF EXISTING 40883415201	61314.000	LS	129600.00000	129600.00				
0655 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 25023425201		LUMP	1500.00000	1500.00				
0660 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 40883415201		LUMP	1500.00000	1500.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0665 0110 86 DELIVERY OF SALVAGEABLE MATERIAL TO FDOT 25023445201	LUMP	1500.00000	1500.00				
0670 0120 1 EXCAVATION REGULAR	158757.000 CY	4.25000	674717.25				
0675 0120 4 EXCAVATION SUBSOIL	23774.000 CY	12.00000	285288.00				
0676 0120 5 EXCAVATION CHANNEL	15624.000 CY	13.00000	203112.00				
0680 0120 6 EMBANKMENT	192802.000 CY	5.60000	1079691.20				
0685 0121 70 FLOWABLE FILL	70.000 CY	180.00000	12600.00				
0690 0160 4 STABILIZATION TYPE B	125602.200 SY	1.90000	238644.18				
0695 0162 3101 FINISH SOIL LAYER(GRASSING OPERATIONS) (6")	142490.000 SY	0.60000	85494.00				
0700 0285704 BASE OPTIONAL (BASE GROUP 04)	11654.600 SY	13.40000	156171.64				
0705 0285706 BASE OPTIONAL (BASE GROUP 06)	191.000 SY	23.00000	4393.00				
0710 0285709 BASE OPTIONAL (BASE GROUP 09)	2992.600 SY	16.00000	47881.60				
0715 0285710 BASE OPTIONAL (BASE GROUP 10)	95521.900 SY	18.00000	1719394.20				
0720 0285715 BASE OPTIONAL (BASE GROUP 15)	1268.000 SY	57.00000	72276.00				
0725 0327 70 6 MILLING EXIST ASPH PAVT (1 1/2" AVG DEPTH)	44656.000 SY	3.10000	138433.60				
0730 0327 70 13 MILLING EXIST ASPH PAVT (1 3/4" AVG DEPTH)	277.000 SY	15.00000	4155.00				
0735 0334 1 11 SUPERPAVE ASPHALTIC CONC (TRAFFIC A)	1815.800 TN	220.00000	399476.00				
0740 0334 1 13 SUPERPAVE ASPHALTIC CONC (TRAFFIC C)	14579.700 TN	75.00000	1093477.50				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0745 0334 1 14 SUPERPAVE ASPHALTIC CONC (TRAFFIC D)	2158.000	TN	75.00000	161850.00				
0750 0337 7 6 ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(FC-6)	12170.400	TN	82.00000	997972.80				
0755 0337 7 7 ASPH CONC FRICTION COURSE(INC BIT / RUBBER) (FC-9.5)	1393.200	TN	92.00000	128174.40				
0760 0339 1 ASPHALT PAVEMENT MISCELLANEOUS	431.000	TN	160.00000	68960.00				
0765 0400 1 2 CONC CLASS I(ENDWALLS)	352.690	CY	575.00000	202796.75				
0770 0400 1 11 CONC CLASS I(RETAINING WALLS)	22.800	CY	520.00000	11856.00				
0775 0400 1 15 CONC CLASS I(MISCELLANEOUS)	768.900	CY	532.00000	409054.80				
0780 0400 4 11 CONC CLASS IV (RETAINING WALLS)	144.000	CY	560.00000	80640.00				
0785 0410 70 64 PRECAST CONC BOX CULVERT (F&I) (6' SPAN)(4' HT)	25.000	LF	920.00000	23000.00				
0790 0415 1 1 REINF STEEL (ROADWAY)	1573.000	LB	0.98000	1541.54				
0795 0415 1 3 REINF STEEL (RETAINING WALL)	20425.000	LB	0.98000	20016.50				
0800 0425 1311 INLETS (CURB) (TYPE P-1) (<10')	2.000	EA	2800.00000	5600.00				
0805 0425 1341 INLETS (CURB) (TYPE P-4) (<10')	3.000	EA	2850.00000	8550.00				
0810 0425 1351 INLETS (CURB) (TYPE P-5) (<10')	26.000	EA	2700.00000	70200.00				
0815 0425 1352 INLETS (CURB) (TYPE P-5) (>10')	2.000	EA	2900.00000	5800.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0820 0425 1361 INLETS (CURB) (TYPE P-6) (<10')	9.000 EA	3500.00000	31500.00				
0825 0425 1451 INLETS (CURB) (TYPE J-5) (<10')	6.000 EA	7200.00000	43200.00				
0830 0425 1452 INLETS (CURB) (TYPE J-5) (>10')	2.000 EA	12665.00000	25330.00				
0835 0425 1461 INLETS (CURB) (TYPE J-6) (<10')	2.000 EA	6705.00000	13410.00				
0840 0425 1481 INLETS (CURB) (TYPE 8) (<10')	2.000 EA	2200.00000	4400.00				
0845 0425 1501 INLETS (DT BOT) (TYPE A) (<10')	3.000 EA	2635.00000	7905.00				
0850 0425 1541 INLETS (DT BOT) (TYPE D) (<10')	27.000 EA	2560.00000	69120.00				
0855 0425 1561 INLETS (DT BOT) (TYPE F) (<10')	1.000 EA	2720.00000	2720.00				
0860 0425 1571 INLETS (DT BOT) (TYPE G) (<10')	9.000 EA	2710.00000	24390.00				
0865 0425 1701 INLETS (GUTTER) (TYPE S) (<10')	9.000 EA	2600.00000	23400.00				
0870 0425 1702 INLETS (GUTTER) (TYPE S) (>10')	3.000 EA	3215.00000	9645.00				
0875 0425 1703 INLETS (GUTTER) (TYPE S) (J BOT, <10')	1.000 EA	3865.00000	3865.00				
0880 0425 1705 INLETS (GUTTER) (TYPE S) (PARTIAL)	2.000 EA	2040.00000	4080.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0885 0425 1711 INLETS (GUTTER) (TYPE V) (<10')	1.000 EA	2600.00000	2600.00				
0890 0425 1713 INLETS (GUTTER) (TYPE V) (J BOT, <10')	1.000 EA	4350.00000	4350.00				
0895 0425 1881 INLETS (BARRIER WALL,RIGID,CURB & GUTTER) (<10')	3.000 EA	3765.00000	11295.00				
0900 0425 1891 INLETS (BARRIER WALL) (<10')	15.000 EA	3710.00000	55650.00				
0905 0425 1892 INLETS (BARRIER WALL) (>10')	3.000 EA	4495.00000	13485.00				
0910 0425 1910 INLETS (CLOSED FLUME)(N/A)	25.000 EA	2245.00000	56125.00				
0915 0425 2 41 MANHOLES (P-7) (<10')	15.000 EA	2270.00000	34050.00				
0920 0425 2 42 MANHOLES (P-7) (>10')	2.000 EA	2675.00000	5350.00				
0925 0425 2 43 MANHOLES (P-7) (PARTIAL)	8.000 EA	1660.00000	13280.00				
0930 0425 2 71 MANHOLES (J-7) (<10')	5.000 EA	3565.00000	17825.00				
0935 0425 2 72 MANHOLES (J-7) (>10')	6.000 EA	8200.00000	49200.00				
0940 0425 2101 MANHOLES (SPECIAL) (<10')	3.000 EA	5850.00000	17550.00				
0945 0425 2102 MANHOLES (SPECIAL) (>10')	4.000 EA	6640.00000	26560.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0950 0425 2103 MANHOLES (SPECIAL) (PARTIAL)	1.000 EA	3150.00000	3150.00				
0955 0425 3 83 JUNCTION BOXES (SPECIAL) (PARTIAL)	1.000 EA	3135.00000	3135.00				
0960 0425 5 MANHOLE (ADJUST)	13.000 EA	660.00000	8580.00				
0965 0426733023 SLOTTED DRAIN PIPE (OPTIONAL) (GA 16)(15")	30.000 LF	170.00000	5100.00				
0970 0430171125 PIPE CULV(OPT MATL)(ROUND)(18"SS)	7334.000 LF	40.00000	293360.00				
0975 0430171129 PIPE CULV(OPT MATL)(ROUND)(24"SS)	1756.000 LF	50.00000	87800.00				
0980 0430171133 PIPE CULV(OPT MATL)(ROUND)(30"SS)	101.000 LF	72.00000	7272.00				
0985 0430171138 PIPE CULV(OPT MATL)(ROUND)(36"SS)	99.000 LF	100.00000	9900.00				
0990 0430171140 PIPE CULV(OPT MATL)(ROUND)(42"SS)	425.000 LF	120.00000	51000.00				
0995 0430171141 PIPE CULV(OPT MATL)(ROUND)(48"SS)	644.000 LF	150.00000	96600.00				
1000 0430171223 PIPE CULV(OPT MATL)(OTHER)(15"SS)	2.000 LF	150.00000	300.00				
1005 0430172133 PIPE CULV(OPT MAT)(ROUND)(30"CD)	537.000 LF	66.00000	35442.00				
1010 0430172138 PIPE CULV(OPT MATL)(ROUND)(36"CD)	45.000 LF	100.00000	4500.00				
1015 0430173125 PIPE CULV(OPT MATL)(ROUND)(18"GD)	578.000 LF	68.00000	39304.00				
1020 0430173129 PIPE CULV(OPT MATL)(ROUND)(24"GD)	12.000 LF	60.00000	720.00				
1025 0430173133 PIPE CULV(OPT MATL)(ROUND)(30"GD)	42.000 LF	64.00000	2688.00				
1030 0430610 25 U-ENDWALL WITH GRATE (18")	1.000 EA	3110.00000	3110.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1035 0430941 02 PIPE ELLIP DESILTING (14" X 23" SS)	4.000 LF	18.00000	72.00				
1040 0430941 23 PIPE DESILTING (15" SS)	416.500 LF	7.65000	3186.23				
1045 0430941 25 PIPE DESILTING (18" SS)	472.100 LF	8.15000	3847.62				
1050 0430941 29 PIPE DESILTING (24" SS)	161.000 LF	9.15000	1473.15				
1055 0430941 33 PIPE DESILTING (30" SS)	1695.000 LF	13.50000	22882.50				
1060 0430941 38 PIPE DESILTING (36" SS)	347.000 LF	14.00000	4858.00				
1065 0430941 40 PIPE DESILTING (42" SS)	153.000 LF	19.50000	2983.50				
1070 0430941 41 PIPE DESILTING (48" SS)	216.000 LF	22.65000	4892.40				
1075 0430941 43 PIPE DESILTING (60" SS)	1112.000 LF	30.50000	33916.00				
1080 0430982125 MITERED END SECTION (OPTIONAL ROUND) (18" CD)	27.000 EA	920.00000	24840.00				
1085 0430982129 MITERED END SECTION (OPTIONAL ROUND) (24" CD)	8.000 EA	1025.00000	8200.00				
1090 0443 70 3 FRENCH DRAINS (18")	160.000 LF	145.00000	23200.00				
1095 0443 70 4 FRENCH DRAINS (24")	1926.000 LF	155.00000	298530.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1100 0451 70 PREST SOIL ANCHORS	518.000 EA	2000.00000	1036000.00				
1105 0451 70 1 PREST SOIL ANCHOR (PERFORMANCE TEST)	52.000 EA	667.00000	34684.00				
1110 0451 70 2 PREST SOIL ANCHOR (CREEP TEST)	26.000 EA	2001.00000	52026.00				
1115 0455133 1 SHEET PILING STEEL (TEMPORARY)	173650.000 SF	12.00000	2083800.00				
1120 0460 5 ENDWALL GRATE	326.000 LB	8.00000	2608.00				
1125 0520 1 10 CURB & GUTTER CONC (TYPE F)	31271.000 LF	18.00000	562878.00				
1130 0520 5 41 TRAF SEP CONC (TYPE IV) (4' WIDE)	1014.000 LF	52.00000	52728.00				
1135 0520 5 46 TRAF SEP CONC (TYPE IV) (8.5' WIDE)	239.000 LF	94.00000	22466.00				
1140 0520 6 GUTTER SHLDR CONC	2912.000 LF	23.00000	66976.00				
1145 0521 1 BARRIER WALL CONC	550.000 LF	125.00000	68750.00				
1150 0521 8 1 CONC TRAF RAIL BARRIER(RET WALL SYSTEM)32" F SHAPE	3539.000 LF	185.00000	654715.00				
1155 0521 72 3 BARRIER WALL CONC (RIGID-SHOULDER)	751.000 LF	89.00000	66839.00				
1160 0521 72 5 BARRIER WALL CONC (RIGID-CURB & GUTTER)	50.000 LF	460.00000	23000.00				
1165 0521 72 6 BARRIER WALL CONC (PLAIN-SHOULDER)	2615.000 LF	140.00000	366100.00				
1170 0521 73 BARRIER WALL REMOVAL (CONCRETE)	1543.000 LF	11.00000	16973.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1175 0522 1 SIDEWALK CONC (4" THICK)	1738.000 SY	45.00000	78210.00				
1180 0522 2 SIDEWALK CONC (6" THICK)	433.000 SY	59.00000	25547.00				
1185 0524 1 1 DITCH PAVT CONC (3")	515.400 SY	29.00000	14946.60				
1190 0524 2 2 SLOPE PAVT CONC (4")	92.000 SY	45.00000	4140.00				
1195 0536 1 1 GUARDRAIL (ROADWAY)	6168.000 LF	18.00000	111024.00				
1200 0536 2 GUARDRAIL (SHOP-BENT PANELS)	488.000 LF	21.00000	10248.00				
1205 0536 7 GUARDRAIL POST SPECIAL	4.000 EA	173.00000	692.00				
1210 0536 8 GUARDRAIL BRIDGE ANCHORAGE ASSEM	2.000 EA	2615.00000	5230.00				
1215 0536 73 GUARDRAIL REMOVAL	10363.800 LF	2.20000	22800.36				
1220 0536 82 GUARDRAIL ANCHORAGE (CONCRETE BARRIER WALL)	17.000 EA	2950.00000	50150.00				
1225 0536 85 22 GUARDRAIL END ANCHORAGE ASSEMBLY FLARED	8.000 EA	2445.00000	19560.00				
1230 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY PARALLEL	11.000 EA	2995.00000	32945.00				
1235 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY TYPE I	11.000 EA	565.00000	6215.00				
1240 0544 75 14 IMPACT ATTENUATOR VEHICULAR (QUADGURD)	4.000 EA	19280.00000	77120.00				
1245 0546 72 51 RUMBLE STRIP (GROUND-IN) (16" MIN. WIDTH)	0.644 PM	15000.00000	9660.00				
1250 0548 12 RETAINING WALL SYSTEM(PERMANENT)(EXCLUDING BARRIER)	87129.000 SF	24.00000	2091096.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1255 0548 13 RETAINING WALL SYSTEM(TEMPORARY)(EXCLUDING BARRIER)	40410.000 SF	11.00000	444510.00				
1260 0550 2 5 FENCING, TYPE B (5' HEIGHT)	142.000 LF	8.00000	1136.00				
1261 0550 2 7 FENCING, TYPE B (8' HEIGHT)	2038.000 LF	11.00000	22418.00				
1265 0550 2 7 FENCING, TYPE B (8' HEIGHT)	905.500 LF	11.40000	10322.70				
1270 0550 3 2 FENCE CORNER POST ASSEM (TYPE B)	2.000 EA	111.00000	222.00				
1275 0550 3 4 FENCE CORNER POST ASSEM (SPECIAL)	2.000 EA	222.00000	444.00				
1285 0550 4 4 FENCE PULL & END POST ASSEM (SPECIAL	4.000 EA	195.00000	780.00				
1286 0550 5 3 FENCE PULL POST ASSEMBLY (TYPE B) (SPECIAL)	8.000 EA	278.00000	2224.00				
1288 0550 6 3 FENCE END POST ASSEMBLY (TYPE B) (SPECIAL)	6.000 EA	278.00000	1668.00				
1315 0550 76121 FENCE GATE (TYPE B) (SINGLE 12')(12' OPENING)	1.000 EA	2000.00000	2000.00				
1320 0556 1 2 JACK AND BORE CASING DIAMETER(6" TO <12")	232.000 LF	213.00000	49416.00				
1325 0556 1 5 JACK AND BORE CASING DIAMETER(24" TO <36")	245.000 LF	1500.00000	367500.00				
1330 0570 2 SEED & MULCH	98714.000 SY	0.52000	51331.28				
1335 0570 3 1 SEED GRASS (PERM TYPE, ARGEN BAHIA)	2023.000 LB	8.00000	16184.00				
1340 0570 4 MULCH MATL	77.100 TN	610.00000	47031.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1345 0570 10 SEED GRASS (QUICK-GROWING TYPE)	145.000 LB	8.00000	1160.00				
1350 0571 1 12 PLASTIC EROSION MAT (TRM)(TYPE 2)	4218.720 SY	5.75000	24257.64				
1355 0575 1 3 SODDING (ARGENTINE BAHIA)	43776.000 SY	2.05000	89740.80				
1360 0580340 1 TREE PROTECTION (BATTERBOARD)	260.000 LF	20.00000	5200.00				
1365 0710 5 1 GUIDE LINES (PAINT) (WHITE)	2391.000 LF	0.27000	645.57				
1370 0710 5 2 GUIDE LINES (PAINT) (YELLOW)	1650.212 LF	0.27000	445.56				
1375 0710 6 DIRECTIONAL ARROWS, PAINTED	116.000 EA	22.00000	2552.00				
1380 0710 7 PAVT MESSAGE, PAINTED	118.000 EA	56.00000	6608.00				
1385 0710 11 MARKINGS (PAINT) REMOVAL	84744.000 SF	1.40000	118641.60				
1390 0710 21 TRAFFIC STRIPE SKIP (WHITE/BLACK)	20.940 GM	417.00000	8731.98				
1395 0710 22 TRAFFIC STRIPE SKIP (YELLOW)	0.280 GM	417.00000	116.76				
1400 0710 23 61 TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	33.620 NM	767.00000	25786.54				
1405 0710 23 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	1.626 NM	1938.00000	3151.19				
1410 0710 24 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	22.949 NM	767.00000	17601.88				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1415 0710 24 81 TRAFFIC STRIPE SOLID (YELLOW) (8")	0.106 NM	1938.00000	205.43				
1420 0710 25 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	6808.400 LF	0.36000	2451.02				
1425 0710 25121 TRAFFIC STRIPE SOLID (WHITE/BLACK) (12")	3104.000 LF	1.11000	3445.44				
1430 0710 25181 TRAFFIC STRIPE SOLID (WHITE/BLACK) (18")	3115.000 LF	1.60000	4984.00				
1435 0710 25241 TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	1796.000 LF	1.66000	2981.36				
1440 0710 26 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	3051.800 LF	0.14000	427.25				
1445 0710 26181 TRAFFIC STRIPE SOLID (YELLOW) (18")	1447.000 LF	1.60000	2315.20				
1450 0710 27 TRAFFIC STRIPE SKIP (WHITE/BLACK)	1860.000 LF	0.50000	930.00				
1455 0710 30 REFLECTIVE PAINT (ISLAND NOSE) (YELLOW)	6.000 SY	23.00000	138.00				
1460 0711 7 PAVT MARKING REMOVE THERMOPLASTIC	28012.000 SF	1.40000	39216.80				
1465 0715 2112 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (1")	68784.000 LF	4.55000	312967.20				
1470 0715 2115 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (2")	12559.000 LF	4.90000	61539.10				
1475 0715 2117 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (4")	25457.000 LF	5.78000	147141.46				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1480 0715 2215 CONDUIT (F&I UNDERPAVEMENT) (PVC SCH 40) (2")	95.000 LF	20.00000	1900.00				
1485 0715 2335 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (2")	420.000 LF	21.00000	8820.00				
1490 0715 2337 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (4")	420.000 LF	34.00000	14280.00				
1495 0715 14 11 PULL BOX (F&I) (ROADSIDE)	40.000 EA	344.00000	13760.00				
1500 0715 14 14 PULL BOX (F&I) (SURFACE MOUNT)	29.000 EA	140.00000	4060.00				
1505 0736 72 11 UTILITY RELOCATION (WATER) (PERMANENT) 25023445201	LUMP	73880.00000	73880.00				
1510 0999 10 CALENDAR DAYS (TIME BID)	10000.000 DD	1550.00000	15500000.00				
1515 0999 16 PARTNERING (DO NOT BID) 25023445201	LUMP	30000.00000	30000.00				
1520 0999 16 PARTNERING (DO NOT BID) 40883415201	LUMP	30000.00000	30000.00				
1525 0999 20 DISPUTES REVIEW BOARD (DO NOT BID)	15.000 DA	3000.00000	45000.00				
1530 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 25023425201	LUMP	150000.00000	150000.00				
1535 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 25023445201	LUMP	100000.00000	100000.00				
1540 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 40883415201	LUMP	50000.00000	50000.00				
SECTION 0002 TOTALS			$ 52,617,911.71		$		$
SECTION 0003 SIGNING							

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1545 0700 40 1 SIGN SINGLE POST (LESS THAN 12)	115.000 AS	271.00000	31165.00				
1550 0700 40 4 SIGN SINGLE POST (SPECIAL-EXIT GORE SIGN)	5.000 AS	1037.00000	5185.00				
1555 0700 41 10 SIGN MULTI POST (50 OR LESS)	11.000 AS	2797.00000	30767.00				
1560 0700 41 12 SIGN MULTI-POST (101 - 150 SF)	1.000 AS	5320.00000	5320.00				
1565 0700 41 14 SIGN MULTI-POST (201 - 250 SF)	1.000 AS	7055.00000	7055.00				
1570 0700 44033 SIGN LT'D OVHD TRUSS (T 41 TO 60,S 201 TO 300)	1.000 AS	53354.00000	53354.00				
1575 0700 44034 SIGN LT'D OVHD TRUSS (T 41 TO 60,S 301 TO 400)	1.000 AS	47690.00000	47690.00				
1580 0700 44043 SIGN LT'D OVHD TRUSS (T 61 TO 80,S 201 TO 300)	1.000 AS	44484.00000	44484.00				
1585 0700 44053 SIGN LT'D OVHD TRUSS (T 81 TO 100,S 201 TO 300)	1.000 AS	62430.00000	62430.00				
1590 0700 44056 SIGN LT'D OVHD TRUSS (T 81 TO 100,S 501 TO 600)	1.000 AS	88985.00000	88985.00				
1595 0700 44076 SIGN LT'D OVHD TRUSS (T 121 TO 140,S 501 TO 600)	1.000 AS	84035.00000	84035.00				
1600 0700 44084 SIGN LT'D OVHD TRUSS (T 141 TO 160,S 301 TO 400)	1.000 AS	70420.00000	70420.00				
1605 0700 45 12 SIGN LT'D OVHD CTLVR(C 20 OR <, S 51 TO 100)	2.000 AS	16150.00000	32300.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1610 0700 45 23 SIGN LT'D OVHD CTLVR(C 21 TO 30, S 101 TO 150)	5.000 AS	19231.00000	96155.00				
1615 0700 45 24 SIGN LT'D OVHD CTLVR(C 21 TO 30, S 151 TO 200)	1.000 AS	25725.00000	25725.00				
1620 0700 45 34 SIGN LT'D OVHD CTLVR(C 31 TO 40, S 151 TO 200)	1.000 AS	28291.00000	28291.00				
1625 0700 45 35 SIGN LT'D OVHD CTLVR(C 31 TO 40, S 201 TO 250)	1.000 AS	32723.00000	32723.00				
1630 0700 46 11 SIGN EXISTING (REMOVAL) (SINGLE POST)	175.000 AS	44.00000	7700.00				
1635 0700 46 12 SIGN EXISTING (REMOVAL) (MULTI - POST)	13.000 AS	348.00000	4524.00				
1640 0700 46 13 SIGN EXISTING (REMOVAL) (OVERHEAD TRUSS)	5.000 AS	2170.00000	10850.00				
1645 0700 46 14 SIGN EXISTING (REMOVAL) (OVERHEAD CANTILEVER)	13.000 AS	1042.00000	13546.00				
1650 0700 46 16 SIGN EXISTING (REMOVAL) (BRIDGE MOUNTED)	9.000 AS	2055.00000	18495.00				
1655 0700 48 60 SIGN PANELS (REMOVE)	17.000 EA	88.00000	1496.00				
1660 0700 83 SIGN OVHD (BRIDGE MOUNTED)	9.000 AS	5042.00000	45378.00				
1665 0705 10 11 MARKER OBJECT (POST MOUNT) (TYPE 1)	24.000 EA	116.00000	2784.00				
1670 0705 71 DELINEATOR TUBULAR (FLEXIBLE)	15.000 EA	56.00000	840.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1675 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 25023425201	LUMP	19538.00000	19538.00				
1680 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 25023445201	LUMP	50574.00000	50574.00				
1685 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 40883415201	LUMP	12411.00000	12411.00				
SECTION 0003 TOTALS		$	934,220.00	$		$	
SECTION 0004 LIGHTING							
1690 0400 1 15 CONC CLASS I(MISCELLANEOUS)	100.440 CY	295.00000	29629.80				
1695 0715 1111 CONDUCTORS (F&I)(INSULATED) (NO 10)	4453.000 LF	0.55000	2449.15				
1700 0715 1113 CONDUCTORS (F&I)(INSULATED) (NO 6)	79856.000 LF	0.77000	61489.12				
1705 0715 1114 CONDUCTORS (F&I)(INSULATED) (NO 4)	6370.000 LF	1.11000	7070.70				
1710 0715 1115 CONDUCTORS (F&I)(INSULATED) (NO 2)	1516.000 LF	1.22000	1849.52				
1715 0715 1119 CONDUCTORS (F&I)(INSULATED) (1/0 TO 3/0)	1952.000 LF	2.22000	4333.44				
1720 0715 2111 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (3/4")	264.000 LF	5.56000	1467.84				
1725 0715 2115 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (2")	16497.000 LF	4.67000	77040.99				
1730 0715 2215 CONDUIT (F&I UNDERPAVEMENT) (PVC SCH 40) (2")	5669.000 LF	16.00000	90704.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1735 0715 2332 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (1")	1636.000 LF	16.00000	26176.00				
1740 0715 2335 CONDUIT (F&I SURFACE MOUNT) (RIGID GALV) (2")	1192.000 LF	14.90000	17760.80				
1745 0715 7 11 LOAD CENTER (F&I) (SECONDARY VOLTAGE)	2.000 EA	6122.00000	12244.00				
1750 0715 7 21 LOAD CENTER (REWORK) (SECONDARY VOLTAGE)	1.000 EA	7332.00000	7332.00				
1755 0715 10 2 LIGHT POLE FOUNDATION (F&I)	4.000 EA	601.00000	2404.00				
1760 0715 11125 LUMINAIRE (F&I)(UNDERDECK WALL MOUNT)	19.000 EA	709.00000	13471.00				
1765 0715 14 11 PULL BOX (F&I) (ROADSIDE)	97.000 EA	344.00000	33368.00				
1770 0715 14 12 PULL BOX (F&I) (SIDEWALK)	13.000 EA	431.00000	5603.00				
1775 0715 14 14 PULL BOX (F&I) (SURFACE MOUNT)	87.000 EA	104.00000	9048.00				
1780 0715191100 LIGHT POLE COMPLETE HIGH MAST (F&I)(100')	12.000 EA	21931.00000	263172.00				
1785 0715500 1 POLE CABLE DISTRIBUTION SYSTEM (CONVENTIONAL)	108.000 EA	1086.00000	117288.00				
1790 0715500 2 POLE CABLE DISTRIBUTION SYSTEM (HIGH MAST)	12.000 EA	1146.00000	13752.00				
1795 0715500 3 POLE CABLE DISTRIBUTION SYSTEM (WALL MOUNTED)	18.000 EA	1146.00000	20628.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1800 0715511130 LIGHT POLE COMP(F&I)(SGL ARM SHLDR MNT-ALUM)(30')	104.000 EA	4825.00000	501800.00				
1805 0715512130 LIGHT POLE COMPLETE(F&I)(DBL ARM SHLDR MNT-ALUM)(30')	4.000 EA	7380.00000	29520.00				
1810 0715513130 LIGHT POLE COMP(F&I)(SGL ARM WALL MNT-ALUM)(30')	3.000 EA	4855.00000	14565.00				
1820 0715540000 LIGHT POLE COMP(RELOCATE)	4.000 EA	1219.00000	4876.00				
1825 0715550000 LIGHT POLE COMP(REMOVE)	137.000 EA	246.00000	33702.00				
SECTION 0004 TOTALS		$	1,402,744.36	$		$	
SECTION 0005 SIGNALIZATION							
1830 0630 1 12 CONDUIT (FURNISH & INSTALL)(UNDERGROUND	9060.000 LF	5.56000	50373.60				
1835 0630 1 13 CONDUIT (FURNISH & INSTALL)(UNDER PAVEMENT)	2586.000 LF	16.60000	42927.60				
1840 0632 7 1 CABLE (SIGNAL) (FURNISH & INSTALL)	5.000 PI	2358.00000	11790.00				
1845 0632 8112 CABLE (INTERCONNECT)(F&I) (UNDER-GRND)	2100.000 LF	2.22000	4662.00				
1850 0635 1 11 PULL & JUNCTION BOXES (F&I) (PULL BOX)	98.000 EA	344.00000	33712.00				
1855 0635 1 15 PULL & JUNCTION BOXES (F&I) (FIBER OPTICS)	12.000 EA	891.00000	10692.00				
1860 0639 1 13 ELECTRICAL POWER SERVICE (OVERHEAD)	4.000 AS	637.00000	2548.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1865 0639 2 1 ELECTRICAL SERVICE WIRE	3492.000 LF	1.11000	3876.12				
1870 0649411001 M/ARM (F&I/HL)(SGL ARM W/O LUM(1ST ARM TYPE B1(2ND 0(Q1	2.000 EA	9788.00000	19576.00				
1875 0649413002 M/ARM(F&I/HL)(SGL ARM W/O LUM)(1ST ARM(B3) 2ND ARM(0)POLE(Q2)	2.000 EA	11089.00000	22178.00				
1880 0649415003 M/ARM (F&I/HL)(SGL ARM W/O LUM)1ST ARM(B5) 2ND ARM(0)POLE(Q3)	5.000 EA	14394.00000	71970.00				
1885 0649416004 M/ARM (F&I/HL)(SGL ARM W/O LUM)(1ST ARM(B6)2ND(0)POLE(Q4)	4.000 EA	17250.00000	69000.00				
1890 0649435009 M/ARM(F&I/HL)(SI ARM W/ LUM)(1ST ARM(B5) 2NDARM(0)POLE(Q23LU)	1.000 EA	17809.00000	17809.00				
1895 0650 51111 SIGNAL TRAFFIC(F&I)(1 SECT 1 WAY)(STD)	2.000 AS	249.00000	498.00				
1900 0650 51311 SIGNAL TRAFFIC(F&I)(3 SECT 1 WAY)(STD)	29.000 AS	527.00000	15283.00				
1905 0650 51511 SIGNAL TRAFFIC(F&I)(5 SECT 1 WAY)(STD)	8.000 AS	743.00000	5944.00				
1910 0653171 SIGNAL PEDESTRIAN(NEON INTERNATIONAL SYM LOW WATT (1 WAY)	10.000 AS	580.00000	5800.00				
1915 0653172 SIGNAL PEDESTRIAN (NEON INT SYM LOW WATT)	4.000 AS	1011.00000	4044.00				
1920 0659107 SIGNAL HEAD AUXILIARIES (ALUMINUM PEDESTAL)	4.000 EA	757.00000	3028.00				
1925 0660 1109 LOOP DETECTOR INDUCTIVE (F&I) (TYPE 9)	19.000 EA	148.00000	2812.00				
1930 0660 2101 LOOP ASSEMBLY (F&I) (TYPE A)	35.000 AS	708.00000	24780.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1935 0665 11 DETECTOR PEDEST(F&I)(DET STA POLE OR CABINET MTD)	10.000 EA	113.00000	1130.00				
1940 0670 5120 CNTL ASSEM ACT SS F&I 170 PRE(NONE)	3.000 AS	13458.00000	40374.00				
1945 0670 5121 CNTL ASSEM ACT SS F&I 170 PRE(ONE)	1.000 AS	14659.00000	14659.00				
1950 0671 2 42 TRAFFIC CONTROLLER(MOD)(TYPE 170)	1.000 EA	1042.00000	1042.00				
1955 0685120 SYSTEM AUXILIARIES (TELEMETRY TRANSCEIVER)	4.000 EA	1442.00000	5768.00				
1960 0685124 SYSTEM AUXILIARIES (UNIVERSAL ADAPTER)	4.000 EA	1442.00000	5768.00				
1965 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	39.000 EA	45.00000	1755.00				
1970 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	2.000 EA	45.00000	90.00				
1975 0690 31 SIGNAL PEDESTAL REMOVAL	1.000 EA	45.00000	45.00				
1980 0690 33 1 POLE REMOVAL (DEEP DIRECT BURIAL)	226.000 LF	244.00000	55144.00				
1985 0690 50 CNTRL ASSEM REMOVE	5.000 EA	175.00000	875.00				
1990 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	2.000 EA	45.00000	90.00				
1995 0690 80 SPAN WIRE ASSEMBLY REMOVE	3.000 EA	348.00000	1044.00				
2000 0690 90 CONDUIT & CABLING REMOVE	5.000 PI	1388.00000	6940.00				
2005 0690 91 SIGNAL INTERCONNECT CABLE REMOVE	1915.000 LF	1.33000	2546.95				
2010 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	5.000 PI	1388.00000	6940.00				
2015 0700 40 1 SIGN SINGLE POST (LESS THAN 12)	1.000 AS	286.00000	286.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
2020 0700 48 18 SIGN PANELS (F & I) (15 OR <)	21.000 EA	247.00000	5187.00				
2025 0700 48 60 SIGN PANELS (REMOVE)	12.000 EA	88.00000	1056.00				
2030 0715 2112 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (1")	77404.000 LF	4.55000	352188.20				
2035 0715 2117 CONDUIT (F&I UNDERGROUND) (PVC SCH 40) (4")	19351.000 LF	5.67000	109720.17				
2040 0730 76113 CASING STEEL (F&I) (24")	120.000 LF	350.00000	42000.00				
2045 0745 70 12 TMS INDUCTIVE LOOP ASSEM(F&I)(2 LOOPS/LN)	9.000 AS	1215.00000	10935.00				
2050 0746 71111 TMS CABINET(F&I)(TYPE III)(BASE MNT)(1 BACKPLANE)	1.000 EA	2700.00000	2700.00				
2055 0746 71112 TMS CABINET(F&I)(TYPE III)(BASE MNT)(2 BACKPLANE)	1.000 EA	3000.00000	3000.00				
SECTION 0005 TOTALS		$	1,094,586.64	$		$	
SECTION 0006 LANDSCAPE / PERIPHERAL							
2060 0430961211 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (3")	183.900 LF	17.00000	3126.30				
2065 0430961213 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (4")	1274.600 LF	18.00000	22942.80				
2070 0430961216 PIPE PVC (SCHEDULE 40)(NOT ENCASED) (6")	2473.800 LF	19.00000	47002.20				
SECTION 0006 TOTALS		$	73,071.30	$		$	
SECTION 0007 UTILITIES							

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0076 0556 1 5 JACK AND BORE CASING DIAMETER(24" TO <36")	114.000 LF	710.00000	80940.00				
2075 0101 1 MOBILIZATION 25023455601	LUMP	264000.00000	264000.00				
2080 0102 1 MAINTENANCE OF TRAFFIC 25023455601	120.000 LS	190000.00000	190000.00				
2085 0102 14 TRAFFIC CONTROL OFFICER	160.000 MH	39.00000	6240.00				
2090 0102 60 WORK ZONE SIGNS	1879.000 ED	0.22000	413.38				
2095 0102 71 11 BARRIER WALL (TEMPORARY) (F&I)(CONCRETE	1250.000 LF	16.35000	20437.50				
2100 0102 71 21 BARRIER WALL (TEMPORARY) (RELOCATE)(CONCRETE)	1120.000 LF	8.00000	8960.00				
2105 0102 74 1 BARRICADE (TEMPORARY)(TYPES I,II,VP & DRUM)	8852.000 ED	0.20000	1770.40				
2110 0102 74 2 BARRICADE (TEMPORARY)(TYPE III) (6')	949.000 ED	0.44000	417.56				
2115 0102 76 PANELS ARROW ADVANCE WARNING	188.000 ED	7.80000	1466.40				
2120 0102 77 HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	717.000 ED	0.44000	315.48				
2125 0102 78 MARKER PAVT REFLECTIVE (TEMPORARY)	160.000 EA	2.78000	444.80				
2130 0102 79 LIGHTS(TEMP-BARR. WALL MOUNT)(TYPE C STEADY BURN)	2790.000 ED	0.17000	474.30				
2135 0102 89 7 IMPACT ATTENUATOR (REDIRECTIVE OPTION)(TEMPORARY)	4.000 LO	1400.00000	5600.00				
2140 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	6.000 ED	20.00000	120.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
2145 0125 1 EXCAVATION FOR STRUCTURES	67.000 CY	60.00000	4020.00				
2150 0710 6 DIRECTIONAL ARROWS, PAINTED	10.000 EA	22.00000	220.00				
2155 0710 7 PAVT MESSAGE, PAINTED	1.000 EA	55.00000	55.00				
2160 0710 25 61 TRAFFIC STRIPE SOLID (WHITE/BLACK) (6")	1720.000 LF	0.14000	240.80				
2165 0710 25 81 TRAFFIC STRIPE SOLID (WHITE/BLACK) (8")	42.000 LF	0.37000	15.54				
2170 0710 25121 TRAFFIC STRIPE SOLID (WHITE/BLACK) (12")	248.000 LF	1.12000	277.76				
2175 0710 25181 TRAFFIC STRIPE SOLID (WHITE/BLACK) (18")	6.000 LF	1.60000	9.60				
2180 0710 25241 TRAFFIC STRIPE SOLID (WHITE/BLACK) (24")	124.000 LF	1.70000	210.80				
2185 0710 26 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	3880.000 LF	0.15000	582.00				
2190 0710 27 TRAFFIC STRIPE SKIP (WHITE/BLACK)	143.000 LF	0.50000	71.50				
2195 0711 7 PAVT MARKING REMOVE THERMOPLASTIC	1991.000 SF	1.40000	2787.40				
2200 0730 76116 CASING STEEL (F&I) (30")	373.000 LF	278.00000	103694.00				
2205 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 25023455601	LUMP	150000.00000	150000.00				
2210 1010 1 PIPE(PLUG & PLACE OUT OF SERVICE)(8" OR LESS)	3.000 EA	650.00000	1950.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
2215 1010 3 PIPE(PLUG & PLACE OUT OF SERVICE)(9" OR MORE)	25.000 LF	262.00000	6550.00				
2220 1060144 51 UTILITY STRUCT(F&I)(SPECIAL)METERING SYSTEM(CONT OPT)0-6'	1.000 EA	45245.00000	45245.00				
2225 1070111113 VALVE ASSEMBLY GATE (F&I)(CI) (150 PSI)(16")	13.000 EA	5165.00000	67145.00				
2230 1070111208 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(6")	1.000 EA	2414.00000	2414.00				
2235 1070111209 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(8")	1.000 EA	2700.00000	2700.00				
2240 1070111211 VALVE ASSEMBLY GATE (F&I)(CI) (250 PSI)(12")	4.000 EA	2710.00000	10840.00				
2245 1070116205 VALVE ASSEMBLY(BLOWOFF ASSEMBLY)(F&I)(CI)(250 PSI)(2")	4.000 EA	1685.00000	6740.00				
2250 1070118205 VALVE ASSEMBLY(F&I)(CAST IRON)(AIR RELEASE ASSEMBLY) (250PSI)(2")	11.000 EA	2670.00000	29370.00				
2255 1100111813 PIPE(CAST/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(250PSI)(16")	6492.000 LF	88.00000	571296.00				
2260 1100111908 PIPE(CASTI/DUCTILE IRON)CEMENT LINED(F&I)(PUSH ON)(350P)(6")	36.000 LF	61.00000	2196.00				
2265 1100111909 PIPE(CASTI/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(350P)(8")	60.000 LF	69.00000	4140.00				
2270 1100111911 PIPE(CAST/DUCTILE IRON)(CMT)(F&I)(PUSH ON)(350PSI)(12")	323.000 LF	88.00000	28424.00				
2275 1110132213 PIPE(STEEL)(COATED)(F&I)(FLANGE JOINT)(CLASS 5/16)(16")	228.000 LF	502.00000	114456.00				

CALL ORDER: 019 PROPOSAL ID: T6047 LETTING DATE: 04/28/04 10:30 A.M. DISTRICT: 06

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ASTALDI CONSTRUCTION CORPOR UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
2280 1610140	6.900 TN	13855.00000	95599.50				
FITTINGS WATER(FURNISH&INSTALL)(DI-CEMENT LINED)							
2285 1637131106 VLV BOX,TAP CROSS&VALVE,WITH SLV&VALVE(F&I)(8"X 8")	1.000 EA	5270.00000	5270.00				
2290 1637131134 VALV BOX,TAP CROSS&VALVE(2PC)W/SLEEVE&VALV(F&I)(DI) (24"X16")	1.000 EA	12937.00000	12937.00				
2295 1644900 FIRE HYDRANT(REMOVE)	4.000 EA	888.00000	3552.00				
2300 1698170 02 WATER SERVICE COPPER(FURNISH & INSTALL)(1")	39.000 LF	126.00000	4914.00				
SECTION 0007 TOTALS		$ 1,859,522.72		$		$	
CONTRACT TOTALS		$ 96,524,195.68		$	0.00	$	

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, shall constitute a waiver of proceeding under chapter 120, Florida Statutes.