LBTHEAD VENDOR RANKING

CALL ORDER : 018 PROPOSAL ID : T3193 PROPOSAL DESC :
LETTING DATE : 04/26/06 10:30 A.M. DISTRICT : 03 Contract Execution Days:20.
SET-ASIDE : U/R CODE : Calendar Days:70.
CONTRACT TIME : 60 CALENDAR DAYS Special Start Time:N/A.
Acquisition Time:16th.

The improvements under this contract consist of adding a left turn lane to an existing two lane roadway with a culvert extension, guardrail relocation, signing and pavement markings and other miscellaneous associated items.

FINPROJ(S) : 41793145201 (*) F.A. NO. : 1011035P COUNTIES : HOLMES

LOCAL NAME(*) : SR 79 WAUKESHA ST. S.R. NO.(*) : SR 79 US NO.(*) :
PROJ LIMITS(*): @ CR 177A INTERSECTION

LBTAVR1

VENDOR RANKING

RANK	VENDOR NAME	BID TYPE	BID STATUS		TOTAL BID	% OVER LOW BID
1	ANDERSON COLUMBIA CO., INC.	Responsive	Winning bid	$	601,433.34	0.000%
2	ROBERTS, C.W., CONTRACTING, INC.	Responsive	Non-Winning Bi	$	658,486.00	9.486%
3	APAC-SOUTHEAST, INC.	Responsive	Non-Winning Bi	$	775,180.51	28.888%

TABULATION OF BIDS

CALL ORDER : 018 PROPOSAL ID : T3193 PROPOSAL DESC :
LETTING DATE : 04/26/06 10:30 A.M. DISTRICT : 03 Contract Execution Days:20.
SET-ASIDE : U/R CODE : Calendar Days:70.
CONTRACT TIME : 60 CALENDAR DAYS Special Start Time:N/A.
Acquisition Time:16th.

The improvements under this contract consist of adding a left turn lane to an existing two lane roadway with a culvert extension, guardrail relocation, signing and pavement markings and other miscellaneous associated items.

FINPROJ(S) : 41793145201 (*) F.A. NO. : 1011035P COUNTIES : HOLMES

LOCAL NAME(*) : SR 79 WAUKESHA ST. S.R. NO.(*) : SR 79 US NO.(*) :
PROJ LIMITS(*): @ CR 177A INTERSECTION

LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(2) ROBERTS, C.W., CONTRACTING, UNIT PRICE	 AMOUNT	(3) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 41793145201	LUMP	56100.00000	56100.00	80000.00000	80000.00	74520.00000	74520.00
0010 0102 1 MAINTENANCE OF TRAFFIC 41793145201	70.000 LS	65900.00000	65900.00	60000.00000	60000.00	134950.00000	134950.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	152.00000	38000.00	30.00000	7500.00	60.00000	15000.00
0020 0102 60 WORK ZONE SIGNS	1078.000 ED	1.00000	1078.00	1.00000	1078.00	0.50000	539.00
0025 0102 74 1 BARRICADE (TEMPORARY)(TYPES I,II,DI,VP & DRUM)	1386.000 ED	1.00000	1386.00	1.00000	1386.00	0.31000	429.66
0030 0102 76 PANELS ARROW ADVANCE WARNING	154.000 ED	15.00000	2310.00	10.00000	1540.00	16.50000	2541.00
0035 0102 77 HIGH INTENSITY FLASHING LIGHTS (TEMP - TYPE B)	385.000 ED	1.00000	385.00	1.00000	385.00	1.05000	404.25
0040 0102 78 MARKER PAVT REFLECTIVE (TEMPORARY)	304.000 EA	7.00000	2128.00	7.00000	2128.00	7.15000	2173.60

CALL ORDER: 018 PROPOSAL ID: T3193 LETTING DATE: 04/26/06 10:30 A.M. DISTRICT: 03
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(2) ROBERTS, C.W., CONTRACTING, UNIT PRICE	 AMOUNT	(3) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT
0045 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN (TEMPORARY)	154.000 ED	33.00000	5082.00	30.00000	4620.00	38.50000	5929.00
0050 0104 4 MOWING	0.720 AC	1000.00000	720.00	1000.00000	720.00	3300.00000	2376.00
0055 0104 13 1 SILT FENCE STAKED (TYPE III)	2263.000 LF	2.50000	5657.50	3.00000	6789.00	5.00000	11315.00
0060 0110 1 1 CLEARING & GRUBBING 41793145201	0.340 LS	23500.00000	23500.00	50000.00000	50000.00	68400.00000	68400.00
0065 0110 7 1 MAILBOX (F&I) (SINGLE)	17.000 EA	125.00000	2125.00	150.00000	2550.00	115.50000	1963.50
0070 0120 1 EXCAVATION REGULAR	498.000 CY	16.00000	7968.00	40.00000	19920.00	46.00000	22908.00
0075 0120 4 EXCAVATION SUBSOIL	66.000 CY	110.00000	7260.00	40.00000	2640.00	90.00000	5940.00
0080 0120 6 EMBANKMENT	351.000 CY	26.00000	9126.00	40.00000	14040.00	60.00000	21060.00
0085 0160 4 STABILIZATION TYPE B	2943.000 SY	15.50000	45616.50	11.00000	32373.00	19.00000	55917.00
0090 0162 3101 FINISH SOIL LAYER, GRASSING OPERATIONS, 6"	1727.000 SY	4.00000	6908.00	3.00000	5181.00	9.00000	15543.00
0095 0285701 BASE OPTIONAL (BASE GROUP 01)	1690.000 SY	16.00000	27040.00	24.00000	40560.00	42.00000	70980.00
0100 0285706 BASE OPTIONAL (BASE GROUP 06)	1223.000 SY	29.00000	35467.00	28.00000	34244.00	38.00000	46474.00
0105 0285714 BASE OPTIONAL (BASE GROUP 14)	206.000 SY	39.00000	8034.00	50.00000	10300.00	58.00000	11948.00
0110 0334 1 12 SUPERPAVE ASPHALTIC CONC (TRAFFIC B)	250.100 TN	226.00000	56522.60	150.00000	37515.00	120.00000	30012.00
0115 0337 7 6 ASPH CONC FRICTION COURSE(INC BIT/RUBBER)FC 12.5(FC-6)	620.000 TN	149.00000	92380.00	200.00000	124000.00	125.00000	77500.00
0120 0339 1 ASPHALT PAVEMENT MISCELLANEOUS	18.800 TN	406.00000	7632.80	250.00000	4700.00	340.00000	6392.00
0125 0400 1 2 CONC CLASS I(ENDWALLS)	2.200 CY	2550.00000	5610.00	2000.00000	4400.00	2000.00000	4400.00

CALL ORDER: 018 PROPOSAL ID: T3193 LETTING DATE: 04/26/06 10:30 A.M. DISTRICT: 03
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(2) ROBERTS, C.W., CONTRACTING, UNIT PRICE	 AMOUNT	(3) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT
0130 0430172129 PIPE CULV(OPT MATL)(ROUND)(24"CD)	6.000 LF	445.00000	2670.00	800.00000	4800.00	400.00000	2400.00
0135 0536 1 1 GUARDRAIL (ROADWAY)	87.500 LF	36.00000	3150.00	50.00000	4375.00	21.00000	1837.50
0140 0538 1 GUARDRAIL RESET	383.000 LF	18.00000	6894.00	50.00000	19150.00	11.00000	4213.00
0145 0570 5 FERTILIZER	0.100 TN	1000.00000	100.00	2000.00000	200.00	900.00000	90.00
0150 0570 9 WATER FOR GRASS	11.000 MG	42.00000	462.00	200.00000	2200.00	75.00000	825.00
0155 0570 10 SEED GRASS (QUICK-GROWING TYPE)	7.000 LB	4.00000	28.00	10.00000	70.00	75.00000	525.00
0160 0575 1 SODDING	1727.000 SY	3.12000	5388.24	6.00000	10362.00	15.00000	25905.00
0165 0710 23 61 TRAFFIC STRIPE SOLID (WHITE/BLACK/BLUE)(6")	1.364 NM	3225.00000	4398.90	3000.00000	4092.00	2000.00000	2728.00
0170 0710 24 61 TRAFFIC STRIPE SOLID (YELLOW) (6")	1.968 NM	3225.00000	6346.80	3000.00000	5904.00	2200.00000	4329.60
0175 0710 26181 TRAFFIC STRIPE SOLID (YELLOW) (18")	408.000 LF	7.50000	3060.00	8.00000	3264.00	5.00000	2040.00
0180 0999 25 INITIAL CONTINGENCY AMOUNT (DO NOT BID) 41793145201	LUMP	29300.00000	29300.00	29300.00000	29300.00	29300.00000	29300.00
SECTION 0001 TOTALS		$	575,734.34	$	632,286.00	$	763,808.11
SECTION 0002 SIGNING							
0185 0700 40 1 SIGN SINGLE POST (LESS THAN 12)	8.000 AS	345.00000	2760.00	350.00000	2800.00	200.00000	1600.00
0190 0700 46 11 SIGN EXISTING (REMOVAL) (SINGLE POST)	8.000 AS	100.00000	800.00	100.00000	800.00	30.00000	240.00

CALL ORDER: 018 PROPOSAL ID: T3193 LETTING DATE: 04/26/06 10:30 A.M. DISTRICT: 03
LBTABT1

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(2) ROBERTS, C.W., CONTRACTING, UNIT PRICE	 AMOUNT	(3) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT
0195 0705 10 11 MARKER OBJECT (POST MOUNT) (TYPE 1)	3.000 EA	63.00000	189.00	200.00000	600.00	250.00000	750.00
0200 0710 90 PAINTED PAVEMENT MARKINGS(FINAL SURFACE) 41793145201	LUMP	21950.00000	21950.00	22000.00000	22000.00	8782.40000	8782.40
SECTION 0002 TOTALS		$	25,699.00	$	26,200.00	$	11,372.40
CONTRACT TOTALS		$	601,433.34	$	658,486.00	$	775,180.51

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, shall constitute a waiver of proceeding under chapter 120, Florida Statutes.