VENDOR RANKING

CALL ORDER : 015
LETTING DATE : 06/20/07 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 55 CALENDAR DAYS

PROPOSAL ID : T3237
DISTRICT : 03
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of upgrading existing pedestrian features along SR 10A. The upgrades include signing and pavement marking modifications, reconstructing existing curb ramps, constructing new curb ramps and constructing patterned and textured crosswalks. Signalization work is also included to implement new signalized pedestrian phasing at the intersection of SR 10A and Perry Avenue. In addition, the improvements include removing an existing slip lane at the intersection of SR 10A and Chipley Avenue. The removal includes sidewalk construction, minor drainage modifications, earthwork and pavement construction.

FINPROJ(S) : 42026615201 (*)
F.A. NO. : 4261031P
COUNTIES : ESCAMBIA

LOCAL NAME : SR 10A (US 90)
ROAD NAME : SR 10A SCENIC HIGHWAY
PROJ LIMITS : FROM BAYOU TEXAR BRIDGE TO END OF 4 LANE SECTION

RANK	VENDOR NAME	BID TYPE	BID STATUS		TOTAL BID	% OVER LOW BID
1	GULF ATLANTIC CONSTRUCTORS, INC.	Responsive	Winning bid	$	402,308.00	0.00%
2	APAC-SOUTHEAST, INC.	Responsive	Non-Winning Bi	$	404,573.05	0.56%
3	PANHANDLE GRADING & PAVING, INC.	Responsive	Non-Winning Bi	$	413,990.45	2.90%

CALL ORDER : 015
LETTING DATE : 06/20/07 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 55 CALENDAR DAYS

PROPOSAL ID : T3237
DISTRICT : 03
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of upgrading existing pedestrian features along SR 10A. The upgrades include signing and pavement marking modifications, reconstructing existing curb ramps, constructing new curb ramps and constructing patterned and textured crosswalks. Signalization work is also included to implement new signalized pedestrian phasing at the intersection of SR 10A and Perry Avenue. In addition, the improvements include removing an existing slip lane at the intersection of SR 10A and Chipley Avenue. The removal includes sidewalk construction, minor drainage modifications, earthwork and pavement construction.

FINPROJ(S) : 42026615201 (*)
F.A. NO. : 4261031P
COUNTIES : ESCAMBIA

LOCAL NAME : SR 10A (US 90)
ROAD NAME : SR 10A SCENIC HIGHWAY
PROJ LIMITS : FROM BAYOU TEXAR BRIDGE TO END OF 4 LANE SECTION

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GULF ATLANTIC CONSTRUCTORS, UNIT PRICE	 AMOUNT	(2) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT	(3) PANHANDLE GRADING & PAVING, INC UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION	LUMP	40000.00000	40000.00	38500.00000	38500.00	48500.00000	48500.00
0010 0102 1 MAINTENANCE OF TRAFFIC	55.000 LS	50000.00000	50000.00	24300.00000	24300.00	42500.00000	42500.00
0015 0102 60 WORK ZONE SIGNS	3185.000 ED	1.00000	3185.00	0.65000	2070.25	0.68000	2165.80
0020 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	10736.000 ED	0.50000	5368.00	0.35000	3757.60	0.36000	3864.96
0025 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	27.000 ED	1.00000	27.00	0.85000	22.95	0.89000	24.03
0030 0102 76 ADVANCE WARNING ARROW PANEL	39.000 ED	30.00000	1170.00	25.00000	975.00	26.00000	1014.00
0035 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	1149.000 ED	1.50000	1723.50	1.25000	1436.25	1.30000	1493.70
0040 0102 99 CHANGEABLE-VARIABLE MESSAGE SIGN, TEMPORARY	102.000 ED	30.00000	3060.00	24.00000	2448.00	25.00000	2550.00

CALL ORDER: 015 PROPOSAL ID: T3237 LETTING DATE: 06/20/07 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GULF ATLANTIC CONSTRUCTORS, UNIT PRICE	 AMOUNT	(2) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT	(3) PANHANDLE GRADING & PAVING, INC UNIT PRICE	 AMOUNT
0045 0104 13 1 STAKED SILT FENCE, TYPE III	271.000 LF	3.00000	813.00	12.00000	3252.00	3.50000	948.50
0050 0104 16 ROCK BAGS	320.000 EA	12.00000	3840.00	15.00000	4800.00	20.00000	6400.00
0055 0110 1 1 CLEARING & GRUBBING	0.084 LS	13550.50000	13550.50	7500.00000	7500.00	32400.00000	32400.00
0060 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	339.000 SY	36.00000	12204.00	45.00000	15255.00	15.00000	5085.00
0065 0120 2 2 BORROW EXCAVATION,TRUCK MEASURE	219.000 CY	25.00000	5475.00	30.00000	6570.00	34.00000	7446.00
0070 0285706 OPTIONAL BASE, BASE GROUP 06	20.000 SY	200.00000	4000.00	200.00000	4000.00	124.00000	2480.00
0075 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	3.400 TN	550.00000	1870.00	950.00000	3230.00	720.00000	2448.00
0080 0337 7 7 ASPHALT CONCRETE FRICTION COURSE, INC BIT / RUBBER, FC-9.5	1.100 TN	1500.00000	1650.00	2500.00000	2750.00	1060.00000	1166.00
0085 0400 1 15 CONCRETE CLASS I, MISCELLANEOUS	5.000 CY	620.00000	3100.00	1500.00000	7500.00	1180.00000	5900.00
0090 0425 1545 INLETS, DITCH BOTTOM, TYPE D, PARTIAL	1.000 EA	7800.00000	7800.00	2800.00000	2800.00	4980.00000	4980.00
0095 0520 1 7 CONCRETE CURB & GUTTER, TYPE E	86.000 LF	50.00000	4300.00	35.00000	3010.00	62.00000	5332.00
0100 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	529.000 LF	36.00000	19044.00	28.00000	14812.00	58.00000	30682.00
0105 0520 2 2 CONCRETE CURB, TYPE B	8.000 LF	100.00000	800.00	150.00000	1200.00	59.00000	472.00
0110 0522 1 SIDEWALK CONCRETE, 4" THICK	273.000 SY	60.00000	16380.00	150.00000	40950.00	54.00000	14742.00
0115 0522 2 SIDEWALK CONCRETE, 6" THICK	16.000 SY	150.00000	2400.00	160.00000	2560.00	72.00000	1152.00
0120 0523 1 1 PATTERNED / TEXTURED PAVEMENT, ASPHALT	946.000 SY	100.00000	94600.00	95.00000	89870.00	85.00000	80410.00
0125 0523 1 2 PATTERNED / TEXTURED PAVEMENT, CONCRETE	16.000 SY	100.00000	1600.00	150.00000	2400.00	85.00000	1360.00
0130 0527 1 DETECTABLE WARNING ON WALKING SURFACE, RETROFIT	9.000 EA	700.00000	6300.00	750.00000	6750.00	702.00000	6318.00

CALL ORDER: 015 PROPOSAL ID: T3237 LETTING DATE: 06/20/07 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GULF ATLANTIC CONSTRUCTORS, UNIT PRICE	(1) AMOUNT	(2) APAC-SOUTHEAST, INC. UNIT PRICE	(2) AMOUNT	(3) PANHANDLE GRADING & PAVING, INC UNIT PRICE	(3) AMOUNT
0135 0570 1 2 PERFORMANCE TURF, SOD	520.000 SY	4.00000	2080.00	11.00000	5720.00	6.00000	3120.00
0140 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID	LUMP	20500.00000	20500.00	20500.00000	20500.00	20500.00000	20500.00
SECTION 0001 TOTALS		$	326,840.00	$	318,939.05	$	335,453.99
SECTION 0002 SIGNING							
0145 0700 40 1 SIGN SINGLE POST- LESS THAN 12	35.000 AS	265.00000	9275.00	300.00000	10500.00	275.60000	9646.00
0150 0700 46 11 SIGN EXISTING- REMOVE, SINGLE POST	15.000 AS	65.00000	975.00	70.00000	1050.00	67.60000	1014.00
0155 0700 46 21 SIGN EXISTING- RELOCATE, SINGLE POST	1.000 AS	85.00000	85.00	90.00000	90.00	88.40000	88.40
0160 0705 1 DELINEATOR SINGLE UNIT	5.000 EA	95.00000	475.00	105.00000	525.00	98.80000	494.00
0165 0705 10 11 OBJECT MARKER - POST MOUNT, TYPE 1	2.000 EA	125.00000	250.00	130.00000	260.00	130.00000	260.00
0170 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	77.000 EA	10.50000	808.50	12.00000	924.00	11.00000	847.00
0175 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	17.000 SF	28.50000	484.50	30.00000	510.00	29.64000	503.88
0180 0711 11121 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	25.000 LF	3.60000	90.00	4.00000	100.00	3.75000	93.75
0185 0711 11122 THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	1126.000 LF	4.80000	5404.80	5.00000	5630.00	5.00000	5630.00
0190 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	2008.000 LF	7.20000	14457.60	8.00000	16064.00	7.50000	15060.00
0195 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	406.000 LF	9.25000	3755.50	11.00000	4466.00	9.62000	3905.72
0200 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	286.000 LF	14.40000	4118.40	16.00000	4576.00	15.00000	4290.00

CALL ORDER: 015 PROPOSAL ID: T3237 LETTING DATE: 06/20/07 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GULF ATLANTIC CONSTRUCTORS, UNIT PRICE	 AMOUNT	(2) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT	(3) PANHANDLE GRADING & PAVING, INC UNIT PRICE	 AMOUNT
0205 0711 11141 THERMOPLASTIC, STANDARD, WHITE, SKIP, 6	477.000 LF	3.60000	1717.20	4.00000	1908.00	3.75000	1788.75
0210 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	6.000 EA	375.00000	2250.00	450.00000	2700.00	390.00000	2340.00
0215 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	4.000 EA	225.00000	900.00	300.00000	1200.00	234.00000	936.00
0220 0711 11221 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	100.000 LF	3.60000	360.00	4.00000	400.00	3.75000	375.00
0225 0711 17 THERMOPLASTIC, REMOVE	3522.000 SF	4.75000	16729.50	5.50000	19371.00	4.94000	17398.68
SECTION 0002 TOTALS		$	62,136.00	$	70,274.00	$	64,671.18
SECTION 0003 SIGNALIZATION							
0230 0630 1 11 CONDUIT - SIGNALS, FURNISH & INSTALL, ABOVEGROUND	4.000 LF	10.00000	40.00	11.00000	44.00	10.40000	41.60
0235 0630 1 13 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDER EXISTING PAVEMENT	13.000 LF	11.00000	143.00	12.00000	156.00	11.44000	148.72
0240 0630 1 14 CONDUIT, SIGNALS, F & I, UNDERGROUND -JACKED	188.000 LF	18.00000	3384.00	20.00000	3760.00	18.72000	3519.36
0245 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	1.000 PI	2800.00000	2800.00	3000.00000	3000.00	2912.00000	2912.00
0250 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	3.000 EA	380.00000	1140.00	400.00000	1200.00	395.20000	1185.60
0255 0653181 PEDESTRIAN SIGNAL, F&I, LED, 1 DIRECTIO	1.000 AS	775.00000	775.00	900.00000	900.00	806.00000	806.00
0260 0653182 PEDESTRIAN SIGNAL, F&I, LED, 2 DIRECTIONS	1.000 AS	1300.00000	1300.00	1500.00000	1500.00	1352.00000	1352.00
0265 0659109 SIGNAL HEAD AUXILIARIES, F&I, CONC PEDESTAL TYPE II	2.000 EA	500.00000	1000.00	600.00000	1200.00	520.00000	1040.00
0270 0665 11 PEDESTRIAN DETECTOR, F&I, DETECTOR STATION, POLE OR CONTROLLER CABINET MOUNTED	6.000 EA	150.00000	900.00	200.00000	1200.00	156.00000	936.00

CALL ORDER: 015 PROPOSAL ID: T3237 LETTING DATE: 06/20/07 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GULF ATLANTIC CONSTRUCTORS, UNIT PRICE	 AMOUNT	(2) APAC-SOUTHEAST, INC. UNIT PRICE	 AMOUNT	(3) PANHANDLE GRADING & PAVING, INC UNIT PRICE	 AMOUNT
0275 0670 5410 TRAFFIC CONTROLLER ASSEMBLY, MODIFY, NEMA	1.000 AS	1500.00000	1500.00	1800.00000	1800.00	1560.00000	1560.00
0280 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	1.000 EA	150.00000	150.00	200.00000	200.00	156.00000	156.00
0285 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	4.000 EA	50.00000	200.00	100.00000	400.00	52.00000	208.00
SECTION 0003 TOTALS			$ 13,332.00		$ 15,360.00		$ 13,865.28
CONTRACT TOTALS			$ 402,308.00		$ 404,573.05		$ 413,990.45

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.