VENDOR RANKING

CALL ORDER : 010
LETTING DATE : 08/26/09 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 510 WORKING DAYS (AVAILABLE DAYS)

PROPOSAL ID : T2293
DISTRICT : 02
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of replacing the bridge over Sixteen Mile Creek, on CR 13. Work includes removing the existing timber bridge, constructing a new concrete bridge and realigning the asphaltic concrete roadway to accommodate the new bridge location.

FINPROJ(S) : 21238215201 (*)
F.A. NO. : 00B2018B
COUNTIES : ST JOHNS

LOCAL NAME : CR 13
ROAD NAME : CR 13
PROJ LIMITS : AT DEEP CREEK BR # 784004

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	SUPERIOR CONSTRUCTION COMPANY	Responsive	Winning bid	$ 3,439,514.64	0.00%
2	LEWARE CONSTRUCTION COMPANY OF FLORIDA, INC.	Responsive	Non-Winning Bid	$ 3,527,000.00	2.54%
3	HAL JONES CONTRACTOR, INC	Responsive	Non-Winning Bid	$ 3,592,885.00	4.45%
4	BALFOUR BEATTY INFRASTRUCTURE, INC.	Responsive	Non-Winning Bid	$ 3,695,583.52	7.44%
5	HUBBARD CONSTRUCTION COMPANY	Responsive	Non-Winning Bid	$ 3,852,595.54	12.00%
6	RUSSELL ENGINEERING, INC.	Responsive	Non-Winning Bid	$ 4,162,195.72	21.01%
7	JOHNSON BROS., LLC.	Responsive	Non-Winning Bid	$ 4,430,915.37	28.82%
8	MISENER MARINE CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$ 4,483,544.28	30.35%

CALL ORDER : 010
LETTING DATE : 08/26/09 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 510 WORKING DAYS (AVAILABLE DAYS)

PROPOSAL ID : T2293
DISTRICT : 02
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of replacing the bridge over Sixteen Mile Creek, on CR 13. Work includes removing the existing timber bridge, constructing a new concrete bridge and realigning the asphaltic concrete roadway to accommodate the new bridge location.

FINPROJ(S) : 21238215201 (*)
F.A. NO. : 00B2018B
COUNTIES : ST JOHNS

LOCAL NAME : CR 13
ROAD NAME : CR 13
PROJ LIMITS : AT DEEP CREEK BR # 784004

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 21238215201	11440.000 LS	98000.00000	98000.00	150000.00000	150000.00	175000.00000	175000.00
0010 0400 2 4 CONC CLASS II, SUPERSTRUCTURE	643.700 CY	550.00000	354035.00	675.00000	434497.50	700.00000	450590.00
0015 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	106.700 CY	300.00000	32010.00	325.00000	34677.50	350.00000	37345.00
0020 0400 4 5 CONCRETE CLASS IV, SUBSTRUCTURE	218.900 CY	800.00000	175120.00	775.00000	169647.50	800.00000	175120.00
0025 0400 9 BRIDGE DECK GROOVING & PLANING, DECK 8. 5"&>	2271.000 SY	4.80000	10900.80	6.00000	13626.00	6.00000	13626.00
0030 0400147 COMPOSITE NEOPRENE PADS	30.000 CF	820.00000	24600.00	1200.00000	36000.00	800.00000	24000.00
0035 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	149591.000 LB	0.55000	82275.05	0.85000	127152.35	0.60000	89754.60
0040 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	29769.000 LB	0.60000	17861.40	0.85000	25303.65	1.00000	29769.00
0045 0415 1 9 REINFORCING STEEL- APPROACH SLABS	20917.000 LB	0.60000	12550.20	0.85000	17779.45	1.00000	20917.00
0050 0450 1 2 PRESTRESSED BEAMS, TYPE III	3030.000 LF	150.00000	454500.00	110.00000	333300.00	100.00000	303000.00
0055 0455 34 5 PRESTRESSED CONCRETE PILING, 24" SQ	2895.000 LF	75.00000	217125.00	85.00000	246075.00	60.00000	173700.00
0060 0455133 2 SHEET PILING STEEL, TEMPORARY-CRITICAL	5013.000 SF	10.00000	50130.00	15.00000	75195.00	11.00000	55143.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
0065 0455143 5 TEST PILES-PRESTRESSED CONCRETE,24" SQ	490.000 LF	200.00000	98000.00	250.00000	122500.00	150.00000	73500.00
0070 0455146 EMBEDDED DATA COLLECTOR	5.000 EA	2000.00000	10000.00	3200.00000	16000.00	2000.00000	10000.00
0075 0458 1 12 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	90.000 LF	400.00000	36000.00	200.00000	18000.00	400.00000	36000.00
0080 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	1155.000 LF	70.00000	80850.00	80.00000	92400.00	40.00000	46200.00
0085 0530 1 RIPRAP, SAND-CEMENT	34.800 CY	400.00000	13920.00	650.00000	22620.00	250.00000	8700.00
0090 0530 3 3 RIPRAP, RUBBLE, BANK AND SHORE	1553.300 TN	50.00000	77665.00	65.00000	100964.50	50.00000	77665.00
0095 0530 74 BEDDING STONE	553.200 TN	60.00000	33192.00	75.00000	41490.00	50.00000	27660.00
SECTION 0001 TOTALS		$	1,878,734.45	$	2,077,228.45	$	1,827,689.60
SECTION 0002 ROADWAY							
0100 0101 1 MOBILIZATION 21238215201	LUMP	325000.00000	325000.00	295000.00000	295000.00	353000.00000	353000.00
0105 0102 1 MAINTENANCE OF TRAFFIC 21238215201	510.000 LS	240000.00000	240000.00	145000.00000	145000.00	314640.79000	314640.79
0110 0102 14 TRAFFIC CONTROL OFFICER	112.000 MH	75.00000	8400.00	30.00000	3360.00	45.00000	5040.00
0115 0102 60 WORK ZONE SIGN	14520.000 ED	0.25000	3630.00	0.30000	4356.00	0.25000	3630.00
0120 0102 71 11 BARRIER WALL, TEMPORARY, F&I, CONCRETE	524.000 LF	14.00000	7336.00	26.00000	13624.00	40.00000	20960.00
0125 0102 71 21 BARRIER WALL, TEMPORARY, RELOCATE, CONCRETE	497.000 LF	5.00000	2485.00	6.00000	2982.00	5.00000	2485.00
0130 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	32979.000 ED	0.16000	5276.64	0.20000	6595.80	0.14000	4617.06
0135 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	600.000 ED	0.40000	240.00	0.45000	270.00	0.50000	300.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
0140 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	3345.000 ED	0.40000	1338.00	0.45000	1505.25	0.35000	1170.75
0145 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	312.000 EA	4.00000	1248.00	4.50000	1404.00	5.00000	1560.00
0150 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	2521.000 ED	0.14000	352.94	0.15000	378.15	0.10000	252.10
0155 0102 89 7 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	20.000 LO	2000.00000	40000.00	1000.00000	20000.00	1200.00000	24000.00
0160 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	1152.000 LF	2.00000	2304.00	2.10000	2419.20	2.25000	2592.00
0165 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	243.000 SY	10.00000	2430.00	2.10000	510.30	6.00000	1458.00
0170 0104 10 2 SYNTHETIC BALES	252.000 LF	10.00000	2520.00	7.70000	1940.40	10.00000	2520.00
0175 0104 11 FLOATING TURBIDITY BARRIER	375.000 LF	15.00000	5625.00	10.00000	3750.00	12.00000	4500.00
0180 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	1123.000 LF	12.00000	13476.00	3.10000	3481.30	5.00000	5615.00
0185 0104 13 1 STAKED SILT FENCE, TYPE III	7930.000 LF	1.00000	7930.00	0.70000	5551.00	2.50000	19825.00
0190 0104 16 ROCK BAG	104.000 EA	3.00000	312.00	6.70000	696.80	9.00000	936.00
0195 0110 1 1 CLEARING & GRUBBING 21238215201	5.320 LS	81274.11000	81274.11	77000.00000	77000.00	110000.00000	110000.00
0200 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	159.000 SY	20.00000	3180.00	25.00000	3975.00	5.00000	795.00
0205 0110 7 1 MAILBOX, F&I SINGLE	13.000 EA	160.00000	2080.00	85.00000	1105.00	150.00000	1950.00
0210 0120 1 REGULAR EXCAVATION	4994.000 CY	5.00000	24970.00	7.00000	34958.00	4.00000	19976.00
0215 0120 6 EMBANKMENT	17974.000 CY	9.00000	161766.00	13.00000	233662.00	15.00000	269610.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
0220 0160 4 TYPE B STABILIZATION	9746.000 SY	9.00000	87714.00	5.90000	57501.40	5.00000	48730.00
0225 0285701 OPTIONAL BASE, BASE GROUP 01	2461.000 SY	10.00000	24610.00	8.00000	19688.00	10.00000	24610.00
0230 0285706 OPTIONAL BASE, BASE GROUP 06	6210.000 SY	13.00000	80730.00	14.50000	90045.00	13.00000	80730.00
0235 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	2534.000 SY	2.20000	5574.80	2.50000	6335.00	2.50000	6335.00
0240 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	940.100 TN	81.00000	76148.10	95.00000	89309.50	82.00000	77088.20
0245 0337 7 31 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, RUBBER	880.600 TN	101.00000	88940.60	120.00000	105672.00	110.00000	96866.00
0250 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	57.200 TN	200.00000	11440.00	160.00000	9152.00	140.00000	8008.00
0255 0425 1701 INLETS, GUTTER, TYPE S, <10'	4.000 EA	2500.00000	10000.00	3700.00000	14800.00	4000.00000	16000.00
0260 0430174101 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 0-24"SD	112.000 LF	75.00000	8400.00	42.00000	4704.00	65.00000	7280.00
0265 0430174201 PIPE CULVERT, OPTIONAL MATERIAL, OTHER - ELLIP/ARCH, 0-24"SD	104.000 LF	75.00000	7800.00	55.00000	5720.00	65.00000	6760.00
0270 0430175101 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 0-24"S/CD	381.000 LF	75.00000	28575.00	42.00000	16002.00	70.00000	26670.00
0275 0430611025 U-ENDWALL, STD 261, BAFFLES, 1:6 SLOPE, 18"PIPE	1.000 EA	2500.00000	2500.00	2900.00000	2900.00	3000.00000	3000.00
0280 0430611125 U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 18"PIPE	1.000 EA	2500.00000	2500.00	2500.00000	2500.00	2500.00000	2500.00
0285 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	14.000 EA	1000.00000	14000.00	1300.00000	18200.00	1600.00000	22400.00
0290 0520 6 SHOULDER GUTTER- CONCRETE	367.000 LF	20.00000	7340.00	17.00000	6239.00	30.00000	11010.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
0295 0522 2 SIDEWALK CONCRETE, 6" THICK	44.000 SY	75.00000	3300.00	65.00000	2860.00	50.00000	2200.00
0300 0536 1 1 GUARDRAIL -ROADWAY	800.000 LF	13.00000	10400.00	13.50000	10800.00	16.00000	12800.00
0305 0536 2 GUARDRAIL- SHOP-BENT PANELS	69.000 LF	16.00000	1104.00	17.00000	1173.00	20.00000	1380.00
0310 0536 73 GUARDRAIL REMOVAL	1935.000 LF	1.00000	1935.00	1.50000	2902.50	2.00000	3870.00
0315 0536 85 22 GUARDRAIL END ANCHORAGE ASSEMBLY- FLARE	2.000 EA	1375.00000	2750.00	1450.00000	2900.00	1500.00000	3000.00
0320 0536 85 26 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE CRT	2.000 EA	1273.00000	2546.00	1350.00000	2700.00	1500.00000	3000.00
0325 0570 1 2 PERFORMANCE TURF, SOD	24271.000 SY	3.00000	72813.00	1.90000	46114.90	2.50000	60677.50
0330 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	2.158 NM	1000.00000	2158.00	1100.00000	2373.80	1250.00000	2697.50
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	2.158 NM	1000.00000	2158.00	1100.00000	2373.80	1250.00000	2697.50
0340 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 21238215201	LUMP	52585.00000	52585.00	52585.00000	52585.00	52585.00000	52585.00
SECTION 0002 TOTALS			$ 1,551,195.19		$ 1,439,075.10		$ 1,754,327.40
SECTION 0003 SIGNING							
0345 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	7.000 AS	238.00000	1666.00	250.00000	1750.00	250.00000	1750.00
0350 0700 20 40 SINGLE POST SIGN, RELOCATE	1.000 AS	123.00000	123.00	130.00000	130.00	150.00000	150.00
0355 0700 20 60 SINGLE POST SIGN, REMOVE	8.000 AS	49.00000	392.00	55.00000	440.00	50.00000	400.00
0360 0700 48 48 SIGN PANELS RELOCATE, 15 OR <	4.000 EA	141.00000	564.00	150.00000	600.00	150.00000	600.00
0365 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 21238215201	LUMP	5200.00000	5200.00	6070.85000	6070.85	6000.00000	6000.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(2) LEWARE CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT	(3) HAL JONES CONTRACTOR, INC UNIT PRICE	 AMOUNT
0370 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	0.219 NM	5000.00000	1095.00	5200.00000	1138.80	6000.00000	1314.00
0375 0711 11231 THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	0.109 GM	5000.00000	545.00	5200.00000	566.80	6000.00000	654.00
SECTION 0003 TOTALS			$ 9,585.00		$ 10,696.45		$ 10,868.00
CONTRACT TOTALS			$ 3,439,514.64		$ 3,527,000.00		$ 3,592,885.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) BALFOUR BEATTY INFRASTRUCTU UNIT PRICE	 AMOUNT	(5) HUBBARD CONSTRUCTION COMPAN UNIT PRICE	 AMOUNT	(6) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 21238215201	11440.000 LS	170000.00000	170000.00	283000.00000	283000.00	150000.00000	150000.00
0010 0400 2 4 CONC CLASS II, SUPERSTRUCTURE	643.700 CY	900.00000	579330.00	700.00000	450590.00	675.00000	434497.50
0015 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	106.700 CY	250.00000	26675.00	300.00000	32010.00	325.00000	34677.50
0020 0400 4 5 CONCRETE CLASS IV, SUBSTRUCTURE	218.900 CY	1000.00000	218900.00	900.00000	197010.00	775.00000	169647.50
0025 0400 9 BRIDGE DECK GROOVING & PLANING, DECK 8. 5"&>	2271.000 SY	6.00000	13626.00	5.00000	11355.00	6.00000	13626.00
0030 0400147 COMPOSITE NEOPRENE PADS	30.000 CF	800.00000	24000.00	600.00000	18000.00	1200.00000	36000.00
0035 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	149591.000 LB	0.75000	112193.25	1.00000	149591.00	0.85000	127152.35
0040 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	29769.000 LB	0.75000	22326.75	1.00000	29769.00	0.85000	25303.65
0045 0415 1 9 REINFORCING STEEL- APPROACH SLABS	20917.000 LB	0.75000	15687.75	1.00000	20917.00	0.85000	17779.45
0050 0450 1 2 PRESTRESSED BEAMS, TYPE III	3030.000 LF	120.00000	363600.00	123.00000	372690.00	115.00000	348450.00
0055 0455 34 5 PRESTRESSED CONCRETE PILING, 24" SQ	2895.000 LF	100.00000	289500.00	55.00000	159225.00	92.00000	266340.00
0060 0455133 2 SHEET PILING STEEL, TEMPORARY-CRITICAL	5013.000 SF	25.00000	125325.00	15.00000	75195.00	15.00000	75195.00
0065 0455143 5 TEST PILES-PRESTRESSED CONCRETE,24" SQ	490.000 LF	120.00000	58800.00	140.00000	68600.00	250.00000	122500.00
0070 0455146 EMBEDDED DATA COLLECTOR	5.000 EA	2000.00000	10000.00	2000.00000	10000.00	3200.00000	16000.00
0075 0458 1 12 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	90.000 LF	449.90000	40491.00	250.00000	22500.00	200.00000	18000.00
0080 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	1155.000 LF	75.00000	86625.00	63.00000	72765.00	80.00000	92400.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) BALFOUR BEATTY INFRASTRUCTU UNIT PRICE	 AMOUNT	(5) HUBBARD CONSTRUCTION COMPAN UNIT PRICE	 AMOUNT	(6) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT
0085 0530 1 RIPRAP, SAND-CEMENT	34.800 CY	325.00000	11310.00	450.00000	15660.00	650.00000	22620.00
0090 0530 3 3 RIPRAP, RUBBLE, BANK AND SHORE	1553.300 TN	75.00000	116497.50	61.00000	94751.30	65.00000	100964.50
0095 0530 74 BEDDING STONE	553.200 TN	55.00000	30426.00	54.00000	29872.80	75.00000	41490.00
SECTION 0001 TOTALS		$	2,315,313.25	$	2,113,501.10	$	2,112,643.45
SECTION 0002 ROADWAY							
0100 0101 1 MOBILIZATION 21238215201	LUMP	185000.00000	185000.00	370000.00000	370000.00	400000.00000	400000.00
0105 0102 1 MAINTENANCE OF TRAFFIC 21238215201	510.000 LS	325000.00000	325000.00	350000.00000	350000.00	238723.00000	238723.00
0110 0102 14 TRAFFIC CONTROL OFFICER	112.000 MH	60.00000	6720.00	45.00000	5040.00	50.00000	5600.00
0115 0102 60 WORK ZONE SIGN	14520.000 ED	0.25000	3630.00	0.25000	3630.00	0.25000	3630.00
0120 0102 71 11 BARRIER WALL, TEMPORARY, F&I, CONCRETE	524.000 LF	17.00000	8908.00	40.00000	20960.00	17.00000	8908.00
0125 0102 71 21 BARRIER WALL, TEMPORARY, RELOCATE, CONCRETE	497.000 LF	5.40000	2683.80	6.00000	2982.00	4.45000	2211.65
0130 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	32979.000 ED	0.16000	5276.64	0.16000	5276.64	0.12000	3957.48
0135 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	600.000 ED	0.40000	240.00	0.40000	240.00	0.45000	270.00
0140 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	3345.000 ED	0.40000	1338.00	0.40000	1338.00	0.35000	1170.75
0145 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	312.000 EA	4.00000	1248.00	4.00000	1248.00	4.00000	1248.00
0150 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	2521.000 ED	0.14000	352.94	0.14000	352.94	0.08000	201.68
0155 0102 89 7 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	20.000 LO	775.00000	15500.00	775.00000	15500.00	900.00000	18000.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) BALFOUR BEATTY INFRASTRUCTU UNIT PRICE	 AMOUNT	(5) HUBBARD CONSTRUCTION COMPAN UNIT PRICE	 AMOUNT	(6) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT
0160 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	1152.000 LF	2.00000	2304.00	2.00000	2304.00	2.00000	2304.00
0165 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	243.000 SY	1.50000	364.50	2.50000	607.50	3.25000	789.75
0170 0104 10 2 SYNTHETIC BALES	252.000 LF	6.00000	1512.00	6.75000	1701.00	8.00000	2016.00
0175 0104 11 FLOATING TURBIDITY BARRIER	375.000 LF	7.00000	2625.00	6.50000	2437.50	8.50000	3187.50
0180 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	1123.000 LF	3.00000	3369.00	3.25000	3649.75	5.10000	5727.30
0185 0104 13 1 STAKED SILT FENCE, TYPE III	7930.000 LF	0.55000	4361.50	0.60000	4758.00	0.88000	6978.40
0190 0104 16 ROCK BAG	104.000 EA	3.00000	312.00	7.75000	806.00	8.00000	832.00
0195 0110 1 1 CLEARING & GRUBBING 21238215201	5.320 LS	58064.81000	58064.81	350000.00000	350000.00	429066.00000	429066.00
0200 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	159.000 SY	15.00000	2385.00	5.80000	922.20	13.25000	2106.75
0205 0110 7 1 MAILBOX, F&I SINGLE	13.000 EA	135.20000	1757.60	50.00000	650.00	175.00000	2275.00
0210 0120 1 REGULAR EXCAVATION	4994.000 CY	14.25000	71164.50	2.00000	9988.00	13.00000	64922.00
0215 0120 6 EMBANKMENT	17974.000 CY	8.67000	155834.58	4.00000	71896.00	14.00000	251636.00
0220 0160 4 TYPE B STABILIZATION	9746.000 SY	1.72000	16763.12	2.00000	19492.00	2.95000	28750.70
0225 0285701 OPTIONAL BASE, BASE GROUP 01	2461.000 SY	7.69000	18925.09	6.00000	14766.00	10.25000	25225.25
0230 0285706 OPTIONAL BASE, BASE GROUP 06	6210.000 SY	11.26000	69924.60	10.00000	62100.00	12.85000	79798.50
0235 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	2534.000 SY	2.32000	5878.88	3.00000	7602.00	3.90000	9882.60
0240 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	940.100 TN	85.97000	80820.40	87.00000	81788.70	105.00000	98710.50

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) BALFOUR BEATTY INFRASTRUCTU UNIT PRICE	 AMOUNT	(5) HUBBARD CONSTRUCTION COMPAN UNIT PRICE	 AMOUNT	(6) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT
0245 0337 7 31 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, RUBBER	880.600 TN	106.86000	94100.92	95.00000	83657.00	115.00000	101269.00
0250 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	57.200 TN	120.36000	6884.59	179.00000	10238.80	360.00000	20592.00
0255 0425 1701 INLETS, GUTTER, TYPE S, <10'	4.000 EA	3381.00000	13524.00	4500.00000	18000.00	3165.00000	12660.00
0260 0430174101 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 0-24"SD	112.000 LF	58.22000	6520.64	75.00000	8400.00	58.00000	6496.00
0265 0430174201 PIPE CULVERT, OPTIONAL MATERIAL, OTHER - ELLIP/ARCH, 0-24"SD	104.000 LF	67.72000	7042.88	85.00000	8840.00	47.00000	4888.00
0270 0430175101 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 0-24"S/CD	381.000 LF	123.17000	46927.77	70.00000	26670.00	22.00000	8382.00
0275 0430611025 U-ENDWALL, STD 261, BAFFLES, 1:6 SLOPE, 18"PIPE	1.000 EA	2030.50000	2030.50	2500.00000	2500.00	1546.00000	1546.00
0280 0430611125 U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 18"PIPE	1.000 EA	1420.00000	1420.00	3000.00000	3000.00	1546.00000	1546.00
0285 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	14.000 EA	1551.04000	21714.56	2500.00000	35000.00	956.00000	13384.00
0290 0520 6 SHOULDER GUTTER- CONCRETE	367.000 LF	15.49000	5684.83	15.00000	5505.00	32.25000	11835.75
0295 0522 2 SIDEWALK CONCRETE, 6" THICK	44.000 SY	31.82000	1400.08	36.00000	1584.00	64.50000	2838.00
0300 0536 1 1 GUARDRAIL -ROADWAY	800.000 LF	13.13000	10504.00	13.00000	10400.00	22.00000	17600.00
0305 0536 2 GUARDRAIL- SHOP-BENT PANELS	69.000 LF	16.50000	1138.50	16.00000	1104.00	26.00000	1794.00
0310 0536 73 GUARDRAIL REMOVAL	1935.000 LF	1.41000	2728.35	2.00000	3870.00	3.32000	6424.20
0315 0536 85 22 GUARDRAIL END ANCHORAGE ASSEMBLY- FLARE	2.000 EA	1402.89000	2805.78	1400.00000	2800.00	1800.00000	3600.00
0320 0536 85 26 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE CRT	2.000 EA	1298.77000	2597.54	1300.00000	2600.00	950.00000	1900.00

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) BALFOUR BEATTY INFRASTRUCTU UNIT PRICE	 AMOUNT	(5) HUBBARD CONSTRUCTION COMPAN UNIT PRICE	 AMOUNT	(6) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT
0325 0570 1 2 PERFORMANCE TURF, SOD	24271.000 SY	1.45000	35192.95	1.50000	36406.50	2.81000	68201.51
0330 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	2.158 NM	1000.93000	2160.01	1000.93000	2160.01	1000.00000	2158.00
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	2.158 NM	1000.93000	2160.01	1000.93000	2160.01	1000.00000	2158.00
0340 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 21238215201	LUMP	52585.00000	52585.00	52585.00000	52585.00	52585.00000	52585.00
SECTION 0002 TOTALS			$ 1,371,386.87		$ 1,729,516.55		$ 2,039,986.27
SECTION 0003 SIGNING							
0345 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	7.000 AS	212.00000	1484.00	237.78000	1664.46	238.00000	1666.00
0350 0700 20 40 SINGLE POST SIGN, RELOCATE	1.000 AS	96.00000	96.00	123.39000	123.39	123.00000	123.00
0355 0700 20 60 SINGLE POST SIGN, REMOVE	8.000 AS	14.00000	112.00	49.36000	394.88	49.00000	392.00
0360 0700 48 48 SIGN PANELS RELOCATE, 15 OR <	4.000 EA	90.00000	360.00	140.94000	563.76	141.00000	564.00
0365 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 21238215201	LUMP	5181.40000	5181.40	5181.40000	5181.40	5181.00000	5181.00
0370 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	0.219 NM	5022.83000	1100.00	5022.83000	1100.00	5000.00000	1095.00
0375 0711 11231 THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	0.109 GM	5045.87000	550.00	5045.87000	550.00	5000.00000	545.00
SECTION 0003 TOTALS			$ 8,883.40		$ 9,577.89		$ 9,566.00
CONTRACT TOTALS			$ 3,695,583.52		$ 3,852,595.54		$ 4,162,195.72

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) JOHNSON BROS., LLC. UNIT PRICE	 AMOUNT	(8) MISENER MARINE CONSTRUCTION UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 21238215201	11440.000 LS	160000.00000	160000.00	178444.09000	178444.09		
0010 0400 2 4 CONC CLASS II, SUPERSTRUCTURE	643.700 CY	927.50000	597031.75	621.25000	399898.63		
0015 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	106.700 CY	500.00000	53350.00	213.35000	22764.45		
0020 0400 4 5 CONCRETE CLASS IV, SUBSTRUCTURE	218.900 CY	1100.00000	240790.00	631.89000	138320.72		
0025 0400 9 BRIDGE DECK GROOVING & PLANING, DECK 8. 5"&>	2271.000 SY	8.23000	18690.33	6.84000	15533.64		
0030 0400147 COMPOSITE NEOPRENE PADS	30.000 CF	1300.00000	39000.00	794.35000	23830.50		
0035 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	149591.000 LB	1.00000	149591.00	0.74000	110697.34		
0040 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	29769.000 LB	1.00000	29769.00	0.73000	21731.37		
0045 0415 1 9 REINFORCING STEEL- APPROACH SLABS	20917.000 LB	1.00000	20917.00	0.70000	14641.90		
0050 0450 1 2 PRESTRESSED BEAMS, TYPE III	3030.000 LF	200.00000	606000.00	92.90000	281487.00		
0055 0455 34 5 PRESTRESSED CONCRETE PILING, 24" SQ	2895.000 LF	100.00000	289500.00	94.40000	273288.00		
0060 0455133 2 SHEET PILING STEEL, TEMPORARY-CRITICAL	5013.000 SF	36.25000	181721.25	10.55000	52887.15		
0065 0455143 5 TEST PILES-PRESTRESSED CONCRETE,24" SQ	490.000 LF	175.00000	85750.00	125.63000	61558.70		
0070 0455146 EMBEDDED DATA COLLECTOR	5.000 EA	2000.00000	10000.00	2378.92000	11894.60		
0075 0458 1 12 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I STRIP SEAL	90.000 LF	9.00000	810.00	465.06000	41855.40		
0080 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	1155.000 LF	100.00000	115500.00	63.59000	73446.45		

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) JOHNSON BROS., LLC. UNIT PRICE	 AMOUNT	(8) MISENER MARINE CONSTRUCTION UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0085 0530 1 RIPRAP, SAND-CEMENT	34.800 CY	400.00000	13920.00	997.23000	34703.60		
0090 0530 3 3 RIPRAP, RUBBLE, BANK AND SHORE	1553.300 TN	85.00000	132030.50	88.00000	136690.40		
0095 0530 74 BEDDING STONE	553.200 TN	80.00000	44256.00	69.74000	38580.17		
SECTION 0001 TOTALS		$ 2,788,626.83		$ 1,932,254.11		$	
SECTION 0002 ROADWAY							
0100 0101 1 MOBILIZATION 21238215201	LUMP	426000.00000	426000.00	863945.90000	863945.90		
0105 0102 1 MAINTENANCE OF TRAFFIC 21238215201	510.000 LS	270000.00000	270000.00	320818.58000	320818.58		
0110 0102 14 TRAFFIC CONTROL OFFICER	112.000 MH	65.00000	7280.00	102.54000	11484.48		
0115 0102 60 WORK ZONE SIGN	14520.000 ED	0.29000	4210.80	0.40000	5808.00		
0120 0102 71 11 BARRIER WALL, TEMPORARY, F&I, CONCRETE	524.000 LF	20.00000	10480.00	23.24000	12177.76		
0125 0102 71 21 BARRIER WALL, TEMPORARY, RELOCATE, CONCRETE	497.000 LF	6.00000	2982.00	7.38000	3667.86		
0130 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	32979.000 ED	0.20000	6595.80	0.27000	8904.33		
0135 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	600.000 ED	0.38000	228.00	0.52000	312.00		
0140 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	3345.000 ED	0.36000	1204.20	0.49000	1639.05		
0145 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	312.000 EA	3.13000	976.56	4.24000	1322.88		
0150 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	2521.000 ED	0.15000	378.15	0.21000	529.41		
0155 0102 89 7 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	20.000 LO	1020.20000	20404.00	1380.87000	27617.40		

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) JOHNSON BROS., LLC. UNIT PRICE	 AMOUNT	(8) MISENER MARINE CONSTRUCTION UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0160 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	1152.000 LF	1.57000	1808.64	2.12000	2442.24		
0165 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	243.000 SY	1.35000	328.05	3.62000	879.66		
0170 0104 10 2 SYNTHETIC BALES	252.000 LF	5.85000	1474.20	8.70000	2192.40		
0175 0104 11 FLOATING TURBIDITY BARRIER	375.000 LF	5.75000	2156.25	11.56000	4335.00		
0180 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	1123.000 LF	2.79000	3133.17	4.03000	4525.69		
0185 0104 13 1 STAKED SILT FENCE, TYPE III	7930.000 LF	0.51000	4044.30	1.03000	8167.90		
0190 0104 16 ROCK BAG	104.000 EA	3.13000	325.52	4.85000	504.40		
0195 0110 1 1 CLEARING & GRUBBING 21238215201	5.320 LS	50000.00000	50000.00	122321.70000	122321.70		
0200 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	159.000 SY	10.00000	1590.00	9.21000	1464.39		
0205 0110 7 1 MAILBOX, F&I SINGLE	13.000 EA	81.82000	1063.66	110.74000	1439.62		
0210 0120 1 REGULAR EXCAVATION	4994.000 CY	5.00000	24970.00	14.94000	74610.36		
0215 0120 6 EMBANKMENT	17974.000 CY	15.00000	269610.00	20.77000	373319.98		
0220 0160 4 TYPE B STABILIZATION	9746.000 SY	3.00000	29238.00	5.20000	50679.20		
0225 0285701 OPTIONAL BASE, BASE GROUP 01	2461.000 SY	9.00000	22149.00	12.41000	30541.01		
0230 0285706 OPTIONAL BASE, BASE GROUP 06	6210.000 SY	14.00000	86940.00	16.43000	102030.30		
0235 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	2534.000 SY	2.27000	5752.18	3.17000	8032.78		
0240 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	940.100 TN	83.98000	78949.60	117.54000	110499.35		

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) JOHNSON BROS., LLC. UNIT PRICE	 AMOUNT	(8) MISENER MARINE CONSTRUCTION UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0245 0337 7 31 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, RUBBER	880.600 TN	104.38000	91917.03	146.10000	128655.66		
0250 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	57.200 TN	117.57000	6725.00	164.56000	9412.83		
0255 0425 1701 INLETS, GUTTER, TYPE S, <10'	4.000 EA	3000.00000	12000.00	4046.71000	16186.84		
0260 0430174101 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 0-24"SD	112.000 LF	63.00000	7056.00	54.18000	6068.16		
0265 0430174201 PIPE CULVERT, OPTIONAL MATERIAL, OTHER - ELLIP/ARCH, 0-24"SD	104.000 LF	66.00000	6864.00	64.27000	6684.08		
0270 0430175101 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 0-24"S/CD	381.000 LF	50.00000	19050.00	51.90000	19773.90		
0275 0430611025 U-ENDWALL, STD 261, BAFFLES, 1:6 SLOPE, 18"PIPE	1.000 EA	2000.00000	2000.00	3603.56000	3603.56		
0280 0430611125 U-ENDWALL WITH BAFFLES, STD 261, 1:4 SLOPE, 18"PIPE	1.000 EA	1600.00000	1600.00	2525.99000	2525.99		
0285 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	14.000 EA	2300.00000	32200.00	1875.07000	26250.98		
0290 0520 6 SHOULDER GUTTER- CONCRETE	367.000 LF	15.00000	5505.00	47.67000	17494.89		
0295 0522 2 SIDEWALK CONCRETE, 6" THICK	44.000 SY	45.00000	1980.00	62.13000	2733.72		
0300 0536 1 1 GUARDRAIL -ROADWAY	800.000 LF	13.38000	10704.00	17.60000	14080.00		
0305 0536 2 GUARDRAIL- SHOP-BENT PANELS	69.000 LF	16.81000	1159.89	22.11000	1525.59		
0310 0536 73 GUARDRAIL REMOVAL	1935.000 LF	1.43000	2767.05	1.89000	3657.15		
0315 0536 85 22 GUARDRAIL END ANCHORAGE ASSEMBLY- FLARE	2.000 EA	1429.11000	2858.22	1879.90000	3759.80		
0320 0536 85 26 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE CRT	2.000 EA	1323.04000	2646.08	1740.44000	3480.88		

CALL ORDER: 010 PROPOSAL ID: T2293 LETTING DATE: 08/26/09 10:30 A.M. DISTRICT: 02

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) JOHNSON BROS., LLC. UNIT PRICE	 AMOUNT	(8) MISENER MARINE CONSTRUCTION UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0325 0570 1 2 PERFORMANCE TURF, SOD	24271.000 SY	1.45000	35192.95	2.41000	58493.11		
0330 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	2.158 NM	1021.15000	2203.64	1375.75000	2968.87		
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	2.158 NM	1021.15000	2203.64	1375.75000	2968.87		
0340 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 21238215201	LUMP	52585.00000	52585.00	52585.00000	52585.00		
SECTION 0002 TOTALS		$	1,633,489.58	$	2,539,123.51	$	
SECTION 0003 SIGNING							
0345 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	7.000 AS	214.14000	1498.98	289.85000	2028.95		
0350 0700 20 40 SINGLE POST SIGN, RELOCATE	1.000 AS	96.97000	96.97	131.25000	131.25		
0355 0700 20 60 SINGLE POST SIGN, REMOVE	8.000 AS	14.14000	113.12	19.14000	153.12		
0360 0700 48 48 SIGN PANELS RELOCATE, 15 OR <	4.000 EA	100.00000	400.00	192.77000	771.08		
0365 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 21238215201	LUMP	4912.12000	4912.12	6676.00000	6676.00		
0370 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	0.219 NM	6544.89000	1433.33	8858.68000	1940.05		
0375 0711 11231 THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	0.109 GM	3160.00000	344.44	4277.16000	466.21		
SECTION 0003 TOTALS		$	8,798.96	$	12,166.66	$	
CONTRACT TOTALS		$	4,430,915.37	$	4,483,544.28	$	0.00

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.