VENDOR RANKING

CALL ORDER : 001 PROPOSAL ID : T1402 PROPOSAL DESC :
LETTING DATE : 03/30/11 10:30 A.M. DISTRICT : 01
SET-ASIDE : U/R CODE :
CONTRACT TIME : 360 WORKING DAYS (AVAILABLE DAYS)

The improvements under this contract consist of new construction, adding lanes, widening, milling and resurfacing, drainage improvements, signing and pavement marking, signalization and lighting on SR 35/700.

FINPROJ(S) : 19756225201 (*) F.A. NO. : 3491012P COUNTIES : POLK

LOCAL NAME : US 98 (BARTOW HWY) ROAD NAME : SR 35
PROJ LIMITS : FROM BROOKS STREET TO EDGEWOOD DRIVE

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	CONALVIAS USA LLC	Responsive	Winning bid	$ 4,341,916.77	0.00%
2	BETTER ROADS, INC.	Responsive	Non-Winning Bid	$ 4,853,919.75	11.79%
3	LANE CONSTRUCTION CORPORATION (THE)	Responsive	Non-Winning Bid	$ 4,944,497.68	13.87%
4	PURCELL, R.E. CONSTRUCTION CO., INC.	Responsive	Non-Winning Bid	$ 4,979,650.67	14.68%
5	RUSSELL ENGINEERING, INC.	Responsive	Non-Winning Bid	$ 4,992,370.96	14.98%
6	CONE & GRAHAM, INC.	Responsive	Non-Winning Bid	$ 5,085,196.97	17.11%
7	SOUTHLAND CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$ 5,125,600.00	18.04%
8	EMERALD UTILITIES & SITE DEVELOPMENT	Responsive	Non-Winning Bid	$ 5,227,300.00	20.39%
9	MIDDLESEX CORPORATION (THE)	Responsive	Non-Winning Bid	$ 5,386,000.00	24.04%
10	AJAX PAVING INDUSTRIES OF FLORIDA LLC	Responsive	Non-Winning Bid	$ 5,525,308.98	27.25%

CALL ORDER : 001
LETTING DATE : 03/30/11 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 360 WORKING DAYS (AVAILABLE DAYS)

PROPOSAL ID : T1402
DISTRICT : 01
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of new construction, adding lanes, widening, milling and resurfacing, drainage improvements, signing and pavement marking, signalization and lighting on SR 35/700.

FINPROJ(S) : 19756225201 (*)
F.A. NO. : 3491012P
COUNTIES : POLK

LOCAL NAME : US 98 (BARTOW HWY)
ROAD NAME : SR 35
PROJ LIMITS : FROM BROOKS STREET TO EDGEWOOD DRIVE

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 19756225201	LUMP	400000.00000	400000.00	408800.00000	408800.00	456000.00000	456000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 19756225201	360.000 LS	125000.00000	125000.00	331500.00000	331500.00	80000.00000	80000.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	500.000 CY	22.00000	11000.00	16.25000	8125.00	18.40000	9200.00
0020 0102 14 TRAFFIC CONTROL OFFICER	56.000 MH	45.00000	2520.00	45.90000	2570.40	38.00000	2128.00
0025 0102 60 WORK ZONE SIGN	23850.000 ED	0.25000	5962.50	0.29000	6916.50	0.22000	5247.00
0030 0102 61 BUSINESS SIGN	16.000 EA	75.00000	1200.00	51.00000	816.00	30.00000	480.00
0035 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	121044.000 ED	0.12000	14525.28	0.11000	13314.84	0.14000	16946.16
0040 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	6234.000 ED	0.35000	2181.90	0.25000	1558.50	0.26000	1620.84
0045 0102 76 ADVANCE WARNING ARROW PANEL	1008.000 ED	7.00000	7056.00	6.10000	6148.80	6.00000	6048.00
0050 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	7200.000 ED	0.35000	2520.00	0.15000	1080.00	0.26000	1872.00
0055 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	2174.000 EA	2.55000	5543.70	2.60000	5652.40	3.00000	6522.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0060 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	618.000 ED	12.00000	7416.00	14.80000	9146.40	15.00000	9270.00
0065 0102104 2 TEMPORARY TRAFFIC CONTROL, FIXED SIGNAL	247.000 ED	17.60000	4347.20	19.40000	4791.80	14.79000	3653.13
0070 0102107 TEMPORARY TRAFFIC DETECTION, INTERSECT	247.000 DA	8.35000	2062.45	4.10000	1012.70	8.40000	2074.80
0075 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	300.000 SY	2.50000	750.00	1.25000	375.00	1.50000	450.00
0080 0104 10 3 SEDIMENT BARRIER	10966.000 LF	0.85000	9321.10	0.50000	5483.00	0.42000	4605.72
0085 0104 11 FLOATING TURBIDITY BARRIER	58.000 LF	13.50000	783.00	6.90000	400.20	7.00000	406.00
0090 0104 15 SOIL TRACKING PREVENTION DEVICE	3.000 EA	1055.00000	3165.00	1530.00000	4590.00	1850.00000	5550.00
0095 0104 18 INLET PROTECTION SYSTEM	62.000 EA	19.50000	1209.00	29.60000	1835.20	45.00000	2790.00
0100 0107 1 LITTER REMOVAL	55.600 AC	25.00000	1390.00	102.00000	5671.20	10.00000	556.00
0105 0107 2 MOWING	55.600 AC	20.00000	1112.00	128.00000	7116.80	10.00000	556.00
0110 0110 1 1 CLEARING & GRUBBING 19756225201	17.410 LS	37500.00000	37500.00	123400.00000	123400.00	90000.00000	90000.00
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	4022.000 SY	10.95000	44040.90	15.50000	62341.00	7.95000	31974.90
0120 0110 7 1 MAILBOX, F&I SINGLE	7.000 EA	100.00000	700.00	187.00000	1309.00	100.00000	700.00
0125 0120 1 REGULAR EXCAVATION	23045.000 CY	2.00000	46090.00	2.05000	47242.25	5.80000	133661.00
0130 0120 4 SUBSOIL EXCAVATION	3518.000 CY	3.00000	10554.00	3.70000	13016.60	8.00000	28144.00
0135 0120 6 EMBANKMENT	9875.000 CY	7.00000	69125.00	3.55000	35056.25	16.00000	158000.00
0140 0145 2 GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	1300.000 SY	4.85000	6305.00	3.95000	5135.00	9.60000	12480.00
0145 0160 4 TYPE B STABILIZATION	50449.000 SY	2.45000	123600.05	3.55000	179093.95	3.35000	169004.15

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0150 0285701 OPTIONAL BASE, BASE GROUP 01	79.000 SY	13.00000	1027.00	6.90000	545.10	10.20000	805.80
0155 0285712 OPTIONAL BASE, BASE GROUP 12	45556.000 SY	12.00000	546672.00	12.55000	571727.80	15.55000	708395.80
0160 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	11235.000 SY	1.25000	14043.75	2.55000	28649.25	1.55000	17414.25
0165 0327 70 19 MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	970.000 SY	1.25000	1212.50	2.30000	2231.00	1.55000	1503.50
0170 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5143.700 TN	71.25000	366488.63	74.25000	381919.73	80.00000	411496.00
0175 0334 1 24 SUPERPAVE ASPH CONC, TRAF D, PG76-22	3763.600 TN	84.00000	316142.40	93.80000	353025.68	97.00000	365069.20
0180 0337 7 22 ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	39.000 TN	100.00000	3900.00	122.00000	4758.00	200.00000	7800.00
0185 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	4690.500 TN	90.00000	422145.00	101.00000	473740.50	93.60000	439030.80
0190 0400 0 11 CONCRETE CLASS NS, GRAVITY WALL	7.200 CY	390.00000	2808.00	530.00000	3816.00	525.00000	3780.00
0195 0425 1311 INLETS, CURB, TYPE P-1, <10'	1.000 EA	2419.77000	2419.77	2720.00000	2720.00	3495.00000	3495.00
0200 0425 1315 INLETS, CURB TYPE P-1, PARTIAL	1.000 EA	2250.00000	2250.00	2130.00000	2130.00	1380.00000	1380.00
0205 0425 1351 INLETS, CURB, TYPE P-5, <10'	24.000 EA	2415.00000	57960.00	2715.00000	65160.00	2622.00000	62928.00
0210 0425 1481 INLETS, CURB, TYPE 8, <10'	22.000 EA	2370.00000	52140.00	2695.00000	59290.00	4135.00000	90970.00
0215 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	2360.00000	2360.00	1590.00000	1590.00	1273.00000	1273.00
0220 0425 1531 INLETS, DT BOT, TYPE C, MODIFIED, <10''	4.000 EA	2045.00000	8180.00	1180.00000	4720.00	1170.00000	4680.00
0225 0425 1541 INLETS, DT BOT, TYPE D, <10'	6.000 EA	2650.00000	15900.00	2225.00000	13350.00	1762.00000	10572.00
0230 0425 1549 INLETS, DT BOT, TYPE D, MODIFY	1.000 EA	3905.00000	3905.00	8440.00000	8440.00	6975.00000	6975.00
0235 0425 1551 INLETS, DT BOT, TYPE E, <10'	1.000 EA	3380.00000	3380.00	3620.00000	3620.00	2866.00000	2866.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0240 0425 1561 INLETS, DT BOT, TYPE F, <10'	1.000 EA	2615.00000	2615.00	2265.00000	2265.00	1772.00000	1772.00
0245 0425 1702 INLETS, GUTTER, TYPE S, >10'	1.000 EA	3760.00000	3760.00	4110.00000	4110.00	5635.00000	5635.00
0250 0425 2 61 MANHOLES, P-8, <10'	4.000 EA	2440.00000	9760.00	1815.00000	7260.00	1552.00000	6208.00
0255 0425 2 91 MANHOLES, J-8, <10'	7.000 EA	3430.00000	24010.00	3855.00000	26985.00	2511.00000	17577.00
0260 0425 2 92 MANHOLES, J-8, >10'	6.000 EA	4525.00000	27150.00	6320.00000	37920.00	3576.00000	21456.00
0265 0425 3 41 JUNCTION BOX, DRAINAGE, P-7, <10'	1.000 EA	2205.00000	2205.00	1420.00000	1420.00	1376.00000	1376.00
0270 0425 3 43 JUNCTION BOX, DRAINAGE, P-7, PARTIAL	1.000 EA	1190.00000	1190.00	731.00000	731.00	980.00000	980.00
0275 0425 10 YARD DRAIN	2.000 EA	1320.00000	2640.00	980.00000	1960.00	1302.00000	2604.00
0280 0430 94 1 DESILTING PIPE, 0 - 24"	226.000 LF	3.00000	678.00	4.10000	926.60	5.15000	1163.90
0285 0430 94 2 DESILTING PIPE, 25 - 36"	354.000 LF	5.00000	1770.00	6.10000	2159.40	9.15000	3239.10
0290 0430 94 3 DESILTING PIPE, 37 - 48"	1385.000 LF	8.50000	11772.50	8.15000	11287.75	16.15000	22367.75
0295 0430 94 4 DESILTING PIPE, 49 - 60"	159.000 LF	15.00000	2385.00	10.20000	1621.80	22.15000	3521.85
0300 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	22.000 LF	42.00000	924.00	26.95000	592.90	54.15000	1191.30
0305 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	3295.000 LF	34.75000	114501.25	31.70000	104451.50	35.17000	115885.15
0310 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	3289.000 LF	41.50000	136493.50	36.75000	120870.75	36.50000	120048.50
0315 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	60.000 LF	50.00000	3000.00	58.30000	3498.00	46.85000	2811.00
0320 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	1074.000 LF	61.50000	66051.00	73.85000	79314.90	55.20000	59284.80

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0325 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	294.000 LF	71.50000	21021.00	93.50000	27489.00	105.80000	31105.20
0330 0430175154 PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	828.000 LF	102.55000	84911.40	120.00000	99360.00	135.00000	111780.00
0335 0430175248 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	70.000 LF	56.50000	3955.00	146.00000	10220.00	152.80000	10696.00
0340 0430982129 MITERED END SECTION, OPTIONAL ROUND, 24" CD	2.000 EA	825.00000	1650.00	1170.00000	2340.00	586.00000	1172.00
0345 0430982138 MITERED END SECTION, OPTIONAL ROUND, 36" CD	1.000 EA	1375.00000	1375.00	2090.00000	2090.00	1112.00000	1112.00
0350 0430984133 MITERED END SECTION , OPTIONAL ROUND, 30" SD	1.000 EA	1195.00000	1195.00	1555.00000	1555.00	1475.00000	1475.00
0355 0430990 MITERED END SECT, REPLACE GRATE	1.000 EA	710.00000	710.00	792.00000	792.00	1362.00000	1362.00
0360 0440 1 30 UNDERDRAIN, TYPE III	284.000 LF	25.00000	7100.00	22.80000	6475.20	25.60000	7270.40
0365 0440 70 UNDERDRAIN INSPECTION BOX	2.000 EA	1000.00000	2000.00	1000.00000	2000.00	926.00000	1852.00
0370 0440 73 3 UNDERDRAIN OUTLET PIPE, 8"	3.000 LF	12.00000	36.00	15.00000	45.00	18.75000	56.25
0375 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM	71.000 LF	29.00000	2059.00	35.70000	2534.70	28.90000	2051.90
0380 0520 1 7 CONCRETE CURB & GUTTER, TYPE E	1283.000 LF	11.50000	14754.50	11.05000	14177.15	14.65000	18795.95
0385 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	10840.000 LF	11.00000	119240.00	10.50000	113820.00	8.15000	88346.00
0390 0520 2 4 CONCRETE CURB, TYPE D	180.000 LF	14.00000	2520.00	7.95000	1431.00	13.10000	2358.00
0395 0520 3 VALLEY GUTTER- CONCRETE	270.000 LF	15.00000	4050.00	17.95000	4846.50	14.95000	4036.50
0400 0520 5 16 TRAFFIC SEPARATOR CONCRETE- TYPE I, 8. 5' WIDE	234.000 LF	26.75000	6259.50	27.55000	6446.70	29.50000	6903.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0405 0520 5 41 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	506.000 LF	24.00000	12144.00	24.90000	12599.40	23.50000	11891.00
0410 0520 5 42 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	232.000 LF	27.00000	6264.00	33.90000	7864.80	28.50000	6612.00
0415 0520 5 46 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	1177.000 LF	30.00000	35310.00	36.00000	42372.00	33.50000	39429.50
0420 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL-VARIABLE WIDTH	8.000 SY	30.00000	240.00	29.65000	237.20	55.00000	440.00
0425 0522 1 SIDEWALK CONCRETE, 4" THICK	2142.000 SY	20.00000	42840.00	23.25000	49801.50	21.25000	45517.50
0430 0522 2 SIDEWALK CONCRETE, 6" THICK	980.000 SY	24.00000	23520.00	29.60000	29008.00	26.85000	26313.00
0435 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	98.000 SY	28.00000	2744.00	28.55000	2797.90	33.85000	3317.30
0440 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	38.300 TN	39.07000	1496.38	42.45000	1625.84	135.00000	5170.50
0445 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD	1035.000 LF	5.95000	6158.25	5.35000	5537.25	5.25000	5433.75
0450 0550 60124 FENCE GATE, TYPE A, DOUBLE, 18.1-20.0' OPENING	2.000 EA	485.00000	970.00	816.00000	1632.00	800.00000	1600.00
0455 0570 1 2 PERFORMANCE TURF, SOD	29602.000 SY	1.35000	39962.70	1.15000	34042.30	1.13000	33450.26
0460 0590 70 IRRIGATION SYSTEM 19756225201	LUMP	30000.00000	30000.00	3570.00000	3570.00	1870.00000	1870.00
0465 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	7.407 NM	810.33000	6002.11	826.00000	6118.18	1000.00000	7407.00
0470 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	263.000 LF	1.45000	381.35	1.50000	394.50	1.25000	328.75
0475 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	6.365 GM	335.26000	2133.93	342.00000	2176.83	350.00000	2227.75

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0480 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	806.000 LF	0.28000	225.68	0.30000	241.80	0.20000	161.20
0485 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	38.00000	1330.00	38.75000	1356.25	50.00000	1750.00
0490 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	86.000 EA	18.00000	1548.00	18.35000	1578.10	20.00000	1720.00
0495 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	5.363 NM	809.55000	4341.62	826.00000	4429.84	1000.00000	5363.00
0500 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	868.000 LF	0.28000	243.04	0.30000	260.40	0.20000	173.60
0505 0999 16 PARTNERING, DO NOT BID 19756225201	LUMP	5000.00000	5000.00	5000.00000	5000.00	5000.00000	5000.00
0510 0999 20 DISPUTES REVIEW BOARD, DO NOT BID	12.000 DA	3300.00000	39600.00	3300.00000	39600.00	3300.00000	39600.00
0515 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 3,766,110.84		$ 4,280,172.79		$ 4,352,643.71
SECTION 0002 SIGNING							
0520 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	26000.00000	26000.00	27075.00000	27075.00	25406.01000	25406.01
0525 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	37.000 AS	218.00000	8066.00	222.00000	8214.00	276.11000	10216.07
0530 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	7.000 AS	544.00000	3808.00	555.00000	3885.00	370.98000	2596.86
0535 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	2.000 AS	1265.00000	2530.00	1290.00000	2580.00	998.67000	1997.34
0540 0700 20 40 SINGLE POST SIGN, RELOCATE	10.000 AS	40.00000	400.00	40.80000	408.00	50.66000	506.60

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0545 0700 20 60 SINGLE POST SIGN, REMOVE	3.000 AS	1.00000	3.00	1.00000	3.00	16.89000	50.67
0550 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	3.000 AS	2480.00000	7440.00	2530.00000	7590.00	2982.38000	8947.14
0555 0700 46 15 SIGN EXISTING- REMOVE, SPAN WIRE	1.000 AS	2800.00000	2800.00	2855.00000	2855.00	1950.48000	1950.48
0560 0700 48 19 SIGN PANELS, F & I, 16 - 100	2.000 EA	590.00000	1180.00	696.00000	1392.00	480.40000	960.80
0565 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	15.000 EA	68.00000	1020.00	69.35000	1040.25	70.00000	1050.00
0570 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	903.000 EA	3.55000	3205.65	3.60000	3250.80	4.00000	3612.00
0575 0710 11190 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	76.000 SF	0.95000	72.20	0.95000	72.20	1.00000	76.00
0580 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	182.000 SF	0.95000	172.90	0.95000	172.90	1.00000	182.00
0585 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	2.837 NM	3700.85000	10499.31	3785.00000	10738.05	5000.00000	14185.00
0590 0711 11122 THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	4007.000 LF	1.05000	4207.35	1.05000	4207.35	1.50000	6010.50
0595 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	1131.000 LF	1.38000	1560.78	1.40000	1583.40	2.20000	2488.20
0600 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	1011.000 LF	2.65000	2679.15	2.70000	2729.70	3.00000	3033.00
0605 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	525.000 LF	3.65000	1916.25	3.70000	1942.50	4.00000	2100.00
0610 0711 11131 THERMOPLASTIC, STANDARD, WHITE, SKIP, 6	3.257 GM	1211.11000	3944.59	1235.00000	4022.40	1500.00000	4885.50
0615 0711 11151 THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	414.000 LF	0.98000	405.72	1.00000	414.00	1.00000	414.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0620 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	47.000 EA	186.00000	8742.00	190.00000	8930.00	170.00000	7990.00
0625 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	74.000 EA	52.00000	3848.00	53.05000	3925.70	65.00000	4810.00
0630 0711 11211 THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	2.103 NM	3704.71000	7791.01	3785.00000	7959.86	5000.00000	10515.00
0635 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	288.000 LF	2.65000	763.20	2.70000	777.60	1.00000	288.00
0640 0711 11251 THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	274.000 LF	0.98000	268.52	1.00000	274.00	1.00000	274.00
SECTION 0002 TOTALS		$	103,323.63	$	106,042.71	$	114,545.17
SECTION 0003 LIGHTING							
0645 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	320.000 LF	13.00000	4160.00	13.25000	4240.00	12.75000	4080.00
0650 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	25570.000 LF	1.00000	25570.00	1.10000	28127.00	1.03000	26337.10
0655 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	4880.000 LF	4.00000	19520.00	2.50000	12200.00	3.35000	16348.00
0660 0715 4033 LIGHT POLE COMPLETE,F&I, SPECIAL FOUNDATION,WIND SPEED 110, POLE HEIGHT 50'	19.000 EA	4100.00000	77900.00	3970.00000	75430.00	4310.00000	81890.00
0665 0715 4133 LIGHT POLE COMPLETE, F&I, WIND SPEED 110, POLE HEIGHT 50'	29.000 EA	3400.00000	98600.00	3165.00000	91785.00	3630.00000	105270.00
0670 0715 4600 LIGHT POLE COMPLETE, REMOVE	27.000 EA	200.00000	5400.00	259.00000	6993.00	203.00000	5481.00
0675 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	12000.00000	12000.00	15255.00000	15255.00	16815.00000	16815.00
0680 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	57.000 EA	350.00000	19950.00	265.00000	15105.00	369.00000	21033.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0685 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	48.000 EA	250.00000	12000.00	317.00000	15216.00	300.00000	14400.00
SECTION 0003 TOTALS		$	275,100.00	$	264,351.00	$	291,654.10
SECTION 0004 SIGNALIZATION							
0690 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	400.000 LF	12.62000	5048.00	17.80000	7120.00	13.55000	5420.00
0695 0555 1 3 DIRECTIONAL BORE, 12" TO < 18"	170.000 LF	21.74000	3695.80	25.70000	4369.00	27.45000	4666.50
0700 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	300.000 LF	4.23000	1269.00	3.10000	930.00	3.95000	1185.00
0705 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	1.000 PI	4999.00000	4999.00	3320.00000	3320.00	5158.00000	5158.00
0710 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	23.000 EA	221.00000	5083.00	239.00000	5497.00	308.00000	7084.00
0715 0639 1 22 SIGNALS,ELECTRICAL POWER SERVICE, UNDERGROUND, PURCHASED BYCONTRACTOR FROM POWER COMPANY	1.000 AS	765.00000	765.00	934.00000	934.00	956.00000	956.00
0720 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	60.000 LF	0.85000	51.00	2.70000	162.00	2.07000	124.20
0725 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1.000 EA	709.00000	709.00	714.00000	714.00	726.00000	726.00
0730 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	24886.00000	49772.00	24565.00000	49130.00	24260.00000	48520.00
0735 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	23429.00000	23429.00	23475.00000	23475.00	22755.00000	22755.00
0740 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	11.000 AS	637.00000	7007.00	657.00000	7227.00	630.00000	6930.00
0745 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	2.000 AS	1100.00000	2200.00	1020.00000	2040.00	1091.00000	2182.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0750 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	6.000 AS	553.00000	3318.00	650.00000	3900.00	503.00000	3018.00
0755 0659101 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES 3 SECT	11.000 EA	126.00000	1386.00	135.00000	1485.00	103.00000	1133.00
0760 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	6.000 EA	712.00000	4272.00	781.00000	4686.00	727.00000	4362.00
0765 0659118 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES, 5 SECT CLUSTER	2.000 EA	129.00000	258.00	194.00000	388.00	150.00000	300.00
0770 0660 2102 LOOP ASSEMBLY, F&I, TYPE B	4.000 AS	460.00000	1840.00	414.00000	1656.00	642.00000	2568.00
0775 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	5.000 AS	662.00000	3310.00	603.00000	3015.00	662.00000	3310.00
0780 0663 74 14 VEHICLE DETECTOR ASSEMBLIES, F&I, EMERGENCY PRE-EMPTION	3.000 EA	1426.00000	4278.00	2000.00000	6000.00	1509.00000	4527.00
0785 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	4.000 EA	3904.00000	15616.00	5975.00000	23900.00	2229.00000	8916.00
0790 0665 13 PEDESTRIAN DETECTOR, F&I, DETECTOR WITH SIGN ONLY	6.000 EA	111.00000	666.00	135.00000	810.00	159.00000	954.00
0795 0670 5111 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.000 AS	15816.00000	15816.00	20300.00000	20300.00	16389.00000	16389.00
0800 0685106 SYSTEM AUXILIARIES, F&I, UNINTERRUPTIBLE POWER SOURCE	1.000 EA	5566.00000	5566.00	5915.00000	5915.00	5711.00000	5711.00
0805 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	11.000 EA	88.00000	968.00	38.75000	426.25	33.80000	371.80
0810 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	4.000 EA	88.00000	352.00	38.75000	155.00	16.90000	67.60
0815 0690 31 SIGNAL PEDESTAL REMOVAL	4.000 EA	168.00000	672.00	76.50000	306.00	152.00000	608.00
0820 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	2.000 EA	1510.00000	3020.00	1210.00000	2420.00	1775.00000	3550.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0825 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	431.00000	431.00	76.50000	76.50	304.00000	304.00
0830 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	4.000 EA	42.00000	168.00	38.75000	155.00	16.90000	67.60
0835 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	264.00000	264.00	153.00000	153.00	304.00000	304.00
0840 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	176.00000	176.00	153.00000	153.00	405.00000	405.00
0845 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	264.00000	264.00	153.00000	153.00	811.00000	811.00
0850 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	3.000 EA	3077.00000	9231.00	2500.00000	7500.00	2651.00000	7953.00
0855 0782 1 40 ITS CCTV CAMERA, RELOCATE	1.000 EA	3600.00000	3600.00	2360.00000	2360.00	3718.00000	3718.00
0860 0783 1422 ITS FIBER OPTIC CABLE, RELOCATE, UNDERGROUND, 13 -48 FIBERS	305.000 LF	2.50000	762.50	2.50000	762.50	2.45000	747.25
0865 0783 2 31 ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	4.000 EA	140.00000	560.00	75.50000	302.00	143.00000	572.00
0870 0783 3 45 ITS FIBER OPTIC CONNECTION HARDWARE, REL, PATCH PANEL, PRETERMINATED	1.000 EA	250.00000	250.00	576.00000	576.00	257.00000	257.00
0875 0783 4111 ITS CONDUIT, F& I, ABOVEGROUND	30.000 LF	15.00000	450.00	17.15000	514.50	13.90000	417.00
0880 0783 4112 ITS CONDUIT, F& I, UNDERGROUND	85.000 LF	6.00000	510.00	3.50000	297.50	4.55000	386.75
0885 0783 5 1 ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	1.000 EA	1300.00000	1300.00	592.00000	592.00	1023.00000	1023.00
0890 0784 1 4 ITS MANAGED FIELD ETHERNET SWITCH, RELOCATE	1.000 EA	300.00000	300.00	610.00000	610.00	286.00000	286.00
0895 0784 3 40 ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, RELOCATE	1.000 EA	250.00000	250.00	694.00000	694.00	229.00000	229.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(2) BETTER ROADS, INC. UNIT PRICE	 AMOUNT	(3) LANE CONSTRUCTION CORPORATION (UNIT PRICE	 AMOUNT
0900 0785 1 13 ITS POLE, F&I, CONCRETE WITHOUT LOWERING DEVICE	1.000 EA	12000.00000	12000.00	7225.00000	7225.00	5627.00000	5627.00
0905 0785 1 60 ITS POLE, REMOVE	1.000 EA	1500.00000	1500.00	949.00000	949.00	1055.00000	1055.00
SECTION 0004 TOTALS		$	197,382.30	$	203,353.25	$	185,654.70
CONTRACT TOTALS		$	4,341,916.77	$	4,853,919.75	$	4,944,497.68

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 19756225201	LUMP	306150.00000	306150.00	404500.00000	404500.00	445000.00000	445000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 19756225201	360.000 LS	226000.00000	226000.00	268264.00000	268264.00	125000.00000	125000.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	500.000 CY	25.00000	12500.00	12.00000	6000.00	15.00000	7500.00
0020 0102 14 TRAFFIC CONTROL OFFICER	56.000 MH	40.00000	2240.00	47.00000	2632.00	45.00000	2520.00
0025 0102 60 WORK ZONE SIGN	23850.000 ED	0.33000	7870.50	0.01000	238.50	0.24000	5724.00
0030 0102 61 BUSINESS SIGN	16.000 EA	61.00000	976.00	88.00000	1408.00	68.00000	1088.00
0035 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	121044.000 ED	0.14000	16946.16	0.01000	1210.44	0.18000	21787.92
0040 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	6234.000 ED	0.30000	1870.20	0.20000	1246.80	0.32000	1994.88
0045 0102 76 ADVANCE WARNING ARROW PANEL	1008.000 ED	7.30000	7358.40	5.00000	5040.00	5.00000	5040.00
0050 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	7200.000 ED	0.20000	1440.00	0.30000	2160.00	0.32000	2304.00
0055 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	2174.000 EA	3.76000	8174.24	2.85000	6195.90	2.55000	5543.70
0060 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	618.000 ED	17.60000	10876.80	13.00000	8034.00	15.00000	9270.00
0065 0102104 2 TEMPORARY TRAFFIC CONTROL, FIXED SIGNAL	247.000 ED	16.00000	3952.00	14.79000	3653.13	14.79000	3653.13
0070 0102107 TEMPORARY TRAFFIC DETECTION, INTERSECT	247.000 DA	9.08000	2242.76	8.40000	2074.80	8.40000	2074.80
0075 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	300.000 SY	1.75000	525.00	2.85000	855.00	1.50000	450.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0080 0104 10 3 SEDIMENT BARRIER	10966.000 LF	0.80000	8772.80	0.47000	5154.02	0.75000	8224.50
0085 0104 11 FLOATING TURBIDITY BARRIER	58.000 LF	9.66000	560.28	7.00000	406.00	7.00000	406.00
0090 0104 15 SOIL TRACKING PREVENTION DEVICE	3.000 EA	1620.00000	4860.00	500.00000	1500.00	500.00000	1500.00
0095 0104 18 INLET PROTECTION SYSTEM	62.000 EA	70.15000	4349.30	55.67000	3451.54	55.00000	3410.00
0100 0107 1 LITTER REMOVAL	55.600 AC	29.35000	1631.86	19.03000	1058.07	20.00000	1112.00
0105 0107 2 MOWING	55.600 AC	88.00000	4892.80	19.03000	1058.07	35.00000	1946.00
0110 0110 1 1 CLEARING & GRUBBING 19756225201	17.410 LS	75000.00000	75000.00	122667.00000	122667.00	319500.00000	319500.00
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	4022.000 SY	5.35000	21517.70	8.97000	36077.34	6.50000	26143.00
0120 0110 7 1 MAILBOX, F&I SINGLE	7.000 EA	190.00000	1330.00	255.00000	1785.00	125.00000	875.00
0125 0120 1 REGULAR EXCAVATION	23045.000 CY	4.75000	109463.75	6.92000	159471.40	3.93000	90566.85
0130 0120 4 SUBSOIL EXCAVATION	3518.000 CY	18.75000	65962.50	6.85000	24098.30	15.00000	52770.00
0135 0120 6 EMBANKMENT	9875.000 CY	3.00000	29625.00	2.30000	22712.50	9.82000	96972.50
0140 0145 2 GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	1300.000 SY	5.20000	6760.00	4.30000	5590.00	6.00000	7800.00
0145 0160 4 TYPE B STABILIZATION	50449.000 SY	3.70000	186661.30	0.86000	43386.14	3.80000	191706.20
0150 0285701 OPTIONAL BASE, BASE GROUP 01	79.000 SY	51.20000	4044.80	11.44000	903.76	11.00000	869.00
0155 0285712 OPTIONAL BASE, BASE GROUP 12	45556.000 SY	14.75000	671951.00	14.54000	662384.24	14.10000	642339.60
0160 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	11235.000 SY	2.75000	30896.25	1.55000	17414.25	1.55000	17414.25
0165 0327 70 19 MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	970.000 SY	5.25000	5092.50	1.55000	1503.50	1.55000	1503.50

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0170 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5143.700 TN	76.10000	391435.57	80.00000	411496.00	80.00000	411496.00
0175 0334 1 24 SUPERPAVE ASPH CONC, TRAF D, PG76-22	3763.600 TN	87.50000	329315.00	97.00000	365069.20	97.00000	365069.20
0180 0337 7 22 ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	39.000 TN	169.00000	6591.00	200.00000	7800.00	200.00000	7800.00
0185 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	4690.500 TN	88.35000	414405.68	93.60000	439030.80	93.60000	439030.80
0190 0400 0 11 CONCRETE CLASS NS, GRAVITY WALL	7.200 CY	800.00000	5760.00	1066.00000	7675.20	400.00000	2880.00
0195 0425 1311 INLETS, CURB, TYPE P-1, <10'	1.000 EA	3658.00000	3658.00	3505.00000	3505.00	3900.00000	3900.00
0200 0425 1315 INLETS, CURB TYPE P-1, PARTIAL	1.000 EA	1100.00000	1100.00	2888.00000	2888.00	2500.00000	2500.00
0205 0425 1351 INLETS, CURB, TYPE P-5, <10'	24.000 EA	2685.00000	64440.00	2430.00000	58320.00	2400.00000	57600.00
0210 0425 1481 INLETS, CURB, TYPE 8, <10'	22.000 EA	2950.00000	64900.00	4211.00000	92642.00	3700.00000	81400.00
0215 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	1920.00000	1920.00	2190.00000	2190.00	1400.00000	1400.00
0220 0425 1531 INLETS, DT BOT, TYPE C, MODIFIED, <10''	4.000 EA	1745.00000	6980.00	2036.00000	8144.00	1600.00000	6400.00
0225 0425 1541 INLETS, DT BOT, TYPE D, <10'	6.000 EA	2275.00000	13650.00	2253.00000	13518.00	1950.00000	11700.00
0230 0425 1549 INLETS, DT BOT, TYPE D, MODIFY	1.000 EA	2180.00000	2180.00	5007.00000	5007.00	3300.00000	3300.00
0235 0425 1551 INLETS, DT BOT, TYPE E, <10'	1.000 EA	3965.00000	3965.00	2905.00000	2905.00	4300.00000	4300.00
0240 0425 1561 INLETS, DT BOT, TYPE F, <10'	1.000 EA	2370.00000	2370.00	1989.00000	1989.00	2200.00000	2200.00
0245 0425 1702 INLETS, GUTTER, TYPE S, >10'	1.000 EA	4615.00000	4615.00	5944.00000	5944.00	3900.00000	3900.00
0250 0425 2 61 MANHOLES, P-8, <10'	4.000 EA	2075.00000	8300.00	2403.00000	9612.00	1600.00000	6400.00
0255 0425 2 91 MANHOLES, J-8, <10'	7.000 EA	3715.00000	26005.00	4298.00000	30086.00	3300.00000	23100.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0260 0425 2 92 MANHOLES, J-8, >10'	6.000 EA	4675.00000	28050.00	6018.00000	36108.00	5000.00000	30000.00
0265 0425 3 41 JUNCTION BOX, DRAINAGE, P-7, <10'	1.000 EA	3000.00000	3000.00	2017.00000	2017.00	1950.00000	1950.00
0270 0425 3 43 JUNCTION BOX, DRAINAGE, P-7, PARTIAL	1.000 EA	1280.00000	1280.00	1639.00000	1639.00	1500.00000	1500.00
0275 0425 10 YARD DRAIN	2.000 EA	980.00000	1960.00	1562.00000	3124.00	1200.00000	2400.00
0280 0430 94 1 DESILTING PIPE, 0 - 24"	226.000 LF	2.15000	485.90	5.59000	1263.34	3.00000	678.00
0285 0430 94 2 DESILTING PIPE, 25 - 36"	354.000 LF	3.50000	1239.00	8.04000	2846.16	6.00000	2124.00
0290 0430 94 3 DESILTING PIPE, 37 - 48"	1385.000 LF	4.85000	6717.25	8.64000	11966.40	8.50000	11772.50
0295 0430 94 4 DESILTING PIPE, 49 - 60"	159.000 LF	6.20000	985.80	12.48000	1984.32	17.00000	2703.00
0300 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	22.000 LF	47.10000	1036.20	33.15000	729.30	150.00000	3300.00
0305 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	3295.000 LF	42.25000	139213.75	35.86000	118158.70	30.00000	98850.00
0310 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	3289.000 LF	49.50000	162805.50	35.59000	117055.51	40.00000	131560.00
0315 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	60.000 LF	61.10000	3666.00	49.65000	2979.00	53.00000	3180.00
0320 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	1074.000 LF	76.50000	82161.00	59.66000	64074.84	64.00000	68736.00
0325 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	294.000 LF	123.00000	36162.00	80.31000	23611.14	88.00000	25872.00
0330 0430175154 PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	828.000 LF	160.00000	132480.00	140.04000	115953.12	140.00000	115920.00
0335 0430175248 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	70.000 LF	155.00000	10850.00	2009.68000	140677.60	127.00000	8890.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0340 0430982129 2.000 EA MITERED END SECTION, OPTIONAL ROUND, 24" CD	1200.00000	2400.00	856.00000	1712.00	1100.00000	2200.00
0345 0430982138 1.000 EA MITERED END SECTION, OPTIONAL ROUND, 36" CD	2030.00000	2030.00	2400.00000	2400.00	1650.00000	1650.00
0350 0430984133 1.000 EA MITERED END SECTION , OPTIONAL ROUND, 30" SD	2470.00000	2470.00	2366.00000	2366.00	2000.00000	2000.00
0355 0430990 1.000 EA MITERED END SECT, REPLACE GRATE	2405.00000	2405.00	1074.00000	1074.00	800.00000	800.00
0360 0440 1 30 284.000 LF UNDERDRAIN, TYPE III	31.25000	8875.00	30.99000	8801.16	18.00000	5112.00
0365 0440 70 2.000 EA UNDERDRAIN INSPECTION BOX	945.00000	1890.00	1052.00000	2104.00	850.00000	1700.00
0370 0440 73 3 3.000 LF UNDERDRAIN OUTLET PIPE, 8"	76.15000	228.45	30.05000	90.15	25.00000	75.00
0375 0515 1 2 71.000 LF PIPE HANDRAIL - GUIDERAIL, ALUMINUM	23.75000	1686.25	21.00000	1491.00	30.00000	2130.00
0380 0520 1 7 1283.000 LF CONCRETE CURB & GUTTER, TYPE E	9.80000	12573.40	9.59000	12303.97	8.50000	10905.50
0385 0520 1 10 10840.000 LF CONCRETE CURB & GUTTER, TYPE F	9.95000	107858.00	9.39000	101787.60	8.00000	86720.00
0390 0520 2 4 180.000 LF CONCRETE CURB, TYPE D	14.45000	2601.00	14.09000	2536.20	7.50000	1350.00
0395 0520 3 270.000 LF VALLEY GUTTER- CONCRETE	16.55000	4468.50	20.34000	5491.80	15.00000	4050.00
0400 0520 5 16 234.000 LF TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	49.00000	11466.00	44.97000	10522.98	26.00000	6084.00
0405 0520 5 41 506.000 LF TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	25.00000	12650.00	29.67000	15013.02	23.50000	11891.00
0410 0520 5 42 232.000 LF TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	35.00000	8120.00	43.32000	10050.24	32.00000	7424.00
0415 0520 5 46 1177.000 LF TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	49.00000	57673.00	43.04000	50658.08	34.00000	40018.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0420 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL-VARIABLE WIDTH	8.000 SY	65.00000	520.00	72.45000	579.60	28.00000	224.00
0425 0522 1 SIDEWALK CONCRETE, 4" THICK	2142.000 SY	27.50000	58905.00	23.66000	50679.72	20.00000	42840.00
0430 0522 2 SIDEWALK CONCRETE, 6" THICK	980.000 SY	40.00000	39200.00	28.29000	27724.20	24.00000	23520.00
0435 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	98.000 SY	48.00000	4704.00	42.39000	4154.22	25.00000	2450.00
0440 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	38.300 TN	123.00000	4710.90	119.41000	4573.40	95.00000	3638.50
0445 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD	1035.000 LF	6.45000	6675.75	5.25000	5433.75	6.00000	6210.00
0450 0550 60124 FENCE GATE, TYPE A, DOUBLE, 18.1-20.0' OPENING	2.000 EA	525.00000	1050.00	800.00000	1600.00	600.00000	1200.00
0455 0570 1 2 PERFORMANCE TURF, SOD	29602.000 SY	2.25000	66604.50	1.38000	40850.76	2.00000	59204.00
0460 0590 70 IRRIGATION SYSTEM 19756225201	LUMP	3540.00000	3540.00	6407.00000	6407.00	5600.00000	5600.00
0465 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	7.407 NM	875.00000	6481.13	975.00000	7221.83	810.00000	5999.67
0470 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	263.000 LF	1.15000	302.45	1.75000	460.25	1.45000	381.35
0475 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	6.365 GM	425.00000	2705.13	550.00000	3500.75	335.00000	2132.28
0480 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	806.000 LF	0.30000	241.80	0.45000	362.70	0.28000	225.68
0485 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	42.00000	1470.00	40.00000	1400.00	38.00000	1330.00
0490 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	86.000 EA	30.00000	2580.00	30.00000	2580.00	18.00000	1548.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0495 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	5.363 NM	855.00000	4585.37	975.00000	5228.93	810.00000	4344.03
0500 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	868.000 LF	0.30000	260.40	0.45000	390.60	0.28000	243.04
0505 0999 16 PARTNERING, DO NOT BID 19756225201	LUMP	5000.00000	5000.00	5000.00000	5000.00	5000.00000	5000.00
0510 0999 20 DISPUTES REVIEW BOARD, DO NOT BID	12.000 DA	3300.00000	39600.00	3300.00000	39600.00	3300.00000	39600.00
0515 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 4,344,707.58		$ 4,422,292.24		$ 4,487,620.38
SECTION 0002 SIGNING							
0520 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	27415.00000	27415.00	25406.00000	25406.00	25406.00000	25406.00
0525 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	37.000 AS	298.00000	11026.00	276.11000	10216.07	276.00000	10212.00
0530 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	7.000 AS	401.00000	2807.00	370.98000	2596.86	371.00000	2597.00
0535 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	2.000 AS	1080.00000	2160.00	998.67000	1997.34	998.00000	1996.00
0540 0700 20 40 SINGLE POST SIGN, RELOCATE	10.000 AS	55.00000	550.00	50.66000	506.60	51.00000	510.00
0545 0700 20 60 SINGLE POST SIGN, REMOVE	3.000 AS	18.25000	54.75	16.89000	50.67	17.00000	51.00
0550 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	3.000 AS	3220.00000	9660.00	2982.38000	8947.14	2982.00000	8946.00
0555 0700 46 15 SIGN EXISTING- REMOVE, SPAN WIRE	1.000 AS	2105.00000	2105.00	1950.48000	1950.48	1950.00000	1950.00
0560 0700 48 19 SIGN PANELS, F & I, 16 - 100	2.000 EA	520.00000	1040.00	480.40000	960.80	480.00000	960.00
0565 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	15.000 EA	35.00000	525.00	47.49000	712.35	47.00000	705.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0570 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	903.000 EA	3.75000	3386.25	3.00000	2709.00	3.55000	3205.65
0575 0710 11190 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	76.000 SF	0.70000	53.20	1.50000	114.00	0.95000	72.20
0580 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	182.000 SF	0.70000	127.40	1.50000	273.00	0.95000	172.90
0585 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	2.837 NM	4560.00000	12936.72	3148.95000	8933.57	9710.00000	27547.27
0590 0711 11122 THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	4007.000 LF	1.50000	6010.50	1.35000	5409.45	1.05000	4207.35
0595 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	1131.000 LF	2.25000	2544.75	1.99000	2250.69	1.38000	1560.78
0600 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	1011.000 LF	3.36000	3396.96	2.99000	3022.89	2.65000	2679.15
0605 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	525.000 LF	4.50000	2362.50	3.99000	2094.75	3.65000	1916.25
0610 0711 11131 THERMOPLASTIC, STANDARD, WHITE, SKIP, 6	3.257 GM	1460.00000	4755.22	787.23000	2564.01	1210.00000	3940.97
0615 0711 11151 THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	414.000 LF	1.26000	521.64	1.01000	418.14	0.98000	405.72
0620 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	47.000 EA	226.00000	10622.00	34.40000	1616.80	186.00000	8742.00
0625 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	74.000 EA	61.00000	4514.00	34.63000	2562.62	52.00000	3848.00
0630 0711 11211 THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	2.103 NM	4560.00000	9589.68	3074.05000	6464.73	3710.00000	7802.13
0635 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	288.000 LF	3.36000	967.68	2.92000	840.96	2.65000	763.20

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0640 0711 11251 THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	274.000 LF	1.26000	345.24	0.99000	271.26	0.98000	268.52
SECTION 0002 TOTALS		$	119,476.49	$	92,890.18	$	120,465.09
SECTION 0003 LIGHTING							
0645 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	320.000 LF	13.75000	4400.00	12.73000	4073.60	12.73000	4073.60
0650 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	25570.000 LF	1.12000	28638.40	1.03000	26337.10	1.03000	26337.10
0655 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	4880.000 LF	3.60000	17568.00	3.34000	16299.20	3.34000	16299.20
0660 0715 4033 LIGHT POLE COMPLETE,F&I, SPECIAL FOUNDATION,WIND SPEED 110, POLE HEIGHT 50'	19.000 EA	4650.00000	88350.00	4309.50000	81880.50	4310.00000	81890.00
0665 0715 4133 LIGHT POLE COMPLETE, F&I, WIND SPEED 110, POLE HEIGHT 50'	29.000 EA	3920.00000	113680.00	3629.02000	105241.58	3629.00000	105241.00
0670 0715 4600 LIGHT POLE COMPLETE, REMOVE	27.000 EA	219.00000	5913.00	202.65000	5471.55	203.00000	5481.00
0675 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	18150.00000	18150.00	16816.86000	16816.86	16816.00000	16816.00
0680 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	57.000 EA	400.00000	22800.00	368.41000	20999.37	368.00000	20976.00
0685 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	48.000 EA	325.00000	15600.00	300.16000	14407.68	300.00000	14400.00
SECTION 0003 TOTALS		$	315,099.40	$	291,527.44	$	291,513.90
SECTION 0004 SIGNALIZATION							
0690 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	400.000 LF	14.65000	5860.00	13.56000	5424.00	13.56000	5424.00
0695 0555 1 3 DIRECTIONAL BORE, 12" TO < 18"	170.000 LF	29.65000	5040.50	27.46000	4668.20	27.46000	4668.20

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0700 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	300.000 LF	4.25000	1275.00	3.93000	1179.00	4.00000	1200.00
0705 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	1.000 PI	5565.00000	5565.00	5158.03000	5158.03	5158.00000	5158.00
0710 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	23.000 EA	333.00000	7659.00	307.97000	7083.31	308.00000	7084.00
0715 0639 1 22 SIGNALS,ELECTRICAL POWER SERVICE, UNDERGROUND, PURCHASED BYCONTRACTOR FROM POWER COMPANY	1.000 AS	1031.00000	1031.00	956.22000	956.22	956.00000	956.00
0720 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	60.000 LF	2.25000	135.00	2.07000	124.20	2.07000	124.20
0725 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1.000 EA	783.00000	783.00	726.13000	726.13	726.00000	726.00
0730 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	26180.00000	52360.00	24261.01000	48522.02	24216.00000	48432.00
0735 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	24555.00000	24555.00	22752.93000	22752.93	22753.00000	22753.00
0740 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	11.000 AS	680.00000	7480.00	630.43000	6934.73	630.00000	6930.00
0745 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	2.000 AS	1177.00000	2354.00	1090.74000	2181.48	1091.00000	2182.00
0750 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	6.000 AS	542.00000	3252.00	502.88000	3017.28	503.00000	3018.00
0755 0659101 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES 3 SECT	11.000 EA	110.00000	1210.00	102.59000	1128.49	103.00000	1133.00
0760 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	6.000 EA	785.00000	4710.00	726.85000	4361.10	727.00000	4362.00
0765 0659118 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES, 5 SECT CLUSTER	2.000 EA	162.00000	324.00	150.08000	300.16	150.00000	300.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0770 0660 2102 LOOP ASSEMBLY, F&I, TYPE B	4.000 AS	693.00000	2772.00	642.51000	2570.04	642.00000	2568.00
0775 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	5.000 AS	715.00000	3575.00	662.40000	3312.00	662.00000	3310.00
0780 0663 74 14 VEHICLE DETECTOR ASSEMBLIES, F&I, EMERGENCY PRE-EMPTION	3.000 EA	1628.00000	4884.00	1508.75000	4526.25	1509.00000	4527.00
0785 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	4.000 EA	2405.00000	9620.00	2228.80000	8915.20	2229.00000	8916.00
0790 0665 13 PEDESTRIAN DETECTOR, F&I, DETECTOR WITH SIGN ONLY	6.000 EA	172.00000	1032.00	159.37000	956.22	159.00000	954.00
0795 0670 5111 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.000 AS	17685.00000	17685.00	16388.92000	16388.92	16389.00000	16389.00
0800 0685106 SYSTEM AUXILIARIES, F&I, UNINTERRUPTIBLE POWER SOURCE	1.000 EA	6163.00000	6163.00	5711.81000	5711.81	5712.00000	5712.00
0805 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	11.000 EA	36.45000	400.95	33.78000	371.58	34.00000	374.00
0810 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	4.000 EA	18.25000	73.00	16.89000	67.56	17.00000	68.00
0815 0690 31 SIGNAL PEDESTAL REMOVAL	4.000 EA	164.00000	656.00	151.99000	607.96	152.00000	608.00
0820 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	2.000 EA	1915.00000	3830.00	1775.33000	3550.66	1776.00000	3552.00
0825 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	328.00000	328.00	303.98000	303.98	304.00000	304.00
0830 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	4.000 EA	18.25000	73.00	16.89000	67.56	17.00000	68.00
0835 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	328.00000	328.00	303.98000	303.98	304.00000	304.00
0840 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	438.00000	438.00	405.31000	405.31	405.00000	405.00
0845 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	875.00000	875.00	810.62000	810.62	811.00000	811.00
0850 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	3.000 EA	2860.00000	8580.00	2651.21000	7953.63	2651.00000	7953.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) PURCELL, R.E. CONSTRUCTION UNIT PRICE	 AMOUNT	(5) RUSSELL ENGINEERING, INC. UNIT PRICE	 AMOUNT	(6) CONE & GRAHAM, INC. UNIT PRICE	 AMOUNT
0855 0782 1 40 ITS CCTV CAMERA, RELOCATE	1.000 EA	4012.00000	4012.00	3718.54000	3718.54	3719.00000	3719.00
0860 0783 1422 ITS FIBER OPTIC CABLE, RELOCATE, UNDERGROUND, 13 -48 FIBERS	305.000 LF	2.65000	808.25	2.46000	750.30	2.46000	750.30
0865 0783 2 31 ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	4.000 EA	154.00000	616.00	143.02000	572.08	143.00000	572.00
0870 0783 3 45 ITS FIBER OPTIC CONNECTION HARDWARE, REL, PATCH PANEL, PRETERMINATED	1.000 EA	288.00000	288.00	257.44000	257.44	257.00000	257.00
0875 0783 4111 ITS CONDUIT, F& I, ABOVEGROUND	30.000 LF	15.00000	450.00	13.91000	417.30	14.00000	420.00
0880 0783 4112 ITS CONDUIT, F& I, UNDERGROUND	85.000 LF	4.90000	416.50	4.54000	385.90	4.54000	385.90
0885 0783 5 1 ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	1.000 EA	1104.00000	1104.00	1023.56000	1023.56	1024.00000	1024.00
0890 0784 1 4 ITS MANAGED FIELD ETHERNET SWITCH, RELOCATE	1.000 EA	308.00000	308.00	286.04000	286.04	286.00000	286.00
0895 0784 3 40 ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, RELOCATE	1.000 EA	247.00000	247.00	228.83000	228.83	229.00000	229.00
0900 0785 1 13 ITS POLE, F&I, CONCRETE WITHOUT LOWERING DEVICE	1.000 EA	6075.00000	6075.00	5627.53000	5627.53	5628.00000	5628.00
0905 0785 1 60 ITS POLE, REMOVE	1.000 EA	1136.00000	1136.00	1053.02000	1053.02	1053.00000	1053.00
SECTION 0004 TOTALS		$	200,367.20	$	185,661.10	$	185,597.60
CONTRACT TOTALS		$	4,979,650.67	$	4,992,370.96	$	5,085,196.97

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 19756225201	LUMP	408753.30000	408753.30	490159.90000	490159.90	425000.00000	425000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 19756225201	360.000 LS	178000.00000	178000.00	145000.00000	145000.00	380083.20000	380083.20
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	500.000 CY	18.80000	9400.00	15.00000	7500.00	8.00000	4000.00
0020 0102 14 TRAFFIC CONTROL OFFICER	56.000 MH	42.30000	2368.80	50.00000	2800.00	45.00000	2520.00
0025 0102 60 WORK ZONE SIGN	23850.000 ED	0.21000	5008.50	0.33000	7870.50	0.19000	4531.50
0030 0102 61 BUSINESS SIGN	16.000 EA	42.00000	672.00	61.66000	986.56	88.00000	1408.00
0035 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	121044.000 ED	0.12000	14525.28	0.14000	16946.16	0.10000	12104.40
0040 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	6234.000 ED	0.32000	1994.88	0.31000	1932.54	0.20000	1246.80
0045 0102 76 ADVANCE WARNING ARROW PANEL	1008.000 ED	5.23000	5271.84	7.40000	7459.20	5.00000	5040.00
0050 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	7200.000 ED	0.32000	2304.00	0.18000	1296.00	0.30000	2160.00
0055 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	2174.000 EA	3.20000	6956.80	3.51000	7630.74	3.00000	6522.00
0060 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	618.000 ED	15.70000	9702.60	17.88000	11049.84	13.00000	8034.00
0065 0102104 2 TEMPORARY TRAFFIC CONTROL, FIXED SIGNAL	247.000 ED	20.10000	4964.70	14.79000	3653.13	60.00000	14820.00
0070 0102107 TEMPORARY TRAFFIC DETECTION, INTERSECT	247.000 DA	4.20000	1037.40	8.40000	2074.80	40.00000	9880.00
0075 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	300.000 SY	1.30000	390.00	3.36000	1008.00	2.00000	600.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0080 0104 10 3 SEDIMENT BARRIER	10966.000 LF	0.50000	5483.00	1.80000	19738.80	1.00000	10966.00
0085 0104 11 FLOATING TURBIDITY BARRIER	58.000 LF	7.00000	406.00	6.75000	391.50	15.00000	870.00
0090 0104 15 SOIL TRACKING PREVENTION DEVICE	3.000 EA	1300.00000	3900.00	2652.41000	7957.23	850.00000	2550.00
0095 0104 18 INLET PROTECTION SYSTEM	62.000 EA	63.00000	3906.00	250.00000	15500.00	100.00000	6200.00
0100 0107 1 LITTER REMOVAL	55.600 AC	20.00000	1112.00	93.99000	5225.84	5.00000	278.00
0105 0107 2 MOWING	55.600 AC	42.00000	2335.20	100.00000	5560.00	30.00000	1668.00
0110 0110 1 1 CLEARING & GRUBBING 19756225201	17.410 LS	154000.00000	154000.00	152890.77000	152890.77	290000.00000	290000.00
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	4022.000 SY	8.00000	32176.00	2.99000	12025.78	7.00000	28154.00
0120 0110 7 1 MAILBOX, F&I SINGLE	7.000 EA	90.00000	630.00	397.60000	2783.20	140.00000	980.00
0125 0120 1 REGULAR EXCAVATION	23045.000 CY	2.65000	61069.25	4.66000	107389.70	5.00000	115225.00
0130 0120 4 SUBSOIL EXCAVATION	3518.000 CY	5.70000	20052.60	10.90000	38346.20	3.00000	10554.00
0135 0120 6 EMBANKMENT	9875.000 CY	6.90000	68137.50	13.00000	128375.00	5.00000	49375.00
0140 0145 2 GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	1300.000 SY	3.80000	4940.00	4.00000	5200.00	5.00000	6500.00
0145 0160 4 TYPE B STABILIZATION	50449.000 SY	2.86000	144284.14	3.00000	151347.00	2.25000	113510.25
0150 0285701 OPTIONAL BASE, BASE GROUP 01	79.000 SY	14.30000	1129.70	16.00000	1264.00	13.00000	1027.00
0155 0285712 OPTIONAL BASE, BASE GROUP 12	45556.000 SY	16.05000	731173.80	15.00000	683340.00	15.00000	683340.00
0160 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	11235.000 SY	2.60000	29211.00	1.55000	17414.25	2.50000	28087.50
0165 0327 70 19 MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	970.000 SY	2.60000	2522.00	1.55000	1503.50	2.50000	2425.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0170 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5143.700 TN	92.50000	475792.25	80.00000	411496.00	88.00000	452645.60
0175 0334 1 24 SUPERPAVE ASPH CONC, TRAF D, PG76-22	3763.600 TN	109.00000	410232.40	97.00000	365069.20	103.00000	387650.80
0180 0337 7 22 ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	39.000 TN	218.00000	8502.00	200.00000	7800.00	207.00000	8073.00
0185 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	4690.500 TN	108.00000	506574.00	90.00000	422145.00	102.00000	478431.00
0190 0400 0 11 CONCRETE CLASS NS, GRAVITY WALL	7.200 CY	685.00000	4932.00	1000.00000	7200.00	425.00000	3060.00
0195 0425 1311 INLETS, CURB, TYPE P-1, <10'	1.000 EA	3130.00000	3130.00	3000.00000	3000.00	3400.00000	3400.00
0200 0425 1315 INLETS, CURB TYPE P-1, PARTIAL	1.000 EA	2450.00000	2450.00	2000.00000	2000.00	1000.00000	1000.00
0205 0425 1351 INLETS, CURB, TYPE P-5, <10'	24.000 EA	2900.00000	69600.00	4000.00000	96000.00	2600.00000	62400.00
0210 0425 1481 INLETS, CURB, TYPE 8, <10'	22.000 EA	3050.00000	67100.00	4318.38000	95004.36	3200.00000	70400.00
0215 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	2250.00000	2250.00	2400.00000	2400.00	1600.00000	1600.00
0220 0425 1531 INLETS, DT BOT, TYPE C, MODIFIED, <10''	4.000 EA	1220.00000	4880.00	3000.00000	12000.00	1600.00000	6400.00
0225 0425 1541 INLETS, DT BOT, TYPE D, <10'	6.000 EA	2600.00000	15600.00	2700.00000	16200.00	2400.00000	14400.00
0230 0425 1549 INLETS, DT BOT, TYPE D, MODIFY	1.000 EA	3400.00000	3400.00	5100.00000	5100.00	3700.00000	3700.00
0235 0425 1551 INLETS, DT BOT, TYPE E, <10'	1.000 EA	3500.00000	3500.00	3500.00000	3500.00	3600.00000	3600.00
0240 0425 1561 INLETS, DT BOT, TYPE F, <10'	1.000 EA	2660.00000	2660.00	2500.00000	2500.00	2400.00000	2400.00
0245 0425 1702 INLETS, GUTTER, TYPE S, >10'	1.000 EA	3445.00000	3445.00	7000.00000	7000.00	4200.00000	4200.00
0250 0425 2 61 MANHOLES, P-8, <10'	4.000 EA	1825.00000	7300.00	2500.00000	10000.00	1800.00000	7200.00
0255 0425 2 91 MANHOLES, J-8, <10'	7.000 EA	2760.00000	19320.00	3500.00000	24500.00	2600.00000	18200.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0260 0425 2 92 MANHOLES, J-8, >10'	6.000 EA	3770.00000	22620.00	8000.00000	48000.00	3800.00000	22800.00
0265 0425 3 41 JUNCTION BOX, DRAINAGE, P-7, <10'	1.000 EA	2070.00000	2070.00	2500.00000	2500.00	2300.00000	2300.00
0270 0425 3 43 JUNCTION BOX, DRAINAGE, P-7, PARTIAL	1.000 EA	1340.00000	1340.00	1300.00000	1300.00	1400.00000	1400.00
0275 0425 10 YARD DRAIN	2.000 EA	1115.00000	2230.00	750.00000	1500.00	3100.00000	6200.00
0280 0430 94 1 DESILTING PIPE, 0 - 24"	226.000 LF	2.60000	587.60	10.00000	2260.00	5.00000	1130.00
0285 0430 94 2 DESILTING PIPE, 25 - 36"	354.000 LF	3.70000	1309.80	8.00000	2832.00	7.00000	2478.00
0290 0430 94 3 DESILTING PIPE, 37 - 48"	1385.000 LF	5.10000	7063.50	8.00000	11080.00	11.00000	15235.00
0295 0430 94 4 DESILTING PIPE, 49 - 60"	159.000 LF	6.75000	1073.25	26.00000	4134.00	21.00000	3339.00
0300 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	22.000 LF	55.00000	1210.00	39.00000	858.00	55.00000	1210.00
0305 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	3295.000 LF	43.00000	141685.00	45.00000	148275.00	45.00000	148275.00
0310 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	3289.000 LF	39.00000	128271.00	50.00000	164450.00	50.00000	164450.00
0315 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	60.000 LF	98.00000	5880.00	90.00000	5400.00	65.00000	3900.00
0320 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	1074.000 LF	68.00000	73032.00	75.00000	80550.00	65.00000	69810.00
0325 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	294.000 LF	98.00000	28812.00	105.00000	30870.00	85.00000	24990.00
0330 0430175154 PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	828.000 LF	118.00000	97704.00	135.00000	111780.00	145.00000	120060.00
0335 0430175248 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	70.000 LF	176.50000	12355.00	170.00000	11900.00	165.00000	11550.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0340 0430982129 MITERED END SECTION, OPTIONAL ROUND, 24" CD	2.000 EA	830.00000	1660.00	1300.00000	2600.00	1000.00000	2000.00
0345 0430982138 MITERED END SECTION, OPTIONAL ROUND, 36" CD	1.000 EA	1750.00000	1750.00	1900.00000	1900.00	1470.00000	1470.00
0350 0430984133 MITERED END SECTION , OPTIONAL ROUND, 30" SD	1.000 EA	2000.00000	2000.00	5000.00000	5000.00	2530.00000	2530.00
0355 0430990 MITERED END SECT, REPLACE GRATE	1.000 EA	520.00000	520.00	1350.00000	1350.00	1530.00000	1530.00
0360 0440 1 30 UNDERDRAIN, TYPE III	284.000 LF	30.15000	8562.60	35.00000	9940.00	27.00000	7668.00
0365 0440 70 UNDERDRAIN INSPECTION BOX	2.000 EA	770.00000	1540.00	1800.00000	3600.00	1550.00000	3100.00
0370 0440 73 3 UNDERDRAIN OUTLET PIPE, 8"	3.000 LF	220.00000	660.00	50.00000	150.00	290.00000	870.00
0375 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM	71.000 LF	37.00000	2627.00	38.00000	2698.00	21.00000	1491.00
0380 0520 1 7 CONCRETE CURB & GUTTER, TYPE E	1283.000 LF	11.55000	14818.65	10.00000	12830.00	8.50000	10905.50
0385 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	10840.000 LF	9.45000	102438.00	8.50000	92140.00	8.00000	86720.00
0390 0520 2 4 CONCRETE CURB, TYPE D	180.000 LF	11.00000	1980.00	11.00000	1980.00	10.00000	1800.00
0395 0520 3 VALLEY GUTTER- CONCRETE	270.000 LF	16.00000	4320.00	12.00000	3240.00	15.00000	4050.00
0400 0520 5 16 TRAFFIC SEPARATOR CONCRETE- TYPE I, 8. 5' WIDE	234.000 LF	27.00000	6318.00	34.00000	7956.00	28.00000	6552.00
0405 0520 5 41 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	506.000 LF	25.00000	12650.00	28.00000	14168.00	25.00000	12650.00
0410 0520 5 42 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	232.000 LF	34.00000	7888.00	38.00000	8816.00	34.00000	7888.00
0415 0520 5 46 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8. 5' WIDE	1177.000 LF	36.00000	42372.00	34.00000	40018.00	36.00000	42372.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0420 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	8.000 SY	27.00000	216.00	33.00000	264.00	32.00000	256.00
0425 0522 1 SIDEWALK CONCRETE, 4" THICK	2142.000 SY	26.00000	55692.00	25.30000	54192.60	25.00000	53550.00
0430 0522 2 SIDEWALK CONCRETE, 6" THICK	980.000 SY	28.00000	27440.00	30.00000	29400.00	27.00000	26460.00
0435 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	98.000 SY	44.00000	4312.00	30.00000	2940.00	31.00000	3038.00
0440 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	38.300 TN	63.00000	2412.90	102.74000	3934.94	100.00000	3830.00
0445 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD	1035.000 LF	5.55000	5744.25	6.19000	6406.65	5.25000	5433.75
0450 0550 60124 FENCE GATE, TYPE A, DOUBLE, 18.1-20.0' OPENING	2.000 EA	845.00000	1690.00	984.00000	1968.00	800.00000	1600.00
0455 0570 1 2 PERFORMANCE TURF, SOD	29602.000 SY	1.46000	43218.92	1.40000	41442.80	1.35000	39962.70
0460 0590 70 IRRIGATION SYSTEM 19756225201	LUMP	2970.00000	2970.00	5000.00000	5000.00	2700.00000	2700.00
0465 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	7.407 NM	1230.00000	9110.61	1300.00000	9629.10	1000.00000	7407.00
0470 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	263.000 LF	2.65000	696.95	2.00000	526.00	1.25000	328.75
0475 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	6.365 GM	560.00000	3564.40	600.00000	3819.00	350.00000	2227.75
0480 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	806.000 LF	0.40000	322.40	0.41000	330.46	0.20000	161.20
0485 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	42.30000	1480.50	46.00000	1610.00	1.00000	35.00
0490 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	86.000 EA	26.50000	2279.00	29.00000	2494.00	20.00000	1720.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0495 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	5.363 NM	1225.00000	6569.68	1350.00000	7240.05	1000.00000	5363.00
0500 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	868.000 LF	0.37000	321.16	0.41000	355.88	0.20000	173.60
0505 0999 16 PARTNERING, DO NOT BID 19756225201	LUMP	5000.00000	5000.00	5000.00000	5000.00	5000.00000	5000.00
0510 0999 20 DISPUTES REVIEW BOARD, DO NOT BID	12.000 DA	3300.00000	39600.00	3300.00000	39600.00	3300.00000	39600.00
0515 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 4,530,474.11		$ 4,658,763.18		$ 4,799,990.30
SECTION 0002 SIGNING							
0520 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	28000.00000	28000.00	22000.00000	22000.00	22000.00000	22000.00
0525 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	37.000 AS	280.00000	10360.00	270.00000	9990.00	275.00000	10175.00
0530 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	7.000 AS	430.00000	3010.00	370.00000	2590.00	370.00000	2590.00
0535 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	2.000 AS	700.00000	1400.00	1000.00000	2000.00	1000.00000	2000.00
0540 0700 20 40 SINGLE POST SIGN, RELOCATE	10.000 AS	158.00000	1580.00	50.00000	500.00	50.00000	500.00
0545 0700 20 60 SINGLE POST SIGN, REMOVE	3.000 AS	21.15000	63.45	16.00000	48.00	17.00000	51.00
0550 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	3.000 AS	3490.00000	10470.00	3000.00000	9000.00	3000.00000	9000.00
0555 0700 46 15 SIGN EXISTING- REMOVE, SPAN WIRE	1.000 AS	2750.00000	2750.00	1900.00000	1900.00	1950.00000	1950.00
0560 0700 48 19 SIGN PANELS, F & I, 16 - 100	2.000 EA	720.00000	1440.00	480.00000	960.00	480.00000	960.00
0565 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	15.000 EA	79.00000	1185.00	45.00000	675.00	35.00000	525.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0570 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	903.000 EA	3.05000	2754.15	3.50000	3160.50	4.00000	3612.00
0575 0710 11190 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	76.000 SF	2.10000	159.60	2.35000	178.60	1.00000	76.00
0580 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	182.000 SF	2.10000	382.20	2.35000	427.70	1.00000	182.00
0585 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	2.837 NM	4070.00000	11546.59	4500.00000	12766.50	5000.00000	14185.00
0590 0711 11122 THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	4007.000 LF	1.10000	4407.70	1.23000	4928.61	1.50000	6010.50
0595 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	1131.000 LF	2.10000	2375.10	2.34000	2646.54	2.20000	2488.20
0600 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	1011.000 LF	3.20000	3235.20	3.51000	3548.61	3.00000	3033.00
0605 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	525.000 LF	4.25000	2231.25	4.68000	2457.00	4.00000	2100.00
0610 0711 11131 THERMOPLASTIC, STANDARD, WHITE, SKIP, 6	3.257 GM	1270.00000	4136.39	1403.55000	4571.36	1500.00000	4885.50
0615 0711 11151 THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	414.000 LF	0.95000	393.30	1.05000	434.70	0.50000	207.00
0620 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	47.000 EA	175.00000	8225.00	192.99000	9070.53	170.00000	7990.00
0625 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	74.000 EA	55.00000	4070.00	60.82000	4500.68	65.00000	4810.00
0630 0711 11211 THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	2.103 NM	4070.00000	8559.21	4503.04000	9469.89	5000.00000	10515.00
0635 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	288.000 LF	3.15000	907.20	3.51000	1010.88	1.00000	288.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0640 0711 11251 THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	274.000 LF	0.95000	260.30	1.05000	287.70	1.00000	274.00
SECTION 0002 TOTALS		$	113,901.64	$	109,122.80	$	110,407.20
SECTION 0003 LIGHTING							
0645 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	320.000 LF	13.75000	4400.00	12.73000	4073.60	13.00000	4160.00
0650 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	25570.000 LF	1.20000	30684.00	1.03000	26337.10	1.00000	25570.00
0655 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	4880.000 LF	2.60000	12688.00	3.34000	16299.20	4.00000	19520.00
0660 0715 4033 LIGHT POLE COMPLETE,F&I, SPECIAL FOUNDATION,WIND SPEED 110, POLE HEIGHT 50'	19.000 EA	4100.00000	77900.00	4309.50000	81880.50	4300.00000	81700.00
0665 0715 4133 LIGHT POLE COMPLETE, F&I, WIND SPEED 110, POLE HEIGHT 50'	29.000 EA	3200.00000	92800.00	3629.02000	105241.58	3630.00000	105270.00
0670 0715 4600 LIGHT POLE COMPLETE, REMOVE	27.000 EA	270.00000	7290.00	202.65000	5471.55	200.00000	5400.00
0675 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	15800.00000	15800.00	16816.85000	16816.85	16800.00000	16800.00
0680 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	57.000 EA	275.00000	15675.00	368.41000	20999.37	370.00000	21090.00
0685 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	48.000 EA	325.00000	15600.00	300.16000	14407.68	300.00000	14400.00
SECTION 0003 TOTALS		$	272,837.00	$	291,527.43	$	293,910.00
SECTION 0004 SIGNALIZATION							
0690 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	400.000 LF	18.45000	7380.00	13.56000	5424.00	13.50000	5400.00
0695 0555 1 3 DIRECTIONAL BORE, 12" TO < 18"	170.000 LF	26.65000	4530.50	27.46000	4668.20	27.50000	4675.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0700 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	300.000 LF	3.25000	975.00	3.93000	1179.00	4.00000	1200.00
0705 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	1.000 PI	3400.00000	3400.00	5158.03000	5158.03	2500.00000	2500.00
0710 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	23.000 EA	240.00000	5520.00	307.97000	7083.31	310.00000	7130.00
0715 0639 1 22 SIGNALS,ELECTRICAL POWER SERVICE, UNDERGROUND, PURCHASED BYCONTRACTOR FROM POWER COMPANY	1.000 AS	960.00000	960.00	956.22000	956.22	960.00000	960.00
0720 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	60.000 LF	2.80000	168.00	2.07000	124.20	2.00000	120.00
0725 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1.000 EA	740.00000	740.00	726.13000	726.13	725.00000	725.00
0730 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	25000.00000	50000.00	19000.00000	38000.00	24300.00000	48600.00
0735 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	24000.00000	24000.00	20000.00000	20000.00	22800.00000	22800.00
0740 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	11.000 AS	680.00000	7480.00	600.00000	6600.00	630.00000	6930.00
0745 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	2.000 AS	1050.00000	2100.00	1000.00000	2000.00	1090.00000	2180.00
0750 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	6.000 AS	670.00000	4020.00	500.00000	3000.00	500.00000	3000.00
0755 0659101 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES 3 SECT	11.000 EA	140.00000	1540.00	102.00000	1122.00	100.00000	1100.00
0760 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	6.000 EA	810.00000	4860.00	700.00000	4200.00	725.00000	4350.00
0765 0659118 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES, 5 SECT CLUSTER	2.000 EA	200.00000	400.00	150.00000	300.00	150.00000	300.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0770 0660 2102 LOOP ASSEMBLY, F&I, TYPE B	4.000 AS	420.00000	1680.00	640.00000	2560.00	645.00000	2580.00
0775 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	5.000 AS	620.00000	3100.00	660.00000	3300.00	665.00000	3325.00
0780 0663 74 14 VEHICLE DETECTOR ASSEMBLIES, F&I, EMERGENCY PRE-EMPTION	3.000 EA	2000.00000	6000.00	1500.00000	4500.00	1510.00000	4530.00
0785 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	4.000 EA	6100.00000	24400.00	2200.00000	8800.00	2230.00000	8920.00
0790 0665 13 PEDESTRIAN DETECTOR, F&I, DETECTOR WITH SIGN ONLY	6.000 EA	130.00000	780.00	160.00000	960.00	160.00000	960.00
0795 0670 5111 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.000 AS	21000.00000	21000.00	14000.00000	14000.00	16400.00000	16400.00
0800 0685106 SYSTEM AUXILIARIES, F&I, UNINTERRUPTIBLE POWER SOURCE	1.000 EA	6100.00000	6100.00	5000.00000	5000.00	5700.00000	5700.00
0805 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	11.000 EA	40.00000	440.00	33.00000	363.00	34.00000	374.00
0810 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	4.000 EA	40.00000	160.00	16.50000	66.00	17.00000	68.00
0815 0690 31 SIGNAL PEDESTAL REMOVAL	4.000 EA	79.00000	316.00	150.00000	600.00	150.00000	600.00
0820 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	2.000 EA	1250.00000	2500.00	1700.00000	3400.00	1030.00000	2060.00
0825 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	79.00000	79.00	300.00000	300.00	300.00000	300.00
0830 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	4.000 EA	40.00000	160.00	16.00000	64.00	17.00000	68.00
0835 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	158.00000	158.00	300.00000	300.00	300.00000	300.00
0840 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	158.00000	158.00	400.00000	400.00	400.00000	400.00
0845 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	158.00000	158.00	800.00000	800.00	800.00000	800.00
0850 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	3.000 EA	2600.00000	7800.00	2600.00000	7800.00	2650.00000	7950.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) SOUTHLAND CONSTRUCTION, INC UNIT PRICE	 AMOUNT	(8) EMERALD UTILITIES & SITE DE UNIT PRICE	 AMOUNT	(9) MIDDLESEX CORPORATION (THE) UNIT PRICE	 AMOUNT
0855 0782 1 40 ITS CCTV CAMERA, RELOCATE	1.000 EA	2400.00000	2400.00	3700.00000	3700.00	3700.00000	3700.00
0860 0783 1422 ITS FIBER OPTIC CABLE, RELOCATE, UNDERGROUND, 13 -48 FIBERS	305.000 LF	2.50000	762.50	2.50000	762.50	2.50000	762.50
0865 0783 2 31 ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	4.000 EA	78.00000	312.00	140.00000	560.00	145.00000	580.00
0870 0783 3 45 ITS FIBER OPTIC CONNECTION HARDWARE, REL, PATCH PANEL, PRETERMINATED	1.000 EA	590.00000	590.00	250.00000	250.00	260.00000	260.00
0875 0783 4111 ITS CONDUIT, F& I, ABOVEGROUND	30.000 LF	17.00000	510.00	14.00000	420.00	14.00000	420.00
0880 0783 4112 ITS CONDUIT, F& I, UNDERGROUND	85.000 LF	3.65000	310.25	4.00000	340.00	5.00000	425.00
0885 0783 5 1 ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	1.000 EA	610.00000	610.00	1000.00000	1000.00	1025.00000	1025.00
0890 0784 1 4 ITS MANAGED FIELD ETHERNET SWITCH, RELOCATE	1.000 EA	630.00000	630.00	280.00000	280.00	300.00000	300.00
0895 0784 3 40 ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, RELOCATE	1.000 EA	720.00000	720.00	220.00000	220.00	230.00000	230.00
0900 0785 1 13 ITS POLE, F&I, CONCRETE WITHOUT LOWERING DEVICE	1.000 EA	7500.00000	7500.00	5600.00000	5600.00	5630.00000	5630.00
0905 0785 1 60 ITS POLE, REMOVE	1.000 EA	980.00000	980.00	1000.00000	1000.00	1055.00000	1055.00
SECTION 0004 TOTALS		$	208,387.25	$	167,886.59	$	181,692.50
CONTRACT TOTALS		$	5,125,600.00	$	5,227,300.00	$	5,386,000.00

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 19756225201	LUMP	336670.68000	336670.68				
0010 0102 1 MAINTENANCE OF TRAFFIC 19756225201	360.000 LS	597417.59000	597417.59				
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	500.000 CY	29.91000	14955.00				
0020 0102 14 TRAFFIC CONTROL OFFICER	56.000 MH	45.00000	2520.00				
0025 0102 60 WORK ZONE SIGN	23850.000 ED	0.28000	6678.00				
0030 0102 61 BUSINESS SIGN	16.000 EA	52.28000	836.48				
0035 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	121044.000 ED	0.11000	13314.84				
0040 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	6234.000 ED	0.26000	1620.84				
0045 0102 76 ADVANCE WARNING ARROW PANEL	1008.000 ED	6.27000	6320.16				
0050 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	7200.000 ED	0.16000	1152.00				
0055 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	2174.000 EA	2.67000	5804.58				
0060 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	618.000 ED	15.16000	9368.88				
0065 0102104 2 TEMPORARY TRAFFIC CONTROL, FIXED SIGNAL	247.000 ED	15.46000	3818.62				
0070 0102107 TEMPORARY TRAFFIC DETECTION, INTERSECT	247.000 DA	8.78000	2168.66				
0075 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	300.000 SY	1.57000	471.00				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0080 0104 10 3 SEDIMENT BARRIER	10966.000 LF	0.57000	6250.62				
0085 0104 11 FLOATING TURBIDITY BARRIER	58.000 LF	8.36000	484.88				
0090 0104 15 SOIL TRACKING PREVENTION DEVICE	3.000 EA	522.76000	1568.28				
0095 0104 18 INLET PROTECTION SYSTEM	62.000 EA	47.05000	2917.10				
0100 0107 1 LITTER REMOVAL	55.600 AC	5.23000	290.79				
0105 0107 2 MOWING	55.600 AC	52.28000	2906.77				
0110 0110 1 1 CLEARING & GRUBBING 19756225201	17.410 LS	120366.34000	120366.34				
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	4022.000 SY	10.11000	40662.42				
0120 0110 7 1 MAILBOX, F&I SINGLE	7.000 EA	104.55000	731.85				
0125 0120 1 REGULAR EXCAVATION	23045.000 CY	6.26000	144261.70				
0130 0120 4 SUBSOIL EXCAVATION	3518.000 CY	5.10000	17941.80				
0135 0120 6 EMBANKMENT	9875.000 CY	6.87000	67841.25				
0140 0145 2 GEOSYNTHETIC REINFORCED FOUNDATION OVER SOFT SOIL	1300.000 SY	6.22000	8086.00				
0145 0160 4 TYPE B STABILIZATION	50449.000 SY	3.62000	182625.38				
0150 0285701 OPTIONAL BASE, BASE GROUP 01	79.000 SY	12.22000	965.38				
0155 0285712 OPTIONAL BASE, BASE GROUP 12	45556.000 SY	16.07000	732084.92				
0160 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	11235.000 SY	2.53000	28424.55				
0165 0327 70 19 MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH	970.000 SY	4.70000	4559.00				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0170 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5143.700 TN	99.72000	512929.76				
0175 0334 1 24 SUPERPAVE ASPH CONC, TRAF D, PG76-22	3763.600 TN	102.06000	384113.02				
0180 0337 7 22 ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG76-22	39.000 TN	224.56000	8757.84				
0185 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	4690.500 TN	98.31000	461123.06				
0190 0400 0 11 CONCRETE CLASS NS, GRAVITY WALL	7.200 CY	612.77000	4411.94				
0195 0425 1311 INLETS, CURB, TYPE P-1, <10'	1.000 EA	1720.25000	1720.25				
0200 0425 1315 INLETS, CURB TYPE P-1, PARTIAL	1.000 EA	1586.35000	1586.35				
0205 0425 1351 INLETS, CURB, TYPE P-5, <10'	24.000 EA	3015.49000	72371.76				
0210 0425 1481 INLETS, CURB, TYPE 8, <10'	22.000 EA	2225.47000	48960.34				
0215 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	1464.73000	1464.73				
0220 0425 1531 INLETS, DT BOT, TYPE C, MODIFIED, <10''	4.000 EA	1346.16000	5384.64				
0225 0425 1541 INLETS, DT BOT, TYPE D, <10'	6.000 EA	2026.66000	12159.96				
0230 0425 1549 INLETS, DT BOT, TYPE D, MODIFY	1.000 EA	8021.74000	8021.74				
0235 0425 1551 INLETS, DT BOT, TYPE E, <10'	1.000 EA	3296.73000	3296.73				
0240 0425 1561 INLETS, DT BOT, TYPE F, <10'	1.000 EA	2038.96000	2038.96				
0245 0425 1702 INLETS, GUTTER, TYPE S, >10'	1.000 EA	8572.44000	8572.44				
0250 0425 2 61 MANHOLES, P-8, <10'	4.000 EA	1785.47000	7141.88				
0255 0425 2 91 MANHOLES, J-8, <10'	7.000 EA	2888.06000	20216.42				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0260 0425 2 92 MANHOLES, J-8, >10'	6.000 EA	4113.70000	24682.20				
0265 0425 3 41 JUNCTION BOX, DRAINAGE, P-7, <10'	1.000 EA	1582.54000	1582.54				
0270 0425 3 43 JUNCTION BOX, DRAINAGE, P-7, PARTIAL	1.000 EA	1128.35000	1128.35				
0275 0425 10 YARD DRAIN	2.000 EA	1497.77000	2995.54				
0280 0430 94 1 DESILTING PIPE, 0 - 24"	226.000 LF	2.61000	589.86				
0285 0430 94 2 DESILTING PIPE, 25 - 36"	354.000 LF	3.14000	1111.56				
0290 0430 94 3 DESILTING PIPE, 37 - 48"	1385.000 LF	4.44000	6149.40				
0295 0430 94 4 DESILTING PIPE, 49 - 60"	159.000 LF	7.84000	1246.56				
0300 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	22.000 LF	60.37000	1328.14				
0305 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	3295.000 LF	38.54000	126989.30				
0310 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	3289.000 LF	40.00000	131560.00				
0315 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	60.000 LF	52.00000	3120.00				
0320 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	1074.000 LF	61.59000	66147.66				
0325 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	294.000 LF	119.74000	35203.56				
0330 0430175154 PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	828.000 LF	153.44000	127048.32				
0335 0430175248 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/CD	70.000 LF	173.82000	12167.40				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0340 0430982129 MITERED END SECTION, OPTIONAL ROUND, 24" CD	2.000 EA	674.44000	1348.88				
0345 0430982138 MITERED END SECTION, OPTIONAL ROUND, 36" CD	1.000 EA	1278.78000	1278.78				
0350 0430984133 MITERED END SECTION , OPTIONAL ROUND, 30" SD	1.000 EA	1696.81000	1696.81				
0355 0430990 MITERED END SECT, REPLACE GRATE	1.000 EA	1567.17000	1567.17				
0360 0440 1 30 UNDERDRAIN, TYPE III	284.000 LF	29.43000	8358.12				
0365 0440 70 UNDERDRAIN INSPECTION BOX	2.000 EA	1065.40000	2130.80				
0370 0440 73 3 UNDERDRAIN OUTLET PIPE, 8"	3.000 LF	21.57000	64.71				
0375 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM	71.000 LF	41.82000	2969.22				
0380 0520 1 7 CONCRETE CURB & GUTTER, TYPE E	1283.000 LF	9.19000	11790.77				
0385 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	10840.000 LF	8.52000	92356.80				
0390 0520 2 4 CONCRETE CURB, TYPE D	180.000 LF	12.03000	2165.40				
0395 0520 3 VALLEY GUTTER- CONCRETE	270.000 LF	15.33000	4139.10				
0400 0520 5 16 TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	234.000 LF	32.65000	7640.10				
0405 0520 5 41 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	506.000 LF	20.05000	10145.30				
0410 0520 5 42 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	232.000 LF	25.46000	5906.72				
0415 0520 5 46 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	1177.000 LF	32.68000	38464.36				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0420 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	8.000 SY	56.58000	452.64				
0425 0522 1 SIDEWALK CONCRETE, 4" THICK	2142.000 SY	24.04000	51493.68				
0430 0522 2 SIDEWALK CONCRETE, 6" THICK	980.000 SY	33.61000	32937.80				
0435 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	98.000 SY	27.32000	2677.36				
0440 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	38.300 TN	1.91000	73.15				
0445 0550 10110 FENCING, TYPE A, 0.0-5.0', STANDARD	1035.000 LF	6.27000	6489.45				
0450 0550 60124 FENCE GATE, TYPE A, DOUBLE, 18.1-20.0' OPENING	2.000 EA	627.31000	1254.62				
0455 0570 1 2 PERFORMANCE TURF, SOD	29602.000 SY	1.39000	41146.78				
0460 0590 70 IRRIGATION SYSTEM 19756225201	LUMP	5584.96000	5584.96				
0465 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	7.407 NM	846.86000	6272.69				
0470 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	263.000 LF	1.52000	399.76				
0475 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	6.365 GM	350.25000	2229.34				
0480 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	806.000 LF	0.29000	233.74				
0485 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	39.73000	1390.55				
0490 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	86.000 EA	18.82000	1618.52				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0495 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	5.363 NM	846.86000	4541.71				
0500 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	868.000 LF	0.29000	251.72				
0505 0999 16 PARTNERING, DO NOT BID 19756225201	LUMP	5000.00000	5000.00				
0510 0999 20 DISPUTES REVIEW BOARD, DO NOT BID	12.000 DA	3300.00000	39600.00				
0515 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID	LUMP	50000.00000	50000.00				
SECTION 0001 TOTALS		$	4,919,080.08	$		$	
SECTION 0002 SIGNING							
0520 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	26562.25000	26562.25				
0525 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	37.000 AS	227.92000	8433.04				
0530 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	7.000 AS	568.76000	3981.32				
0535 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	2.000 AS	1322.57000	2645.14				
0540 0700 20 40 SINGLE POST SIGN, RELOCATE	10.000 AS	41.82000	418.20				
0545 0700 20 60 SINGLE POST SIGN, REMOVE	3.000 AS	1.05000	3.15				
0550 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	3.000 AS	2592.87000	7778.61				
0555 0700 46 15 SIGN EXISTING- REMOVE, SPAN WIRE	1.000 AS	2927.43000	2927.43				
0560 0700 48 19 SIGN PANELS, F & I, 16 - 100	2.000 EA	616.85000	1233.70				
0565 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	15.000 EA	71.09000	1066.35				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0570 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	903.000 EA	3.50000	3160.50				
0575 0710 11190 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	76.000 SF	0.99000	75.24				
0580 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	182.000 SF	0.99000	180.18				
0585 0711 11111 THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	2.837 NM	3878.84000	11004.27				
0590 0711 11122 THERMOPLASTIC, STANDARD, WHITE, SOLID, 8"	4007.000 LF	1.10000	4407.70				
0595 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	1131.000 LF	1.44000	1628.64				
0600 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18"	1011.000 LF	2.77000	2800.47				
0605 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	525.000 LF	3.82000	2005.50				
0610 0711 11131 THERMOPLASTIC, STANDARD, WHITE, SKIP, 6	3.257 GM	1265.07000	4120.33				
0615 0711 11151 THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	414.000 LF	1.02000	422.28				
0620 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	47.000 EA	194.46000	9139.62				
0625 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	74.000 EA	54.37000	4023.38				
0630 0711 11211 THERMOPLASTIC, STANDARD,YELLOW, SOLID, 6"	2.103 NM	3878.84000	8157.20				
0635 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18"	288.000 LF	2.77000	797.76				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0640 0711 11251 THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	274.000 LF	1.02000	279.48				
SECTION 0002 TOTALS		$	107,251.74	$		$	
SECTION 0003 LIGHTING							
0645 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	320.000 LF	13.31000	4259.20				
0650 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	25570.000 LF	1.08000	27615.60				
0655 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	4880.000 LF	3.49000	17031.20				
0660 0715 4033 LIGHT POLE COMPLETE,F&I, SPECIAL FOUNDATION,WIND SPEED 110, POLE HEIGHT 50'	19.000 EA	4505.63000	85606.97				
0665 0715 4133 LIGHT POLE COMPLETE, F&I, WIND SPEED 110, POLE HEIGHT 50'	29.000 EA	3794.18000	110031.22				
0670 0715 4600 LIGHT POLE COMPLETE, REMOVE	27.000 EA	211.87000	5720.49				
0675 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	17582.20000	17582.20				
0680 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	57.000 EA	385.18000	21955.26				
0685 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	48.000 EA	313.82000	15063.36				
SECTION 0003 TOTALS		$	304,865.50	$		$	
SECTION 0004 SIGNALIZATION							
0690 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	400.000 LF	14.18000	5672.00				
0695 0555 1 3 DIRECTIONAL BORE, 12" TO < 18"	170.000 LF	28.71000	4880.70				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0700 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	300.000 LF	4.11000	1233.00				
0705 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	1.000 PI	5392.77000	5392.77				
0710 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	23.000 EA	321.99000	7405.77				
0715 0639 1 22 SIGNALS,ELECTRICAL POWER SERVICE, UNDERGROUND, PURCHASED BYCONTRACTOR FROM POWER COMPANY	1.000 AS	999.74000	999.74				
0720 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	60.000 LF	2.16000	129.60				
0725 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1.000 EA	759.18000	759.18				
0730 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	25365.14000	50730.28				
0735 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	23788.42000	23788.42				
0740 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	11.000 AS	659.12000	7250.32				
0745 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	2.000 AS	1140.38000	2280.76				
0750 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	6.000 AS	525.77000	3154.62				
0755 0659101 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES 3 SECT	11.000 EA	107.26000	1179.86				
0760 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	6.000 EA	759.93000	4559.58				
0765 0659118 SIGNAL HEAD AUXILIARIES, F&I, BACK PLATES, 5 SECT CLUSTER	2.000 EA	156.91000	313.82				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0770 0660 2102 LOOP ASSEMBLY, F&I, TYPE B	4.000 AS	671.75000	2687.00				
0775 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	5.000 AS	692.55000	3462.75				
0780 0663 74 14 VEHICLE DETECTOR ASSEMBLIES, F&I, EMERGENCY PRE-EMPTION	3.000 EA	1577.41000	4732.23				
0785 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	4.000 EA	2330.23000	9320.92				
0790 0665 13 PEDESTRIAN DETECTOR, F&I, DETECTOR WITH SIGN ONLY	6.000 EA	166.62000	999.72				
0795 0670 5111 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	1.000 AS	17134.79000	17134.79				
0800 0685106 SYSTEM AUXILIARIES, F&I, UNINTERRUPTIBLE POWER SOURCE	1.000 EA	5971.76000	5971.76				
0805 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	11.000 EA	35.32000	388.52				
0810 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	4.000 EA	17.66000	70.64				
0815 0690 31 SIGNAL PEDESTAL REMOVAL	4.000 EA	158.91000	635.64				
0820 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	2.000 EA	1856.13000	3712.26				
0825 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	317.81000	317.81				
0830 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	4.000 EA	17.66000	70.64				
0835 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	317.81000	317.81				
0840 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	423.76000	423.76				
0845 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	847.51000	847.51				
0850 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	3.000 EA	2771.87000	8315.61				

CALL ORDER: 001 PROPOSAL ID: T1402 LETTING DATE: 03/30/11 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) AJAX PAVING INDUSTRIES OF F UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0855 0782 1 40 ITS CCTV CAMERA, RELOCATE	1.000 EA	3887.77000	3887.77				
0860 0783 1422 ITS FIBER OPTIC CABLE, RELOCATE, UNDERGROUND, 13 -48 FIBERS	305.000 LF	2.57000	783.85				
0865 0783 2 31 ITS FIBER OPTIC CONNECTION, INSTALL, SPLICE	4.000 EA	149.53000	598.12				
0870 0783 3 45 ITS FIBER OPTIC CONNECTION HARDWARE, REL, PATCH PANEL, PRETERMINATED	1.000 EA	269.16000	269.16				
0875 0783 4111 ITS CONDUIT, F& I, ABOVEGROUND	30.000 LF	14.54000	436.20				
0880 0783 4112 ITS CONDUIT, F& I, UNDERGROUND	85.000 LF	4.75000	403.75				
0885 0783 5 1 ITS PULL BOX FOR FIBER OPTIC CABLE, FURNISH AND INSTALL	1.000 EA	1070.14000	1070.14				
0890 0784 1 4 ITS MANAGED FIELD ETHERNET SWITCH, RELOCATE	1.000 EA	299.06000	299.06				
0895 0784 3 40 ITS DIGITAL VIDEO ENCODER WITH SOFTWARE DECODER, RELOCATE	1.000 EA	239.24000	239.24				
0900 0785 1 13 ITS POLE, F&I, CONCRETE WITHOUT LOWERING DEVICE	1.000 EA	5883.64000	5883.64				
0905 0785 1 60 ITS POLE, REMOVE	1.000 EA	1100.94000	1100.94				
SECTION 0004 TOTALS		$	194,111.66	$		$	
CONTRACT TOTALS		$	5,525,308.98	$	0.00	$	0.00

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.