VENDOR RANKING

CALL ORDER : 011 PROPOSAL ID : T4317 PROPOSAL DESC :
LETTING DATE : 05/23/12 10:30 A.M. DISTRICT : 04
SET-ASIDE : U/R CODE :
CONTRACT TIME : 500 WORKING DAYS (AVAILABLE DAYS)

The improvements under this contract consist of widening the existing two-lane roadway (SR 710) to four lanes. The typical section includes 12 ft. lanes and 4 ft. bike lanes including curb and gutter and a 26 ft. median. Sidewalks will be constructed for both sides of the roadway. Other improvements include signing and pavement markings, signalization, standard roadway lighting and landscaping. Drainage improvements are being proposed with 3 detention ponds. Congress Avenue south of SR 710 is proposed to be milled and resurfaced whereas Congress Avenue north of SR 710 is proposed to be widened, milled and resurfaced in order to accommodate improvements to its intersection.

FINPROJ(S) : 22989725201 (*) F.A. NO. : N/A COUNTIES : PALM BEACH
22989725602 N/A
22989725603 N/A
LOCAL NAME : SR-710/BEELINE HWY ROAD NAME : SR 710
PROJ LIMITS : FROM W. OF CONGRESS AVE TO W. OF AUSTRALIAN AVE

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	RANGER CONSTRUCTION INDUSTRIES, INC.	Responsive	Winning bid	$ 12,189,533.30	0.00%
2	J.W. CHEATHAM, LLC	Responsive	Non-Winning Bid	$ 12,247,199.65	0.47%
3	COMMUNITY ASPHALT CORP.	Responsive	Non-Winning Bid	$ 13,473,070.58	10.52%
4	CONALVIAS USA LLC	Responsive	Non-Winning Bid	$ 15,957,537.77	30.91%
5	PRINCE CONTRACTING, LLC.	Responsive	Non-Winning Bid	$ 16,510,159.32	35.44%

CALL ORDER : 011 PROPOSAL ID : T4317 PROPOSAL DESC :
LETTING DATE : 05/23/12 10:30 A.M. DISTRICT : 04
SET-ASIDE : U/R CODE :
CONTRACT TIME : 500 WORKING DAYS (AVAILABLE DAYS)

The improvements under this contract consist of widening the existing two-lane roadway (SR 710) to four lanes. The typical section includes 12 ft. lanes and 4 ft. bike lanes including curb and gutter and a 26 ft. median. Sidewalks will be constructed for both sides of the roadway. Other improvements include signing and pavement markings, signalization, standard roadway lighting and landscaping. Drainage improvements are being proposed with 3 detention ponds. Congress Avenue south of SR 710 is proposed to be milled and resurfaced whereas Congress Avenue north of SR 710 is proposed to be widened, milled and resurfaced in order to accommodate improvements to its intersection.

FINPROJ(S) : 22989725201 (*) F.A. NO. : N/A COUNTIES : PALM BEACH
22989725602 N/A
22989725603 N/A
LOCAL NAME : SR-710/BEELINE HWY ROAD NAME : SR 710
PROJ LIMITS : FROM W. OF CONGRESS AVE TO W. OF AUSTRALIAN AVE

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 22989725201	LUMP	740000.00000	740000.00	1189250.00000	1189250.00	1069266.00000	1069266.00
0010 0102 1 MAINTENANCE OF TRAFFIC 22989725201	500.000 LS	555000.00000	555000.00	445000.00000	445000.00	1147051.00000	1147051.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	836.000 CY	37.00000	30932.00	10.00000	8360.00	19.50000	16302.00
0020 0102 14 TRAFFIC CONTROL OFFICER	624.000 MH	64.90000	40497.60	51.00000	31824.00	52.10000	32510.40
0025 0102 60 WORK ZONE SIGN	69002.000 ED	0.20000	13800.40	0.25000	17250.50	0.25000	17250.50
0030 0102 61 BUSINESS SIGN	10.000 EA	52.10000	521.00	51.00000	510.00	54.90000	549.00
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1116.000 LF	41.30000	46090.80	40.00000	44640.00	36.00000	40176.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0040 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	6135.000 LF	23.90000	146626.50	17.60000	107976.00	16.90000	103681.50
0045 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	201.000 LF	7.40000	1487.40	10.00000	2010.00	16.10000	3236.10
0050 0102 71 24 BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	3506.000 LF	10.00000	35060.00	5.40000	18932.40	7.85000	27522.10
0055 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	109474.000 ED	0.10000	10947.40	0.15000	16421.10	0.15000	16421.10
0060 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	4138.000 ED	0.20000	827.60	0.20000	827.60	0.20000	827.60
0065 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	187.000 ED	5.10000	953.70	5.00000	935.00	5.30000	991.10
0070 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	23676.000 ED	0.10000	2367.60	0.06000	1420.56	0.05000	1183.80
0075 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	1687.000 EA	2.90000	4892.30	2.85000	4807.95	2.85000	4807.95
0080 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	17582.000 ED	0.10000	1758.20	0.06000	1054.92	0.05000	879.10
0085 0102 89 7 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	20.000 LO	1730.00000	34600.00	1500.00000	30000.00	981.00000	19620.00
0090 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	1138.000 ED	13.30000	15135.40	13.00000	14794.00	14.00000	15932.00
0095 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	1500.000 ED	15.40000	23100.00	15.00000	22500.00	15.10000	22650.00
0100 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	1500.000 ED	9.60000	14400.00	10.00000	15000.00	9.35000	14025.00
0105 0104 10 3 SEDIMENT BARRIER	5732.000 LF	0.70000	4012.40	1.00000	5732.00	0.75000	4299.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0110 0104 11 FLOATING TURBIDITY BARRIER	64.000 LF	9.00000	576.00	10.00000	640.00	8.85000	566.40
0115 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	56.000 LF	5.30000	296.80	10.00000	560.00	3.90000	218.40
0120 0104 15 SOIL TRACKING PREVENTION DEVICE	14.000 EA	2230.00000	31220.00	500.00000	7000.00	521.00000	7294.00
0125 0104 18 INLET PROTECTION SYSTEM	106.000 EA	69.10000	7324.60	150.00000	15900.00	67.70000	7176.20
0130 0107 1 LITTER REMOVAL	321.900 AC	31.90000	10268.61	58.00000	18670.20	30.00000	9657.00
0135 0107 2 MOWING	321.900 AC	63.80000	20537.22	81.00000	26073.90	60.00000	19314.00
0140 0110 1 1 CLEARING & GRUBBING 22989725201	24.680 LS	160000.00000	160000.00	363400.00000	363400.00	384930.00000	384930.00
0145 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	6666.000 SY	6.20000	41329.20	7.00000	46662.00	13.30000	88657.80
0150 0120 1 REGULAR EXCAVATION	59835.000 CY	3.30000	197455.50	3.00000	179505.00	5.65000	338067.75
0155 0120 6 EMBANKMENT	5980.000 CY	3.70000	22126.00	10.00000	59800.00	13.40000	80132.00
0160 0160 4 TYPE B STABILIZATION	49715.000 SY	4.00000	198860.00	2.05000	101915.75	3.05000	151630.75
0165 0285701 OPTIONAL BASE, BASE GROUP 01	165.000 SY	24.50000	4042.50	21.00000	3465.00	6.80000	1122.00
0170 0285706 OPTIONAL BASE, BASE GROUP 06	772.000 SY	11.10000	8569.20	10.60000	8183.20	13.50000	10422.00
0175 0285709 OPTIONAL BASE, BASE GROUP 09	29641.000 SY	9.30000	275661.30	9.10000	269733.10	10.70000	317158.70
0180 0285711 OPTIONAL BASE, BASE GROUP 11	4091.000 SY	28.80000	117820.80	38.25000	156480.75	44.00000	180004.00
0185 0285713 OPTIONAL BASE, BASE GROUP 13	1916.000 SY	36.80000	70508.80	40.70000	77981.20	49.20000	94267.20
0190 0285715 OPTIONAL BASE, BASE GROUP 15	1118.000 SY	42.10000	47067.80	47.85000	53496.30	56.70000	63390.60
0195 0286 1 TURNOUT CONSTRUCTION	687.000 SY	64.60000	44380.20	30.00000	20610.00	39.20000	26930.40
0200 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	18940.000 SY	1.80000	34092.00	1.35000	25569.00	1.75000	33145.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0205 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	14144.000 SY	2.00000	28288.00	1.35000	19094.40	2.05000	28995.20
0210 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	83.500 TN	106.00000	8851.00	105.00000	8767.50	169.80000	14178.30
0215 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	2005.400 TN	92.70000	185900.58	105.00000	210567.00	108.80000	218187.52
0220 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5735.000 TN	81.60000	467976.00	103.20000	591852.00	94.75000	543391.25
0225 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	3938.100 TN	120.00000	472572.00	116.70000	459576.27	124.00000	488324.40
0230 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	110.600 TN	160.00000	17696.00	150.00000	16590.00	154.00000	17032.40
0235 0350 1 3 PLAIN CEMENT CONCRETE PAVEMENT, 8"	129.000 SY	72.90000	9404.10	42.00000	5418.00	41.50000	5353.50
0240 0400 1 2 CONCRETE CLASS I, ENDWALLS	14.400 CY	957.00000	13780.80	927.00000	13348.80	930.00000	13392.00
0245 0400 2 1 CONCRETE CLASS II, CULVERTS	2.200 CY	2130.00000	4686.00	2060.00000	4532.00	2066.00000	4545.20
0250 0400 2 2 CONCRETE CLASS II, ENDWALLS	37.600 CY	1590.00000	59784.00	1545.00000	58092.00	1549.00000	58242.40
0255 0415 1 1 REINF STEEL- ROADWAY	3570.000 LB	2.10000	7497.00	2.06000	7354.20	2.05000	7318.50
0260 0425 1201 INLETS, CURB, TYPE 9, <10'	5.000 EA	2870.00000	14350.00	2781.00000	13905.00	2789.00000	13945.00
0265 0425 1203 INLETS, CURB, TYPE 9, J BOT, <10'	1.000 EA	4780.00000	4780.00	4635.00000	4635.00	4648.00000	4648.00
0270 0425 1331 INLETS, CURB, TYPE P-3, <10'	2.000 EA	5320.00000	10640.00	5150.00000	10300.00	5164.00000	10328.00
0275 0425 1332 INLETS, CURB. TYPE P-3, >10'	1.000 EA	7440.00000	7440.00	7210.00000	7210.00	7230.00000	7230.00
0280 0425 1341 INLETS, CURB, TYPE P-4, <10'	3.000 EA	5320.00000	15960.00	5150.00000	15450.00	5164.00000	15492.00
0285 0425 1351 INLETS, CURB, TYPE P-5, <10'	7.000 EA	4250.00000	29750.00	4120.00000	28840.00	4132.00000	28924.00
0290 0425 1352 INLETS, CURB, TYPE P-5, >10'	1.000 EA	4570.00000	4570.00	4430.00000	4430.00	4441.00000	4441.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0295 0425 1361 INLETS, CURB, TYPE P-6, <10'	15.000 EA	4250.00000	63750.00	4120.00000	61800.00	4132.00000	61980.00
0300 0425 1431 INLETS, CURB, TYPE J-3, <10'	2.000 EA	12800.00000	25600.00	12360.00000	24720.00	12395.00000	24790.00
0305 0425 1441 INLETS, CURB, TYPE J-4, <10'	2.000 EA	13300.00000	26600.00	12875.00000	25750.00	12911.00000	25822.00
0310 0425 1451 INLETS, CURB, TYPE J-5, <10'	3.000 EA	5530.00000	16590.00	5356.00000	16068.00	5371.00000	16113.00
0315 0425 1452 INLETS, CURB, TYPE J-5, >10'	3.000 EA	10100.00000	30300.00	9785.00000	29355.00	9812.00000	29436.00
0320 0425 1461 INLETS, CURB, TYPE J-6, <10'	6.000 EA	6910.00000	41460.00	6695.00000	40170.00	6714.00000	40284.00
0325 0425 1521 INLETS, DT BOT, TYPE C,<10'	9.000 EA	1810.00000	16290.00	1751.00000	15759.00	1756.00000	15804.00
0330 0425 1523 INLETS, DT BOT, TYPE C,JBOT, <10'	3.000 EA	6380.00000	19140.00	6180.00000	18540.00	6197.00000	18591.00
0335 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	1.000 EA	2660.00000	2660.00	2575.00000	2575.00	2582.00000	2582.00
0340 0425 1541 INLETS, DT BOT, TYPE D, <10'	2.000 EA	2660.00000	5320.00	2575.00000	5150.00	2582.00000	5164.00
0345 0425 1581 INLETS, DT BOT, TYPE H, <10'	1.000 EA	4780.00000	4780.00	4635.00000	4635.00	4648.00000	4648.00
0350 0425 1910 INLETS, CLOSED FLUME	10.000 EA	8510.00000	85100.00	8240.00000	82400.00	8263.00000	82630.00
0355 0425 2 41 MANHOLES, P-7, <10'	10.000 EA	4250.00000	42500.00	4120.00000	41200.00	4132.00000	41320.00
0360 0425 2 42 MANHOLES, P-7, >10'	9.000 EA	5320.00000	47880.00	5150.00000	46350.00	5164.00000	46476.00
0365 0425 2 43 MANHOLES, P-7, PARTIAL	7.000 EA	2340.00000	16380.00	2266.00000	15862.00	2272.00000	15904.00
0370 0425 2 71 MANHOLES, J-7, <10'	5.000 EA	17000.00000	85000.00	16480.00000	82400.00	16526.00000	82630.00
0375 0425 2 72 MANHOLES, J-7, >10'	9.000 EA	17000.00000	153000.00	16480.00000	148320.00	16526.00000	148734.00
0380 0425 2 73 MANHOLES, J-7, PARTIAL	1.000 EA	2340.00000	2340.00	2266.00000	2266.00	2272.00000	2272.00
0385 0425 2 91 MANHOLES, J-8, <10'	3.000 EA	17000.00000	51000.00	16480.00000	49440.00	16526.00000	49578.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0390 0425 2 93 MANHOLES, J-8, PARTIAL	3.000 EA	2340.00000	7020.00	2376.00000	7128.00	2272.00000	6816.00
0395 0425 74 1 MANHOLES & INLETS CLEANING & SEALING, <10'	22.000 EA	1830.00000	40260.00	1850.00000	40700.00	1302.00000	28644.00
0400 0430 94 1 DESILTING PIPE, 0 - 24"	2131.000 LF	3.20000	6819.20	2.60000	5540.60	2.60000	5540.60
0405 0430 94 2 DESILTING PIPE, 25 - 36"	1066.000 LF	3.80000	4050.80	3.10000	3304.60	3.10000	3304.60
0410 0430174118 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	16.000 LF	53.20000	851.20	51.50000	824.00	51.70000	827.20
0415 0430174124 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	54.000 LF	63.80000	3445.20	61.80000	3337.20	62.00000	3348.00
0420 0430174136 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	13.000 LF	106.00000	1378.00	103.00000	1339.00	103.00000	1339.00
0425 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	2502.000 LF	65.90000	164881.80	64.00000	160128.00	64.00000	160128.00
0430 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	474.000 LF	69.10000	32753.40	67.00000	31758.00	67.10000	31805.40
0435 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	94.000 LF	106.00000	9964.00	103.00000	9682.00	103.00000	9682.00
0440 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	472.000 LF	128.00000	60416.00	124.00000	58528.00	124.00000	58528.00
0445 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	8.000 LF	213.00000	1704.00	206.00000	1648.00	207.00000	1656.00
0450 0430175218 PIPE CULVERT,OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	83.000 LF	95.70000	7943.10	93.00000	7719.00	93.00000	7719.00
0455 0430175224 PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	2418.000 LF	117.00000	282906.00	113.00000	273234.00	114.00000	275652.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0460 0430175236 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	88.000 LF	202.00000	17776.00	196.00000	17248.00	196.00000	17248.00
0465 0430175254 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 54"S/CD	1385.000 LF	266.00000	368410.00	258.00000	357330.00	258.00000	357330.00
0470 0430175272 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 72"S/CD	1244.000 LF	319.00000	396836.00	309.00000	384396.00	310.00000	385640.00
0475 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	5.000 EA	957.00000	4785.00	927.00000	4635.00	930.00000	4650.00
0480 0430982638 MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 36" CD	1.000 EA	3720.00000	3720.00	3605.00000	3605.00	3615.00000	3615.00
0485 0430982642 MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 54" CD	2.000 EA	5530.00000	11060.00	5356.00000	10712.00	5371.00000	10742.00
0490 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	1.000 EA	957.00000	957.00	927.00000	927.00	930.00000	930.00
0495 0430984129 MITERED END SECTION, OPTIONAL ROUND, 24" SD	1.000 EA	1120.00000	1120.00	1082.00000	1082.00	1085.00000	1085.00
0500 0430984138 MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	1.000 EA	3400.00000	3400.00	3296.00000	3296.00	3305.00000	3305.00
0505 0443 70 4 FRENCH DRAIN, 24"	413.000 LF	138.00000	56994.00	134.00000	55342.00	134.00000	55342.00
0510 0455133 2 SHEET PILING STEEL, TEMPORARY-CRITICAL	106467.000 SF	0.10000	10646.70	0.10000	10646.70	0.01000	1064.67
0515 0455133 3 SHEET PILING STEEL, F&I PERMANENT	2548.000 SF	37.20000	94785.60	30.00000	76440.00	25.00000	63700.00
0520 0460 70 1 ALUMINUM BULLET RAILINGS, SINGLE RAIL	140.000 LF	27.40000	3836.00	26.50000	3710.00	33.30000	4662.00
0525 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM	58.000 LF	28.90000	1676.20	28.00000	1624.00	28.30000	1641.40
0530 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	25056.000 LF	12.90000	323222.40	13.00000	325728.00	14.10000	353289.60

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0535 0520 2 4 CONCRETE CURB, TYPE D	37.000 LF	12.80000	473.60	20.00000	740.00	13.80000	510.60
0540 0520 3 VALLEY GUTTER- CONCRETE	594.000 LF	14.10000	8375.40	13.00000	7722.00	11.50000	6831.00
0545 0520 5 42 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	352.000 LF	41.90000	14748.80	28.00000	9856.00	54.00000	19008.00
0550 0521 8 3 CONCRETE TRAFFIC RAILING BARRIER, WITH JUNCTION SLAB, 32" VERTICAL FACE	140.000 LF	273.00000	38220.00	250.00000	35000.00	294.00000	41160.00
0555 0522 1 SIDEWALK CONCRETE, 4" THICK	7114.000 SY	27.50000	195635.00	26.20000	186386.80	32.70000	232627.80
0560 0522 2 SIDEWALK CONCRETE, 6" THICK	556.000 SY	42.10000	23407.60	33.10000	18403.60	42.70000	23741.20
0565 0522 4 BUS SHELTER PAD- CONCRETE	178.000 SY	46.60000	8294.80	42.00000	7476.00	62.70000	11160.60
0570 0523 2 PATTERNED PAVEMENT, NON-VEHICULAR AREAS	448.000 SY	62.90000	28179.20	56.00000	25088.00	62.30000	27910.40
0575 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	482.000 SY	61.60000	29691.20	30.00000	14460.00	41.50000	20003.00
0580 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	155.000 TN	117.00000	18135.00	93.00000	14415.00	93.00000	14415.00
0585 0536 1 1 GUARDRAIL -ROADWAY	38.000 LF	19.20000	729.60	19.00000	722.00	18.80000	714.40
0590 0536 73 GUARDRAIL REMOVAL	28.000 LF	2.70000	75.60	3.00000	84.00	2.60000	72.80
0595 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	2.000 EA	615.00000	1230.00	600.00000	1200.00	603.00000	1206.00
0600 0547 70 1 RIPRAP FABRIC-FORMED CONCRETE, 8" FILTER POINTS	159.000 SY	137.00000	21783.00	130.00000	20670.00	51.20000	8140.80
0605 0550 10222 FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	4481.000 LF	12.60000	56460.60	18.00000	80658.00	16.70000	74832.70
0610 0550 60233 FENCE GATE, TYPE B, SLIDING/CANTILEVER, 12.1-18' OPENING	3.000 EA	1900.00000	5700.00	1840.00000	5520.00	1875.00000	5625.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0615 0570 1 1 PERFORMANCE TURF	8311.000 SY	2.60000	21608.60	0.80000	6648.80	3.10000	25764.10
0617 0570 1 2 PERFORMANCE TURF, SOD	54623.000 SY	3.00000	163869.00	1.95000	106514.85	2.85000	155675.55
0620 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	10.593 NM	898.00000	9512.51	870.00000	9215.91	880.00000	9321.84
0625 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	2675.000 LF	0.20000	535.00	0.20000	535.00	0.20000	535.00
0630 0710 11123 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	4621.000 LF	0.50000	2310.50	0.50000	2310.50	0.50000	2310.50
0635 0710 11124 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	228.000 LF	0.90000	205.20	0.85000	193.80	0.85000	193.80
0640 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	2475.000 LF	1.20000	2970.00	1.20000	2970.00	1.20000	2970.00
0645 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.328 GM	265.00000	86.92	263.00000	86.26	266.00000	87.25
0650 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	1282.000 LF	0.20000	256.40	0.20000	256.40	0.15000	192.30
0655 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	42.50000	1487.50	41.00000	1435.00	41.70000	1459.50
0660 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	141.000 EA	18.10000	2552.10	17.50000	2467.50	17.70000	2495.70
0665 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	9.049 NM	897.00000	8116.95	870.00000	7872.63	880.00000	7963.12
0670 0710 11222 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 8"	598.000 LF	0.20000	119.60	0.20000	119.60	0.20000	119.60

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	(1) AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	(2) AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	(3) AMOUNT
0675 0710 11224 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 18"	854.000 LF	0.90000	768.60	0.85000	725.90	0.85000	725.90
0680 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.130 GM	271.00000	35.23	263.00000	34.19	266.00000	34.58
0685 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	472.000 LF	0.20000	94.40	0.20000	94.40	0.20000	94.40
0690 0730 76110 STEEL CASING, OPEN TRENCH, F&I, 18"	32.000 LF	213.00000	6816.00	206.00000	6592.00	207.00000	6624.00
0695 0730 76113 STEEL CASING, OPEN TRENCH, F&I, 24"	16.000 LF	239.00000	3824.00	239.00000	3824.00	232.00000	3712.00
0700 0730 76116 STEEL CASING, OPEN TRENCH, F&I, 30"	36.000 LF	340.00000	12240.00	330.00000	11880.00	331.00000	11916.00
0705 0730 76119 STEEL CASING, OPEN TRENCH, F&I, 36"	28.000 LF	425.00000	11900.00	412.00000	11536.00	413.00000	11564.00
0710 0730 76130 STEEL CASING, OPEN TRENCH, F&I, 72"	12.000 LF	1060.00000	12720.00	1030.00000	12360.00	1033.00000	12396.00
0715 0999 16 PARTNERING, DO NOT BID 22989725201	LUMP	6000.00000	6000.00	6000.00000	6000.00	6000.00000	6000.00
0720 0999 20 1 DISPUTES REVIEW BOARD, MEETING- DO NOT BID	17.000 DA	3300.00000	56100.00	3300.00000	56100.00	3300.00000	56100.00
0725 0999 20 2 DISPUTES REVIEW BOARD, HEARING- DO NOT BID	2.000 EA	3300.00000	6600.00	3300.00000	6600.00	3300.00000	6600.00
0730 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 22989725201	LUMP	141257.00000	141257.00	141257.00000	141257.00	141257.00000	141257.00
SECTION 0001 TOTALS			$ 7,961,504.82		$ 8,295,236.84		$ 9,385,298.03
SECTION 0002 SIGNING							
0735 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	93.000 AS	388.00000	36084.00	376.00000	34968.00	380.00000	35340.00
0740 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	14.000 AS	601.00000	8414.00	582.00000	8148.00	589.00000	8246.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0745 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	14.000 AS	723.00000	10122.00	700.00000	9800.00	708.00000	9912.00
0750 0700 20 15 SINGLE POST SIGN, F&I, 31 SF	2.000 AS	792.00000	1584.00	767.00000	1534.00	776.00000	1552.00
0755 0700 20 40 SINGLE POST SIGN, RELOCATE	6.000 AS	186.00000	1116.00	180.00000	1080.00	182.00000	1092.00
0760 0700 20 60 SINGLE POST SIGN, REMOVE	81.000 AS	5.30000	429.30	6.00000	486.00	5.20000	421.20
0765 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	7.000 AS	5950.00000	41650.00	3100.00000	21700.00	3125.00000	21875.00
0770 0700 21 40 MULTI- POST SIGN, RELOCATE	1.000 AS	4420.00000	4420.00	2000.00000	2000.00	1979.00000	1979.00
0775 0700 22132 OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL, TRUSS LENGTH 101-150', SIGN AREA 301-500 SF	1.000 AS	132000.00000	132000.00	127720.00000	127720.00	129156.00000	129156.00
0780 0700 90 11 SIGN FLASHING BEACON, F&I GROUND MOUNT	4.000 AS	4300.00000	17200.00	4162.00000	16648.00	4208.00000	16832.00
0785 0705 10 1 OBJECT MARKER, TYPE 1	8.000 EA	79.80000	638.40	78.00000	624.00	78.10000	624.80
0790 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	101.00000	606.00	98.00000	588.00	99.00000	594.00
0795 0705 11 3 DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	3.000 EA	5.30000	15.90	6.00000	18.00	5.20000	15.60
0800 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 22989725201	LUMP	29100.00000	29100.00	28230.00000	28230.00	28548.00000	28548.00
SECTION 0002 TOTALS		$	283,379.60	$	253,544.00	$	256,187.60
SECTION 0003 LIGHTING							
0805 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	27003.000 LF	1.30000	35103.90	1.24000	33483.72	1.25000	33753.75
0810 0715 1 13 LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	2123.000 LF	1.70000	3609.10	1.65000	3502.95	1.65000	3502.95

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0815 0715 1 60 LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	2022.000 LF	0.40000	808.80	0.41000	829.02	0.40000	808.80
0820 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	8520.000 LF	4.00000	34080.00	3.92000	33398.40	3.95000	33654.00
0825 0715 4600 LIGHT POLE COMPLETE, REMOVE	13.000 EA	149.00000	1937.00	144.00000	1872.00	146.00000	1898.00
0830 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	2.000 EA	8040.00000	16080.00	7790.00000	15580.00	7874.00000	15748.00
0835 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	22.000 EA	468.00000	10296.00	453.00000	9966.00	458.00000	10076.00
0840 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	55.000 EA	415.00000	22825.00	402.00000	22110.00	406.00000	22330.00
0845 0715511130 LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30'	55.000 EA	3600.00000	198000.00	3492.00000	192060.00	3531.00000	194205.00
SECTION 0003 TOTALS		$	322,739.80	$	312,802.09	$	315,976.50
SECTION 0004 SIGNALIZATION							
0850 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	689.000 LF	19.10000	13159.90	18.55000	12780.95	18.80000	12953.20
0855 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	441.000 LF	23.40000	10319.40	22.66000	9993.06	22.90000	10098.90
0860 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	4414.000 LF	4.80000	21187.20	4.64000	20480.96	4.70000	20745.80
0865 0630 1 13 CONDUIT - SIGNALS, FURNISH & INSTALL, SAWCUT & PLACE UNDER EXISTING PAVEMENT	42.000 LF	53.20000	2234.40	52.00000	2184.00	52.10000	2188.20
0870 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	3.000 PI	3940.00000	11820.00	3821.00000	11463.00	3864.00000	11592.00
0875 0633121 2 CABLE - FIBER OPTIC, F&I, UNDERGROUND, SGL MODE, 26 - 50PR	4719.000 LF	1.80000	8494.20	1.70000	8022.30	1.70000	8022.30

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0880 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	39.000 EA	510.00000	19890.00	495.00000	19305.00	500.00000	19500.00
0885 0635 1 15 PULL & JUNCTION BOXES, F&I, FIBER OPTIC	13.000 EA	1070.00000	13910.00	1040.00000	13520.00	1052.00000	13676.00
0890 0639 1 23 SIGNALS, ELECTRICAL POWER SERVICE, UNDERGROUND	2.000 AS	1270.00000	2540.00	1226.00000	2452.00	1239.00000	2478.00
0895 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	234.000 LF	1.30000	304.20	1.25000	292.50	1.25000	292.50
0900 0639 3 11 SIGNALS, ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	1.000 EA	202.00000	202.00	196.00000	196.00	198.00000	198.00
0907 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	2.000 EA	702.00000	1404.00	680.00000	1360.00	687.00000	1374.00
0910 0649 31101 STEEL MAST ARM,F&I, WIND SPEED-150, SINGLE ARM, W/0 LUMINAIRE-36	2.000 EA	21900.00000	43800.00	21230.00000	42460.00	21467.00000	42934.00
0915 0649 31102 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-46	2.000 EA	24600.00000	49200.00	23793.00000	47586.00	24060.00000	48120.00
0920 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	2.000 EA	36700.00000	73400.00	35600.00000	71200.00	35997.00000	71994.00
0925 0649 31999 MAST ARM,F&I, CUSTOM WIND SPEED, CUSTOM ARM LENGTH(S)	2.000 EA	33700.00000	67400.00	32610.00000	65220.00	32976.00000	65952.00
0930 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	16.000 AS	787.00000	12592.00	762.00000	12192.00	771.00000	12336.00
0935 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	5.000 AS	1220.00000	6100.00	1185.00000	5925.00	1198.00000	5990.00
0940 0650 54 TRAFFIC SIGNAL, RELOCATE	2.000 AS	638.00000	1276.00	618.00000	1236.00	625.00000	1250.00
0945 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	10.000 AS	574.00000	5740.00	556.00000	5560.00	562.00000	5620.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
0950 0653192 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 2 DIRECTIONS	2.000 AS	1140.00000	2280.00	1103.00000	2206.00	1114.00000	2228.00
0955 0653400 SIGNAL PEDESTRIAN, RELOCATE	1.000 AS	532.00000	532.00	515.00000	515.00	521.00000	521.00
0960 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	5.000 EA	712.00000	3560.00	690.00000	3450.00	698.00000	3490.00
0965 0659407 SIGNAL HEAD AUXILIARIES, RELOCATE, ALUMINUM PEDESTAL	1.000 EA	404.00000	404.00	391.00000	391.00	396.00000	396.00
0970 0660 1104 LOOP DETECTOR, INDUCTIVE, F&I, TYPE 4, 2CHANNEL, SOLID STATE, SHELF MOUNTED, TIME DELAY	2.000 EA	53.20000	106.40	52.00000	104.00	52.10000	104.20
0975 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	2.000 AS	553.00000	1106.00	536.00000	1072.00	542.00000	1084.00
0980 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	11.000 EA	5810.00000	63910.00	5624.00000	61864.00	5687.00000	62557.00
0985 0665 11 PEDESTRIAN DETECTOR, F&I, POLE OR CONTROLLER CABINET MOUNTED DETECTOR STATION & SIGN	2.000 EA	95.70000	191.40	93.00000	186.00	93.80000	187.60
0990 0665 12 PEDESTRIAN DETECTOR, F&I, DETECTOR STATION WITH POST & SIGN	18.000 EA	191.00000	3438.00	186.00000	3348.00	187.00000	3366.00
0995 0665 40 PEDESTRIAN DETECTOR, RELOCATE	2.000 EA	51.00000	102.00	50.00000	100.00	50.00000	100.00
1000 0670 5110 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	2.000 AS	29300.00000	58600.00	28335.00000	56670.00	28654.00000	57308.00
1005 0670 5410 TRAFFIC CONTROLLER ASSEMBLY, MODIFY, NEMA	1.000 AS	404.00000	404.00	392.00000	392.00	396.00000	396.00
1010 0670 5430 TRAFFIC CONTROLLER ASSEMBLY, MODIFY, SPECIAL	1.000 AS	404.00000	404.00	392.00000	392.00	396.00000	396.00
1015 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	9.000 EA	25.50000	229.50	25.00000	225.00	25.00000	225.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
1020 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	25.50000	204.00	25.00000	200.00	25.00000	200.00
1025 0690 34 1 COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	2.000 EA	1910.00000	3820.00	1854.00000	3708.00	1875.00000	3750.00
1030 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	202.00000	202.00	196.00000	196.00	198.00000	198.00
1035 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	14.000 EA	12.80000	179.20	13.00000	182.00	12.50000	175.00
1040 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	914.00000	914.00	885.00000	885.00	896.00000	896.00
1045 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	617.00000	617.00	597.00000	597.00	604.00000	604.00
1050 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	542.00000	542.00	525.00000	525.00	531.00000	531.00
1055 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	7.000 EA	2160.00000	15120.00	2090.00000	14630.00	2114.00000	14798.00
1060 0699 1 41 INTERNAL ILLUM SIGN, RELOCATE, ST NAME	1.000 EA	808.00000	808.00	783.00000	783.00	792.00000	792.00
1065 0700 46 25 SIGN EXISTING- RELOCATE, SPAN WIRE	1.000 AS	351.00000	351.00	340.00000	340.00	344.00000	344.00
1070 0700 48 18 SIGN PANELS, F & I, 15 OR <	3.000 EA	447.00000	1341.00	433.00000	1299.00	437.00000	1311.00
1075 0700 48 60 SIGN PANELS, REMOVE	2.000 EA	25.50000	51.00	25.00000	50.00	25.00000	50.00
1080 0741 70111 TMS VEHICLE SENSOR, CLASS II, F&I, TYP 1, 1/2 LN	4.000 EA	978.00000	3912.00	948.00000	3792.00	958.00000	3832.00
1085 0745 70 12 TMS INDUCTIVE LOOP ASSEM, F&I, 2 LOOPS / LANE	4.000 AS	744.00000	2976.00	721.00000	2884.00	729.00000	2916.00
1090 0746 71112 TMS CABINET, F&I, TYPE III, BASE MOUNT, 2 BACKPLANE	1.000 EA	2230.00000	2230.00	2163.00000	2163.00	2187.00000	2187.00
SECTION 0004 TOTALS		$	533,507.80	$	516,577.77	$	522,257.70
SECTION 0005 LANDSCAPE / PERIPHERAL							

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	(1) AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	(2) AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	(3) AMOUNT
1095 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	140.000 LF	12.80000	1792.00	23.00000	3220.00	91.10000	12754.00
1110 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 22989725201	LUMP	326000.00000	326000.00	322300.00000	322300.00	312474.00000	312474.00
SECTION 0005 TOTALS		$	327,792.00	$	325,520.00	$	325,228.00
SECTION 0006 UTILITIES							
1150 0000700 1 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 1 Support Utility During Construction-LF	913.000 ZZ	21.30000	19446.90	21.00000	19173.00	20.70000	18899.10
1155 0000700 2 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 2 Utility Fittings,F&I,DI/CI-TN	26.000 ZZ	8510.00000	221260.00	8240.00000	214240.00	8263.00000	214838.00
1160 0000700 3 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 3 Utility Fixture, Sample Point-EA	26.000 ZZ	532.00000	13832.00	515.00000	13390.00	516.00000	13416.00
1165 0000700 4 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 4 Bypass Pumping,Grvty Swr Constr-LS	2.000 ZZ	39900.00000	79800.00	36050.00000	72100.00	38733.00000	77466.00
1170 0000700 6 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 6 Pipe, FI, PVC, WT, 8-19.9" - LF	153.000 ZZ	63.80000	9761.40	62.00000	9486.00	62.00000	9486.00
1175 0000700 7 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 7 Pipe, FI, DI/CI, WT, 0-4" - LF	84.000 ZZ	53.20000	4468.80	52.00000	4368.00	51.70000	4342.80
1180 0000700 8 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 8 Pipe,FI,DI/CI,WT,5-7.9"-LF	666.000 ZZ	37.20000	24775.20	36.00000	23976.00	36.20000	24109.20
1185 0000700 9 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 9 Pipe,FI,DI/CI,WT,8-19.9"-LF	6991.000 ZZ	61.70000	431344.70	60.00000	419460.00	59.90000	418760.90
1190 0000700 10 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 10 Pipe,FI,PVC-C900,SW,5-7.9"-LF	856.000 ZZ	37.20000	31843.20	36.00000	30816.00	36.20000	30987.20

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
1195 0000700 11 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 11 Pipe, FI, PVC-C900, SW, 8-19.9", <6' D-L	593.000 ZZ	34.00000	20162.00	33.00000	19569.00	33.10000	19628.30
1200 0000700 12 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 12 Pipe, FI, PVC-C900, SW, 8-19.9", 6-7.9'	901.000 ZZ	69.10000	62259.10	67.00000	60367.00	67.10000	60457.10
1205 0000700 13 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 13 Pipe,FI,PVC-C900,SW,8-19.9",8-9. 9'D-LF	752.000 ZZ	79.80000	60009.60	78.00000	58656.00	77.50000	58280.00
1210 0000700 14 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 14 Pipe,FI,PVC-C900,SW,8-19.9", 10-11.9'D-LF	556.000 ZZ	90.40000	50262.40	88.00000	48928.00	87.80000	48816.80
1215 0000700 15 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 15 Pipe,FI,PVC-C900,SW,8-19.9", 12-13.9'D-LF	363.000 ZZ	79.80000	28967.40	78.00000	28314.00	77.50000	28132.50
1220 0000700 16 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 16 Pipe Liner,FI,Sanitary SW, 8-10"-LF	4890.000 ZZ	37.20000	181908.00	36.10000	176529.00	36.50000	178485.00
1225 0110 1 1 CLEARING & GRUBBING 22989725602	0.200 LS	9320.00000	9320.00	5000.00000	5000.00	1751.00000	1751.00
1230 0110 1 1 CLEARING & GRUBBING 22989725603	0.100 LS	4660.00000	4660.00	5000.00000	5000.00	2627.00000	2627.00
1235 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	298.000 SY	6.40000	1907.20	7.50000	2235.00	13.50000	4023.00
1240 0160 4 TYPE B STABILIZATION	1449.000 SY	5.30000	7679.70	2.05000	2970.45	9.95000	14417.55
1245 0285711 OPTIONAL BASE, BASE GROUP 11	1414.000 SY	34.00000	48076.00	38.25000	54085.50	15.80000	22341.20
1250 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	182.400 TN	95.70000	17455.68	105.00000	19152.00	150.00000	27360.00
1255 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	155.000 LF	16.00000	2480.00	13.00000	2015.00	14.60000	2263.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
1260 0555 1 5 DIRECTIONAL BORE, 24" TO < 36"	429.000 LF	319.00000	136851.00	309.00000	132561.00	310.00000	132990.00
1265 0570 1 2 PERFORMANCE TURF, SOD	1288.000 SY	4.40000	5667.20	3.00000	3864.00	4.15000	5345.20
1270 0730 76107 STEEL CASING, OPEN TRENCH, F&I, 12"	33.000 LF	638.00000	21054.00	309.00000	10197.00	620.00000	20460.00
1275 0730 76111 STEEL CASING, OPEN TRENCH, F&I, 20"	124.000 LF	1280.00000	158720.00	1236.00000	153264.00	1239.00000	153636.00
1280 0730 76123 STEEL CASING, OPEN TRENCH, F&I, 48"	66.000 LF	4360.00000	287760.00	2223.00000	146718.00	4235.00000	279510.00
1285 1050 11212 UTILITY PIPE, F&I, PVC, CASING / CONDUIT, 2-4.9"	1131.000 LF	11.70000	13232.70	12.00000	13572.00	11.40000	12893.40
1290 1050 11321 UTILITY PIPE, F&I, PE, WATER / SEWER, 0 - 1.9"	1848.000 LF	10.60000	19588.80	11.00000	20328.00	10.30000	19034.40
1295 1050 11512 UTILITY PIPE, F&I, STEEL, CASING / CONDUIT, 2.0-4.9"	55.000 LF	12.80000	704.00	13.00000	715.00	12.40000	682.00
1300 1050 15002 UTILITY PIPE, ADJUST/MODIFY, 2 - 4.9"	330.000 LF	16.00000	5280.00	16.00000	5280.00	15.50000	5115.00
1305 1050 16002 UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	757.000 LF	10.60000	8024.20	11.00000	8327.00	10.30000	7797.10
1310 1050 16003 UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	534.000 LF	12.80000	6835.20	13.00000	6942.00	12.40000	6621.60
1315 1050 16004 UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	3649.000 LF	14.90000	54370.10	15.00000	54735.00	14.50000	52910.50
1320 1050 18000 UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, CAP FOR UP TO 4" DIAMETER PIPE	5963.000 EA	9.60000	57244.80	10.00000	59630.00	9.30000	55455.90
1325 1050 18004 UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	5820.000 LF	8.50000	49470.00	9.00000	52380.00	8.25000	48015.00
1330 1055 11254 UTILITY FITTING, F&I, PVC, CAP/PLUG, 8 - 19.9"	11.000 EA	159.00000	1749.00	155.00000	1705.00	155.00000	1705.00
1335 1055 11264 UTILITY FITTING, F&I, PVC, Y FITTING, 8 - 19.9"	25.000 EA	478.00000	11950.00	464.00000	11600.00	465.00000	11625.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
1340 1055 11273 UTILITY FITTING, F&I, PVC, CLEANOUT	25.000 EA	638.00000	15950.00	618.00000	15450.00	620.00000	15500.00
1345 1055 16 UTILITY FITTINGS, REMOVE & DISPOSAL	75.000 EA	106.00000	7950.00	103.00000	7725.00	103.00000	7725.00
1350 1060 11222 UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, 6.1 - 12'	13.000 EA	6380.00000	82940.00	6180.00000	80340.00	6197.00000	80561.00
1355 1060 11223 UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, > 12'	2.000 EA	7970.00000	15940.00	7725.00000	15450.00	7747.00000	15494.00
1360 1060 15 UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	20.000 EA	505.00000	10100.00	490.00000	9800.00	491.00000	9820.00
1365 1060 16 UTILITY STRUCTURE, BELOW GROUND, REMOVE&DISPOSE CONTRACTOR TAKES OWNERSHIP	13.000 EA	851.00000	11063.00	824.00000	10712.00	826.00000	10738.00
1370 1080 11101 UTILITY FIXTURES, F&I, 0 - 1.9", VALVE/METER BOX	25.000 EA	319.00000	7975.00	309.00000	7725.00	310.00000	7750.00
1375 1080 11203 UTILITY FIXTURES, F&I, 2-4.9", TAPPING SADDLE/SLEEVE	30.000 EA	532.00000	15960.00	515.00000	15450.00	516.00000	15480.00
1380 1080 11204 UTILITY FIXTURES, F&I, 2-4.9", VALVE ASSEMBLY	7.000 EA	638.00000	4466.00	618.00000	4326.00	620.00000	4340.00
1385 1080 11206 UTILITY FIXTURES, F&I, 2-4.9", VAC/AIR ASSEMBLY	7.000 EA	8510.00000	59570.00	8240.00000	57680.00	8263.00000	57841.00
1390 1080 11207 UTILITY FIXTURES, F&I, 2-4.9", LINE STOP ASSEMBLY	3.000 EA	2870.00000	8610.00	2781.00000	8343.00	2789.00000	8367.00
1395 1080 11304 UTILITY FIXTURES, F&I, 5.0 - 7.9", VALVE ASSEMBLY	33.000 EA	1060.00000	34980.00	1030.00000	33990.00	1033.00000	34089.00
1400 1080 11307 UTILITY FIXTURES, F&I, 5-7.9", LINE STOP ASSEMBLY	3.000 EA	5100.00000	15300.00	4944.00000	14832.00	4958.00000	14874.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) RANGER CONSTRUCTION INDUSTR UNIT PRICE	 AMOUNT	(2) J.W. CHEATHAM, LLC UNIT PRICE	 AMOUNT	(3) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT
1405 1080 11404 UTILITY FIXTURES, F&I, 8.0-19.9", VALVE ASSEMBLY	68.000 EA	1810.00000	123080.00	1751.00000	119068.00	1756.00000	119408.00
1410 1080 11407 UTILITY FIXTURES, F&I, 8-19.9", LINE STOP ASSEMBLY	10.000 EA	9570.00000	95700.00	9270.00000	92700.00	9296.00000	92960.00
1415 1080 11409 UTILITY FIXTURES, F&I, 8-19.9", MECHANICAL JOINT RESTRAINT	24.000 EA	532.00000	12768.00	515.00000	12360.00	516.00000	12384.00
1420 1080 14 UTILITY FIXTURES, RELOCATE	27.000 EA	532.00000	14364.00	515.00000	13905.00	516.00000	13932.00
1425 1080 15 UTILITY FIXTURES, ADJUST & MODIFY	9.000 EA	532.00000	4788.00	515.00000	4635.00	516.00000	4644.00
1430 1080 16 UTILITY FIXTURES, REMOVE & DISPOSE	26.000 EA	213.00000	5538.00	206.00000	5356.00	207.00000	5382.00
1435 1644136 08 FIRE HYDRANT, F&I, TRAFFIC, 3 WAY - 2 HOSE, 1PUMPER, 6"	13.000 EA	3190.00000	41470.00	3090.00000	40170.00	3099.00000	40287.00
1440 1644900 FIRE HYDRANT, REMOVE	9.000 EA	213.00000	1917.00	206.00000	1854.00	207.00000	1863.00
SECTION 0006 TOTALS			$ 2,760,609.28		$ 2,543,518.95		$ 2,668,122.75
CONTRACT TOTALS			$ 12,189,533.30		$ 12,247,199.65		$ 13,473,070.58

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 22989725201	LUMP	1415792.54200	1415792.54	1450000.00000	1450000.00		
0010 0102 1 MAINTENANCE OF TRAFFIC 22989725201	500.000 LS	504709.00000	504709.00	1290000.00000	1290000.00		
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	836.000 CY	61.07200	51056.19	65.00000	54340.00		
0020 0102 14 TRAFFIC CONTROL OFFICER	624.000 MH	44.17500	27565.20	45.00000	28080.00		
0025 0102 60 WORK ZONE SIGN	69002.000 ED	0.30800	21252.62	0.20000	13800.40		
0030 0102 61 BUSINESS SIGN	10.000 EA	30.72900	307.29	45.00000	450.00		
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1116.000 LF	136.73200	152592.91	21.00000	23436.00		
0040 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	6135.000 LF	4.11300	25233.26	22.00000	134970.00		
0045 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	201.000 LF	2.47500	497.48	4.00000	804.00		
0050 0102 71 24 BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	3506.000 LF	3.42800	12018.57	3.75000	13147.50		
0055 0102 74 1 BARRICADE, TEMPORARY, TYPES I, II, DI, VP & DRUM	109474.000 ED	0.14300	15654.78	0.12000	13136.88		
0060 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	4138.000 ED	0.30800	1274.50	0.16000	662.08		
0065 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	187.000 ED	7.17000	1340.79	5.00000	935.00		
0070 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	23676.000 ED	0.30800	7292.21	0.04000	947.04		
0075 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	1687.000 EA	3.07300	5184.15	2.50000	4217.50		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0080 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	17582.000 ED	0.29700	5221.85	0.04000	703.28		
0085 0102 89 7 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	20.000 LO	819.45600	16389.12	800.00000	16000.00		
0090 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	1138.000 ED	13.31600	15153.61	12.00000	13656.00		
0095 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	1500.000 ED	102.43200	153648.00	8.50000	12750.00		
0100 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	1500.000 ED	102.43200	153648.00	8.50000	12750.00		
0105 0104 10 3 SEDIMENT BARRIER	5732.000 LF	0.76900	4407.91	3.00000	17196.00		
0110 0104 11 FLOATING TURBIDITY BARRIER	64.000 LF	6.65800	426.11	20.00000	1280.00		
0115 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	56.000 LF	9.73100	544.94	13.00000	728.00		
0120 0104 15 SOIL TRACKING PREVENTION DEVICE	14.000 EA	957.50800	13405.11	100.00000	1400.00		
0125 0104 18 INLET PROTECTION SYSTEM	106.000 EA	56.33800	5971.83	190.00000	20140.00		
0130 0107 1 LITTER REMOVAL	321.900 AC	19.84100	6386.82	15.00000	4828.50		
0135 0107 2 MOWING	321.900 AC	409.72800	131891.44	25.00000	8047.50		
0140 0110 1 1 CLEARING & GRUBBING 22989725201	24.680 LS	302195.71000	302195.71	725000.00000	725000.00		
0145 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	6666.000 SY	47.30700	315348.46	60.00000	399960.00		
0150 0120 1 REGULAR EXCAVATION	59835.000 CY	4.68700	280446.65	13.00000	777855.00		
0155 0120 6 EMBANKMENT	5980.000 CY	2.02100	12085.58	10.00000	59800.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0160 0160 4 TYPE B STABILIZATION	49715.000 SY	6.63200	329709.88	15.00000	745725.00		
0165 0285701 OPTIONAL BASE, BASE GROUP 01	165.000 SY	4.81800	794.97	33.00000	5445.00		
0170 0285706 OPTIONAL BASE, BASE GROUP 06	772.000 SY	10.43100	8052.73	47.00000	36284.00		
0175 0285709 OPTIONAL BASE, BASE GROUP 09	29641.000 SY	10.55400	312831.11	27.00000	800307.00		
0180 0285711 OPTIONAL BASE, BASE GROUP 11	4091.000 SY	12.93600	52921.18	47.00000	192277.00		
0185 0285713 OPTIONAL BASE, BASE GROUP 13	1916.000 SY	14.70100	28167.12	77.00000	147532.00		
0190 0285715 OPTIONAL BASE, BASE GROUP 15	1118.000 SY	107.55400	120245.37	75.00000	83850.00		
0195 0286 1 TURNOUT CONSTRUCTION	687.000 SY	102.43200	70370.78	110.00000	75570.00		
0200 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	18940.000 SY	2.04800	38789.12	1.75000	33145.00		
0205 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	14144.000 SY	2.04800	28966.91	1.75000	24752.00		
0210 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	83.500 TN	103.16200	8614.03	90.00000	7515.00		
0215 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	2005.400 TN	103.16200	206881.07	90.00000	180486.00		
0220 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	5735.000 TN	106.10900	608535.12	105.00000	602175.00		
0225 0337 7 45 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC D, FC-12.5, PG 76-22	3938.100 TN	112.67500	443725.42	105.00000	413500.50		
0230 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	110.600 TN	92.18900	10196.10	150.00000	16590.00		
0235 0350 1 3 PLAIN CEMENT CONCRETE PAVEMENT, 8"	129.000 SY	60.43500	7796.12	85.00000	10965.00		
0240 0400 1 2 CONCRETE CLASS I, ENDWALLS	14.400 CY	825.28900	11884.16	900.00000	12960.00		
0245 0400 2 1 CONCRETE CLASS II, CULVERTS	2.200 CY	409.73100	901.41	2000.00000	4400.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0250 0400 2 2 CONCRETE CLASS II, ENDWALLS	37.600 CY	431.20900	16213.46	1500.00000	56400.00		
0255 0415 1 1 REINF STEEL- ROADWAY	3570.000 LB	0.97300	3473.61	2.00000	7140.00		
0260 0425 1201 INLETS, CURB, TYPE 9, <10'	5.000 EA	3574.11600	17870.58	2700.00000	13500.00		
0265 0425 1203 INLETS, CURB, TYPE 9, J BOT, <10'	1.000 EA	4323.72000	4323.72	4500.00000	4500.00		
0270 0425 1331 INLETS, CURB, TYPE P-3, <10'	2.000 EA	4686.47000	9372.94	5000.00000	10000.00		
0275 0425 1332 INLETS, CURB. TYPE P-3, >10'	1.000 EA	13397.51000	13397.51	7000.00000	7000.00		
0280 0425 1341 INLETS, CURB, TYPE P-4, <10'	3.000 EA	4830.49300	14491.48	5000.00000	15000.00		
0285 0425 1351 INLETS, CURB, TYPE P-5, <10'	7.000 EA	3929.47200	27506.30	4000.00000	28000.00		
0290 0425 1352 INLETS, CURB, TYPE P-5, >10'	1.000 EA	11899.32000	11899.32	4300.00000	4300.00		
0295 0425 1361 INLETS, CURB, TYPE P-6, <10'	15.000 EA	4186.00800	62790.12	4000.00000	60000.00		
0300 0425 1431 INLETS, CURB, TYPE J-3, <10'	2.000 EA	6947.97000	13895.94	12000.00000	24000.00		
0305 0425 1441 INLETS, CURB, TYPE J-4, <10'	2.000 EA	7298.07500	14596.15	12500.00000	25000.00		
0310 0425 1451 INLETS, CURB, TYPE J-5, <10'	3.000 EA	4680.14700	14040.44	5200.00000	15600.00		
0315 0425 1452 INLETS, CURB, TYPE J-5, >10'	3.000 EA	15170.13300	45510.40	9500.00000	28500.00		
0320 0425 1461 INLETS, CURB, TYPE J-6, <10'	6.000 EA	5273.13100	31638.79	6500.00000	39000.00		
0325 0425 1521 INLETS, DT BOT, TYPE C,<10'	9.000 EA	3172.48800	28552.39	1700.00000	15300.00		
0330 0425 1523 INLETS, DT BOT, TYPE C,JBOT, <10'	3.000 EA	4768.46300	14305.39	6000.00000	18000.00		
0335 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	1.000 EA	2946.43000	2946.43	2500.00000	2500.00		
0340 0425 1541 INLETS, DT BOT, TYPE D, <10'	2.000 EA	864.23000	1728.46	2500.00000	5000.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0345 0425 1581 INLETS, DT BOT, TYPE H, <10'	1.000 EA	4481.42000	4481.42	4500.00000	4500.00		
0350 0425 1910 INLETS, CLOSED FLUME	10.000 EA	4300.11200	43001.12	8000.00000	80000.00		
0355 0425 2 41 MANHOLES, P-7, <10'	10.000 EA	5020.30600	50203.06	4000.00000	40000.00		
0360 0425 2 42 MANHOLES, P-7, >10'	9.000 EA	6919.70900	62277.38	5000.00000	45000.00		
0365 0425 2 43 MANHOLES, P-7, PARTIAL	7.000 EA	3322.47000	23257.29	2200.00000	15400.00		
0370 0425 2 71 MANHOLES, J-7, <10'	5.000 EA	11562.07600	57810.38	16000.00000	80000.00		
0375 0425 2 72 MANHOLES, J-7, >10'	9.000 EA	25200.90800	226808.17	16000.00000	144000.00		
0380 0425 2 73 MANHOLES, J-7, PARTIAL	1.000 EA	3659.92000	3659.92	2200.00000	2200.00		
0385 0425 2 91 MANHOLES, J-8, <10'	3.000 EA	7971.09000	23913.27	16000.00000	48000.00		
0390 0425 2 93 MANHOLES, J-8, PARTIAL	3.000 EA	11394.28700	34182.86	2200.00000	6600.00		
0395 0425 74 1 MANHOLES & INLETS CLEANING & SEALING, <10'	22.000 EA	1205.98900	26531.76	1250.00000	27500.00		
0400 0430 94 1 DESILTING PIPE, 0 - 24"	2131.000 LF	2.47200	5267.83	2.50000	5327.50		
0405 0430 94 2 DESILTING PIPE, 25 - 36"	1066.000 LF	2.96600	3161.76	3.00000	3198.00		
0410 0430174118 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	16.000 LF	65.46900	1047.50	50.00000	800.00		
0415 0430174124 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	54.000 LF	70.22100	3791.93	60.00000	3240.00		
0420 0430174136 PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	13.000 LF	88.18100	1146.35	100.00000	1300.00		
0425 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	2502.000 LF	27.89100	69783.28	62.00000	155124.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0430 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	474.000 LF	34.62100	16410.35	65.00000	30810.00		
0435 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	94.000 LF	79.76800	7498.19	100.00000	9400.00		
0440 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	472.000 LF	57.82800	27294.82	120.00000	56640.00		
0445 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	8.000 LF	110.67600	885.41	200.00000	1600.00		
0450 0430175218 PIPE CULVERT,OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	83.000 LF	71.46200	5931.35	90.00000	7470.00		
0455 0430175224 PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	2418.000 LF	45.40600	109791.71	110.00000	265980.00		
0460 0430175236 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 36"S/CD	88.000 LF	112.85700	9931.42	190.00000	16720.00		
0465 0430175254 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 54"S/CD	1385.000 LF	155.20900	214964.47	250.00000	346250.00		
0470 0430175272 PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 72"S/CD	1244.000 LF	242.71500	301937.46	300.00000	373200.00		
0475 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	5.000 EA	796.72600	3983.63	900.00000	4500.00		
0480 0430982638 MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 36" CD	1.000 EA	6403.35000	6403.35	3500.00000	3500.00		
0485 0430982642 MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 54" CD	2.000 EA	3662.17000	7324.34	5200.00000	10400.00		
0490 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	1.000 EA	5542.86000	5542.86	900.00000	900.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0495 0430984129 MITERED END SECTION, OPTIONAL ROUND, 24" SD	1.000 EA	5613.99000	5613.99	1050.00000	1050.00		
0500 0430984138 MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	1.000 EA	5424.17000	5424.17	3200.00000	3200.00		
0505 0443 70 4 FRENCH DRAIN, 24"	413.000 LF	749.28600	309455.12	130.00000	53690.00		
0510 0455133 2 SHEET PILING STEEL, TEMPORARY-CRITICAL	106467.000 SF	8.54200	909441.11	0.01000	1064.67		
0515 0455133 3 SHEET PILING STEEL, F&I PERMANENT	2548.000 SF	21.12400	53823.95	64.53000	164422.44		
0520 0460 70 1 ALUMINUM BULLET RAILINGS, SINGLE RAIL	140.000 LF	26.34500	3688.30	25.00000	3500.00		
0525 0515 1 2 PIPE HANDRAIL - GUIDERAIL, ALUMINUM	58.000 LF	27.80000	1612.40	27.00000	1566.00		
0530 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	25056.000 LF	12.54800	314402.69	18.00000	451008.00		
0535 0520 2 4 CONCRETE CURB, TYPE D	37.000 LF	25.60800	947.50	12.50000	462.50		
0540 0520 3 VALLEY GUTTER- CONCRETE	594.000 LF	21.25500	12625.47	18.00000	10692.00		
0545 0520 5 42 TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	352.000 LF	35.85100	12619.55	20.00000	7040.00		
0550 0521 8 3 CONCRETE TRAFFIC RAILING BARRIER, WITH JUNCTION SLAB, 32" VERTICAL FACE	140.000 LF	257.10400	35994.56	216.00000	30240.00		
0555 0522 1 SIDEWALK CONCRETE, 4" THICK	7114.000 SY	29.70500	211321.37	35.00000	248990.00		
0560 0522 2 SIDEWALK CONCRETE, 6" THICK	556.000 SY	37.90000	21072.40	50.00000	27800.00		
0565 0522 4 BUS SHELTER PAD- CONCRETE	178.000 SY	54.80100	9754.58	130.00000	23140.00		
0570 0523 2 PATTERNED PAVEMENT, NON-VEHICULAR AREAS	448.000 SY	56.33800	25239.42	60.00000	26880.00		
0575 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	482.000 SY	41.99800	20243.04	65.00000	31330.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0580 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	155.000 TN	88.09100	13654.11	90.00000	13950.00		
0585 0536 1 1 GUARDRAIL -ROADWAY	38.000 LF	18.51000	703.38	17.00000	646.00		
0590 0536 73 GUARDRAIL REMOVAL	28.000 LF	2.56100	71.71	2.00000	56.00		
0595 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	2.000 EA	592.67500	1185.35	550.00000	1100.00		
0600 0547 70 1 RIPRAP FABRIC-FORMED CONCRETE, 8" FILTER POINTS	159.000 SY	76.82400	12215.02	175.00000	27825.00		
0605 0550 10222 FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	4481.000 LF	16.39000	73443.59	15.00000	67215.00		
0610 0550 60233 FENCE GATE, TYPE B, SLIDING/CANTILEVER, 12.1-18' OPENING	3.000 EA	1843.77300	5531.32	1700.00000	5100.00		
0615 0570 1 1 PERFORMANCE TURF	8311.000 SY	1.93600	16090.10	5.00000	41555.00		
0617 0570 1 2 PERFORMANCE TURF, SOD	54623.000 SY	2.25000	122901.75	6.00000	327738.00		
0620 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	10.593 NM	973.85100	10316.00	835.00000	8845.16		
0625 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	2675.000 LF	0.43000	1150.25	0.16000	428.00		
0630 0710 11123 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	4621.000 LF	0.70700	3267.05	0.46000	2125.66		
0635 0710 11124 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 18"	228.000 LF	1.12700	256.96	0.75000	171.00		
0640 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	2475.000 LF	1.33100	3294.23	1.00000	2475.00		
0645 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.328 GM	438.01800	143.67	235.00000	77.08		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0650 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	1282.000 LF	0.35800	458.96	0.15000	192.30		
0655 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	35.000 EA	56.33800	1971.83	35.00000	1225.00		
0660 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	141.000 EA	35.85100	5054.99	16.50000	2326.50		
0665 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	9.049 NM	1280.54100	11587.62	800.00000	7239.20		
0670 0710 11222 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 8"	598.000 LF	1.17800	704.44	0.16000	95.68		
0675 0710 11224 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 18"	854.000 LF	1.43400	1224.64	0.75000	640.50		
0680 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.130 GM	2765.69200	359.54	250.00000	32.50		
0685 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	472.000 LF	0.61400	289.81	0.15000	70.80		
0690 0730 76110 STEEL CASING, OPEN TRENCH, F&I, 18"	32.000 LF	135.60500	4339.36	230.00000	7360.00		
0695 0730 76113 STEEL CASING, OPEN TRENCH, F&I, 24"	16.000 LF	135.60200	2169.63	270.00000	4320.00		
0700 0730 76116 STEEL CASING, OPEN TRENCH, F&I, 30"	36.000 LF	135.60400	4881.74	330.00000	11880.00		
0705 0730 76119 STEEL CASING, OPEN TRENCH, F&I, 36"	28.000 LF	135.60300	3796.88	350.00000	9800.00		
0710 0730 76130 STEEL CASING, OPEN TRENCH, F&I, 72"	12.000 LF	135.60600	1627.27	590.00000	7080.00		
0715 0999 16 PARTNERING, DO NOT BID 22989725201	LUMP	6000.00000	6000.00	6000.00000	6000.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0720 0999 20 1 DISPUTES REVIEW BOARD, MEETING- DO NOT BID	17.000 DA	3300.00000	56100.00	3300.00000	56100.00		
0725 0999 20 2 DISPUTES REVIEW BOARD, HEARING- DO NOT BID	2.000 EA	3300.00000	6600.00	3300.00000	6600.00		
0730 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 22989725201	LUMP	141257.00000	141257.00	141257.00000	141257.00		
SECTION 0001 TOTALS			$ 10,121,031.12		$ 12,510,400.67		$
SECTION 0002 SIGNING							
0735 0700 20 11 SINGLE POST SIGN, F&I, LESS THAN 12 SF	93.000 AS	529.57300	49250.29	245.00000	22785.00		
0740 0700 20 12 SINGLE POST SIGN, F&I, 12-20 SF	14.000 AS	854.28300	11959.96	735.00000	10290.00		
0745 0700 20 14 SINGLE POST SIGN, F&I, 21-30 SF	14.000 AS	921.88800	12906.43	950.00000	13300.00		
0750 0700 20 15 SINGLE POST SIGN, F&I, 31 SF	2.000 AS	1324.45000	2648.90	900.00000	1800.00		
0755 0700 20 40 SINGLE POST SIGN, RELOCATE	6.000 AS	457.87200	2747.23	145.00000	870.00		
0760 0700 20 60 SINGLE POST SIGN, REMOVE	81.000 AS	28.68100	2323.16	11.00000	891.00		
0765 0700 21 11 MULTI- POST SIGN, F&I, 50 SF OR LESS	7.000 AS	3987.67700	27913.74	3100.00000	21700.00		
0770 0700 21 40 MULTI- POST SIGN, RELOCATE	1.000 AS	3533.89000	3533.89	750.00000	750.00		
0775 0700 22132 OVERHEAD TRUSS SPAN SIGN, FURNISH & INSTALL, TRUSS LENGTH 101-150', SIGN AREA 301-500 SF	1.000 AS	165332.33000	165332.33	145000.00000	145000.00		
0780 0700 90 11 SIGN FLASHING BEACON, F&I GROUND MOUNT	4.000 AS	7941.55300	31766.21	7500.00000	30000.00		
0785 0705 10 1 OBJECT MARKER, TYPE 1	8.000 EA	265.29900	2122.39	110.00000	880.00		
0790 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	265.30000	1591.80	110.00000	660.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0795 0705 11 3 DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	3.000 EA	376.95300	1130.86	75.00000	225.00		
0800 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 22989725201	LUMP	148526.33000	148526.33	20000.00000	20000.00		
SECTION 0002 TOTALS		$	463,753.52	$	269,151.00	$	
SECTION 0003 LIGHTING							
0805 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	27003.000 LF	1.22900	33186.69	1.10000	29703.30		
0810 0715 1 13 LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	2123.000 LF	2.97000	6305.31	2.75000	5838.25		
0815 0715 1 60 LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	2022.000 LF	0.61400	1241.51	0.55000	1112.10		
0820 0715 2 11 LIGHTING - CONDUIT, F&I, UNDERGROUND	8520.000 LF	6.55600	55857.12	6.20000	52824.00		
0825 0715 4600 LIGHT POLE COMPLETE, REMOVE	13.000 EA	228.42300	2969.50	200.00000	2600.00		
0830 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	2.000 EA	6021.97500	12043.95	5500.00000	11000.00		
0835 0715 14 11 LIGHTING - PULL BOX, F&I, ROADSIDE-MOULDED	22.000 EA	405.63100	8923.88	375.00000	8250.00		
0840 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	55.000 EA	313.44200	17239.31	290.00000	15950.00		
0845 0715511130 LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, SINGLE ARM SHOULDER MOUNT, ALUMINUM, 30'	55.000 EA	3265.53100	179604.21	3000.00000	165000.00		
SECTION 0003 TOTALS		$	317,371.48	$	292,277.65	$	
SECTION 0004 SIGNALIZATION							

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0850 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	689.000 LF	13.52100	9315.97	13.00000	8957.00		
0855 0555 1 2 DIRECTIONAL BORE, 6" TO < 12"	441.000 LF	27.04200	11925.52	25.00000	11025.00		
0860 0630 1 12 CONDUIT - SIGNALS, FURNISH & INSTALL, UNDERGROUND	4414.000 LF	5.42900	23963.61	5.00000	22070.00		
0865 0630 1 13 CONDUIT - SIGNALS, FURNISH & INSTALL, SAWCUT & PLACE UNDER EXISTING PAVEMENT	42.000 LF	23.96900	1006.70	23.00000	966.00		
0870 0632 7 1 CABLE, SIGNAL, FURNISH & INSTALL	3.000 PI	4910.59000	14731.77	4700.00000	14100.00		
0875 0633121 2 CABLE - FIBER OPTIC, F&I, UNDERGROUND, SGL MODE, 26 - 50PR	4719.000 LF	6.04300	28516.92	5.00000	23595.00		
0880 0635 1 11 PULL & JUNCTION BOXES, F&I, PULL BOX	39.000 EA	405.63100	15819.61	395.00000	15405.00		
0885 0635 1 15 PULL & JUNCTION BOXES, F&I, FIBER OPTIC	13.000 EA	1065.29400	13848.82	1000.00000	13000.00		
0890 0639 1 23 SIGNALS, ELECTRICAL POWER SERVICE, UNDERGROUND	2.000 AS	1276.30500	2552.61	1200.00000	2400.00		
0895 0639 2 1 SIGNALS, ELECTRICAL SERVICE WIRE	234.000 LF	2.04800	479.23	2.00000	468.00		
0900 0639 3 11 SIGNALS, ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	1.000 EA	557.24000	557.24	500.00000	500.00		
0907 0641 2 12 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	2.000 EA	1240.00000	2480.00	1000.00000	2000.00		
0910 0649 31101 STEEL MAST ARM,F&I, WIND SPEED-150, SINGLE ARM, W/0 LUMINAIRE-36	2.000 EA	21016.99000	42033.98	20000.00000	40000.00		
0915 0649 31102 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-46	2.000 EA	24129.90000	48259.80	21000.00000	42000.00		
0920 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	2.000 EA	35813.28500	71626.57	32000.00000	64000.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0925 0649 31999 MAST ARM,F&I, CUSTOM WIND SPEED, CUSTOM ARM LENGTH(S)	2.000 EA	34696.77500	69393.55	30000.00000	60000.00		
0930 0650 51311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, STANDARD	16.000 AS	703.70800	11259.33	650.00000	10400.00		
0935 0650 51511 TRAFFIC SIGNAL, F&I, 5 SECTIONS, 1 WAY, STANDARD	5.000 AS	1161.57800	5807.89	1100.00000	5500.00		
0940 0650 54 TRAFFIC SIGNAL, RELOCATE	2.000 AS	228.42500	456.85	200.00000	400.00		
0945 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	10.000 AS	534.69400	5346.94	500.00000	5000.00		
0950 0653192 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 2 DIRECTIONS	2.000 AS	1068.37000	2136.74	1000.00000	2000.00		
0955 0653400 SIGNAL PEDESTRIAN, RELOCATE	1.000 AS	228.43000	228.43	222.00000	222.00		
0960 0659107 SIGNAL HEAD AUXILIARIES, F&I, ALUMINUM PEDESTAL	5.000 EA	661.71000	3308.55	635.00000	3175.00		
0965 0659407 SIGNAL HEAD AUXILIARIES, RELOCATE, ALUMINUM PEDESTAL	1.000 EA	522.41000	522.41	500.00000	500.00		
0970 0660 1104 LOOP DETECTOR, INDUCTIVE, F&I, TYPE 4, 2CHANNEL, SOLID STATE, SHELF MOUNTED, TIME DELAY	2.000 EA	255.06000	510.12	240.00000	480.00		
0975 0660 2106 LOOP ASSEMBLY, F&I, TYPE F	2.000 AS	1240.45500	2480.91	1200.00000	2400.00		
0980 0663 74 15 VEHICLE DETECTOR ASSEMBLIES, F&I, VIDEO	11.000 EA	5057.06600	55627.73	4500.00000	49500.00		
0985 0665 11 PEDESTRIAN DETECTOR, F&I, POLE OR CONTROLLER CABINET MOUNTED DETECTOR STATION & SIGN	2.000 EA	186.43000	372.86	175.00000	350.00		
0990 0665 12 PEDESTRIAN DETECTOR, F&I, DETECTOR STATION WITH POST & SIGN	18.000 EA	186.42600	3355.67	175.00000	3150.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0995 0665 40 PEDESTRIAN DETECTOR, RELOCATE	2.000 EA	1792.56000	3585.12	220.00000	440.00		
1000 0670 5110 TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	2.000 AS	30777.72500	61555.45	29000.00000	58000.00		
1005 0670 5410 TRAFFIC CONTROLLER ASSEMBLY, MODIFY, NEMA	1.000 AS	1241.48000	1241.48	1100.00000	1100.00		
1010 0670 5430 TRAFFIC CONTROLLER ASSEMBLY, MODIFY, SPECIAL	1.000 AS	1241.48000	1241.48	1100.00000	1100.00		
1015 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	9.000 EA	57.36200	516.26	55.00000	495.00		
1020 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	57.36400	458.91	55.00000	440.00		
1025 0690 34 1 COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	2.000 EA	456.85500	913.71	445.00000	890.00		
1030 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	1.000 EA	685.28000	685.28	650.00000	650.00		
1035 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	14.000 EA	57.36200	803.07	50.00000	700.00		
1040 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	685.28000	685.28	650.00000	650.00		
1045 0690 90 CONDUIT & CABLING REMOVE	1.000 PI	685.28000	685.28	650.00000	650.00		
1050 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	1.000 PI	685.28000	685.28	650.00000	650.00		
1055 0699 1 1 INTERNAL ILLUM SIGN, FURNISH & INSTALL, STREET NAME	7.000 EA	2656.06000	18592.42	2600.00000	18200.00		
1060 0699 1 41 INTERNAL ILLUM SIGN, RELOCATE, ST NAME	1.000 EA	1012.03000	1012.03	975.00000	975.00		
1065 0700 46 25 SIGN EXISTING- RELOCATE, SPAN WIRE	1.000 AS	393.35000	393.35	375.00000	375.00		
1070 0700 48 18 SIGN PANELS, F & I, 15 OR <	3.000 EA	213.06300	639.19	200.00000	600.00		
1075 0700 48 60 SIGN PANELS, REMOVE	2.000 EA	57.36500	114.73	55.00000	110.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1080 0741 70111 TMS VEHICLE SENSOR, CLASS II, F&I, TYP 1, 1/2 LN	4.000 EA	1364.39500	5457.58	1300.00000	5200.00		
1085 0745 70 12 TMS INDUCTIVE LOOP ASSEM, F&I, 2 LOOPS / LANE	4.000 AS	1116.51300	4466.05	1000.00000	4000.00		
1090 0746 71112 TMS CABINET, F&I, TYPE III, BASE MOUNT, 2 BACKPLANE	1.000 EA	3467.32000	3467.32	3350.00000	3350.00		
SECTION 0004 TOTALS		$	555,125.60	$	502,138.00	$	
SECTION 0005 LANDSCAPE / PERIPHERAL							
1095 0555 1 1 DIRECTIONAL BORE, LESS THAN 6"	140.000 LF	19.25700	2695.98	19.00000	2660.00		
1110 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 22989725201	LUMP	1.94000	1.94	250000.00000	250000.00		
SECTION 0005 TOTALS		$	2,697.92	$	252,660.00	$	
SECTION 0006 UTILITIES							
1150 0000700 1 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 1 Support Utility During Construction-LF	913.000 ZZ	50.16900	45804.30	20.00000	18260.00		
1155 0000700 2 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 2 Utility Fittings,F&I,DI/CI-TN	26.000 ZZ	2683.93100	69782.21	8000.00000	208000.00		
1160 0000700 3 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 3 Utility Fixture, Sample Point-EA	26.000 ZZ	190.56700	4954.74	500.00000	13000.00		
1165 0000700 4 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 4 Bypass Pumping,Grvty Swr Constr-LS	2.000 ZZ	68.25500	136.51	37500.00000	75000.00		
1170 0000700 6 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 6 Pipe, FI, PVC, WT, 8-19.9" - LF	153.000 ZZ	68.25000	10442.25	60.00000	9180.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1175 0000700 7 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 7 Pipe, FI, DI/CI, WT, 0-4" - LF	84.000 ZZ	77.02300	6469.93	50.00000	4200.00		
1180 0000700 8 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 8 Pipe,FI,DI/CI,WT,5-7.9"-LF	666.000 ZZ	72.57000	48331.62	35.00000	23310.00		
1185 0000700 9 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 9 Pipe,FI,DI/CI,WT,8-19.9"-LF	6991.000 ZZ	86.16700	602393.50	58.00000	405478.00		
1190 0000700 10 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 10 Pipe,FI,PVC-C900,SW,5-7.9"-LF	856.000 ZZ	61.23300	52415.45	35.00000	29960.00		
1195 0000700 11 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 11 Pipe, FI, PVC-C900, SW, 8-19.9", <6' D-L	593.000 ZZ	161.52100	95781.95	32.00000	18976.00		
1200 0000700 12 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 12 Pipe, FI, PVC-C900, SW, 8-19.9", 6-7.9'	901.000 ZZ	161.52100	145530.42	65.00000	58565.00		
1205 0000700 13 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 13 Pipe,FI,PVC-C900,SW,8-19.9",8-9. 9'D-LF	752.000 ZZ	161.52100	121463.79	75.00000	56400.00		
1210 0000700 14 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 14 Pipe,FI,PVC-C900,SW,8-19.9", 10-11.9'D-LF	556.000 ZZ	161.52100	89805.68	85.00000	47260.00		
1215 0000700 15 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 15 Pipe,FI,PVC-C900,SW,8-19.9", 12-13.9'D-LF	363.000 ZZ	161.52100	58632.12	75.00000	27225.00		
1220 0000700 16 UTILITIES DESIGN GROUP- GENERIC PAY ITEM 16 Pipe Liner,FI,Sanitary SW, 8-10"-LF	4890.000 ZZ	68.24900	333737.61	42.00000	205380.00		
1225 0110 1 1 CLEARING & GRUBBING 22989725602	0.200 LS	285240.86000	285240.86	0.00000	0.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1230 0110 1 1 CLEARING & GRUBBING 22989725603	0.100 LS	285240.86000	285240.86	0.00000	0.00		
1235 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	298.000 SY	47.30800	14097.78	67.00000	19966.00		
1240 0160 4 TYPE B STABILIZATION	1449.000 SY	6.91400	10018.39	27.00000	39123.00		
1245 0285711 OPTIONAL BASE, BASE GROUP 11	1414.000 SY	12.93600	18291.50	38.50000	54439.00		
1250 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	182.400 TN	107.55400	19617.85	100.00000	18240.00		
1255 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	155.000 LF	14.38500	2229.68	70.00000	10850.00		
1260 0555 1 5 DIRECTIONAL BORE, 24" TO < 36"	429.000 LF	768.24000	329574.96	300.00000	128700.00		
1265 0570 1 2 PERFORMANCE TURF, SOD	1288.000 SY	1.93600	2493.57	2.25000	2898.00		
1270 0730 76107 STEEL CASING, OPEN TRENCH, F&I, 12"	33.000 LF	904.02500	29832.83	600.00000	19800.00		
1275 0730 76111 STEEL CASING, OPEN TRENCH, F&I, 20"	124.000 LF	135.60300	16814.77	1200.00000	148800.00		
1280 0730 76123 STEEL CASING, OPEN TRENCH, F&I, 48"	66.000 LF	135.60400	8949.86	4100.00000	270600.00		
1285 1050 11212 UTILITY PIPE, F&I, PVC, CASING / CONDUIT, 2-4.9"	1131.000 LF	36.60900	41404.78	11.00000	12441.00		
1290 1050 11321 UTILITY PIPE, F&I, PE, WATER / SEWER, 0 - 1.9"	1848.000 LF	41.12900	76006.39	10.00000	18480.00		
1295 1050 11512 UTILITY PIPE, F&I, STEEL, CASING / CONDUIT, 2.0-4.9"	55.000 LF	68.25000	3753.75	12.00000	660.00		
1300 1050 15002 UTILITY PIPE, ADJUST/MODIFY, 2 - 4.9"	330.000 LF	68.24900	22522.17	15.00000	4950.00		
1305 1050 16002 UTILITY PIPE,REMOVE & DISPOSE, 2-4.9"	757.000 LF	24.85500	18815.24	10.00000	7570.00		
1310 1050 16003 UTILITY PIPE,REMOVE & DISPOSE, 5-7.9"	534.000 LF	27.56800	14721.31	12.00000	6408.00		
1315 1050 16004 UTILITY PIPE,REMOVE & DISPOSE, 8-19.9"	3649.000 LF	36.60900	133586.24	14.00000	51086.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	 AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1320 1050 18000 UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, CAP FOR UP TO 4" DIAMETER PIPE	5963.000 EA	68.24900	406968.79	9.00000	53667.00		
1325 1050 18004 UTILITY PIPE,PLUG & PLACE OUT OF SERVICE, 8-19.9"	5820.000 LF	68.24900	397209.18	8.00000	46560.00		
1330 1055 11254 UTILITY FITTING, F&I, PVC, CAP/PLUG, 8 - 19.9"	11.000 EA	917.97800	10097.76	150.00000	1650.00		
1335 1055 11264 UTILITY FITTING, F&I, PVC, Y FITTING, 8 - 19.9"	25.000 EA	918.05800	22951.45	450.00000	11250.00		
1340 1055 11273 UTILITY FITTING, F&I, PVC, CLEANOUT	25.000 EA	68.25000	1706.25	600.00000	15000.00		
1345 1055 16 UTILITY FITTINGS, REMOVE & DISPOSAL	75.000 EA	692.02700	51902.03	100.00000	7500.00		
1350 1060 11222 UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, 6.1 - 12'	13.000 EA	918.07800	11935.01	6000.00000	78000.00		
1355 1060 11223 UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, > 12'	2.000 EA	68.25500	136.51	7500.00000	15000.00		
1360 1060 15 UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	20.000 EA	918.00300	18360.06	475.00000	9500.00		
1365 1060 16 UTILITY STRUCTURE, BELOW GROUND, REMOVE&DISPOSE CONTRACTOR TAKES OWNERSHIP	13.000 EA	122.49200	1592.40	800.00000	10400.00		
1370 1080 11101 UTILITY FIXTURES, F&I, 0 - 1.9", VALVE/METER BOX	25.000 EA	122.49100	3062.28	300.00000	7500.00		
1375 1080 11203 UTILITY FIXTURES, F&I, 2-4.9", TAPPING SADDLE/SLEEVE	30.000 EA	1370.04500	41101.35	500.00000	15000.00		
1380 1080 11204 UTILITY FIXTURES, F&I, 2-4.9", VALVE ASSEMBLY	7.000 EA	918.12200	6426.85	600.00000	4200.00		

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
1385 1080 11206 UTILITY FIXTURES, F&I, 2-4.9", VAC/AIR ASSEMBLY	7.000 EA	1370.04700	9590.33	8000.00000	56000.00		
1390 1080 11207 UTILITY FIXTURES, F&I, 2-4.9", LINE STOP ASSEMBLY	3.000 EA	4534.14000	13602.42	2700.00000	8100.00		
1395 1080 11304 UTILITY FIXTURES, F&I, 5.0 - 7.9", VALVE ASSEMBLY	33.000 EA	1370.04700	45211.55	1000.00000	33000.00		
1400 1080 11307 UTILITY FIXTURES, F&I, 5-7.9", LINE STOP ASSEMBLY	3.000 EA	4610.97000	13832.91	4800.00000	14400.00		
1405 1080 11404 UTILITY FIXTURES, F&I, 8.0-19.9", VALVE ASSEMBLY	68.000 EA	4534.14200	308321.66	1700.00000	115600.00		
1410 1080 11407 UTILITY FIXTURES, F&I, 8-19.9", LINE STOP ASSEMBLY	10.000 EA	3888.49500	38884.95	9000.00000	90000.00		
1415 1080 11409 UTILITY FIXTURES, F&I, 8-19.9", MECHANICAL JOINT RESTRAINT	24.000 EA	918.03300	22032.79	500.00000	12000.00		
1420 1080 14 UTILITY FIXTURES, RELOCATE	27.000 EA	68.25000	1842.75	500.00000	13500.00		
1425 1080 15 UTILITY FIXTURES, ADJUST & MODIFY	9.000 EA	918.03200	8262.29	500.00000	4500.00		
1430 1080 16 UTILITY FIXTURES, REMOVE & DISPOSE	26.000 EA	122.49200	3184.79	200.00000	5200.00		
1435 1644136 08 FIRE HYDRANT, F&I, TRAFFIC, 3 WAY - 2 HOSE, 1PUMPER, 6"	13.000 EA	2726.08200	35439.07	3000.00000	39000.00		
1440 1644900 FIRE HYDRANT, REMOVE	9.000 EA	556.42600	5007.83	200.00000	1800.00		
SECTION 0006 TOTALS			$ 4,497,558.13		$ 2,683,532.00		$
CONTRACT TOTALS			$ 15,957,537.77		$ 16,510,159.32		$ 0.00

CALL ORDER: 011 PROPOSAL ID: T4317 LETTING DATE: 05/23/12 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) CONALVIAS USA LLC UNIT PRICE	AMOUNT	(5) PRINCE CONTRACTING, LLC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT

CERTIFIED TO BE A TRUE COPY AND APPROVED BY_____ _____
Central Contracts Administrator DATE

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.