VENDOR RANKING

CALL ORDER : 002 PROPOSAL ID : T1A09 PROPOSAL DESC :
LETTING DATE : 08/27/14 10:30 A.M. DISTRICT : 01 The improvements under this contract consist of milling and
SET-ASIDE : U/R CODE : resurfacing, cross slope correction, pavement overbuild,
CONTRACT TIME : 185 WORKING DAYS (AVAILABLE DAYS) driveway replacement, sidewalk improvements, drainage
improvements, signing and pavement markings, lighting and
landscaping along Sixth Street South.

FINPROJ(S) : 42983415201 (*) F.A. NO. : 8886416A COUNTIES : POLK

LOCAL NAME : SIXTH STREET S FROM WOOD AVE E TO HINSON AVE E ROAD NAME : SIXTH STREET S FROM WOOD AVE E TO HINSON AVE E
PROJ LIMITS : FROM WOOD AVE TO HINSON AVE

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	GIBBS & REGISTER, INC.	Responsive	Winning bid	$ 1,499,986.70	0.00%
2	ATLANTIC CIVIL CONSTRUCTORS CORP	Responsive	Non-Winning Bid	$ 1,730,345.05	15.35%
3	CATHCART CONSTRUCTION COMPANY - FLORIDA, LLC	Responsive	Non-Winning Bid	$ 1,902,086.79	26.80%

CALL ORDER : 002 PROPOSAL ID : T1A09 PROPOSAL DESC :
LETTING DATE : 08/27/14 10:30 A.M. DISTRICT : 01 The improvements under this contract consist of milling and
SET-ASIDE : U/R CODE : resurfacing, cross slope correction, pavement overbuild,
CONTRACT TIME : 185 WORKING DAYS (AVAILABLE DAYS) driveway replacement, sidewalk improvements, drainage improvements, signing and pavement markings, lighting and landscaping along Sixth Street South.

FINPROJ(S) : 42983415201 (*) F.A. NO. : 8886416A COUNTIES : POLK

LOCAL NAME : SIXTH STREET S FROM WOOD AVE E TO HINSON AVE E ROAD NAME : SIXTH STREET S FROM WOOD AVE E TO HINSON AVE E
PROJ LIMITS : FROM WOOD AVE TO HINSON AVE

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 42983415201	LUMP	145500.00000	145500.00	197649.37000	197649.37	127000.00000	127000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 42983415201	185.000 LS	50000.00000	50000.00	137030.30000	137030.30	24000.00000	24000.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	30.00000	7500.00	45.51000	11377.50	130.00000	32500.00
0020 0102 60 WORK ZONE SIGN	7648.000 ED	0.25000	1912.00	0.25000	1912.00	0.45000	3441.60
0025 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	596.000 LF	36.00000	21456.00	40.23000	23977.08	43.00000	25628.00
0030 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	40.000 LF	23.00000	920.00	49.55000	1982.00	26.00000	1040.00
0035 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	14210.000 ED	0.15000	2131.50	0.15000	2131.50	0.22000	3126.20
0040 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	266.000 ED	0.40000	106.40	0.38000	101.08	0.33000	87.78
0045 0102 74 5 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	50.000 LF	22.00000	1100.00	20.00000	1000.00	41.00000	2050.00
0050 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	1561.000 ED	0.30000	468.30	0.28000	437.08	0.36000	561.96

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0055 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	2840.000 EA	3.00000	8520.00	3.00000	8520.00	4.00000	11360.00
0060 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	42.000 ED	17.00000	714.00	15.00000	630.00	18.00000	756.00
0065 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	185.000 ED	45.00000	8325.00	20.00000	3700.00	12.00000	2220.00
0070 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	185.000 ED	45.00000	8325.00	6.00000	1110.00	9.00000	1665.00
0075 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	966.000 SY	2.00000	1932.00	4.36000	4211.76	10.00000	9660.00
0080 0104 10 3 SEDIMENT BARRIER	2568.000 LF	1.00000	2568.00	1.07000	2747.76	1.00000	2568.00
0085 0104 15 SOIL TRACKING PREVENTION DEVICE	2.000 EA	5450.00000	10900.00	1993.99000	3987.98	2400.00000	4800.00
0090 0104 18 INLET PROTECTION SYSTEM	12.000 EA	75.00000	900.00	119.44000	1433.28	150.00000	1800.00
0095 0110 1 1 CLEARING & GRUBBING 42983415201	0.802 LS	85000.00000	85000.00	195369.38000	195369.38	222000.00000	222000.00
0100 0110 7 1 MAILBOX, F&I SINGLE	9.000 EA	75.00000	675.00	214.63000	1931.67	130.00000	1170.00
0105 0120 1 REGULAR EXCAVATION	343.000 CY	60.00000	20580.00	92.43000	31703.49	55.00000	18865.00
0110 0120 6 EMBANKMENT	22.000 CY	70.00000	1540.00	302.12000	6646.64	150.00000	3300.00
0115 0160 4 TYPE B STABILIZATION	735.000 SY	25.00000	18375.00	21.35000	15692.25	19.00000	13965.00
0120 0285701 OPTIONAL BASE, BASE GROUP 01	735.000 SY	30.00000	22050.00	54.34000	39939.90	22.00000	16170.00
0125 0327 70 10 MILLING EXIST ASPH PAVT, 5" AVG DEPTH	5934.000 SY	7.00000	41538.00	6.00000	35604.00	10.00000	59340.00
0130 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	1724.000 TN	100.00000	172400.00	105.00000	181020.00	199.00000	343076.00
0135 0425 1201 INLETS, CURB, TYPE 9, <10'	9.000 EA	4600.00000	41400.00	3696.26000	33266.34	4900.00000	44100.00

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0140 0425 1203 INLETS, CURB, TYPE 9, J BOT, <10'	1.000 EA	4900.00000	4900.00	4772.68000	4772.68	5400.00000	5400.00
0145 0425 1351 INLETS, CURB, TYPE P-5, <10'	2.000 EA	4700.00000	9400.00	4070.61000	8141.22	4700.00000	9400.00
0150 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	3500.00000	3500.00	2385.39000	2385.39	3900.00000	3900.00
0155 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	5.000 EA	3700.00000	18500.00	4162.91000	20814.55	4250.00000	21250.00
0160 0425 1533 INLETS, DITCH BOTTOM TYPE C MODIFIED- BACK OF SIDEWALK, J BOT, <10'	4.000 EA	5900.00000	23600.00	6323.36000	25293.44	6000.00000	24000.00
0165 0425 2 61 MANHOLES, P-8, <10'	2.000 EA	3500.00000	7000.00	3369.31000	6738.62	4200.00000	8400.00
0170 0425 2 63 MANHOLES, P-8, PARTIAL	1.000 EA	2800.00000	2800.00	2298.33000	2298.33	3500.00000	3500.00
0175 0425 2 91 MANHOLES, J-8, <10'	4.000 EA	4500.00000	18000.00	4218.62000	16874.48	5700.00000	22800.00
0180 0425 2 92 MANHOLES, J-8, >10'	1.000 EA	12000.00000	12000.00	7917.81000	7917.81	6900.00000	6900.00
0185 0425 5 1 MANHOLE, ADJUST, UTILITIES	9.000 EA	650.00000	5850.00	938.89000	8450.01	1200.00000	10800.00
0190 0425 6 VALVE BOXES, ADJUST	34.000 EA	250.00000	8500.00	332.96000	11320.64	750.00000	25500.00
0195 0430175112 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	8.000 LF	250.00000	2000.00	128.91000	1031.28	100.00000	800.00
0200 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	714.000 LF	100.00000	71400.00	67.18000	47966.52	101.00000	72114.00
0205 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	314.000 LF	120.00000	37680.00	152.96000	48029.44	185.00000	58090.00
0210 0430175218 PIPE CULVERT,OPTIONAL MATERIAL, OTHER-ELIP/ARCH, 18"S/CD	169.000 LF	105.00000	17745.00	99.56000	16825.64	110.00000	18590.00
0215 0430175224 PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	246.000 LF	115.00000	28290.00	111.57000	27446.22	115.00000	28290.00

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0220 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	54.000 CY	300.00000	16200.00	199.45000	10770.30	375.00000	20250.00
0225 0515 1 1 PIPE HANDRAIL - GUIDERAIL, STEEL	108.000 LF	60.00000	6480.00	58.40000	6307.20	60.00000	6480.00
0230 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	26.000 LF	23.00000	598.00	29.84000	775.84	24.00000	624.00
0235 0520 2 4 CONCRETE CURB, TYPE D	2830.000 LF	26.00000	73580.00	21.48000	60788.40	22.00000	62260.00
0240 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	1629.000 SY	27.00000	43983.00	29.90000	48707.10	30.00000	48870.00
0245 0522 2 CONC SIDEWALK AND DRIVEWAYS, 6" THICK	152.000 SY	51.00000	7752.00	50.52000	7679.04	35.00000	5320.00
0250 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	7.000 SY	87.00000	609.00	148.49000	1039.43	130.00000	910.00
0255 0526 1 1 PAVERS, ARCHITECTURAL, ROADWAY	22.000 SY	560.00000	12320.00	285.57000	6282.54	210.00000	4620.00
0260 0527 2 DETECTABLE WARNINGS	412.000 SF	23.00000	9476.00	25.00000	10300.00	30.00000	12360.00
0265 0570 1 2 PERFORMANCE TURF, SOD	966.000 SY	5.00000	4830.00	2.52000	2434.32	4.00000	3864.00
0270 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	0.740 NM	1100.00000	814.00	950.00000	703.00	3500.00000	2590.00
0275 0710 11123 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	2190.000 LF	1.25000	2737.50	1.10000	2409.00	1.45000	3175.50
0280 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	1800.000 LF	1.75000	3150.00	1.50000	2700.00	2.25000	4050.00
0285 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	4.000 EA	39.00000	156.00	35.00000	140.00	75.00000	300.00
0290 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1.880 NM	1100.00000	2068.00	950.00000	1786.00	2200.00000	4136.00
SECTION 0001 TOTALS			$ 1,132,754.70		$ 1,364,240.80		$ 1,475,794.04
SECTION 0002 SIGNING							

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0295 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	15.000 AS	500.00000	7500.00	1209.00000	18135.00	1500.00000	22500.00
0300 0700 1 50 SINGLE POST SIGN, RELOCATE	4.000 AS	250.00000	1000.00	89.00000	356.00	105.00000	420.00
0305 0700 1 60 SINGLE POST SIGN, REMOVE	11.000 AS	70.00000	770.00	50.00000	550.00	2.00000	22.00
0310 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	3.000 AS	2200.00000	6600.00	1964.00000	5892.00	2400.00000	7200.00
0315 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.250 NM	1100.00000	275.00	950.00000	237.50	5800.00000	1450.00
0320 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12"	1095.000 LF	3.00000	3285.00	2.75000	3011.25	2.20000	2409.00
0325 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24"	200.000 LF	6.00000	1200.00	5.50000	1100.00	5.00000	1000.00
0330 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE	2.000 EA	110.00000	220.00	100.00000	200.00	250.00000	500.00
0335 0711 14125 THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24"	700.000 LF	17.00000	11900.00	15.25000	10675.00	17.00000	11900.00
0340 0711 15111 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	0.370 NM	5000.00000	1850.00	4500.00000	1665.00	11000.00000	4070.00
0345 0711 15211 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	0.680 NM	5000.00000	3400.00	4500.00000	3060.00	6300.00000	4284.00
SECTION 0002 TOTALS		$	38,000.00	$	44,881.75	$	55,755.00
SECTION 0003 LIGHTING							
0350 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	1913.000 LF	6.00000	11478.00	7.00000	13391.00	6.75000	12912.75
0355 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	489.000 LF	21.00000	10269.00	17.00000	8313.00	27.00000	13203.00

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0360 0635 2 11 38.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	560.00000	21280.00	325.00000	12350.00	624.00000	23712.00
0365 0639 1121 1.000 AS ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	3000.00000	3000.00	1700.00000	1700.00	2490.00000	2490.00
0370 0639 2 1 10260.000 LF ELECTRICAL SERVICE WIRE	1.75000	17955.00	1.35000	13851.00	1.50000	15390.00
0375 0639 3 11 1.000 EA ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	1000.00000	1000.00	250.00000	250.00	600.00000	600.00
0380 0641 2 12 1.000 EA PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	1500.00000	1500.00	700.00000	700.00	970.00000	970.00
0385 0715 7 11 1.000 EA LOAD CENTER, F&I, SECONDARY VOLTAGE	9000.00000	9000.00	6700.00000	6700.00	9500.00000	9500.00
0390 0715516320 31.000 EA LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I ,POLE TOP MOUNT, CONCRETE, 20'	5500.00000	170500.00	6200.00000	192200.00	6900.00000	213900.00
0395 0715550000 3.000 EA LIGHT POLE COMPLETE- SPECIAL DESIGN, REMOVE	400.00000	1200.00	750.00000	2250.00	690.00000	2070.00
SECTION 0003 TOTALS	$	247,182.00	$	251,705.00	$	294,747.75
SECTION 0004 SIGNALIZATION						
0400 0630 2 11 30.000 LF CONDUIT, FURNISH & INSTALL, OPEN TRENCH	10.00000	300.00	7.50000	225.00	10.00000	300.00
0405 0635 2 11 1.000 EA PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	750.00000	750.00	350.00000	350.00	500.00000	500.00
0410 0660 2106 1.000 AS LOOP ASSEMBLY, F&I, TYPE F	1000.00000	1000.00	900.00000	900.00	990.00000	990.00
SECTION 0004 TOTALS	$	2,050.00	$	1,475.00	$	1,790.00
SECTION 0005 LANDSCAPE / PERIPHERAL						

CALL ORDER: 002 PROPOSAL ID: T1A09 LETTING DATE: 08/27/14 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) GIBBS & REGISTER, INC. UNIT PRICE	 AMOUNT	(2) ATLANTIC CIVIL CONSTRUCTORS UNIT PRICE	 AMOUNT	(3) CATHCART CONSTRUCTION COMPANY - UNIT PRICE	 AMOUNT
0415 0580 1 1 LANDSCAPE COMPLETE- SMALL PLANTS 42983415201	LUMP	15000.00000	15000.00	24021.25000	24021.25	25000.00000	25000.00
0420 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 42983415201	LUMP	25000.00000	25000.00	24021.25000	24021.25	22000.00000	22000.00
0425 0590 70 IRRIGATION SYSTEM 42983415201	LUMP	40000.00000	40000.00	20000.00000	20000.00	27000.00000	27000.00
SECTION 0005 TOTALS			$ 80,000.00		$ 68,042.50		$ 74,000.00
CONTRACT TOTALS			$ 1,499,986.70		$ 1,730,345.05		$ 1,902,086.79

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.