VENDOR RANKING

CALL ORDER : 013 PROPOSAL ID : T4406 PROPOSAL DESC :
LETTING DATE : 12/03/14 10:30 A.M. DISTRICT : 04 The improvements under this contract consist of RRR project
SET-ASIDE : U/R CODE : that includes milling and resurfacing, ADA improvements,
CONTRACT TIME : 267 WORKING DAYS (AVAILABLE DAYS) drainage improvements, curb and gutter, highway signing and pavement markings, sidewalks, traffic signals and other incidental construction on SR 5.

FINPROJ(S) : 42872615201 (*) F.A. NO. : 4853059P COUNTIES : BROWARD

LOCAL NAME : SR-5/US-1 FROM BROWARD BLVD TO NE 17TH WAY ROAD NAME : SR 5
PROJ LIMITS : FROM BROWARD BLVD TO NE 17TH WAY

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	COMMUNITY ASPHALT CORP.	Responsive	Winning bid	$ 3,869,297.18	0.00%
2	WEEKLEY ASPHALT PAVING, INC.	Responsive	Non-Winning Bid	$ 3,988,720.67	3.08%
3	RANGER CONSTRUCTION INDUSTRIES, INC.	Responsive	Non-Winning Bid	$ 4,078,870.00	5.41%
4	MORRISON - COBALT JV	Responsive	Non-Winning Bid	$ 4,149,476.97	7.24%
5	GENERAL ASPHALT CO., INC.	Responsive	Non-Winning Bid	$ 4,282,892.36	10.68%
6	HALLEY ENGINEERING CONTRACTORS, INC.	Responsive	Non-Winning Bid	$ 4,620,039.97	19.40%

CALL ORDER : 013 PROPOSAL ID : T4406 PROPOSAL DESC :
LETTING DATE : 12/03/14 10:30 A.M. DISTRICT : 04 The improvements under this contract consist of RRR project
SET-ASIDE : U/R CODE : that includes milling and resurfacing, ADA improvements,
CONTRACT TIME : 267 WORKING DAYS (AVAILABLE DAYS) drainage improvements, curb and gutter, highway signing and pavement markings, sidewalks, traffic signals and other incidental construction on SR 5.

FINPROJ(S) : 42872615201 (*) F.A. NO. : 4853059P COUNTIES : BROWARD

LOCAL NAME : SR-5/US-1 FROM BROWARD BLVD TO NE 17TH WAY ROAD NAME : SR 5
PROJ LIMITS : FROM BROWARD BLVD TO NE 17TH WAY

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 42872615201	LUMP	391983.12000	391983.12	153548.00000	153548.00	284000.00000	284000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 42872615201	267.000 LS	194059.17000	194059.17	582592.00000	582592.00	112088.10000	112088.10
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	900.000 CY	0.01000	9.00	1.00000	900.00	17.30000	15570.00
0020 0102 14 TRAFFIC CONTROL OFFICER	432.000 MH	57.79000	24965.28	55.00000	23760.00	58.00000	25056.00
0025 0102 60 WORK ZONE SIGN	21981.000 ED	0.22000	4835.82	0.20000	4396.20	0.30000	6594.30
0030 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	487.500 LF	20.00000	9750.00	32.00000	15600.00	27.00000	13162.50
0035 0102 71 24 BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	400.000 LF	8.89000	3556.00	29.00000	11600.00	6.45000	2580.00
0040 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	14772.000 ED	0.22000	3249.84	0.14000	2068.08	0.15000	2215.80
0045 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	741.000 ED	0.16000	118.56	0.28000	207.48	0.40000	296.40
0050 0102 74 5 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	712.000 LF	16.67000	11869.04	15.00000	10680.00	5.40000	3844.80
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	741.000 ED	6.67000	4942.47	6.00000	4446.00	7.50000	5557.50

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	18363.000 ED	0.24000	4407.12	0.22000	4039.86	0.25000	4590.75
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	177.000 EA	3.33000	589.41	2.95000	522.15	4.85000	858.45
0070 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	2.000 LO	1222.46000	2444.92	1640.00000	3280.00	1070.00000	2140.00
0075 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	843.000 ED	16.67000	14052.81	15.00000	12645.00	15.05000	12687.15
0080 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	2937.000 ED	5.31000	15595.47	4.60000	13510.20	4.95000	14538.15
0085 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	2937.000 ED	7.64000	22438.68	11.20000	32894.40	12.05000	35390.85
0090 0104 18 INLET PROTECTION SYSTEM	33.000 EA	50.01000	1650.33	123.00000	4059.00	89.00000	2937.00
0095 0107 1 LITTER REMOVAL	55.450 AC	0.01000	0.55	40.00000	2218.00	26.00000	1441.70
0100 0107 2 MOWING	12.470 AC	0.01000	0.12	25.00000	311.75	500.00000	6235.00
0105 0110 1 1 CLEARING & GRUBBING 42872615201	0.390 LS	185714.26000	185714.26	120600.00000	120600.00	43100.00000	43100.00
0110 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	64.000 SY	53.14000	3400.96	28.20000	1804.80	38.00000	2432.00
0115 0285712 OPTIONAL BASE, BASE GROUP 12	1664.000 SY	34.74000	57807.36	52.40000	87193.60	61.00000	101504.00
0120 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	86073.000 SY	2.28000	196246.44	2.20000	189360.60	3.35000	288344.55
0125 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	253.700 TN	113.27000	28736.60	110.00000	27907.00	153.60000	38968.32
0130 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	7457.100 TN	88.91000	663010.76	106.00000	790452.60	126.50000	943323.15

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0135 0425 1351 INLETS, CURB, TYPE P-5, <10'	2.000 EA	6690.16000	13380.32	8220.00000	16440.00	6450.00000	12900.00
0140 0425 2 71 MANHOLES, J-7, <10'	1.000 EA	8946.15000	8946.15	7900.00000	7900.00	8490.00000	8490.00
0145 0425 5 MANHOLE, ADJUST	26.000 EA	444.52000	11557.52	1306.00000	33956.00	320.00000	8320.00
0150 0425 5 1 MANHOLE, ADJUST, UTILITIES	19.000 EA	722.36000	13724.84	595.00000	11305.00	540.00000	10260.00
0155 0425 6 VALVE BOXES, ADJUST	48.000 EA	388.97000	18670.56	265.00000	12720.00	310.00000	14880.00
0160 0425 11 DRAINAGE STRUCTURE MODIFY	10.000 EA	1666.98000	16669.80	5200.00000	52000.00	3440.00000	34400.00
0165 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	234.000 LF	111.14000	26006.76	146.00000	34164.00	280.00000	65520.00
0170 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	232.000 LF	136.70000	31714.40	149.00000	34568.00	280.00000	64960.00
0175 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	26.000 LF	234.49000	6096.74	163.00000	4238.00	300.00000	7800.00
0180 0430175224 PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	86.000 LF	308.95000	26569.70	182.00000	15652.00	340.00000	29240.00
0185 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	2655.000 LF	24.45000	64914.75	26.00000	69030.00	52.00000	138060.00
0190 0520 2 4 CONCRETE CURB, TYPE D	64.000 LF	22.23000	1422.72	24.00000	1536.00	94.00000	6016.00
0195 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL-VARIABLE WIDTH	48.000 SY	72.24000	3467.52	76.00000	3648.00	64.00000	3072.00
0200 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	1408.000 SY	37.79000	53208.32	43.00000	60544.00	59.00000	83072.00
0205 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	230.000 SY	46.68000	10736.40	50.00000	11500.00	79.00000	18170.00
0210 0527 2 DETECTABLE WARNINGS	1059.000 SF	33.34000	35307.06	32.00000	33888.00	32.00000	33888.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0215 0570 1 2 PERFORMANCE TURF, SOD	71.000 SY	6.67000	473.57	9.50000	674.50	18.80000	1334.80
0220 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	5.643 NM	800.15000	4515.25	1000.00000	5643.00	1180.00000	6658.74
0225 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	3015.000 LF	0.22000	663.30	0.50000	1507.50	0.35000	1055.25
0230 0710 11123 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	8423.000 LF	0.56000	4716.88	0.80000	6738.40	0.45000	3790.35
0235 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	5967.000 LF	0.72000	4296.24	1.25000	7458.75	0.90000	5370.30
0240 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	7.485 GM	422.31000	3160.99	300.00000	2245.50	360.00000	2694.60
0245 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	147.000 EA	34.45000	5064.15	20.00000	2940.00	41.00000	6027.00
0250 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	131.000 EA	22.23000	2912.13	20.00000	2620.00	28.00000	3668.00
0255 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	4.133 NM	800.15000	3307.02	1000.00000	4133.00	1180.00000	4876.94
0260 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 42872615201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 2,266,937.18		$ 2,587,646.37		$ 2,593,980.45
SECTION 0002 SIGNING							
0265 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	121.000 AS	288.94000	34961.74	300.00000	36300.00	310.00000	37510.00
0270 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	52.000 AS	916.84000	47675.68	900.00000	46800.00	1130.00000	58760.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0275 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	3.000 AS	1389.15000	4167.45	1200.00000	3600.00	1340.00000	4020.00
0280 0700 1 60 SINGLE POST SIGN, REMOVE	64.000 AS	11.11000	711.04	20.00000	1280.00	10.75000	688.00
0285 0700 2 12 MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	4.000 AS	1761.45000	7045.80	4000.00000	16000.00	2740.00000	10960.00
0290 0700 3205 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	1.000 EA	2470.75000	2470.75	2415.10000	2415.10	4140.00000	4140.00
0295 0700 3603 SIGN PANEL, REMOVE, 21-30 SF	3.000 EA	148.15000	444.45	183.10000	549.30	86.00000	258.00
0300 0700 11241 ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWER, ELECT WARNING W/FLASHING BEACON, UP TO 12 SF	2.000 AS	14003.37000	28006.74	5191.60000	10383.20	5580.00000	11160.00
0305 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	23.000 EA	61.12000	1405.76	50.00000	1150.00	80.00000	1840.00
0310 0705 11 3 DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	11.000 EA	72.24000	794.64	100.00000	1100.00	170.00000	1870.00
0315 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42872615201	LUMP	57360.94000	57360.94	59306.40000	59306.40	58500.00000	58500.00
0320 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	240.000 EA	305.61000	73346.40	300.00000	72000.00	240.00000	57600.00
0325 0711 14170 THERMOPLASTIC, PREFORMED, WHITE, ARROWS	6.000 EA	102.25000	613.50	150.00000	900.00	70.00000	420.00
0330 0711 14560 THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, MESSAGE	30.000 EA	1105.76000	33172.80	300.00000	9000.00	390.00000	11700.00
0335 0711 17 THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	5686.000 SF	3.33000	18934.38	2.00000	11372.00	2.25000	12793.50
SECTION 0002 TOTALS		$	311,112.07	$	272,156.00	$	272,219.50
SECTION 0003 SIGNALIZATION							

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0340 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	475.000 LF	7.06000	3353.50	15.60000	7410.00	16.75000	7956.25
0345 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	2500.000 LF	14.11000	35275.00	20.30000	50750.00	21.80000	54500.00
0350 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	4.000 PI	3893.47000	15573.88	3226.00000	12904.00	3470.00000	13880.00
0355 0632 7 2 SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	1715.000 LF	1.90000	3258.50	2.40000	4116.00	2.60000	4459.00
0360 0633 1121 FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	100.000 LF	2.77000	277.00	1.70000	170.00	1.85000	185.00
0365 0633 1122 FIBER OPTIC CABLE, F&I, UNDERGROUND, 13-48 FIBERS	13930.000 LF	3.83000	53351.90	2.10000	29253.00	2.25000	31342.50
0370 0633 2 31 FIBER OPTIC CONNECTION, INSTALL, SPLICE	48.000 EA	82.82000	3975.36	43.20000	2073.60	46.00000	2208.00
0375 0633 2 32 FIBER OPTIC CONNECTION, INSTALL, TERMINATION	8.000 EA	78.43000	627.44	80.20000	641.60	86.00000	688.00
0380 0633 3 11 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	13.000 EA	1192.31000	15500.03	679.00000	8827.00	730.00000	9490.00
0385 0633 3 12 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	13.000 EA	233.95000	3041.35	55.60000	722.80	60.00000	780.00
0390 0633 3 14 FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	13.000 EA	1494.51000	19428.63	61.70000	802.10	66.00000	858.00
0395 0633 3 15 FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	13.000 EA	1931.74000	25112.62	1512.30000	19659.90	1620.00000	21060.00
0400 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	115.000 EA	429.99000	49448.85	652.20000	75003.00	700.00000	80500.00
0405 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	5.000 EA	927.24000	4636.20	1492.90000	7464.50	1600.00000	8000.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0410 0635 2 13 PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	13.000 EA	2214.75000	28791.75	2264.60000	29439.80	2430.00000	31590.00
0415 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	4.000 AS	2092.28000	8369.12	1877.70000	7510.80	2020.00000	8080.00
0420 0639 2 1 ELECTRICAL SERVICE WIRE	1210.000 LF	1.64000	1984.40	2.00000	2420.00	2.15000	2601.50
0425 0639 3 11 ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	7.000 EA	2092.05000	14644.35	151.00000	1057.00	160.00000	1120.00
0430 0641 2 11 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	5.000 EA	1333.30000	6666.50	1051.40000	5257.00	1130.00000	5650.00
0435 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	53.000 EA	1244.05000	65934.65	1028.50000	54510.50	1100.00000	58300.00
0440 0649 31101 STEEL MAST ARM,F&I, WIND SPEED-150, SINGLE ARM, W/0 LUMINAIRE-36	1.000 EA	29498.57000	29498.57	31120.20000	31120.20	33400.00000	33400.00
0445 0649 31102 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-46	2.000 EA	30775.67000	61551.34	29576.30000	59152.60	31800.00000	63600.00
0450 0649 31103 MAST ARM,F&I, WIND SPEED-150, SINGLE ARM,W/0 LUMINAIRE-60	4.000 EA	37095.52000	148382.08	36829.00000	147316.00	39600.00000	158400.00
0455 0649 31115 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 46-60	1.000 EA	46795.98000	46795.98	41928.10000	41928.10	45000.00000	45000.00
0460 0649 31116 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 46-70.5	1.000 EA	51162.46000	51162.46	52235.20000	52235.20	56100.00000	56100.00
0465 0649 31117 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 60-60	1.000 EA	50590.54000	50590.54	50939.50000	50939.50	54700.00000	54700.00
0470 0650 1111 TRAFFIC SIGNAL, F&I, 1 SECTION, 1 WAY, ALUMINUM	2.000 AS	728.65000	1457.30	283.60000	567.20	300.00000	600.00
0475 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	28.000 AS	1004.71000	28131.88	755.60000	21156.80	810.00000	22680.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0480 0650 1511 TRAFFIC SIGNAL, F&I, 5 SECTION, 1 WAY, ALUMINUM	6.000 AS	1362.57000	8175.42	1140.80000	6844.80	1230.00000	7380.00
0485 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	64.000 AS	703.45000	45020.80	455.70000	29164.80	490.00000	31360.00
0490 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	5.000 EA	11295.05000	56475.25	9727.20000	48636.00	10500.00000	52500.00
0495 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	17.000 EA	2681.12000	45579.04	2439.30000	41468.10	2620.00000	44540.00
0500 0663 1120 SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, COMPLETE SYSTEM	4.000 EA	8611.46000	34445.84	8229.60000	32918.40	8840.00000	35360.00
0505 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	62.000 EA	214.17000	13278.54	166.90000	10347.80	180.00000	11160.00
0510 0670 5131 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL ONE PREEMPTION PLAN	4.000 AS	26575.98000	106303.92	25446.40000	101785.60	27300.00000	109200.00
0515 0684 1 1 MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	4.000 EA	1879.74000	7518.96	3858.00000	15432.00	4140.00000	16560.00
0520 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	28.000 EA	81.52000	2282.56	68.70000	1923.60	74.00000	2072.00
0525 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	48.000 EA	49.98000	2399.04	45.80000	2198.40	49.00000	2352.00
0530 0690 34 1 COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	11.000 EA	1982.00000	21802.00	1281.80000	14099.80	1380.00000	15180.00
0535 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	3.000 EA	838.81000	2516.43	640.90000	1922.70	690.00000	2070.00
0540 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	11.000 EA	41.28000	454.08	183.10000	2014.10	200.00000	2200.00
0545 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	48.000 EA	28.74000	1379.52	22.90000	1099.20	24.60000	1180.80

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(2) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(3) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0550 0690 80 SPAN WIRE ASSEMBLY, REMOVE	3.000 EA	373.61000	1120.83	274.70000	824.10	300.00000	900.00
0555 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	4.000 PI	647.99000	2591.96	549.30000	2197.20	590.00000	2360.00
0560 0690 91 SIGNAL INTERCONNECT CABLE REMOVE	12690.000 LF	1.28000	16243.20	0.60000	7614.00	0.65000	8248.50
0565 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	3.000 PI	507.44000	1522.32	1098.70000	3296.10	1180.00000	3540.00
0570 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	3.000 EA	455.46000	1366.38	420.80000	1262.40	450.00000	1350.00
0575 0700 5 21 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	10.000 EA	3257.93000	32579.30	1983.30000	19833.00	2130.00000	21300.00
0580 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	990.000 LF	1.20000	1188.00	2.00000	1980.00	2.15000	2128.50
0585 0715 4111 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE - 40'	2.000 EA	7316.12000	14632.24	4914.60000	9829.20	5280.00000	10560.00
0590 0741 1 11 TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL, TYPE 1 AXLE SENSOR- IN ROAD	24.000 EA	1728.86000	41492.64	774.30000	18583.20	830.00000	19920.00
0595 0745 70 12 TMS INDUCTIVE LOOP ASSEM, F&I, 2 LOOPS / LANE	24.000 AS	1170.23000	28085.52	694.20000	16660.80	750.00000	18000.00
0600 0746 71112 TMS CABINET, F&I, TYPE III, BASE MOUNT, 2 BACKPLANE	4.000 EA	6493.24000	25972.96	3143.70000	12574.80	3380.00000	13520.00
SECTION 0003 TOTALS			$ 1,291,247.93		$ 1,128,918.30		$ 1,212,670.05
CONTRACT TOTALS			$ 3,869,297.18		$ 3,988,720.67		$ 4,078,870.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 42872615201	LUMP	400000.00000	400000.00	200000.00000	200000.00	370000.00000	370000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 42872615201	267.000 LS	150000.00000	150000.00	230000.00000	230000.00	297500.00000	297500.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	900.000 CY	45.00000	40500.00	30.00000	27000.00	25.00000	22500.00
0020 0102 14 TRAFFIC CONTROL OFFICER	432.000 MH	55.00000	23760.00	50.00000	21600.00	75.00000	32400.00
0025 0102 60 WORK ZONE SIGN	21981.000 ED	0.31000	6814.11	0.22000	4835.82	0.30000	6594.30
0030 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	487.500 LF	24.50000	11943.75	27.00000	13162.50	21.00000	10237.50
0035 0102 71 24 BARRIER WALL, TEMPORARY, RELOCATE, TYPE K	400.000 LF	6.30000	2520.00	9.00000	3600.00	5.00000	2000.00
0040 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	14772.000 ED	0.13000	1920.36	0.16000	2363.52	0.30000	4431.60
0045 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	741.000 ED	0.37000	274.17	7.00000	5187.00	0.20000	148.20
0050 0102 74 5 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	712.000 LF	5.25000	3738.00	17.00000	12104.00	0.40000	284.80
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	741.000 ED	7.35000	5446.35	7.00000	5187.00	14.00000	10374.00
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	18363.000 ED	0.26000	4774.38	0.24000	4407.12	0.40000	7345.20
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	177.000 EA	3.15000	557.55	3.30000	584.10	3.00000	531.00
0070 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	2.000 LO	2600.00000	5200.00	1000.00000	2000.00	3000.00000	6000.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0075 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	843.000 ED	14.70000	12392.10	17.00000	14331.00	20.00000	16860.00
0080 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	2937.000 ED	4.83000	14185.71	5.00000	14685.00	4.60000	13510.20
0085 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	2937.000 ED	11.76000	34539.12	12.00000	35244.00	11.20000	32894.40
0090 0104 18 INLET PROTECTION SYSTEM	33.000 EA	80.00000	2640.00	70.00000	2310.00	200.00000	6600.00
0095 0107 1 LITTER REMOVAL	55.450 AC	150.00000	8317.50	100.00000	5545.00	0.01000	0.55
0100 0107 2 MOWING	12.470 AC	150.00000	1870.50	100.00000	1247.00	100.00000	1247.00
0105 0110 1 1 CLEARING & GRUBBING 42872615201	0.390 LS	70000.00000	70000.00	180000.00000	180000.00	196020.00000	196020.00
0110 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	64.000 SY	120.00000	7680.00	40.00000	2560.00	47.26000	3024.64
0115 0285712 OPTIONAL BASE, BASE GROUP 12	1664.000 SY	45.00000	74880.00	82.00000	136448.00	27.50000	45760.00
0120 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	86073.000 SY	2.60000	223789.80	2.50000	215182.50	2.70000	232397.10
0125 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	253.700 TN	130.00000	32981.00	190.00000	48203.00	250.00000	63425.00
0130 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	7457.100 TN	144.00000	1073822.40	132.00000	984337.20	154.00000	1148393.40
0135 0425 1351 INLETS, CURB, TYPE P-5, <10'	2.000 EA	6500.00000	13000.00	9000.00000	18000.00	6600.00000	13200.00
0140 0425 2 71 MANHOLES, J-7, <10'	1.000 EA	6000.00000	6000.00	8700.00000	8700.00	8250.00000	8250.00
0145 0425 5 MANHOLE, ADJUST	26.000 EA	800.00000	20800.00	745.00000	19370.00	600.00000	15600.00
0150 0425 5 1 MANHOLE, ADJUST, UTILITIES	19.000 EA	800.00000	15200.00	400.00000	7600.00	900.00000	17100.00
0155 0425 6 VALVE BOXES, ADJUST	48.000 EA	600.00000	28800.00	260.00000	12480.00	600.00000	28800.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0160 0425 11 DRAINAGE STRUCTURE MODIFY	10.000 EA	3625.00000	36250.00	5700.00000	57000.00	3600.00000	36000.00
0165 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	234.000 LF	111.60000	26114.40	160.00000	37440.00	300.00000	70200.00
0170 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	232.000 LF	132.00000	30624.00	165.00000	38280.00	300.00000	69600.00
0175 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	26.000 LF	240.00000	6240.00	180.00000	4680.00	305.00000	7930.00
0180 0430175224 PIPE CULVERT,OPTIONAL MATERIAL,OTHER SHAPE-ELIP/ARCH, 24"S/CD	86.000 LF	142.00000	12212.00	200.00000	17200.00	352.00000	30272.00
0185 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	2655.000 LF	14.70000	39028.50	40.00000	106200.00	32.00000	84960.00
0190 0520 2 4 CONCRETE CURB, TYPE D	64.000 LF	20.00000	1280.00	90.00000	5760.00	68.40000	4377.60
0195 0520 70 CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	48.000 SY	50.00000	2400.00	90.00000	4320.00	65.00000	3120.00
0200 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	1408.000 SY	40.00000	56320.00	63.00000	88704.00	61.29000	86296.32
0205 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	230.000 SY	50.00000	11500.00	95.00000	21850.00	75.00000	17250.00
0210 0527 2 DETECTABLE WARNINGS	1059.000 SF	45.00000	47655.00	27.00000	28593.00	46.20000	48925.80
0215 0570 1 2 PERFORMANCE TURF, SOD	71.000 SY	7.00000	497.00	35.00000	2485.00	10.00000	710.00
0220 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	5.643 NM	756.00000	4266.11	800.00000	4514.40	720.00000	4062.96
0225 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	3015.000 LF	0.21000	633.15	0.22000	663.30	0.20000	603.00
0230 0710 11123 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 12"	8423.000 LF	0.53000	4464.19	0.55000	4632.65	0.50000	4211.50

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0235 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	5967.000 LF	0.68000	4057.56	0.70000	4176.90	0.65000	3878.55
0240 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	7.485 GM	399.00000	2986.52	420.00000	3143.70	380.00000	2844.30
0245 0710 11160 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE	147.000 EA	32.55000	4784.85	35.00000	5145.00	31.00000	4557.00
0250 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	131.000 EA	21.00000	2751.00	22.00000	2882.00	20.00000	2620.00
0255 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	4.133 NM	756.00000	3124.55	800.00000	3306.40	720.00000	2975.76
0260 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 42872615201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 2,645,535.63		$ 2,729,250.11		$ 3,148,823.68
SECTION 0002 SIGNING							
0265 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	121.000 AS	455.70000	55139.70	300.00000	36300.00	315.00000	38115.00
0270 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	52.000 AS	970.51000	50466.52	950.00000	49400.00	1155.00000	60060.00
0275 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	3.000 AS	1707.30000	5121.90	1400.00000	4200.00	1375.00000	4125.00
0280 0700 1 60 SINGLE POST SIGN, REMOVE	64.000 AS	48.09000	3077.76	12.00000	768.00	15.00000	960.00
0285 0700 2 12 MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	4.000 AS	3283.77000	13135.08	1800.00000	7200.00	2805.00000	11220.00
0290 0700 3205 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	1.000 EA	2535.86000	2535.86	5300.00000	5300.00	4235.00000	4235.00

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0295 0700 3603 SIGN PANEL, REMOVE, 21-30 SF	3.000 EA	192.25000	576.75	150.00000	450.00	90.00000	270.00
0300 0700 11241 ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWER, ELECT WARNING W/FLASHING BEACON, UP TO 12 SF	2.000 AS	5451.18000	10902.36	11000.00000	22000.00	12600.63000	25201.26
0305 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	23.000 EA	75.39000	1733.97	61.00000	1403.00	55.00000	1265.00
0310 0705 11 3 DELINEATOR, FLEXIBLE HIGH VISABILITY MEDIAN	11.000 EA	225.12000	2476.32	72.00000	792.00	65.00000	715.00
0315 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42872615201	LUMP	54195.77000	54195.77	60000.00000	60000.00	51615.02000	51615.02
0320 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	240.000 EA	288.75000	69300.00	300.00000	72000.00	280.00000	67200.00
0325 0711 14170 THERMOPLASTIC, PREFORMED, WHITE, ARROWS	6.000 EA	96.60000	579.60	110.00000	660.00	92.00000	552.00
0330 0711 14560 THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, MESSAGE	30.000 EA	1044.75000	31342.50	1100.00000	33000.00	995.00000	29850.00
0335 0711 17 THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	5686.000 SF	3.15000	17910.90	3.30000	18763.80	3.00000	17058.00
SECTION 0002 TOTALS		$	318,494.99	$	312,236.80	$	312,441.28
SECTION 0003 SIGNALIZATION							
0340 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	475.000 LF	16.38000	7780.50	17.00000	8075.00	6.35000	3016.25
0345 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	2500.000 LF	21.32000	53300.00	22.00000	55000.00	12.70000	31750.00
0350 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	4.000 PI	3387.30000	13549.20	3550.00000	14200.00	3503.45000	14013.80
0355 0632 7 2 SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	1715.000 LF	2.52000	4321.80	2.75000	4716.25	1.71000	2932.65

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0360 0633 1121 FIBER OPTIC CABLE, F&I, UNDERGROUND, 2-12 FIBERS	100.000 LF	1.78000	178.00	1.90000	190.00	2.49000	249.00
0365 0633 1122 FIBER OPTIC CABLE, F&I, UNDERGROUND, 13-48 FIBERS	13930.000 LF	2.21000	30785.30	2.30000	32039.00	3.45000	48058.50
0370 0633 2 31 FIBER OPTIC CONNECTION, INSTALL, SPLICE	48.000 EA	45.36000	2177.28	47.60000	2284.80	74.52000	3576.96
0375 0633 2 32 FIBER OPTIC CONNECTION, INSTALL, TERMINATION	8.000 EA	84.21000	673.68	88.00000	704.00	70.57000	564.56
0380 0633 3 11 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	13.000 EA	712.95000	9268.35	750.00000	9750.00	1072.87000	13947.31
0385 0633 3 12 FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	13.000 EA	58.38000	758.94	62.00000	806.00	210.52000	2736.76
0390 0633 3 14 FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	13.000 EA	64.78000	842.14	68.00000	884.00	1344.80000	17482.40
0395 0633 3 15 FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	13.000 EA	1587.91000	20642.83	1665.00000	21645.00	1738.24000	22597.12
0400 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	115.000 EA	684.81000	78753.15	720.00000	82800.00	386.91000	44494.65
0405 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	5.000 EA	1567.55000	7837.75	1640.00000	8200.00	834.36000	4171.80
0410 0635 2 13 PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	13.000 EA	2377.83000	30911.79	2490.00000	32370.00	1992.89000	25907.57
0415 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	4.000 AS	1971.59000	7886.36	2065.00000	8260.00	1882.69000	7530.76
0420 0639 2 1 ELECTRICAL SERVICE WIRE	1210.000 LF	2.10000	2541.00	2.20000	2662.00	1.48000	1790.80
0425 0639 3 11 ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	7.000 EA	158.55000	1109.85	165.00000	1155.00	1882.49000	13177.43

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0430 0641 2 11 PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	5.000 EA	1103.97000	5519.85	1155.00000	5775.00	1199.75000	5998.75
0435 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	53.000 EA	1079.92000	57235.76	1130.00000	59890.00	1119.43000	59329.79
0440 0649 31101 STEEL MAST ARM,F&I, WIND SPEED-150, SINGLE ARM, W/0 LUMINAIRE-36	1.000 EA	32676.21000	32676.21	34000.00000	34000.00	26543.66000	26543.66
0445 0649 31102 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-46	2.000 EA	31055.12000	62110.24	32500.00000	65000.00	27692.83000	55385.66
0450 0649 31103 MAST ARM,F&I, WIND SPEED-150, SINGLE ARM,W/0 LUMINAIRE-60	4.000 EA	38670.45000	154681.80	40500.00000	162000.00	33379.61000	133518.44
0455 0649 31115 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 46-60	1.000 EA	44024.51000	44024.51	46000.00000	46000.00	42108.36000	42108.36
0460 0649 31116 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 46-70.5	1.000 EA	54846.96000	54846.96	58000.00000	58000.00	46037.45000	46037.45
0465 0649 31117 MAST ARM,F&I, WIND SPEED-150,DOUBLE ARM W/0 LUMINAIRE, 60-60	1.000 EA	53486.48000	53486.48	56000.00000	56000.00	45522.82000	45522.82
0470 0650 1111 TRAFFIC SIGNAL, F&I, 1 SECTION, 1 WAY, ALUMINUM	2.000 AS	297.78000	595.56	300.00000	600.00	655.66000	1311.32
0475 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	28.000 AS	793.38000	22214.64	835.00000	23380.00	904.06000	25313.68
0480 0650 1511 TRAFFIC SIGNAL, F&I, 5 SECTION, 1 WAY, ALUMINUM	6.000 AS	1197.84000	7187.04	1255.00000	7530.00	1226.08000	7356.48
0485 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	64.000 AS	478.49000	30623.36	500.00000	32000.00	632.98000	40510.72
0490 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	5.000 EA	10213.56000	51067.80	10700.00000	53500.00	10163.61000	50818.05

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0495 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	17.000 EA	2561.26000	43541.42	2685.00000	45645.00	2412.55000	41013.35
0500 0663 1120 SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, COMPLETE SYSTEM	4.000 EA	8641.08000	34564.32	9050.00000	36200.00	7748.84000	30995.36
0505 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	62.000 EA	175.25000	10865.50	185.00000	11470.00	192.72000	11948.64
0510 0670 5131 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL ONE PREEMPTION PLAN	4.000 AS	26718.72000	106874.88	28000.00000	112000.00	23913.83000	95655.32
0515 0684 1 1 MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	4.000 EA	4050.90000	16203.60	4245.00000	16980.00	1691.44000	6765.76
0520 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	28.000 EA	72.14000	2019.92	76.00000	2128.00	73.35000	2053.80
0525 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	48.000 EA	48.09000	2308.32	51.00000	2448.00	44.97000	2158.56
0530 0690 34 1 COMPLETE POLE REMOVAL- DEEP, DIRECT BURIAL	11.000 EA	1345.89000	14804.79	1400.00000	15400.00	1783.46000	19618.06
0535 0690 50 CONTROLLER ASSEMBLY, REMOVE, COMPLETE ASSEMBLY	3.000 EA	672.95000	2018.85	705.00000	2115.00	754.79000	2264.37
0540 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	11.000 EA	192.25000	2114.75	200.00000	2200.00	37.14000	408.54
0545 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	48.000 EA	24.05000	1154.40	25.00000	1200.00	25.86000	1241.28
0550 0690 80 SPAN WIRE ASSEMBLY, REMOVE	3.000 EA	288.44000	865.32	300.00000	900.00	336.18000	1008.54
0555 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	4.000 PI	576.76000	2307.04	600.00000	2400.00	583.08000	2332.32
0560 0690 91 SIGNAL INTERCONNECT CABLE REMOVE	12690.000 LF	0.63000	7994.70	0.66000	8375.40	1.15000	14593.50
0565 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	3.000 PI	1153.63000	3460.89	1200.00000	3600.00	456.61000	1369.83

CALL ORDER: 013 PROPOSAL ID: T4406 LETTING DATE: 12/03/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) MORRISON - COBALT JV UNIT PRICE	 AMOUNT	(5) GENERAL ASPHALT CO., INC. UNIT PRICE	 AMOUNT	(6) HALLEY ENGINEERING CONTRACTORS, UNIT PRICE	 AMOUNT
0570 0700 3201 SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	3.000 EA	441.84000	1325.52	460.00000	1380.00	409.84000	1229.52
0575 0700 5 21 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	10.000 EA	2082.47000	20824.70	2185.00000	21850.00	2931.58000	29315.80
0580 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	990.000 LF	2.10000	2079.00	2.20000	2178.00	1.08000	1069.20
0585 0715 4111 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE - 40'	2.000 EA	5160.33000	10320.66	5400.00000	10800.00	5000.00000	10000.00
0590 0741 1 11 TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL, TYPE 1 AXLE SENSOR- IN ROAD	24.000 EA	813.01000	19512.24	850.00000	20400.00	1555.68000	37336.32
0595 0745 70 12 TMS INDUCTIVE LOOP ASSEM, F&I, 2 LOOPS / LANE	24.000 AS	728.91000	17493.84	770.00000	18480.00	1053.01000	25272.24
0600 0746 71112 TMS CABINET, F&I, TYPE III, BASE MOUNT, 2 BACKPLANE	4.000 EA	3300.89000	13203.56	3460.00000	13840.00	5842.80000	23371.20
SECTION 0003 TOTALS			$ 1,185,446.35		$ 1,241,405.45		$ 1,158,775.01
CONTRACT TOTALS			$ 4,149,476.97		$ 4,282,892.36		$ 4,620,039.97

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.