VENDOR RANKING

CALL ORDER : 001 PROPOSAL ID : T3428
LETTING DATE : 02/05/14 10:30 A.M. DISTRICT : 03
SET-ASIDE : U/R CODE :
CONTRACT TIME : 160 WORKING DAYS (AVAILABLE DAYS)

PROPOSAL DESC :
The improvements under this contract consist of Replacing Beck's Lake Rd. Bridge No. 484036 with triple 8' x 5' box culvert, mill and resurface, and reconstruct the roadway section to 12-foot lanes. Rip-rap will be placed upstream and downstream of the culvert to prevent erosion. An approximate 70-foot section of the ditches on the westside of the culvert will also be paved to prevent excess erosion. A temporary two-lane bridge and roadway approaches will be constructed to the north of the existing bridge to maintain access to properties on the eastside of the bridge.

FINPROJ(S) : 42623315201 (*) F.A. NO. : 00B3158B COUNTIES : ESCAMBIA

LOCAL NAME : BECK'S LAKE ROAD ROAD NAME : BECK'S LAKE ROAD
PROJ LIMITS : OVER UNNAMMED BRANCH BRIDGE NO. 484036

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	ROADS, INC. OF NWF	Responsive	Winning bid	$ 925,841.15	0.00%
2	SUPERIOR CONSTRUCTION COMPANY SOUTHEAST, LLC	Responsive	Non-Winning Bid	$ 1,039,483.40	12.27%
3	GULF GROUP, INC.	Responsive	Non-Winning Bid	$ 1,070,172.80	15.58%
4	SCOTT BRIDGE COMPANY, INC.	Responsive	Non-Winning Bid	$ 1,253,055.04	35.34%
5	ANDERSON COLUMBIA CO., INC.	Responsive	Non-Winning Bid	$ 1,256,372.55	35.70%
6	PHOENIX CONSTRUCTION SERVICES, INC.	Responsive	Non-Winning Bid	$ 1,393,000.00	50.45%

CALL ORDER : 001 PROPOSAL ID : T3428 PROPOSAL DESC :
LETTING DATE : 02/05/14 10:30 A.M. DISTRICT : 03 The improvements under this contract consist of Replacing
SET-ASIDE : U/R CODE : Beck's Lake Rd. Bridge No. 484036 with triple 8' x 5' box
CONTRACT TIME : 160 WORKING DAYS (AVAILABLE DAYS) culvert, mill and resurface, and reconstruct the roadway section to 12-foot lanes. Rip-rap will be placed upstream and downstream of the culvert to prevent erosion. An approximate 70-foot section of the ditches on the westside of the culvert will also be paved to prevent excess erosion. A temporary two-lane bridge and roadway approaches will be constructed to the north of the existing bridge to maintain access to properties on the eastside of the bridge.

FINPROJ(S) : 42623315201 (*) F.A. NO. : 00B3158B COUNTIES : ESCAMBIA

LOCAL NAME : BECK'S LAKE ROAD ROAD NAME : BECK'S LAKE ROAD
PROJ LIMITS : OVER UNNAMMED BRANCH BRIDGE NO. 484036

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ROADS, INC. OF NWF UNIT PRICE	AMOUNT	(2) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42623315201	796.000 LS	27983.21000	27983.21	55000.00000	55000.00	38550.00000	38550.00
0010 0125 1 EXCAVATION FOR STRUCTURES	1991.000 CY	10.29000	20487.39	14.00000	27874.00	11.50000	22896.50
0015 0400 4 1 CONCRETE CLASS IV, CULVERTS	170.400 CY	783.53000	133513.51	1050.00000	178920.00	975.00000	166140.00
0020 0415 1 1 REINF STEEL- ROADWAY	33760.000 LB	0.84000	28358.40	0.70000	23632.00	1.55000	52328.00
0025 0530 1 RIPRAP, SAND-CEMENT	24.500 CY	235.85000	5778.33	600.00000	14700.00	640.00000	15680.00
0030 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE	181.700 TN	64.65000	11746.91	92.00000	16716.40	170.00000	30889.00
0035 0530 74 BEDDING STONE	64.700 TN	110.61000	7156.47	122.00000	7893.40	100.00000	6470.00
SECTION 0001 TOTALS		$	235,024.22	$	324,735.80	$	332,953.50
SECTION 0002 ROADWAY							
0040 0101 1 MOBILIZATION 42623315201	LUMP	129902.00000	129902.00	90000.00000	90000.00	27000.00000	27000.00

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ROADS, INC. OF NWF UNIT PRICE	 AMOUNT	(2) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	 AMOUNT
0045 0102 1 MAINTENANCE OF TRAFFIC 42623315201	160.000 LS	12424.17000	12424.17	5000.00000	5000.00	18500.00000	18500.00
0050 0102 2 1 SPECIAL DETOUR 1 42623315201	LUMP	269730.01000	269730.01	250000.00000	250000.00	251000.00000	251000.00
0055 0102 60 WORK ZONE SIGN	3520.000 ED	0.28000	985.60	0.25000	880.00	0.45000	1584.00
0060 0102 71 11 BARRIER WALL, TEMPORARY, F&I, CONCRETE	1658.000 LF	18.69000	30988.02	18.00000	29844.00	26.50000	43937.00
0065 0102 74 1 TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, OR LCD	4800.000 ED	0.13000	624.00	0.12000	576.00	0.30000	1440.00
0070 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	1920.000 ED	0.28000	537.60	0.25000	480.00	0.70000	1344.00
0075 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	640.000 ED	0.28000	179.20	0.25000	160.00	0.45000	288.00
0080 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	184.000 EA	5.60000	1030.40	4.25000	782.00	4.50000	828.00
0085 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	5280.000 ED	0.13000	686.40	0.12000	633.60	0.70000	3696.00
0090 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	4.000 LO	940.23000	3760.92	840.00000	3360.00	1300.00000	5200.00
0095 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	14.000 ED	16.79000	235.06	50.00000	700.00	21.50000	301.00
0100 0104 10 3 SEDIMENT BARRIER	1154.000 LF	2.91000	3358.14	1.25000	1442.50	3.00000	3462.00
0105 0104 11 FLOATING TURBIDITY BARRIER	260.000 LF	18.18000	4726.80	8.75000	2275.00	22.00000	5720.00
0110 0110 1 1 CLEARING & GRUBBING 42623315201	1.300 LS	24167.00000	24167.00	120000.00000	120000.00	8000.00000	8000.00
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	1319.000 SY	6.34000	8362.46	8.00000	10552.00	7.00000	9233.00
0120 0120 1 REGULAR EXCAVATION	350.000 CY	12.57000	4399.50	14.00000	4900.00	7.50000	2625.00

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ROADS, INC. OF NWF UNIT PRICE	 AMOUNT	(2) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	 AMOUNT
0125 0120 6 EMBANKMENT	936.000 CY	16.96000	15874.56	9.00000	8424.00	10.50000	9828.00
0130 0125 3 SELECT BEDDING MATERIAL	228.000 CY	18.10000	4126.80	30.00000	6840.00	89.00000	20292.00
0135 0160 4 TYPE B STABILIZATION	3218.000 SY	2.28000	7337.04	3.50000	11263.00	7.00000	22526.00
0140 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	3727.000 SY	2.82000	10510.14	0.10000	372.70	4.00000	14908.00
0145 0285706 OPTIONAL BASE, BASE GROUP 06	2016.000 SY	20.23000	40783.68	20.00000	40320.00	29.00000	58464.00
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	633.000 SY	5.65000	3576.45	6.50000	4114.50	12.00000	7596.00
0155 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	250.400 TN	81.65000	20445.16	90.00000	22536.00	213.00000	53335.20
0160 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	38.900 TN	203.28000	7907.59	295.00000	11475.50	445.00000	17310.50
0165 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	582.000 SY	53.73000	31270.86	50.00000	29100.00	80.00000	46560.00
0170 0536 1 1 GUARDRAIL -ROADWAY	1000.000 LF	18.47000	18470.00	16.70000	16700.00	44.50000	44500.00
0175 0536 1 5 GUARDRAIL- ROADWAY, THRIE BEAM	125.000 LF	27.42000	3427.50	24.80000	3100.00	60.00000	7500.00
0180 0536 7 SPECIAL GUARDRAIL POST	18.000 EA	279.84000	5037.12	253.06000	4555.08	150.00000	2700.00
0185 0536 73 GUARDRAIL REMOVAL	340.000 LF	1.12000	380.80	1.52000	516.80	22.00000	7480.00
0190 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY-PARALLEL	4.000 EA	2182.70000	8730.80	1973.88000	7895.52	3000.00000	12000.00
0195 0570 1 2 PERFORMANCE TURF, SOD	3804.000 SY	2.77000	10537.08	5.00000	19020.00	4.40000	16737.60
0200 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	0.764 NM	1678.99000	1282.75	1050.00000	802.20	3000.00000	2292.00
0205 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.764 NM	1678.99000	1282.75	1050.00000	802.20	3000.00000	2292.00
SECTION 0002 TOTALS		$	687,078.36	$	709,422.60	$	730,479.30
SECTION 0003 SIGNING							

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) ROADS, INC. OF NWF UNIT PRICE	 AMOUNT	(2) SUPERIOR CONSTRUCTION COMPA UNIT PRICE	 AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	 AMOUNT
0210 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	1.000 AS	335.80000	335.80	235.00000	235.00	370.00000	370.00
0215 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	22.39000	44.78	45.00000	90.00	150.00000	300.00
0220 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42623315201	LUMP	3357.99000	3357.99	5000.00000	5000.00	6070.00000	6070.00
SECTION 0003 TOTALS		$	3,738.57	$	5,325.00	$	6,740.00
CONTRACT TOTALS		$	925,841.15	$	1,039,483.40	$	1,070,172.80

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT	(5) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(6) PHOENIX CONSTRUCTION SERVICES, UNIT PRICE	 AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42623315201	796.000 LS	13853.80000	13853.80	45700.00000	45700.00	100000.00000	100000.00
0010 0125 1 EXCAVATION FOR STRUCTURES	1991.000 CY	34.86000	69406.26	48.00000	95568.00	10.00000	19910.00
0015 0400 4 1 CONCRETE CLASS IV, CULVERTS	170.400 CY	985.47000	167924.09	785.00000	133764.00	710.00000	120984.00
0020 0415 1 1 REINF STEEL- ROADWAY	33760.000 LB	1.44000	48614.40	1.50000	50640.00	1.00000	33760.00
0025 0530 1 RIPRAP, SAND-CEMENT	24.500 CY	410.00000	10045.00	500.00000	12250.00	450.00000	11025.00
0030 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE	181.700 TN	114.75000	20850.08	100.00000	18170.00	75.00000	13627.50
0035 0530 74 BEDDING STONE	64.700 TN	221.19000	14310.99	100.00000	6470.00	90.00000	5823.00
SECTION 0001 TOTALS		$	345,004.62	$	362,562.00	$	305,129.50
SECTION 0002 ROADWAY							
0040 0101 1 MOBILIZATION 42623315201	LUMP	125304.25000	125304.25	155000.00000	155000.00	125000.00000	125000.00
0045 0102 1 MAINTENANCE OF TRAFFIC 42623315201	160.000 LS	29184.20000	29184.20	12500.00000	12500.00	15000.00000	15000.00
0050 0102 2 1 SPECIAL DETOUR 1 42623315201	LUMP	430054.02000	430054.02	350000.00000	350000.00	575000.00000	575000.00
0055 0102 60 WORK ZONE SIGN	3520.000 ED	0.25000	880.00	0.30000	1056.00	0.50000	1760.00
0060 0102 71 11 BARRIER WALL, TEMPORARY, F&I, CONCRETE	1658.000 LF	18.00000	29844.00	22.00000	36476.00	18.00000	29844.00
0065 0102 74 1 TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, OR LCD	4800.000 ED	0.20000	960.00	0.20000	960.00	0.25000	1200.00
0070 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	1920.000 ED	0.35000	672.00	0.30000	576.00	0.50000	960.00
0075 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	640.000 ED	0.35000	224.00	0.30000	192.00	0.25000	160.00

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT	(5) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(6) PHOENIX CONSTRUCTION SERVICES, UNIT PRICE	 AMOUNT
0080 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	184.000 EA	4.25000	782.00	5.00000	920.00	6.00000	1104.00
0085 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	5280.000 ED	0.20000	1056.00	0.20000	1056.00	0.50000	2640.00
0090 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	4.000 LO	1050.00000	4200.00	1100.00000	4400.00	1200.00000	4800.00
0095 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	14.000 ED	14.50000	203.00	18.00000	252.00	20.00000	280.00
0100 0104 10 3 SEDIMENT BARRIER	1154.000 LF	4.25000	4904.50	6.25000	7212.50	2.50000	2885.00
0105 0104 11 FLOATING TURBIDITY BARRIER	260.000 LF	17.00000	4420.00	13.00000	3380.00	8.00000	2080.00
0110 0110 1 1 CLEARING & GRUBBING 42623315201	1.300 LS	37375.00000	37375.00	39000.00000	39000.00	70000.00000	70000.00
0115 0110 4 REMOVAL OF EXISTING CONCRETE PAVEMENT	1319.000 SY	4.25000	5605.75	8.50000	11211.50	8.00000	10552.00
0120 0120 1 REGULAR EXCAVATION	350.000 CY	15.00000	5250.00	35.00000	12250.00	10.00000	3500.00
0125 0120 6 EMBANKMENT	936.000 CY	16.50000	15444.00	24.00000	22464.00	17.00000	15912.00
0130 0125 3 SELECT BEDDING MATERIAL	228.000 CY	18.50000	4218.00	120.00000	27360.00	20.00000	4560.00
0135 0160 4 TYPE B STABILIZATION	3218.000 SY	2.10000	6757.80	3.10000	9975.80	5.00000	16090.00
0140 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	3727.000 SY	4.00000	14908.00	2.75000	10249.25	4.00000	14908.00
0145 0285706 OPTIONAL BASE, BASE GROUP 06	2016.000 SY	22.50000	45360.00	16.00000	32256.00	15.00000	30240.00
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	633.000 SY	8.50000	5380.50	10.00000	6330.00	6.00000	3798.00
0155 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	250.400 TN	110.00000	27544.00	150.00000	37560.00	150.00000	37560.00
0160 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	38.900 TN	250.00000	9725.00	275.00000	10697.50	250.00000	9725.00

CALL ORDER: 001 PROPOSAL ID: T3428 LETTING DATE: 02/05/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT	(5) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	(6) PHOENIX CONSTRUCTION SERVICES, UNIT PRICE	 AMOUNT
0165 0524 1 1 CONCRETE DITCH PAVT, NON REINFORCED, 3"	582.000 SY	45.00000	26190.00	59.00000	34338.00	35.00000	20370.00
0170 0536 1 1 GUARDRAIL -ROADWAY	1000.000 LF	26.05000	26050.00	26.00000	26000.00	18.00000	18000.00
0175 0536 1 5 GUARDRAIL- ROADWAY, THRIE BEAM	125.000 LF	47.00000	5875.00	39.00000	4875.00	25.00000	3125.00
0180 0536 7 SPECIAL GUARDRAIL POST	18.000 EA	215.00000	3870.00	255.00000	4590.00	2000.00000	36000.00
0185 0536 73 GUARDRAIL REMOVAL	340.000 LF	21.00000	7140.00	3.25000	1105.00	3.00000	1020.00
0190 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY-PARALLEL	4.000 EA	1795.00000	7180.00	2600.00000	10400.00	2000.00000	8000.00
0195 0570 1 2 PERFORMANCE TURF, SOD	3804.000 SY	3.75000	14265.00	3.00000	11412.00	4.00000	15216.00
0200 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	0.764 NM	1050.00000	802.20	2000.00000	1528.00	2000.00000	1528.00
0205 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.764 NM	1050.00000	802.20	2000.00000	1528.00	2000.00000	1528.00
SECTION 0002 TOTALS		$	902,430.42	$	889,110.55	$	1,084,345.00
SECTION 0003 SIGNING							
0210 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	1.000 AS	235.00000	235.00	400.00000	400.00	350.00000	350.00
0215 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	45.00000	90.00	75.00000	150.00	20.00000	40.00
0220 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42623315201	LUMP	5295.00000	5295.00	4150.00000	4150.00	3135.50000	3135.50
SECTION 0003 TOTALS		$	5,620.00	$	4,700.00	$	3,525.50
CONTRACT TOTALS		$	1,253,055.04	$	1,256,372.55	$	1,393,000.00

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.