VENDOR RANKING

CALL ORDER : 001 PROPOSAL ID : T3429 PROPOSAL DESC :
LETTING DATE : 02/26/14 10:30 A.M. DISTRICT : 03
SET-ASIDE : U/R CODE :
CONTRACT TIME : 180 WORKING DAYS (AVAILABLE DAYS)

The improvements under this contract consist of replacing bridge with an 86-foot two span concrete bridge. Rip-rap will be placed upstream and downstream of the bridge to prevent erosion. Ditches and ditch bottom inlets will also be added for drainage in the vicinity of the bridge. A temporary two-lane bridge and roadway approaches will be constructed to the south of the existing bridge to maintain access to properties on the westside of the bridge.

FINPROJ(S) : 42445815201 (*) F.A. NO. : 00B3156B COUNTIES : ESCAMBIA

LOCAL NAME : PINEVILLE ROAD ROAD NAME : PINEVILLE ROAD
PROJ LIMITS : BRUSHY CREEK BRIDGE BRIDGE NO. 484007

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	MURPHREE BRIDGE CORPORATION	Responsive	Winning bid	$ 1,116,299.22	0.00%
2	GULF GROUP, INC.	Responsive	Non-Winning Bid	$ 1,176,534.17	5.39%
3	SCOTT BRIDGE COMPANY, INC.	Responsive	Non-Winning Bid	$ 1,481,775.99	32.74%
4	ANDERSON COLUMBIA CO., INC.	Responsive	Non-Winning Bid	$ 1,607,931.68	44.04%

CALL ORDER : 001 PROPOSAL ID : T3429 PROPOSAL DESC :
LETTING DATE : 02/26/14 10:30 A.M. DISTRICT : 03 The improvements under this contract consist of replacing
SET-ASIDE : U/R CODE : bridge with an 86-foot two span concrete bridge. Rip-rap
CONTRACT TIME : 180 WORKING DAYS (AVAILABLE DAYS) will be placed upstream and downstream of the bridge to prevent erosion. Ditches and ditch bottom inlets will also be added for drainage in the vicinity of the bridge. A temporary two-lane bridge and roadway approaches will be constructed to the south of the existing bridge to maintain access to properties on the westside of the bridge.

FINPROJ(S) : 42445815201 (*) F.A. NO. : 00B3156B COUNTIES : ESCAMBIA

LOCAL NAME : PINEVILLE ROAD ROAD NAME : PINEVILLE ROAD
PROJ LIMITS : BRUSHY CREEK BRIDGE BRIDGE NO. 484007

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) MURPHREE BRIDGE CORPORATION UNIT PRICE	AMOUNT	(2) GULF GROUP, INC. UNIT PRICE	AMOUNT	(3) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42445815201	1556.000 LS	20000.00000	20000.00	26806.00000	26806.00	75000.00000	75000.00
0010 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	40.800 CY	400.00000	16320.00	323.60000	13202.88	329.56000	13446.05
0015 0400 2 41 CONCRETE CLASS II, PRECAST DECK OVERLAY	47.900 CY	940.00000	45026.00	730.40000	34986.16	1377.69000	65991.35
0020 0400 4 5 CONCRETE CLASS IV, SUBSTRUCTURE	29.800 CY	1200.00000	35760.00	979.00000	29174.20	1086.13000	32366.67
0025 0400 7 BRIDGE DECK GROOVING, LESS THAN 8.5"	240.000 SY	15.00000	3600.00	22.30000	5352.00	18.00000	4320.00
0030 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	8567.000 LB	1.25000	10708.75	1.10000	9423.70	1.01000	8652.67
0035 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	4956.000 LB	1.25000	6195.00	1.10000	5451.60	0.97000	4807.32
0040 0415 1 9 REINFORCING STEEL- APPROACH SLABS	8212.000 LB	0.85000	6980.20	1.05000	8622.60	0.97000	7965.64
0045 0450 3 25 PRESTRESSED SLAB UNITS, WIDTH 60", THICKNESS 15"	338.300 LF	180.00000	60894.00	307.20000	103925.76	247.07000	83583.78
0050 0450 3 95 PRESTRESSED SLAB UNITS, VARIABLE WIDTH 30-47", THICKNESS 15"	169.200 LF	180.00000	30456.00	266.60000	45108.72	184.62000	31237.70

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(2) GULF GROUP, INC. UNIT PRICE	 AMOUNT	(3) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT
0055 0455 35 21 STEEL PILING, 20" DIA. PIPE	753.000 LF	155.00000	116715.00	164.20000	123642.60	144.87000	109087.11
0060 0455120 6 PILE POINT PROTECTION, 20" ROUND	15.000 EA	240.00000	3600.00	235.00000	3525.00	1098.99000	16484.85
0065 0455144 21 TEST PILES - STEEL, 20" DIA PIPE	245.000 LF	165.00000	40425.00	468.50000	114782.50	157.84000	38670.80
0070 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	51.000 LF	40.00000	2040.00	39.65000	2022.15	32.78000	1671.78
0075 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	252.000 LF	70.00000	17640.00	83.75000	21105.00	100.35000	25288.20
0080 0530 1 RIPRAP, SAND-CEMENT	28.600 CY	490.00000	14014.00	480.00000	13728.00	382.32000	10934.35
0085 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE	1072.600 TN	60.00000	64356.00	100.00000	107260.00	89.83000	96351.66
0090 0530 74 BEDDING STONE	382.000 TN	60.00000	22920.00	50.00000	19100.00	84.97000	32458.54
0095 0548 13 RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	602.000 SF	25.00000	15050.00	25.00000	15050.00	35.79000	21545.58
SECTION 0001 TOTALS		$	532,699.95	$	702,268.87	$	679,864.05
SECTION 0002 ROADWAY							
0100 0101 1 MOBILIZATION 42445815201	LUMP	118542.01000	118542.01	76583.00000	76583.00	148177.92000	148177.92
0105 0102 1 MAINTENANCE OF TRAFFIC 42445815201	180.000 LS	10190.75000	10190.75	16300.00000	16300.00	14067.98000	14067.98
0110 0102 2 1 SPECIAL DETOUR 1 42445815201	LUMP	205242.34000	205242.34	77500.00000	77500.00	375000.00000	375000.00
0115 0102 60 WORK ZONE SIGN	4320.000 ED	0.25000	1080.00	0.31000	1339.20	0.25000	1080.00
0120 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	759.000 LF	15.00000	11385.00	26.05000	19771.95	29.73000	22565.07
0125 0102 73 TEMPORARY GUARDRAIL	280.000 LF	48.00000	13440.00	59.50000	16660.00	48.00000	13440.00

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(2) GULF GROUP, INC. UNIT PRICE	 AMOUNT	(3) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT
0130 0102 74 1 TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, OR LCD	3600.000 ED	0.20000	720.00	0.25000	900.00	0.20000	720.00
0135 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	2880.000 ED	0.35000	1008.00	0.43000	1238.40	0.35000	1008.00
0140 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	720.000 ED	0.45000	324.00	0.56000	403.20	0.45000	324.00
0145 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	121.000 EA	4.75000	574.75	4.00000	484.00	4.75000	574.75
0150 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	2700.000 ED	0.18000	486.00	0.22000	594.00	0.18000	486.00
0155 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	4.000 LO	250.00000	1000.00	1178.00000	4712.00	950.00000	3800.00
0160 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	14.000 ED	18.50000	259.00	22.95000	321.30	18.50000	259.00
0165 0104 10 3 SEDIMENT BARRIER	1490.000 LF	3.84000	5721.60	1.25000	1862.50	3.84000	5721.60
0170 0104 11 FLOATING TURBIDITY BARRIER	347.000 LF	12.00000	4164.00	10.00000	3470.00	15.06000	5225.82
0175 0104 18 INLET PROTECTION SYSTEM	5.000 EA	194.88000	974.40	75.00000	375.00	194.88000	974.40
0180 0110 1 1 CLEARING & GRUBBING 42445815201	1.100 LS	25487.57000	25487.57	86750.00000	86750.00	25487.55000	25487.55
0185 0120 1 REGULAR EXCAVATION	515.000 CY	21.85000	11252.75	5.90000	3038.50	21.85000	11252.75
0190 0120 6 EMBANKMENT	521.000 CY	20.52000	10690.92	15.15000	7893.15	20.52000	10690.92
0195 0160 4 TYPE B STABILIZATION	2029.000 SY	3.53000	7162.37	4.50000	9130.50	3.53000	7162.37
0200 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	2316.000 SY	2.77000	6415.32	0.90000	2084.40	2.77000	6415.32
0205 0285702 OPTIONAL BASE, BASE GROUP 02	92.000 SY	20.57000	1892.44	12.00000	1104.00	20.57000	1892.44

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(2) GULF GROUP, INC. UNIT PRICE	 AMOUNT	(3) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT
0210 0285706 OPTIONAL BASE, BASE GROUP 06	419.000 SY	25.61000	10730.59	14.00000	5866.00	25.61000	10730.59
0215 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	77.600 TN	153.94000	11945.74	160.00000	12416.00	153.94000	11945.74
0220 0400 1 2 CONCRETE CLASS I, ENDWALLS	1.600 CY	2296.78000	3674.85	850.00000	1360.00	2296.78000	3674.85
0225 0425 1521 INLETS, DT BOT, TYPE C,<10'	5.000 EA	2839.80000	14199.00	1500.00000	7500.00	2839.80000	14199.00
0230 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	414.000 LF	39.88000	16510.32	42.00000	17388.00	39.88000	16510.32
0235 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	1.000 EA	1000.09000	1000.09	750.00000	750.00	1000.09000	1000.09
0240 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	513.200 TN	99.55000	51089.06	100.00000	51320.00	99.55000	51089.06
0245 0536 1 1 GUARDRAIL -ROADWAY	350.000 LF	22.50000	7875.00	27.90000	9765.00	22.50000	7875.00
0250 0536 8 GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY, FURNISH & INSTALL	4.000 EA	2750.00000	11000.00	3410.00000	13640.00	2750.00000	11000.00
0255 0536 73 GUARDRAIL REMOVAL	150.000 LF	2.00000	300.00	2.50000	375.00	2.00000	300.00
0260 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY-PARALLEL	4.000 EA	1950.00000	7800.00	2418.00000	9672.00	1950.00000	7800.00
0265 0570 1 2 PERFORMANCE TURF, SOD	2316.000 SY	3.15000	7295.40	3.60000	8337.60	3.15000	7295.40
0270 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	0.110 NM	1250.00000	137.50	1550.00000	170.50	1250.00000	137.50
0275 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.110 NM	1250.00000	137.50	1550.00000	170.50	1250.00000	137.50
SECTION 0002 TOTALS		$	581,708.27	$	471,245.70	$	800,020.94
SECTION 0003 SIGNING							

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(2) GULF GROUP, INC. UNIT PRICE	 AMOUNT	(3) SCOTT BRIDGE COMPANY, INC. UNIT PRICE	 AMOUNT
0280 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	20.00000	40.00	24.80000	49.60	20.00000	40.00
0285 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42445815201	LUMP	1851.00000	1851.00	2970.00000	2970.00	1851.00000	1851.00
SECTION 0003 TOTALS			$ 1,891.00		$ 3,019.60		$ 1,891.00
CONTRACT TOTALS			$ 1,116,299.22		$ 1,176,534.17		$ 1,481,775.99

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ANDERSON COLUMBIA CO., INC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42445815201	1556.000 LS	50431.95000	50431.95				
0010 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	40.800 CY	519.88000	21211.10				
0015 0400 2 41 CONCRETE CLASS II, PRECAST DECK OVERLAY	47.900 CY	924.25000	44271.58				
0020 0400 4 5 CONCRETE CLASS IV, SUBSTRUCTURE	29.800 CY	1403.82000	41833.84				
0025 0400 7 BRIDGE DECK GROOVING, LESS THAN 8.5"	240.000 SY	13.62000	3268.80				
0030 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	8567.000 LB	1.03000	8824.01				
0035 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	4956.000 LB	1.02000	5055.12				
0040 0415 1 9 REINFORCING STEEL- APPROACH SLABS	8212.000 LB	1.01000	8294.12				
0045 0450 3 25 PRESTRESSED SLAB UNITS, WIDTH 60", THICKNESS 15"	338.300 LF	338.25000	114429.98				
0050 0450 3 95 PRESTRESSED SLAB UNITS, VARIABLE WIDTH 30-47", THICKNESS 15"	169.200 LF	357.32000	60458.54				
0055 0455 35 21 STEEL PILING, 20" DIA. PIPE	753.000 LF	243.26000	183174.78				
0060 0455120 6 PILE POINT PROTECTION, 20" ROUND	15.000 EA	438.14000	6572.10				
0065 0455144 21 TEST PILES - STEEL, 20" DIA PIPE	245.000 LF	307.86000	75425.70				
0070 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	51.000 LF	57.79000	2947.29				
0075 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	252.000 LF	109.21000	27520.92				

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0080 0530 1 RIPRAP, SAND-CEMENT	28.600 CY	535.88000	15326.17				
0085 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE	1072.600 TN	76.09000	81614.13				
0090 0530 74 BEDDING STONE	382.000 TN	85.97000	32840.54				
0095 0548 13 RETAINING WALL SYSTEM,TEMPORARY, EXCLUDING BARRIER	602.000 SF	27.62000	16627.24				
SECTION 0001 TOTALS		$	800,127.91	$		$	
SECTION 0002 ROADWAY							
0100 0101 1 MOBILIZATION 42445815201	LUMP	266778.00000	266778.00				
0105 0102 1 MAINTENANCE OF TRAFFIC 42445815201	180.000 LS	12582.72000	12582.72				
0110 0102 2 1 SPECIAL DETOUR 1 42445815201	LUMP	278043.18000	278043.18				
0115 0102 60 WORK ZONE SIGN	4320.000 ED	0.27000	1166.40				
0120 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K	759.000 LF	33.95000	25768.05				
0125 0102 73 TEMPORARY GUARDRAIL	280.000 LF	50.92000	14257.60				
0130 0102 74 1 TEMPORARY BARRICADE- TYPES I, II, DI, VP, DRUM, OR LCD	3600.000 ED	0.13000	468.00				
0135 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	2880.000 ED	0.27000	777.60				
0140 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	720.000 ED	0.27000	194.40				
0145 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	121.000 EA	4.77000	577.17				
0150 0102 79 LIGHTS,BARRIER WALL MOUNT,TEMP,TYPE C, STEADY BURN	2700.000 ED	0.12000	324.00				

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ANDERSON COLUMBIA CO., INC. UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT	( ) UNIT PRICE	AMOUNT
0155 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	4.000 LO	1060.79000	4243.16				
0160 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	14.000 ED	26.52000	371.28				
0165 0104 10 3 SEDIMENT BARRIER	1490.000 LF	2.39000	3561.10				
0170 0104 11 FLOATING TURBIDITY BARRIER	347.000 LF	10.61000	3681.67				
0175 0104 18 INLET PROTECTION SYSTEM	5.000 EA	196.25000	981.25				
0180 0110 1 1 CLEARING & GRUBBING 42445815201	1.100 LS	23337.40000	23337.40				
0185 0120 1 REGULAR EXCAVATION	515.000 CY	12.73000	6555.95				
0190 0120 6 EMBANKMENT	521.000 CY	20.16000	10503.36				
0195 0160 4 TYPE B STABILIZATION	2029.000 SY	3.71000	7527.59				
0200 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	2316.000 SY	3.18000	7364.88				
0205 0285702 OPTIONAL BASE, BASE GROUP 02	92.000 SY	19.09000	1756.28				
0210 0285706 OPTIONAL BASE, BASE GROUP 06	419.000 SY	19.09000	7998.71				
0215 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	77.600 TN	238.68000	18521.57				
0220 0400 1 2 CONCRETE CLASS I, ENDWALLS	1.600 CY	689.51000	1103.22				
0225 0425 1521 INLETS, DT BOT, TYPE C,<10'	5.000 EA	3394.53000	16972.65				
0230 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	414.000 LF	37.13000	15371.82				
0235 0430984125 MITERED END SECTION, OPTIONAL ROUND, 18" SD	1.000 EA	901.67000	901.67				

CALL ORDER: 001 PROPOSAL ID: T3429 LETTING DATE: 02/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0240 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	513.200 TN	76.38000	39198.22				
0245 0536 1 1 GUARDRAIL -ROADWAY	350.000 LF	23.87000	8354.50				
0250 0536 8 GUARDRAIL- BRIDGE ANCHORAGE ASSEMBLY, FURNISH & INSTALL	4.000 EA	2917.18000	11668.72				
0255 0536 73 GUARDRAIL REMOVAL	150.000 LF	2.39000	358.50				
0260 0536 85 24 GUARDRAIL END ANCHORAGE ASSEMBLY-PARALLEL	4.000 EA	2068.54000	8274.16				
0265 0570 1 2 PERFORMANCE TURF, SOD	2316.000 SY	2.65000	6137.40				
0270 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	0.110 NM	2651.98000	291.72				
0275 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.110 NM	2651.98000	291.72				
SECTION 0002 TOTALS		$	806,265.62	$		$	
SECTION 0003 SIGNING							
0280 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	53.04000	106.08				
0285 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42445815201	LUMP	1432.07000	1432.07				
SECTION 0003 TOTALS		$	1,538.15	$		$	
CONTRACT TOTALS		$	1,607,931.68	$	0.00	$	0.00

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.