VENDOR RANKING

CALL ORDER : 033 PROPOSAL ID : T4367 PROPOSAL DESC :
LETTING DATE : 06/18/14 10:30 A.M. DISTRICT : 04
SET-ASIDE : U/R CODE :
CONTRACT TIME : 353 WORKING DAYS (AVAILABLE DAYS)

This project involves the reconstruction/realignment of Andrews Ave. from a 2 lane undivided roadway to a 4 lane divided urban section with bike lanes and sidewalks. A new drainage system will be installed consisting of curb inlets and pipes that will collect and convey flow to proposed ponds that will treat the runoff before it is discharged to the Old Pompano (C-14) Canal. New signalization improvements will be constructed at the John Knox Village Blvd. intersection. In addition, new signing and pavement markings, lighting and landscaping will be constructed along the corridor. This project will realign Andrews Avenue and will involve extensive right of way acquisition and utility coordination.

FINPROJ(S) : 23072415201 (*) F.A. NO. : 8886210A COUNTIES : BROWARD

LOCAL NAME : ANDREWS AVE EXT FROM POMPANO PARK PLACE TO S. OF A ROAD NAME : ANDREWS AVE EXT FROM POMPANO PARK PLACE TO S. OF
PROJ LIMITS : FROM POMPANO PARK PLACE TO S. OF ATLANTIC BLVD

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	WEEKLEY ASPHALT PAVING, INC.	Responsive	Winning bid	$ 3,396,284.27	0.00%
2	HARDRIVES OF DELRAY, INC.	Responsive	Non-Winning Bid	$ 3,703,868.92	9.05%
3	WILLIAMS PAVING COMPANY, INC.	Responsive	Non-Winning Bid	$ 3,799,801.11	11.88%
4	TRIPLE R PAVING, INC.	Responsive	Non-Winning Bid	$ 3,846,409.18	13.25%
5	MAYTIN ENGINEERING CORP.	Responsive	Non-Winning Bid	$ 3,878,985.58	14.21%
6	RANGER CONSTRUCTION INDUSTRIES, INC.	Responsive	Non-Winning Bid	$ 3,920,966.73	15.44%
7	CENTRAL FLORIDA EQUIPMENT RENTALS, INC.	Responsive	Non-Winning Bid	$ 3,970,664.78	16.91%
8	BERGERON LAND DEVELOPMENT, INC	Responsive	Non-Winning Bid	$ 3,999,635.84	17.76%
9	HUBBARD CONSTRUCTION COMPANY	Responsive	Non-Winning Bid	$ 4,375,270.69	28.82%
10	DAVID MANCINI & SONS, INC.	Responsive	Non-Winning Bid	$ 4,587,686.40	35.07%
11	COMMUNITY ASPHALT CORP.	Responsive	Non-Winning Bid	$ 4,782,044.23	40.80%
12	MARKS BROTHERS INC.	Responsive	Non-Winning Bid	$ 4,823,213.70	42.01%

CALL ORDER : 033 PROPOSAL ID : T4367 PROPOSAL DESC :
LETTING DATE : 06/18/14 10:30 A.M. DISTRICT : 04
SET-ASIDE : U/R CODE :
CONTRACT TIME : 353 WORKING DAYS (AVAILABLE DAYS)

This project involves the reconstruction/realignment of Andrews Ave. from a 2 lane undivided roadway to a 4 lane divided urban section with bike lanes and sidewalks. A new drainage system will be installed consisting of curb inlets and pipes that will collect and convey flow to proposed ponds that will treat the runoff before it is discharged to the Old Pompano (C-14) Canal. New signalization improvements will be constructed at the John Knox Village Blvd. intersection. In addition, new signing and pavement markings, lighting and landscaping will be constructed along the corridor. This project will realign Andrews Avenue and will involve extensive right of way acquisition and utility coordination.

FINPROJ(S) : 23072415201 (*) F.A. NO. : 8886210A COUNTIES : BROWARD

LOCAL NAME : ANDREWS AVE EXT FROM POMPANO PARK PLACE TO S. OF A ROAD NAME : ANDREWS AVE EXT FROM POMPANO PARK PLACE TO S. OF
PROJ LIMITS : FROM POMPANO PARK PLACE TO S. OF ATLANTIC BLVD

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 23072415201	LUMP	106552.00000	106552.00	386000.00000	386000.00	169999.00000	169999.00
0010 0102 1 MAINTENANCE OF TRAFFIC 23072415201	353.000 LS	366830.00000	366830.00	104000.00000	104000.00	131500.12000	131500.12
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	1.00000	250.00	16.00000	4000.00	16.98000	4245.00
0020 0102 14 TRAFFIC CONTROL OFFICER	80.000 MH	55.00000	4400.00	55.00000	4400.00	50.06000	4004.80
0025 0102 60 WORK ZONE SIGN	16336.000 ED	0.25000	4084.00	0.30000	4900.80	0.39000	6371.04
0030 0102 61 BUSINESS SIGN	6.000 EA	85.00000	510.00	70.00000	420.00	94.56000	567.36
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1262.000 LF	42.23000	53294.26	12.00000	15144.00	11.68000	14740.16

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0040 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	516.000 LF	6.50000	3354.00	5.00000	2580.00	2.80000	1444.80
0045 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	35732.000 ED	0.14000	5002.48	0.16000	5717.12	0.19000	6789.08
0050 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	7413.000 ED	0.30000	2223.90	0.39000	2891.07	0.39000	2891.07
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	166.000 ED	7.00000	1162.00	7.00000	1162.00	6.68000	1108.88
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	11437.000 ED	0.25000	2859.25	0.39000	4460.43	0.31000	3545.47
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	83.000 EA	5.00000	415.00	5.00000	415.00	4.17000	346.11
0070 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	991.000 ED	14.00000	13874.00	15.00000	14865.00	15.58000	15439.78
0075 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	706.000 ED	3.00000	2118.00	9.00000	6354.00	5.56000	3925.36
0080 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	706.000 ED	3.00000	2118.00	14.00000	9884.00	6.68000	4716.08
0085 0102911 1 PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	352.000 LF	2.25000	792.00	4.25000	1496.00	7.79000	2742.08
0090 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	950.000 LF	1.90000	1805.00	4.25000	4037.50	7.79000	7400.50
0095 0104 10 3 SEDIMENT BARRIER	3778.000 LF	0.62000	2342.36	1.25000	4722.50	0.83000	3135.74
0100 0104 11 FLOATING TURBIDITY BARRIER	160.000 LF	10.00000	1600.00	15.00000	2400.00	8.07000	1291.20
0105 0104 15 SOIL TRACKING PREVENTION DEVICE	2.000 EA	1800.00000	3600.00	3850.00000	7700.00	1946.88000	3893.76

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0110 0104 18 INLET PROTECTION SYSTEM	37.000 EA	89.00000	3293.00	120.00000	4440.00	83.44000	3087.28
0115 0107 1 LITTER REMOVAL	48.300 AC	10.00000	483.00	50.00000	2415.00	83.44000	4030.15
0120 0107 2 MOWING	48.300 AC	10.00000	483.00	50.00000	2415.00	83.44000	4030.15
0125 0110 1 1 CLEARING & GRUBBING 23072415201	9.190 LS	66632.00000	66632.00	93000.00000	93000.00	153790.00000	153790.00
0130 0120 1 REGULAR EXCAVATION	25278.000 CY	5.79000	146359.62	3.50000	88473.00	6.07000	153437.46
0135 0120 6 EMBANKMENT	704.000 CY	6.00000	4224.00	1.00000	704.00	14.08000	9912.32
0140 0160 4 TYPE B STABILIZATION	22948.000 SY	3.27000	75039.96	3.75000	86055.00	4.01000	92021.48
0145 0285709 OPTIONAL BASE, BASE GROUP 09	20715.000 SY	16.03000	332061.45	15.30000	316939.50	17.07000	353605.05
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	8381.000 SY	2.00000	16762.00	2.40000	20114.40	2.23000	18689.63
0155 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	10721.000 SY	2.50000	26802.50	2.40000	25730.40	2.50000	26802.50
0160 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	3759.500 TN	100.00000	375950.00	115.00000	432342.50	127.94000	480990.43
0165 0337 7 73 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22, ARB	1680.200 TN	130.00000	218426.00	165.00000	277233.00	155.75000	261691.15
0170 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	928.700 TN	130.00000	120731.00	170.00000	157879.00	155.75000	144645.03
0175 0400 1 2 CONCRETE CLASS I, ENDWALLS	10.000 CY	1250.00000	12500.00	851.00000	8510.00	704.21000	7042.10
0180 0415 1 6 REINFORCING STEEL- MISCELLANEOUS	48.000 LB	3.00000	144.00	34.00000	1632.00	0.78000	37.44
0185 0425 1351 INLETS, CURB, TYPE P-5, <10'	4.000 EA	3885.00000	15540.00	4614.00000	18456.00	4557.17000	18228.68
0190 0425 1361 INLETS, CURB, TYPE P-6, <10'	3.000 EA	4250.00000	12750.00	5230.00000	15690.00	4676.21000	14028.63
0195 0425 1451 INLETS, CURB, TYPE J-5, <10'	5.000 EA	6405.00000	32025.00	9856.00000	49280.00	6496.29000	32481.45

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0200 0425 1521 INLETS, DT BOT, TYPE C,<10'	4.000 EA	2750.00000	11000.00	2531.00000	10124.00	3546.01000	14184.04
0205 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED-BACK OF SIDEWALK, <10'	5.000 EA	2258.00000	11290.00	2375.00000	11875.00	3546.01000	17730.05
0210 0425 1541 INLETS, DT BOT, TYPE D, <10'	1.000 EA	3665.00000	3665.00	3517.00000	3517.00	3546.01000	3546.01
0215 0425 1579 INLETS, DITCH BOTTOM, TYPE G, MODIFY	1.000 EA	5650.00000	5650.00	6417.00000	6417.00	3546.01000	3546.01
0218 0425 1910 INLETS, CLOSED FLUME	1.000 EA	3140.00000	3140.00	3025.00000	3025.00	3546.01000	3546.01
0220 0425 2 41 MANHOLES, P-7, <10'	4.000 EA	2936.00000	11744.00	2620.00000	10480.00	3260.32000	13041.28
0225 0425 2 71 MANHOLES, J-7, <10'	6.000 EA	4633.00000	27798.00	5488.00000	32928.00	5921.74000	35530.44
0227 0425 2 72 MANHOLES, J-7, >10'	1.000 EA	5900.00000	5900.00	6702.00000	6702.00	5921.74000	5921.74
0230 0430 94 1 DESILTING PIPE, 0 - 24"	240.000 LF	6.00000	1440.00	7.00000	1680.00	13.35000	3204.00
0235 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	1575.000 LF	41.70000	65677.50	70.50000	111037.50	57.93000	91239.75
0240 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	103.000 LF	58.50000	6025.50	103.00000	10609.00	65.12000	6707.36
0245 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	14.000 LF	84.10000	1177.40	89.00000	1246.00	124.07000	1736.98
0250 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	418.000 LF	94.25000	39396.50	93.00000	38874.00	84.52000	35329.36
0255 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	789.000 LF	125.50000	99019.50	140.00000	110460.00	147.62000	116472.18
0260 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	264.000 LF	157.60000	41606.40	184.00000	48576.00	147.62000	38971.68
0265 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	10.000 CY	165.00000	1650.00	448.00000	4480.00	389.38000	3893.80

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0270 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	1.000 EA	1900.00000	1900.00	929.00000	929.00	1039.78000	1039.78
0275 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	8249.000 LF	17.48000	144192.52	18.00000	148482.00	21.89000	180570.61
0280 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	2886.000 SY	37.50000	108225.00	28.00000	80808.00	31.88000	92005.68
0285 0522 2 CONC SIDEWALK AND DRIVEWAYS, 6" THICK	348.000 SY	53.90000	18757.20	34.00000	11832.00	37.53000	13060.44
0290 0524 1 4 CONCRETE DITCH PAVEMENT, NON REINFORCED 6"	48.000 SY	69.00000	3312.00	70.00000	3360.00	58.06000	2786.88
0295 0527 2 DETECTABLE WARNINGS	280.000 SF	35.50000	9940.00	31.00000	8680.00	14.88000	4166.40
0300 0536 73 GUARDRAIL REMOVAL	265.000 LF	5.60000	1484.00	2.50000	662.50	3.75000	993.75
0305 0570 1 2 PERFORMANCE TURF, SOD	14872.000 SY	2.46000	36585.12	2.50000	37180.00	4.37000	64990.64
0310 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1.410 NM	1500.00000	2115.00	1478.00000	2083.98	762.06000	1074.50
0315 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	264.000 LF	0.60000	158.40	0.40000	105.60	0.33000	87.12
0320 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	259.000 LF	2.00000	518.00	1.00000	259.00	1.06000	274.54
0325 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.370 GM	750.00000	277.50	392.00000	145.04	293.70000	108.67
0330 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	78.000 LF	0.70000	54.60	0.40000	31.20	0.22000	17.16
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1.150 NM	1500.00000	1725.00	1478.00000	1699.70	1174.80000	1351.02

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0340 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.340 GM	750.00000	255.00	392.00000	133.28	293.70000	99.86
0345 0999 16 PARTNERING, DO NOT BID 23072415201	LUMP	6000.00000	6000.00	6000.00000	6000.00	6000.00000	6000.00
0350 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 23072415201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 2,761,071.92		$ 2,953,280.02		$ 2,981,876.06
SECTION 0002 SIGNING							
0355 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	24.000 AS	305.00000	7320.00	341.00000	8184.00	338.76000	8130.24
0360 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	3.000 AS	965.00000	2895.00	1080.00000	3240.00	1073.57000	3220.71
0365 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	1500.00000	3000.00	1679.00000	3358.00	1668.75000	3337.50
0370 0700 1 50 SINGLE POST SIGN, RELOCATE	1.000 AS	188.00000	188.00	210.00000	210.00	209.15000	209.15
0375 0700 1 60 SINGLE POST SIGN, REMOVE	4.000 AS	26.00000	104.00	28.00000	112.00	28.93000	115.72
0380 0700 2 13 MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	3003.00000	6006.00	3363.00000	6726.00	3340.85000	6681.70
0385 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	1.000 AS	3108.00000	3108.00	3480.00000	3480.00	3457.66000	3457.66
0390 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	157.00000	942.00	94.00000	564.00	174.66000	1047.96
0395 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 23072415201	LUMP	46400.00000	46400.00	22064.00000	22064.00	3844.81000	3844.81
0400 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	36.000 EA	200.00000	7200.00	199.00000	7164.00	389.38000	14017.68
SECTION 0002 TOTALS			$ 77,163.00		$ 55,102.00		$ 44,063.13
SECTION 0003 LIGHTING							

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0405 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	1816.000 LF	5.00000	9080.00	1.00000	1816.00	7.06000	12820.96
0410 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	103.000 LF	12.00000	1236.00	10.80000	1112.40	16.98000	1748.94
0415 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	17.000 EA	400.00000	6800.00	770.00000	13090.00	426.09000	7243.53
0420 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	5742.000 LF	1.75000	10048.50	1.25000	7177.50	1.45000	8325.90
0425 0715 4113 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE HEIGHT- 50'	13.000 EA	4250.00000	55250.00	4817.00000	62621.00	5753.87000	74800.31
0430 0715 4400 LIGHT POLE COMPLETE, RELOCATE	1.000 EA	2500.00000	2500.00	1660.00000	1660.00	3299.68000	3299.68
0435 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	5500.00000	5500.00	10112.00000	10112.00	6307.89000	6307.89
0440 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	13.000 EA	450.00000	5850.00	503.00000	6539.00	547.35000	7115.55
SECTION 0003 TOTALS			$ 96,264.50		$ 104,127.90		$ 121,662.76
SECTION 0004 SIGNALIZATION							
0445 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	167.000 LF	5.00000	835.00	5.50000	918.50	6.96000	1162.32
0450 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	642.000 LF	14.00000	8988.00	19.00000	12198.00	16.98000	10901.16
0455 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	2.000 PI	4000.00000	8000.00	3752.00000	7504.00	3735.79000	7471.58
0460 0633 4 1 SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, FURNISH & INSTALL	285.000 LF	4.50000	1282.50	3.50000	997.50	0.85000	242.25
0465 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	19.000 EA	400.00000	7600.00	660.00000	12540.00	426.09000	8095.71

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0470 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	2.000 EA	1000.00000	2000.00	1188.00000	2376.00	920.04000	1840.08
0475 0635 3 12 JUNCTION BOX, FURNISH & INSTALL, MOUNTE	1.000 EA	800.00000	800.00	1592.00000	1592.00	350.44000	350.44
0480 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	1.000 AS	2000.00000	2000.00	1541.00000	1541.00	2006.96000	2006.96
0485 0639 2 1 ELECTRICAL SERVICE WIRE	45.000 LF	5.00000	225.00	3.00000	135.00	2.00000	90.00
0490 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	6.000 EA	800.00000	4800.00	829.00000	4974.00	1234.88000	7409.28
0495 0649 31103 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-60	1.000 EA	28000.00000	28000.00	35203.00000	35203.00	38670.60000	38670.60
0500 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	29000.00000	58000.00	35686.00000	71372.00	40050.11000	80100.22
0505 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	30000.00000	30000.00	36491.00000	36491.00	40050.11000	40050.11
0510 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	17.000 AS	900.00000	15300.00	1005.00000	17085.00	1030.18000	17513.06
0515 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	8.000 AS	850.00000	6800.00	515.00000	4120.00	1052.43000	8419.44
0520 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	2.000 EA	4500.00000	9000.00	9077.00000	18154.00	6925.33000	13850.66
0525 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	4.000 EA	2500.00000	10000.00	3144.00000	12576.00	6953.14000	27812.56
0530 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	9.000 EA	250.00000	2250.00	170.00000	1530.00	200.25000	1802.25
0535 0670 5130 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL	1.000 AS	27000.00000	27000.00	31185.00000	31185.00	34237.28000	34237.28

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) HARDRIVES OF DELRAY, INC. UNIT PRICE	 AMOUNT	(3) WILLIAMS PAVING COMPANY, INC. UNIT PRICE	 AMOUNT
0540 0670 5400 TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.000 AS	1500.00000	1500.00	266.00000	266.00	912.25000	912.25
0545 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	8.000 EA	50.00000	400.00	32.00000	256.00	89.00000	712.00
0550 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	50.00000	400.00	32.00000	256.00	55.63000	445.04
0555 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	4.000 EA	1000.00000	4000.00	2239.00000	8956.00	611.88000	2447.52
0560 0690 50 1 CONTROLLER ASSEMBLY, REMOVE, CAB ASSEMBLY, LESS FOUNDATION	1.000 EA	500.00000	500.00	168.00000	168.00	845.50000	845.50
0565 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	14.000 EA	100.00000	1400.00	14.00000	196.00	72.31000	1012.34
0570 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	9.000 EA	50.00000	450.00	20.00000	180.00	73.43000	660.87
0575 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	200.00000	200.00	607.00000	607.00	400.50000	400.50
0580 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	1.000 PI	500.00000	500.00	472.00000	472.00	684.19000	684.19
0585 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	2.000 PI	1000.00000	2000.00	300.00000	600.00	554.03000	1108.06
0590 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, 12-18 SF	4.000 EA	2200.00000	8800.00	2390.00000	9560.00	4066.20000	16264.80
SECTION 0004 TOTALS			$ 243,030.50		$ 294,009.00		$ 327,519.03
SECTION 0005 LANDSCAPE / PERIPHERAL							
0595 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK	289.000 SY	119.15000	34434.35	150.00000	43350.00	137.95000	39867.55
0600 0580 1 1 LANDSCAPE COMPLETE- SMALL PLANTS 23072415201	LUMP	59100.00000	59100.00	110000.00000	110000.00	79000.00000	79000.00
0605 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 23072415201	LUMP	97220.00000	97220.00	122000.00000	122000.00	178000.00000	178000.00
0610 0590 70 IRRIGATION SYSTEM 23072415201	LUMP	28000.00000	28000.00	22000.00000	22000.00	27812.58000	27812.58
SECTION 0005 TOTALS			$ 218,754.35		$ 297,350.00		$ 324,680.13
CONTRACT TOTALS			$ 3,396,284.27		$ 3,703,868.92		$ 3,799,801.11

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 23072415201	LUMP	367917.12000	367917.12	374325.31000	374325.31	365165.77000	365165.77
0010 0102 1 MAINTENANCE OF TRAFFIC 23072415201	353.000 LS	108564.84000	108564.84	26685.34800	26685.35	138310.81000	138310.81
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	10.80000	2700.00	10.00000	2500.00	32.66000	8165.00
0020 0102 14 TRAFFIC CONTROL OFFICER	80.000 MH	54.00000	4320.00	59.40000	4752.00	57.15000	4572.00
0025 0102 60 WORK ZONE SIGN	16336.000 ED	0.28000	4574.08	0.34560	5645.72	0.33000	5390.88
0030 0102 61 BUSINESS SIGN	6.000 EA	94.61000	567.66	91.80000	550.80	88.95000	533.70
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1262.000 LF	43.89000	55389.18	10.00000	12620.00	42.99000	54253.38
0040 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	516.000 LF	6.91000	3565.56	5.40000	2786.40	7.07000	3648.12
0045 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	35732.000 ED	0.16000	5717.12	0.15120	5402.68	0.21000	7503.72
0050 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	7413.000 ED	0.34000	2520.42	0.32400	2401.81	0.33000	2446.29
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	166.000 ED	7.79000	1293.14	7.56000	1254.96	5.99000	994.34
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	11437.000 ED	0.28000	3202.36	0.27000	3087.99	0.34000	3888.58
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	83.000 EA	5.25000	435.75	3.78000	313.74	5.64000	468.12
0070 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	991.000 ED	15.59000	15449.69	15.12000	14983.92	15.11000	14974.01

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0075 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	706.000 ED	7.98000	5633.88	8.20800	5794.85	8.92000	6297.52
0080 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	706.000 ED	7.25000	5118.50	7.45200	5261.11	14.11000	9961.66
0085 0102911 1 PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	352.000 LF	2.36000	830.72	3.24000	1140.48	2.54000	894.08
0090 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	950.000 LF	2.00000	1900.00	3.24000	3078.00	2.15000	2042.50
0095 0104 10 3 SEDIMENT BARRIER	3778.000 LF	1.43000	5402.54	2.24624	8486.29	1.13000	4269.14
0100 0104 11 FLOATING TURBIDITY BARRIER	160.000 LF	14.56000	2329.60	12.28028	1964.84	8.47000	1355.20
0105 0104 15 SOIL TRACKING PREVENTION DEVICE	2.000 EA	2453.76000	4907.52	1500.00000	3000.00	5644.94000	11289.88
0110 0104 18 INLET PROTECTION SYSTEM	37.000 EA	40.07000	1482.59	130.90680	4843.55	90.32000	3341.84
0115 0107 1 LITTER REMOVAL	48.300 AC	54.00000	2608.20	10.00000	483.00	135.16000	6528.23
0120 0107 2 MOWING	48.300 AC	54.00000	2608.20	10.00000	483.00	120.59000	5824.50
0125 0110 1 1 CLEARING & GRUBBING 23072415201	9.190 LS	62121.60000	62121.60	102438.00000	102438.00	44208.21000	44208.21
0130 0120 1 REGULAR EXCAVATION	25278.000 CY	8.19000	207026.82	7.94400	200808.43	7.96000	201212.88
0135 0120 6 EMBANKMENT	704.000 CY	6.97000	4906.88	8.28000	5829.12	2.21000	1555.84
0140 0160 4 TYPE B STABILIZATION	22948.000 SY	7.51000	172339.48	3.36456	77209.92	5.53000	126902.44
0145 0285709 OPTIONAL BASE, BASE GROUP 09	20715.000 SY	15.92000	329782.80	18.29700	379022.36	14.36000	297467.40
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	8381.000 SY	3.15000	26400.15	2.16939	18181.66	3.20000	26819.20
0155 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	10721.000 SY	3.15000	33771.15	2.33477	25031.07	3.51000	37630.71

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0160 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	3759.500 TN	105.00000	394747.50	113.40000	426327.30	97.23000	365536.19
0165 0337 7 73 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22, ARB	1680.200 TN	147.00000	246989.40	156.60000	263119.32	149.76000	251626.75
0170 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	928.700 TN	157.50000	146270.25	167.40000	155464.38	143.15000	132943.41
0175 0400 1 2 CONCRETE CLASS I, ENDWALLS	10.000 CY	1260.00000	12600.00	1188.00000	11880.00	1375.42000	13754.20
0180 0415 1 6 REINFORCING STEEL- MISCELLANEOUS	48.000 LB	31.50000	1512.00	27.00000	1296.00	34.39000	1650.72
0185 0425 1351 INLETS, CURB, TYPE P-5, <10'	4.000 EA	4410.00000	17640.00	3845.77848	15383.11	4813.96000	19255.84
0190 0425 1361 INLETS, CURB, TYPE P-6, <10'	3.000 EA	5040.00000	15120.00	4248.44730	12745.34	5501.66000	16504.98
0195 0425 1451 INLETS, CURB, TYPE J-5, <10'	5.000 EA	8400.00000	42000.00	5932.21428	29661.07	9169.44000	45847.20
0200 0425 1521 INLETS, DT BOT, TYPE C,<10'	4.000 EA	2940.00000	11760.00	2737.44252	10949.77	3209.30000	12837.20
0205 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	5.000 EA	2520.00000	12600.00	3161.37438	15806.87	2750.83000	13754.15
0210 0425 1541 INLETS, DT BOT, TYPE D, <10'	1.000 EA	4410.00000	4410.00	4084.98768	4084.99	4813.95000	4813.95
0215 0425 1579 INLETS, DITCH BOTTOM, TYPE G, MODIFY	1.000 EA	6825.00000	6825.00	5912.28018	5912.28	7450.16000	7450.16
0218 0425 1910 INLETS, CLOSED FLUME	1.000 EA	4410.00000	4410.00	3708.89766	3708.90	4813.95000	4813.95
0220 0425 2 41 MANHOLES, P-7, <10'	4.000 EA	7560.00000	30240.00	3561.38532	14245.54	8252.49000	33009.96
0225 0425 2 71 MANHOLES, J-7, <10'	6.000 EA	6090.00000	36540.00	5051.12706	30306.76	6647.84000	39887.04
0227 0425 2 72 MANHOLES, J-7, >10'	1.000 EA	7560.00000	7560.00	4768.06284	4768.06	8252.48000	8252.48
0230 0430 94 1 DESILTING PIPE, 0 - 24"	240.000 LF	6.30000	1512.00	3.78000	907.20	6.30000	1512.00
0235 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	1575.000 LF	54.60000	85995.00	64.50613	101597.15	59.60000	93870.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0240 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	103.000 LF	75.60000	7786.80	74.07450	7629.67	82.52000	8499.56
0245 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	14.000 LF	109.20000	1528.80	85.90207	1202.63	119.20000	1668.80
0250 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	418.000 LF	120.75000	50473.50	99.19147	41462.03	131.81000	55096.58
0255 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	789.000 LF	131.25000	103556.25	119.79004	94514.34	143.27000	113040.03
0260 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	264.000 LF	147.00000	38808.00	136.40179	36010.07	160.47000	42364.08
0265 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	10.000 CY	309.75000	3097.50	243.80460	2438.05	338.12000	3381.20
0270 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	1.000 EA	1050.00000	1050.00	1774.03430	1774.03	1146.18000	1146.18
0275 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	8249.000 LF	15.85000	130746.65	14.04000	115815.96	16.87000	139160.63
0280 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	2886.000 SY	32.35000	93362.10	31.59000	91168.74	35.63000	102828.18
0285 0522 2 CONC SIDEWALK AND DRIVEWAYS, 6" THICK	348.000 SY	38.28000	13321.44	35.47800	12346.34	48.74000	16961.52
0290 0524 1 4 CONCRETE DITCH PAVEMENT, NON REINFORCED 6"	48.000 SY	70.12000	3365.76	40.80200	1958.50	98.26000	4716.48
0295 0527 2 DETECTABLE WARNINGS	280.000 SF	28.88000	8086.40	27.00000	7560.00	33.56000	9396.80
0300 0536 73 GUARDRAIL REMOVAL	265.000 LF	5.31000	1407.15	6.00000	1590.00	8.81000	2334.65
0305 0570 1 2 PERFORMANCE TURF, SOD	14872.000 SY	2.32000	34503.04	4.14720	61677.16	4.42000	65734.24
0310 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1.410 NM	1575.00000	2220.75	864.00000	1218.24	1693.48000	2387.81

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0315 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	264.000 LF	0.63000	166.32	0.54000	142.56	0.68000	179.52
0320 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	259.000 LF	2.10000	543.90	1.18800	307.69	2.26000	585.34
0325 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.370 GM	787.50000	291.38	415.80000	153.85	846.73000	313.29
0330 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	78.000 LF	0.74000	57.72	0.27000	21.06	0.79000	61.62
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1.150 NM	1575.00000	1811.25	864.00000	993.60	1693.49000	1947.51
0340 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.340 GM	787.50000	267.75	415.80000	141.37	846.74000	287.89
0345 0999 16 PARTNERING, DO NOT BID 23072415201	LUMP	6000.00000	6000.00	6000.00000	6000.00	6000.00000	6000.00
0350 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 23072415201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 3,076,571.16		$ 2,944,656.29		$ 3,093,328.04
SECTION 0002 SIGNING							
0355 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	24.000 AS	320.25000	7686.00	354.56400	8509.54	333.05000	7993.20
0360 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	3.000 AS	1013.25000	3039.75	1212.19200	3636.58	1298.33000	3894.99
0365 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	1575.00000	3150.00	1392.55200	2785.10	1495.91000	2991.82
0370 0700 1 50 SINGLE POST SIGN, RELOCATE	1.000 AS	197.40000	197.40	224.31600	224.32	321.76000	321.76

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0375 0700 1 60 SINGLE POST SIGN, REMOVE	4.000 AS	27.30000	109.20	105.73200	422.93	11.29000	45.16
0380 0700 2 13 MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	3153.15000	6306.30	4355.20800	8710.42	2540.22000	5080.44
0385 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	1.000 AS	3263.40000	3263.40	4559.97600	4559.98	3217.62000	3217.62
0390 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	164.85000	989.10	312.22800	1873.37	135.48000	812.88
0395 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 23072415201	LUMP	48720.00000	48720.00	30466.80000	30466.80	52384.98000	52384.98
0400 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	36.000 EA	210.00000	7560.00	367.20000	13219.20	225.80000	8128.80
SECTION 0002 TOTALS		$	81,021.15	$	74,408.24	$	84,871.65
SECTION 0003 LIGHTING							
0405 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	1816.000 LF	9.98000	18123.68	14.14800	25692.77	1.02000	1852.32
0410 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	103.000 LF	22.89000	2357.67	23.00400	2369.41	11.01000	1134.03
0415 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	17.000 EA	747.60000	12709.20	6202.87200	105448.82	783.52000	13319.84
0420 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	5742.000 LF	1.37000	7866.54	3.88800	22324.90	1.30000	7464.60
0425 0715 4113 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE HEIGHT- 50'	13.000 EA	5085.15000	66106.95	5229.57600	67984.49	4899.80000	63697.40
0430 0715 4400 LIGHT POLE COMPLETE, RELOCATE	1.000 EA	2090.55000	2090.55	2149.63200	2149.63	1688.96000	1688.96
0435 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	7380.45000	7380.45	7591.21200	7591.21	10285.07000	10285.07
0440 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	13.000 EA	474.60000	6169.80	488.05200	6344.68	511.43000	6648.59
SECTION 0003 TOTALS		$	122,804.84	$	239,905.91	$	106,090.81

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
SECTION 0004 SIGNALIZATION							
0445 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	167.000 LF	13.76000	2297.92	14.14800	2362.72	5.48000	915.16
0450 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	642.000 LF	22.37000	14361.54	23.00400	14768.57	20.32000	13045.44
0455 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	2.000 PI	6031.20000	12062.40	6202.87200	12405.74	3817.11000	7634.22
0460 0633 4 1 SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, FURNISH & INSTALL	285.000 LF	3.78000	1077.30	3.88800	1108.08	3.67000	1045.95
0465 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	19.000 EA	504.00000	9576.00	491.29200	9334.55	671.75000	12763.25
0470 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	2.000 EA	954.45000	1908.90	955.26000	1910.52	1209.15000	2418.30
0475 0635 3 12 JUNCTION BOX, FURNISH & INSTALL, MOUNTE	1.000 EA	2032.80000	2032.80	2090.88000	2090.88	1620.10000	1620.10
0480 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	1.000 AS	2949.45000	2949.45	3032.96400	3032.96	1568.16000	1568.16
0485 0639 2 1 ELECTRICAL SERVICE WIRE	45.000 LF	1.26000	56.70	1.29600	58.32	3.39000	152.55
0490 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	6.000 EA	915.60000	5493.60	941.97600	5651.86	843.35000	5060.10
0495 0649 31103 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-60	1.000 EA	34641.60000	34641.60	35630.82000	35630.82	35805.82000	35805.82
0500 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	37176.30000	74352.60	38239.02000	76478.04	36296.93000	72593.86
0505 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	36660.75000	36660.75	37707.98400	37707.98	37115.43000	37115.43
0510 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	17.000 AS	809.55000	13762.35	832.68000	14155.56	1022.86000	17388.62

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
0515 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	8.000 AS	505.05000	4040.40	519.48000	4155.84	523.85000	4190.80
0520 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	2.000 EA	6100.50000	12201.00	6274.80000	12549.60	9232.86000	18465.72
0525 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	4.000 EA	2767.80000	11071.20	2847.09600	11388.38	3198.42000	12793.68
0530 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	9.000 EA	196.35000	1767.15	201.31200	1811.81	173.86000	1564.74
0535 0670 5130 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL	1.000 AS	24602.55000	24602.55	25305.37200	25305.37	31718.88000	31718.88
0540 0670 5400 TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.000 AS	822.15000	822.15	845.96400	845.96	270.96000	270.96
0545 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	8.000 EA	51.45000	411.60	52.92000	423.36	32.74000	261.92
0550 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	51.45000	411.60	52.92000	423.36	32.74000	261.92
0555 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	4.000 EA	1233.75000	4935.00	1269.00000	5076.00	2278.30000	9113.20
0560 0690 50 1 CONTROLLER ASSEMBLY, REMOVE, CAB ASSEMBLY, LESS FOUNDATION	1.000 EA	823.20000	823.20	845.96400	845.96	171.61000	171.61
0565 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	14.000 EA	44.10000	617.40	45.36000	635.04	14.68000	205.52
0570 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	9.000 EA	37.80000	340.20	39.63600	356.72	20.32000	182.88
0575 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	926.10000	926.10	951.69600	951.70	617.56000	617.56
0580 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	1.000 PI	926.10000	926.10	951.69600	951.70	480.95000	480.95
0585 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	2.000 PI	1130.85000	2261.70	1163.16000	2326.32	303.70000	607.40
0590 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, 12-18 SF	4.000 EA	2504.25000	10017.00	2576.34000	10305.36	2369.74000	9478.96
SECTION 0004 TOTALS		$	287,408.26	$	295,049.08	$	299,513.66

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) TRIPLE R PAVING, INC. UNIT PRICE	 AMOUNT	(5) MAYTIN ENGINEERING CORP. UNIT PRICE	 AMOUNT	(6) RANGER CONSTRUCTION INDUSTRIES, UNIT PRICE	 AMOUNT
SECTION 0005 LANDSCAPE / PERIPHERAL							
0595 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK	289.000 SY	147.69000	42682.41	68.04000	19663.56	266.40000	76989.60
0600 0580 1 1 LANDSCAPE COMPLETE- SMALL PLANTS 23072415201	LUMP	103143.60000	103143.60	97704.90000	97704.90	113746.28000	113746.28
0605 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 23072415201	LUMP	113673.00000	113673.00	195026.40000	195026.40	125358.06000	125358.06
0610 0590 70 IRRIGATION SYSTEM 23072415201	LUMP	19104.76000	19104.76	12571.20000	12571.20	21068.63000	21068.63
SECTION 0005 TOTALS		$	278,603.77	$	324,966.06	$	337,162.57
CONTRACT TOTALS		$	3,846,409.18	$	3,878,985.58	$	3,920,966.73

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 23072415201	LUMP	577058.72000	577058.72	531114.90000	531114.90	430000.00000	430000.00
0010 0102 1 MAINTENANCE OF TRAFFIC 23072415201	353.000 LS	143455.86000	143455.86	27453.04000	27453.04	116141.03000	116141.03
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	36.04000	9010.00	64.44000	16110.00	25.89000	6472.50
0020 0102 14 TRAFFIC CONTROL OFFICER	80.000 MH	56.43000	4514.40	50.92000	4073.60	45.00000	3600.00
0025 0102 60 WORK ZONE SIGN	16336.000 ED	0.26000	4247.36	0.31000	5064.16	0.25000	4084.00
0030 0102 61 BUSINESS SIGN	6.000 EA	87.22000	523.32	104.52000	627.12	85.00000	510.00
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1262.000 LF	39.58000	49949.96	47.65000	60134.30	58.04000	73246.48
0040 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	516.000 LF	8.55000	4411.80	7.84000	4045.44	4.57000	2358.12
0045 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	35732.000 ED	0.14000	5002.48	0.17000	6074.44	0.14000	5002.48
0050 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	7413.000 ED	0.31000	2298.03	0.37000	2742.81	0.30000	2223.90
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	166.000 ED	7.18000	1191.88	8.61000	1429.26	7.00000	1162.00
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	11437.000 ED	0.26000	2973.62	0.31000	3545.47	0.25000	2859.25
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	83.000 EA	3.69000	306.27	5.09000	422.47	5.00000	415.00
0070 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	991.000 ED	14.36000	14230.76	17.21000	17055.11	14.00000	13874.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0075 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	706.000 ED	26.68000	18836.08	6.79000	4793.74	8.07000	5697.42
0080 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	706.000 ED	18.47000	13039.82	2.26000	1595.56	12.77000	9015.62
0085 0102911 1 PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	352.000 LF	2.13000	749.76	4.28000	1506.56	2.25000	792.00
0090 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	950.000 LF	1.85000	1757.50	4.28000	4066.00	1.90000	1805.00
0095 0104 10 3 SEDIMENT BARRIER	3778.000 LF	1.26000	4760.28	1.30000	4911.40	0.55000	2077.90
0100 0104 11 FLOATING TURBIDITY BARRIER	160.000 LF	11.97000	1915.20	9.28000	1484.80	7.50000	1200.00
0105 0104 15 SOIL TRACKING PREVENTION DEVICE	2.000 EA	2565.23000	5130.46	1584.04000	3168.08	2200.00000	4400.00
0110 0104 18 INLET PROTECTION SYSTEM	37.000 EA	92.20000	3411.40	84.86000	3139.82	65.00000	2405.00
0115 0107 1 LITTER REMOVAL	48.300 AC	18.47000	892.10	22.06000	1065.50	60.00000	2898.00
0120 0107 2 MOWING	48.300 AC	153.91000	7433.85	39.60000	1912.68	60.00000	2898.00
0125 0110 1 1 CLEARING & GRUBBING 23072415201	9.190 LS	72296.39000	72296.39	60628.54000	60628.54	663400.00000	663400.00
0130 0120 1 REGULAR EXCAVATION	25278.000 CY	6.81000	172143.18	3.58000	90495.24	7.78000	196662.84
0135 0120 6 EMBANKMENT	704.000 CY	8.17000	5751.68	6.51000	4583.04	137.07000	96497.28
0140 0160 4 TYPE B STABILIZATION	22948.000 SY	2.68000	61500.64	3.87000	88808.76	2.37000	54386.76
0145 0285709 OPTIONAL BASE, BASE GROUP 09	20715.000 SY	14.11000	292288.65	12.34000	255623.10	11.55000	239258.25
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	8381.000 SY	3.08000	25813.48	1.58000	13241.98	3.35000	28076.35
0155 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	10721.000 SY	3.08000	33020.68	1.87000	20048.27	3.70000	39667.70

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0160 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	3759.500 TN	107.74000	405048.53	118.80000	446628.60	101.60000	381965.20
0165 0337 7 73 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22, ARB	1680.200 TN	148.78000	249980.16	164.06000	275653.61	156.50000	262951.30
0170 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	928.700 TN	159.04000	147700.45	175.38000	162875.41	149.60000	138933.52
0175 0400 1 2 CONCRETE CLASS I, ENDWALLS	10.000 CY	1064.80000	10648.00	859.90000	8599.00	760.00000	7600.00
0180 0415 1 6 REINFORCING STEEL- MISCELLANEOUS	48.000 LB	1.03000	49.44	33.94000	1629.12	30.00000	1440.00
0185 0425 1351 INLETS, CURB, TYPE P-5, <10'	4.000 EA	3490.62000	13962.48	4661.59000	18646.36	4120.00000	16480.00
0190 0425 1361 INLETS, CURB, TYPE P-6, <10'	3.000 EA	3820.18000	11460.54	5283.88000	15851.64	4670.00000	14010.00
0195 0425 1451 INLETS, CURB, TYPE J-5, <10'	5.000 EA	5198.24000	25991.20	9956.78000	49783.90	8800.00000	44000.00
0200 0425 1521 INLETS, DT BOT, TYPE C,<10'	4.000 EA	3646.16000	14584.64	2557.09000	10228.36	2260.00000	9040.00
0205 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	5.000 EA	3646.16000	18230.80	2398.68000	11993.40	2120.00000	10600.00
0210 0425 1541 INLETS, DT BOT, TYPE D, <10'	1.000 EA	3686.41000	3686.41	3552.76000	3552.76	3140.00000	3140.00
0215 0425 1579 INLETS, DITCH BOTTOM, TYPE G, MODIFY	1.000 EA	5181.93000	5181.93	6483.22000	6483.22	5730.00000	5730.00
0218 0425 1910 INLETS, CLOSED FLUME	1.000 EA	4141.04000	4141.04	3066.24000	3066.24	2710.00000	2710.00
0220 0425 2 41 MANHOLES, P-7, <10'	4.000 EA	3257.86000	13031.44	2647.60000	10590.40	2340.00000	9360.00
0225 0425 2 71 MANHOLES, J-7, <10'	6.000 EA	4477.13000	26862.78	5544.12000	33264.72	4900.00000	29400.00
0227 0425 2 72 MANHOLES, J-7, >10'	1.000 EA	5920.02000	5920.02	6770.62000	6770.62	5984.00000	5984.00
0230 0430 94 1 DESILTING PIPE, 0 - 24"	240.000 LF	5.13000	1231.20	6.79000	1629.60	10.00000	2400.00
0235 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	1575.000 LF	70.52000	111069.00	71.28000	112266.00	70.00000	110250.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0240 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	103.000 LF	79.61000	8199.83	104.09000	10721.27	100.00000	10300.00
0245 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	14.000 LF	102.23000	1431.22	90.52000	1267.28	90.00000	1260.00
0250 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	418.000 LF	94.18000	39367.24	93.91000	39254.38	83.00000	34694.00
0255 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	789.000 LF	107.35000	84699.15	141.43000	111588.27	133.00000	104937.00
0260 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	264.000 LF	117.08000	30909.12	185.56000	48987.84	175.00000	46200.00
0265 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	10.000 CY	595.13000	5951.30	452.58000	4525.80	400.00000	4000.00
0270 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	1.000 EA	1035.00000	1035.00	939.10000	939.10	1000.00000	1000.00
0275 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	8249.000 LF	18.62000	153596.38	19.82000	163495.18	11.15000	91976.35
0280 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	2886.000 SY	30.85000	89033.10	32.98000	95180.28	25.33000	73102.38
0285 0522 2 CONC SIDEWALK AND DRIVEWAYS, 6" THICK	348.000 SY	36.52000	12708.96	39.20000	13641.60	42.03000	14626.44
0290 0524 1 4 CONCRETE DITCH PAVEMENT, NON REINFORCED 6"	48.000 SY	64.09000	3076.32	84.23000	4043.04	62.46000	2998.08
0295 0527 2 DETECTABLE WARNINGS	280.000 SF	28.22000	7901.60	34.23000	9584.40	28.35000	7938.00
0300 0536 73 GUARDRAIL REMOVAL	265.000 LF	5.52000	1462.80	11.31000	2997.15	3.00000	795.00
0305 0570 1 2 PERFORMANCE TURF, SOD	14872.000 SY	2.27000	33759.44	2.50000	37180.00	2.21000	32867.12
0310 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1.410 NM	820.88000	1157.44	1493.52000	2105.86	1500.00000	2115.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0315 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	264.000 LF	0.51000	134.64	0.36000	95.04	0.60000	158.40
0320 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	259.000 LF	1.13000	292.67	1.13000	292.67	2.00000	518.00
0325 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.370 GM	395.04000	146.16	396.00000	146.52	750.00000	277.50
0330 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	78.000 LF	0.26000	20.28	0.40000	31.20	0.70000	54.60
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1.150 NM	820.88000	944.01	1493.52000	1717.55	1500.00000	1725.00
0340 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.340 GM	395.04000	134.31	396.00000	134.64	750.00000	255.00
0345 0999 16 PARTNERING, DO NOT BID 23072415201	LUMP	6000.00000	6000.00	6000.00000	6000.00	6000.00000	6000.00
0350 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 23072415201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 3,140,656.64		$ 3,024,407.22		$ 3,556,878.77
SECTION 0002 SIGNING							
0355 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	24.000 AS	338.61000	8126.64	315.44000	7570.56	304.49000	7307.76
0360 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	3.000 AS	1667.40000	5002.20	1748.61000	5245.83	964.88000	2894.64
0365 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	1959.83000	3919.66	2000.04000	4000.08	1499.67000	2999.34
0370 0700 1 50 SINGLE POST SIGN, RELOCATE	1.000 AS	169.31000	169.31	100.57000	100.57	187.95000	187.95

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0375 0700 1 60 SINGLE POST SIGN, REMOVE	4.000 AS	56.43000	225.72	11.43000	45.72	25.50000	102.00
0380 0700 2 13 MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	4078.72000	8157.44	3844.66000	7689.32	3002.87000	6005.74
0385 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	1.000 AS	4340.37000	4340.37	4101.80000	4101.80	3107.73000	3107.73
0390 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	164.18000	985.08	157.72000	946.32	156.76000	940.56
0395 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 23072415201	LUMP	28946.47000	28946.47	22289.61000	22289.61	46400.00000	46400.00
0400 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	36.000 EA	348.87000	12559.32	201.40000	7250.40	200.00000	7200.00
SECTION 0002 TOTALS		$	72,432.21	$	59,240.21	$	77,145.72
SECTION 0003 LIGHTING							
0405 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	1816.000 LF	7.44000	13511.04	7.07000	12839.12	0.92000	1670.72
0410 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	103.000 LF	19.75000	2034.25	13.58000	1398.74	9.96000	1025.88
0415 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	17.000 EA	461.74000	7849.58	707.16000	12021.72	709.11000	12054.87
0420 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	5742.000 LF	1.73000	9933.66	1.70000	9761.40	1.18000	6775.56
0425 0715 4113 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE HEIGHT- 50'	13.000 EA	4904.73000	63761.49	5798.69000	75382.97	4434.48000	57648.24
0430 0715 4400 LIGHT POLE COMPLETE, RELOCATE	1.000 EA	2206.10000	2206.10	3733.79000	3733.79	1528.57000	1528.57
0435 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	6382.29000	6382.29	8072.92000	8072.92	9308.32000	9308.32
0440 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	13.000 EA	743.91000	9670.83	548.75000	7133.75	462.86000	6017.18
SECTION 0003 TOTALS		$	115,349.24	$	130,344.41	$	96,029.34

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
SECTION 0004 SIGNALIZATION							
0445 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	167.000 LF	9.23000	1541.41	16.97000	2833.99	4.96000	828.32
0450 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	642.000 LF	17.96000	11530.32	22.63000	14528.46	18.39000	11806.38
0455 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	2.000 PI	4848.28000	9696.56	4780.39000	9560.78	3454.61000	6909.22
0460 0633 4 1 SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, FURNISH & INSTALL	285.000 LF	5.95000	1695.75	7.24000	2063.40	3.32000	946.20
0465 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	19.000 EA	461.74000	8773.06	502.37000	9545.03	607.95000	11551.05
0470 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	2.000 EA	1282.62000	2565.24	931.19000	1862.38	1094.32000	2188.64
0475 0635 3 12 JUNCTION BOX, FURNISH & INSTALL, MOUNTE	1.000 EA	1898.27000	1898.27	3235.95000	3235.95	1466.24000	1466.24
0480 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	1.000 AS	2513.93000	2513.93	3100.18000	3100.18	1419.24000	1419.24
0485 0639 2 1 ELECTRICAL SERVICE WIRE	45.000 LF	1.73000	77.85	3.73000	167.85	3.07000	138.15
0490 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	6.000 EA	764.43000	4586.58	1029.62000	6177.72	763.26000	4579.56
0495 0649 31103 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-60	1.000 EA	36374.96000	36374.96	46276.40000	46276.40	32405.43000	32405.43
0500 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	38457.93000	76915.86	49048.47000	98096.94	32849.90000	65699.80
0505 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	40776.89000	40776.89	49697.91000	49697.91	33590.68000	33590.68
0510 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	17.000 AS	821.90000	13972.30	1046.59000	17792.03	925.72000	15737.24

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
0515 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	8.000 AS	641.31000	5130.48	728.66000	5829.28	474.10000	3792.80
0520 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	2.000 EA	5335.68000	10671.36	18035.35000	36070.70	8356.04000	16712.08
0525 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	4.000 EA	5643.51000	22574.04	3812.99000	15251.96	2894.68000	11578.72
0530 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	9.000 EA	200.09000	1800.81	160.67000	1446.03	157.35000	1416.15
0535 0670 5130 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL	1.000 AS	26965.69000	26965.69	34339.58000	34339.58	28706.62000	28706.62
0540 0670 5400 TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.000 AS	1893.14000	1893.14	673.21000	673.21	245.22000	245.22
0545 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	8.000 EA	56.43000	451.44	70.15000	561.20	29.63000	237.04
0550 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	56.43000	451.44	70.15000	561.20	29.63000	237.04
0555 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	4.000 EA	1436.53000	5746.12	2557.09000	10228.36	2061.93000	8247.72
0560 0690 50 1 CONTROLLER ASSEMBLY, REMOVE, CAB ASSEMBLY, LESS FOUNDATION	1.000 EA	569.48000	569.48	418.64000	418.64	155.31000	155.31
0565 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	14.000 EA	128.26000	1795.64	17.54000	245.56	13.28000	185.92
0570 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	9.000 EA	56.43000	507.87	35.64000	320.76	18.39000	165.51
0575 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	2873.06000	2873.06	837.27000	837.27	558.91000	558.91
0580 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	1.000 PI	455.58000	455.58	418.64000	418.64	435.27000	435.27
0585 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	2.000 PI	569.48000	1138.96	792.02000	1584.04	274.86000	549.72
0590 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, 12-18 SF	4.000 EA	2488.28000	9953.12	2523.14000	10092.56	2144.70000	8578.80
SECTION 0004 TOTALS		$	305,897.21	$	383,818.01	$	271,068.98

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(7) CENTRAL FLORIDA EQUIPMENT R UNIT PRICE	 AMOUNT	(8) BERGERON LAND DEVELOPMENT, UNIT PRICE	 AMOUNT	(9) HUBBARD CONSTRUCTION COMPANY UNIT PRICE	 AMOUNT
SECTION 0005 LANDSCAPE / PERIPHERAL							
0595 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK	289.000 SY	216.90000	62684.10	249.13000	71998.57	211.42000	61100.38
0600 0580 1 1 LANDSCAPE COMPLETE- SMALL PLANTS 23072415201	LUMP	120419.59000	120419.59	94440.07000	94440.07	90467.50000	90467.50
0605 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 23072415201	LUMP	110129.94000	110129.94	184472.00000	184472.00	180580.00000	180580.00
0610 0590 70 IRRIGATION SYSTEM 23072415201	LUMP	43095.85000	43095.85	50915.35000	50915.35	42000.00000	42000.00
SECTION 0005 TOTALS		$	336,329.48	$	401,825.99	$	374,147.88
CONTRACT TOTALS		$	3,970,664.78	$	3,999,635.84	$	4,375,270.69

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 23072415201	LUMP	612000.00000	612000.00	637054.23000	637054.23	277025.00000	277025.00
0010 0102 1 MAINTENANCE OF TRAFFIC 23072415201	353.000 LS	32000.00000	32000.00	289019.71000	289019.71	418032.00000	418032.00
0015 0102 3 COMMERCIAL MATERIAL FOR DRIVEWAY MAINTENANCE	250.000 CY	22.00000	5500.00	22.63000	5657.50	188.20000	47050.00
0020 0102 14 TRAFFIC CONTROL OFFICER	80.000 MH	61.00000	4880.00	58.84000	4707.20	38.80000	3104.00
0025 0102 60 WORK ZONE SIGN	16336.000 ED	0.30000	4900.80	0.33000	5390.88	0.35000	5717.60
0030 0102 61 BUSINESS SIGN	6.000 EA	94.00000	564.00	88.27000	529.62	92.90000	557.40
0035 0102 71 13 BARRIER WALL, TEMPORARY, F&I, LOW PROFILE, CONCRETE	1262.000 LF	47.00000	59314.00	42.66000	53836.92	44.80000	56537.60
0040 0102 71 23 BARRIER WALL, TEMPORARY, RELOCATE, LOW PROFILE, CONCRETE	516.000 LF	5.50000	2838.00	7.02000	3622.32	7.40000	3818.40
0045 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	35732.000 ED	0.20000	7146.40	0.20000	7146.40	0.22000	7861.04
0050 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6'	7413.000 ED	0.40000	2965.20	0.28000	2075.64	0.35000	2594.55
0055 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	166.000 ED	7.70000	1278.20	5.94000	986.04	6.25000	1037.50
0060 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	11437.000 ED	0.30000	3431.10	0.34000	3888.58	0.40000	4574.80
0065 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	83.000 EA	5.50000	456.50	3.39000	281.37	4.20000	348.60
0070 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	991.000 ED	16.00000	15856.00	14.99000	14855.09	15.80000	15657.80

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0075 0102104 TEMPORARY SIGNALIZATION AND MAINTENANCE INTERSECTION	706.000 ED	14.00000	9884.00	3.39000	2393.34	9.40000	6636.40
0080 0102107 1 TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	706.000 ED	9.90000	6989.40	3.39000	2393.34	14.90000	10519.40
0085 0102911 1 PAVEMENT MARKING REMOVABLE TAPE, WHITE-BLACK, SKIP	352.000 LF	5.70000	2006.40	6.79000	2390.08	5.00000	1760.00
0090 0102912 2 PAVEMENT MARKING REMOVABLE TAPE, YELLOW SOLID	950.000 LF	3.20000	3040.00	5.66000	5377.00	6.25000	5937.50
0095 0104 10 3 SEDIMENT BARRIER	3778.000 LF	0.30000	1133.40	2.83000	10691.74	1.70000	6422.60
0100 0104 11 FLOATING TURBIDITY BARRIER	160.000 LF	9.10000	1456.00	16.97000	2715.20	9.50000	1520.00
0105 0104 15 SOIL TRACKING PREVENTION DEVICE	2.000 EA	2300.00000	4600.00	1131.64000	2263.28	2080.00000	4160.00
0110 0104 18 INLET PROTECTION SYSTEM	37.000 EA	39.00000	1443.00	45.26000	1674.62	89.00000	3293.00
0115 0107 1 LITTER REMOVAL	48.300 AC	83.00000	4008.90	84.87000	4099.22	134.00000	6472.20
0120 0107 2 MOWING	48.300 AC	220.00000	10626.00	84.87000	4099.22	415.00000	20044.50
0125 0110 1 1 CLEARING & GRUBBING 23072415201	9.190 LS	141000.00000	141000.00	64729.55000	64729.55	89825.00000	89825.00
0130 0120 1 REGULAR EXCAVATION	25278.000 CY	5.60000	141556.80	19.84000	501515.52	15.30000	386753.40
0135 0120 6 EMBANKMENT	704.000 CY	9.90000	6969.60	22.52000	15854.08	20.60000	14502.40
0140 0160 4 TYPE B STABILIZATION	22948.000 SY	2.10000	48190.80	4.47000	102577.56	8.40000	192763.20
0145 0285709 OPTIONAL BASE, BASE GROUP 09	20715.000 SY	15.00000	310725.00	18.12000	375355.80	16.60000	343869.00
0150 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH	8381.000 SY	2.70000	22628.70	3.03000	25394.43	1.90000	15923.90
0155 0327 70 6 MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	10721.000 SY	3.20000	34307.20	3.69000	39560.49	2.20000	23586.20

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0160 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C	3759.500 TN	120.00000	451140.00	107.50000	404146.25	119.00000	447380.50
0165 0337 7 73 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-9.5, PG 76-22, ARB	1680.200 TN	170.00000	285634.00	140.09000	235379.22	170.00000	285634.00
0170 0337 7 74 ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22, ARB	928.700 TN	160.00000	148592.00	144.75000	134429.33	174.00000	161593.80
0175 0400 1 2 CONCRETE CLASS I, ENDWALLS	10.000 CY	2000.00000	20000.00	1357.96000	13579.60	1425.00000	14250.00
0180 0415 1 6 REINFORCING STEEL- MISCELLANEOUS	48.000 LB	11.00000	528.00	33.95000	1629.60	35.70000	1713.60
0185 0425 1351 INLETS, CURB, TYPE P-5, <10'	4.000 EA	8000.00000	32000.00	3904.15000	15616.60	4990.00000	19960.00
0190 0425 1361 INLETS, CURB, TYPE P-6, <10'	3.000 EA	6700.00000	20100.00	4752.87000	14258.61	5700.00000	17100.00
0195 0425 1451 INLETS, CURB, TYPE J-5, <10'	5.000 EA	11000.00000	55000.00	6337.16000	31685.80	9505.00000	47525.00
0200 0425 1521 INLETS, DT BOT, TYPE C,<10'	4.000 EA	4100.00000	16400.00	2263.27000	9053.08	3325.00000	13300.00
0205 0425 1531 INLETS, DITCH BOTTOM, TYPE C MODIFIED- BACK OF SIDEWALK, <10'	5.000 EA	5600.00000	28000.00	2036.95000	10184.75	2850.00000	14250.00
0210 0425 1541 INLETS, DT BOT, TYPE D, <10'	1.000 EA	5300.00000	5300.00	3621.23000	3621.23	4990.00000	4990.00
0215 0425 1579 INLETS, DITCH BOTTOM, TYPE G, MODIFY	1.000 EA	7600.00000	7600.00	6223.99000	6223.99	7725.00000	7725.00
0218 0425 1910 INLETS, CLOSED FLUME	1.000 EA	7000.00000	7000.00	2942.25000	2942.25	4990.00000	4990.00
0220 0425 2 41 MANHOLES, P-7, <10'	4.000 EA	7300.00000	29200.00	3281.74000	13126.96	8555.00000	34220.00
0225 0425 2 71 MANHOLES, J-7, <10'	6.000 EA	9400.00000	56400.00	6223.99000	37343.94	6890.00000	41340.00
0227 0425 2 72 MANHOLES, J-7, >10'	1.000 EA	10000.00000	10000.00	7016.14000	7016.14	8555.00000	8555.00
0230 0430 94 1 DESILTING PIPE, 0 - 24"	240.000 LF	30.00000	7200.00	4.53000	1087.20	4.20000	1008.00
0235 0430175118 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	1575.000 LF	120.00000	189000.00	47.53000	74859.75	66.25000	104343.75

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0240 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	103.000 LF	160.00000	16480.00	63.37000	6527.11	90.00000	9270.00
0245 0430175130 PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	14.000 LF	190.00000	2660.00	96.19000	1346.66	126.00000	1764.00
0250 0430175136 PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	418.000 LF	190.00000	79420.00	115.43000	48249.74	142.00000	59356.00
0255 0430175142 PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	789.000 LF	230.00000	181470.00	147.11000	116069.79	154.00000	121506.00
0260 0430175148 PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	264.000 LF	240.00000	63360.00	181.06000	47799.84	171.00000	45144.00
0265 0430830 PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	10.000 CY	440.00000	4400.00	282.91000	2829.10	350.00000	3500.00
0270 0430982125 MITERED END SECTION, OPTIONAL ROUND, 18" CD	1.000 EA	2500.00000	2500.00	1018.47000	1018.47	1200.00000	1200.00
0275 0520 1 10 CONCRETE CURB & GUTTER, TYPE F	8249.000 LF	32.00000	263968.00	31.29000	258111.21	26.25000	216536.25
0280 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	2886.000 SY	34.00000	98124.00	42.49000	122626.14	35.40000	102164.40
0285 0522 2 CONC SIDEWALK AND DRIVEWAYS, 6" THICK	348.000 SY	46.00000	16008.00	57.11000	19874.28	51.50000	17922.00
0290 0524 1 4 CONCRETE DITCH PAVEMENT, NON REINFORCED 6"	48.000 SY	61.00000	2928.00	84.87000	4073.76	55.30000	2654.40
0295 0527 2 DETECTABLE WARNINGS	280.000 SF	35.00000	9800.00	34.23000	9584.40	31.20000	8736.00
0300 0536 73 GUARDRAIL REMOVAL	265.000 LF	7.40000	1961.00	5.66000	1499.90	6.50000	1722.50
0305 0570 1 2 PERFORMANCE TURF, SOD	14872.000 SY	3.60000	53539.20	2.50000	37180.00	2.90000	43128.80
0310 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1.410 NM	770.00000	1085.70	1792.51000	2527.44	950.00000	1339.50

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0315 0710 11122 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	264.000 LF	0.40000	105.60	0.57000	150.48	0.60000	158.40
0320 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 24"	259.000 LF	1.10000	284.90	1.70000	440.30	1.30000	336.70
0325 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6", 10-30 OR 3-9 SKIP	0.370 GM	470.00000	173.90	452.66000	167.48	463.00000	171.31
0330 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, DOTTED / GUIDELINE/ 6-10 GAP EXTENSION, 6"	78.000 LF	0.30000	23.40	1.13000	88.14	0.30000	23.40
0335 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1.150 NM	770.00000	885.50	1792.51000	2061.39	950.00000	1092.50
0340 0710 11231 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	0.340 GM	470.00000	159.80	452.66000	153.90	455.00000	154.70
0345 0999 16 PARTNERING, DO NOT BID 23072415201	LUMP	6000.00000	6000.00	6000.00000	6000.00	6000.00000	6000.00
0350 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 23072415201	LUMP	50000.00000	50000.00	50000.00000	50000.00	50000.00000	50000.00
SECTION 0001 TOTALS			$ 3,728,126.40		$ 3,946,699.80		$ 3,901,664.50
SECTION 0002 SIGNING							
0355 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	24.000 AS	250.00000	6000.00	282.91000	6789.84	362.00000	8688.00
0360 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	3.000 AS	750.00000	2250.00	905.31000	2715.93	1145.00000	3435.00
0365 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	1100.00000	2200.00	1357.96000	2715.92	1785.00000	3570.00
0370 0700 1 50 SINGLE POST SIGN, RELOCATE	1.000 AS	170.00000	170.00	226.32000	226.32	225.00000	225.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0375 0700 1 60 SINGLE POST SIGN, REMOVE	4.000 AS	120.00000	480.00	22.63000	90.52	31.00000	124.00
0380 0700 2 13 MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	2.000 AS	1400.00000	2800.00	1357.96000	2715.92	3570.00000	7140.00
0385 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	1.000 AS	1600.00000	1600.00	226.32000	226.32	3695.00000	3695.00
0390 0705 10 4 OBJECT MARKER, TYPE 4	6.000 EA	38.00000	228.00	147.11000	882.66	186.00000	1116.00
0395 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 23072415201	LUMP	23000.00000	23000.00	13579.63000	13579.63	33520.00000	33520.00
0400 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	36.000 EA	170.00000	6120.00	362.12000	13036.32	404.00000	14544.00
SECTION 0002 TOTALS		$	44,848.00	$	42,979.38	$	76,057.00
SECTION 0003 LIGHTING							
0405 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	1816.000 LF	14.00000	25424.00	5.66000	10278.56	1.10000	1997.60
0410 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	103.000 LF	20.00000	2060.00	13.58000	1398.74	11.60000	1194.80
0415 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	17.000 EA	470.00000	7990.00	480.95000	8176.15	825.00000	14025.00
0420 0715 1 12 LIGHTING CONDUCTORS, F&I, INSULATED, NO 8 - 6	5742.000 LF	1.50000	8613.00	1.98000	11369.16	1.40000	8038.80
0425 0715 4113 LIGHT POLE COMPLETE, F&I, WIND SPEED 150, POLE HEIGHT- 50'	13.000 EA	5300.00000	68900.00	4809.45000	62522.85	5156.00000	67028.00
0430 0715 4400 LIGHT POLE COMPLETE, RELOCATE	1.000 EA	1100.00000	1100.00	4809.45000	4809.45	1775.00000	1775.00
0435 0715 7 11 LOAD CENTER, F&I, SECONDARY VOLTAGE	1.000 EA	6400.00000	6400.00	6223.99000	6223.99	10825.00000	10825.00
0440 0715500 1 POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	13.000 EA	830.00000	10790.00	509.24000	6620.12	540.00000	7020.00
SECTION 0003 TOTALS		$	131,277.00	$	111,399.02	$	111,904.20

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
SECTION 0004 SIGNALIZATION							
0445 0630 2 11 CONDUIT, FURNISH & INSTALL, OPEN TRENCH	167.000 LF	16.00000	2672.00	5.66000	945.22	5.80000	968.60
0450 0630 2 12 CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	642.000 LF	20.00000	12840.00	15.84000	10169.28	21.40000	13738.80
0455 0632 7 1 SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	2.000 PI	9300.00000	18600.00	5092.36000	10184.72	4020.00000	8040.00
0460 0633 4 1 SIGNALS COMMUNICATION CABLE- TWISTED PAIR CABLE, FURNISH & INSTALL	285.000 LF	4.00000	1140.00	5.09000	1450.65	3.90000	1111.50
0465 0635 2 11 PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	19.000 EA	470.00000	8930.00	452.66000	8600.54	707.00000	13433.00
0470 0635 2 12 PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	2.000 EA	1700.00000	3400.00	1131.64000	2263.28	1270.00000	2540.00
0475 0635 3 12 JUNCTION BOX, FURNISH & INSTALL, MOUNTE	1.000 EA	2000.00000	2000.00	905.31000	905.31	1705.00000	1705.00
0480 0639 1123 ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER NOT REQUIRED	1.000 AS	1700.00000	1700.00	2263.27000	2263.27	1650.00000	1650.00
0485 0639 2 1 ELECTRICAL SERVICE WIRE	45.000 LF	5.00000	225.00	5.66000	254.70	3.50000	157.50
0490 0646 1 11 ALUMINUM SIGNALS POLE, PEDESTAL	6.000 EA	1100.00000	6600.00	905.31000	5431.86	890.00000	5340.00
0495 0649 31103 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-60	1.000 EA	35000.00000	35000.00	31685.80000	31685.80	37680.00000	37680.00
0500 0649 31104 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-70.5	2.000 EA	40000.00000	80000.00	33949.07000	67898.14	38200.00000	76400.00
0505 0649 31105 MAST ARM,F&I, WIND SPEED-150,SINGLE ARM W/0 LUMINAIRE-78	1.000 EA	45000.00000	45000.00	36212.34000	36212.34	39060.00000	39060.00
0510 0650 1311 TRAFFIC SIGNAL, F&I, 3 SECTION, 1 WAY, ALUMINUM	17.000 AS	1200.00000	20400.00	1018.47000	17313.99	1075.00000	18275.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
0515 0653191 PEDESTRIAN SIGNAL, F&I, LED - COUNT DOWN, 1 DIRECTION	8.000 AS	690.00000	5520.00	961.89000	7695.12	551.00000	4408.00
0520 0660 4 11 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	2.000 EA	8300.00000	16600.00	5658.18000	11316.36	9720.00000	19440.00
0525 0660 4 12 VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	4.000 EA	4400.00000	17600.00	2829.08000	11316.32	3365.00000	13460.00
0530 0665 1 11 PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	9.000 EA	180.00000	1620.00	282.91000	2546.19	184.00000	1656.00
0535 0670 5130 TRAFFIC CONTROLLER ASSEMBLY, F&I, SPECIAL	1.000 AS	27000.00000	27000.00	31685.80000	31685.80	33380.00000	33380.00
0540 0670 5400 TRAFFIC CONTROLLER ASSEMBLY, MODIFY	1.000 AS	2100.00000	2100.00	2263.27000	2263.27	285.00000	285.00
0545 0690 10 SIGNAL HEAD TRAFFIC ASSEMBLY REMOVAL	8.000 EA	88.00000	704.00	56.58000	452.64	34.60000	276.80
0550 0690 20 SIGNAL PEDESTRIAN ASSEMBLY REMOVAL	8.000 EA	55.00000	440.00	56.58000	452.64	34.60000	276.80
0555 0690 32 1 POLE REMOVAL, SHALLOW, DIRECT BURIAL	4.000 EA	1600.00000	6400.00	1697.45000	6789.80	2400.00000	9600.00
0560 0690 50 1 CONTROLLER ASSEMBLY, REMOVE, CAB ASSEMBLY, LESS FOUNDATION	1.000 EA	530.00000	530.00	565.81000	565.81	182.00000	182.00
0565 0690 60 DETECTOR VEHICLE ASSEMBLY REMOVE	14.000 EA	150.00000	2100.00	113.17000	1584.38	15.60000	218.40
0570 0690 70 DETECTOR PEDESTRIAN ASSEMBLY REMOVE	9.000 EA	33.00000	297.00	56.58000	509.22	21.40000	192.60
0575 0690 80 SPAN WIRE ASSEMBLY, REMOVE	1.000 EA	550.00000	550.00	226.32000	226.32	650.00000	650.00
0580 0690 90 CONDUIT & CABLING- WITHIN INTERSECTION, REMOVE	1.000 PI	400.00000	400.00	565.81000	565.81	508.00000	508.00
0585 0690100 SIGNAL EQUIPMENT MISCELLANOUS REMOVE	2.000 PI	640.00000	1280.00	1131.64000	2263.28	320.00000	640.00
0590 0700 5 22 INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, 12-18 SF	4.000 EA	2200.00000	8800.00	2772.51000	11090.04	2495.00000	9980.00
SECTION 0004 TOTALS		$	330,448.00	$	286,902.10	$	315,253.00

CALL ORDER: 033 PROPOSAL ID: T4367 LETTING DATE: 06/18/14 10:30 A.M. DISTRICT: 04

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(10) DAVID MANCINI & SONS, INC. UNIT PRICE	 AMOUNT	(11) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(12) MARKS BROTHERS INC. UNIT PRICE	 AMOUNT
SECTION 0005 LANDSCAPE / PERIPHERAL							
0595 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK	289.000 SY	83.00000	23987.00	138.06000	39899.34	130.00000	37570.00
0600 0580 1 1 LANDSCAPE COMPLETE- SMALL PLANTS 23072415201	LUMP	98000.00000	98000.00	102375.67000	102375.67	107485.00000	107485.00
0605 0580 1 2 LANDSCAPE COMPLETE- LARGE PLANTS 23072415201	LUMP	195000.00000	195000.00	204260.22000	204260.22	214545.00000	214545.00
0610 0590 70 IRRIGATION SYSTEM 23072415201	LUMP	36000.00000	36000.00	47528.70000	47528.70	58735.00000	58735.00
SECTION 0005 TOTALS		$	352,987.00	$	394,063.93	$	418,335.00
CONTRACT TOTALS		$	4,587,686.40	$	4,782,044.23	$	4,823,213.70

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.