VENDOR RANKING

CALL ORDER : 001 PROPOSAL ID : T3437 PROPOSAL DESC :
LETTING DATE : 03/26/14 10:30 A.M. DISTRICT : 03 The improvements under this contract consist of the
SET-ASIDE : U/R CODE : replacement of a deficient timber bridge with a single span
CONTRACT TIME : 100 WORKING DAYS (AVAILABLE DAYS) cast-in place flat slab bridge. 197 linear feet of the
unpaved roadway will be paved and striped in addition to the
bridge deck. 6,132 sq. ft. of sheet pile will be installed
at the bridge ends.

FINPROJ(S) : 42719715201 (*) F.A. NO. : 00B3164B COUNTIES : HOLMES

LOCAL NAME : JESSE O LEWIS ROAD ROAD NAME : JESSE O LEWIS ROAD
PROJ LIMITS : OVER BOGGY BRANCH BRIDGE NO. 524159

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	F & W CONSTRUCTION COMPANY, INC.	Responsive	Winning bid	$ 635,035.06	0.00%
2	MURPHREE BRIDGE CORPORATION	Responsive	Non-Winning Bid	$ 694,059.49	9.29%
3	GULF GROUP, INC.	Responsive	Non-Winning Bid	$ 696,056.13	9.60%
4	COMMERCIAL INDUSTRIAL CORP.	Responsive	Non-Winning Bid	$ 698,352.87	9.97%
5	NORTH FLORIDA CONSTRUCTION, INC.	Responsive	Non-Winning Bid	$ 791,245.50	24.59%
6	ANDERSON COLUMBIA CO., INC.	Responsive	Non-Winning Bid	$ 844,054.61	32.91%

CALL ORDER : 001 PROPOSAL ID : T3437 PROPOSAL DESC :
LETTING DATE : 03/26/14 10:30 A.M. DISTRICT : 03 The improvements under this contract consist of the
SET-ASIDE : U/R CODE : replacement of a deficient timber bridge with a single span
CONTRACT TIME : 100 WORKING DAYS (AVAILABLE DAYS) cast-in place flat slab bridge. 197 linear feet of the
unpaved roadway will be paved and striped in addition to the
bridge deck. 6,132 sq. ft. of sheet pile will be installed
at the bridge ends.

FINPROJ(S) : 42719715201 (*) F.A. NO. : 00B3164B COUNTIES : HOLMES

LOCAL NAME : JESSE O LEWIS ROAD ROAD NAME : JESSE O LEWIS ROAD
PROJ LIMITS : OVER BOGGY BRANCH BRIDGE NO. 524159

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) F & W CONSTRUCTION COMPANY, UNIT PRICE	AMOUNT	(2) MURPHREE BRIDGE CORPORATION UNIT PRICE	AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42719715201	411.000 LS	86000.00000	86000.00	15000.00000	15000.00	18280.00000	18280.00
0010 0400 2 4 CONC CLASS II, SUPERSTRUCTURE	67.700 CY	500.00000	33850.00	1175.05000	79550.89	716.90000	48534.13
0015 0400 2 5 CONCRETE CLASS II, SUBSTRUCTURE	40.000 CY	500.00000	20000.00	1255.00000	50200.00	916.00000	36640.00
0020 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	42.100 CY	500.00000	21050.00	450.00000	18945.00	331.00000	13935.10
0025 0400 7 BRIDGE DECK GROOVING, LESS THAN 8.5"	96.000 SY	30.00000	2880.00	35.00000	3360.00	30.00000	2880.00
0030 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	11844.000 LB	2.00000	23688.00	1.00000	11844.00	1.10000	13028.40
0035 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	3942.000 LB	2.00000	7884.00	1.00000	3942.00	1.10000	4336.20
0040 0415 1 9 REINFORCING STEEL- APPROACH SLABS	8316.000 LB	2.00000	16632.00	1.00000	8316.00	1.10000	9147.60
0045 0455 34 3 PRESTRESSED CONCRETE PILING, 18" SQ	360.000 LF	60.00000	21600.00	113.00000	40680.00	118.90000	42804.00
0050 0455133 3 SHEET PILING STEEL, F&I PERMANENT	6132.000 SF	35.00000	214620.00	32.00000	196224.00	44.70000	274100.40
0055 0455143 3 TEST PILES-PRESTRESSED CONCRETE,18" SQ	150.000 LF	100.00000	15000.00	242.00000	36300.00	416.35000	62452.50
0060 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	51.000 LF	50.00000	2550.00	50.00000	2550.00	29.25000	1491.75

CALL ORDER: 001 PROPOSAL ID: T3437 LETTING DATE: 03/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) F & W CONSTRUCTION COMPANY, UNIT PRICE	 AMOUNT	(2) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	 AMOUNT
0065 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	154.000 LF	80.00000	12320.00	125.00000	19250.00	80.00000	12320.00
SECTION 0001 TOTALS		$	478,074.00	$	486,161.89	$	539,950.08
SECTION 0002 ROADWAY							
0070 0101 1 MOBILIZATION 42719715201	LUMP	30000.00000	30000.00	77153.64000	77153.64	25000.00000	25000.00
0075 0102 1 MAINTENANCE OF TRAFFIC 42719715201	100.000 LS	0.00000	0.00	3200.00000	3200.00	10120.00000	10120.00
0080 0102 60 WORK ZONE SIGN	8600.000 ED	0.30000	2580.00	0.30000	2580.00	0.50000	4300.00
0085 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	600.000 ED	0.45000	270.00	0.45000	270.00	0.50000	300.00
0090 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	1700.000 ED	0.45000	765.00	0.45000	765.00	0.50000	850.00
0095 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	342.000 ED	14.50000	4959.00	14.50000	4959.00	22.00000	7524.00
0100 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	782.000 SY	3.50000	2737.00	3.50000	2737.00	1.00000	782.00
0105 0104 10 3 SEDIMENT BARRIER	839.000 LF	2.50000	2097.50	2.50000	2097.50	1.00000	839.00
0110 0104 11 FLOATING TURBIDITY BARRIER	174.000 LF	15.00000	2610.00	18.35000	3192.90	17.00000	2958.00
0115 0110 1 1 CLEARING & GRUBBING 42719715201	0.490 LS	19675.00000	19675.00	19675.00000	19675.00	34950.00000	34950.00
0120 0120 1 REGULAR EXCAVATION	126.000 CY	8.00000	1008.00	8.00000	1008.00	4.50000	567.00
0125 0120 2 2 BORROW EXCAVATION, TRUCK MEASURE	504.000 CY	17.84000	8991.36	17.84000	8991.36	8.60000	4334.40
0130 0120 5 CHANNEL EXCAVATION	68.000 CY	5.00000	340.00	5.00000	340.00	23.70000	1611.60
0135 0160 4 TYPE B STABILIZATION	647.000 SY	5.50000	3558.50	5.50000	3558.50	4.50000	2911.50

CALL ORDER: 001 PROPOSAL ID: T3437 LETTING DATE: 03/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) F & W CONSTRUCTION COMPANY, UNIT PRICE	 AMOUNT	(2) MURPHREE BRIDGE CORPORATION UNIT PRICE	 AMOUNT	(3) GULF GROUP, INC. UNIT PRICE	 AMOUNT
0140 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	569.000 SY	6.00000	3414.00	6.00000	3414.00	0.90000	512.10
0145 0285702 OPTIONAL BASE, BASE GROUP 02	115.000 SY	48.86000	5618.90	48.86000	5618.90	12.00000	1380.00
0150 0285706 OPTIONAL BASE, BASE GROUP 06	485.000 SY	33.70000	16344.50	33.70000	16344.50	14.00000	6790.00
0155 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	56.800 TN	248.00000	14086.40	248.00000	14086.40	175.00000	9940.00
0160 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	17.400 TN	248.00000	4315.20	248.00000	4315.20	200.00000	3480.00
0165 0430174218 PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	23.000 LF	75.00000	1725.00	75.00000	1725.00	40.00000	920.00
0170 0430984625 MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	2.000 EA	1100.00000	2200.00	1100.00000	2200.00	815.00000	1630.00
0175 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	154.000 TN	100.00000	15400.00	100.00000	15400.00	85.00000	13090.00
0180 0536 1 1 GUARDRAIL -ROADWAY	163.000 LF	25.50000	4156.50	25.50000	4156.50	32.00000	5216.00
0185 0536 8 1 GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, INSTALL	2.000 EA	2200.00000	4400.00	2200.00000	4400.00	2772.00000	5544.00
0190 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	2.000 EA	700.00000	1400.00	700.00000	1400.00	882.00000	1764.00
0195 0570 1 2 PERFORMANCE TURF, SOD	569.000 SY	3.00000	1707.00	3.00000	1707.00	4.05000	2304.45
SECTION 0002 TOTALS		$	154,358.86	$	205,295.40	$	149,618.05
SECTION 0003 SIGNING							
0200 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	25.00000	50.00	25.00000	50.00	31.50000	63.00
0205 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42719715201	LUMP	2552.20000	2552.20	2552.20000	2552.20	6425.00000	6425.00
SECTION 0003 TOTALS		$	2,602.20	$	2,602.20	$	6,488.00
CONTRACT TOTALS		$	635,035.06	$	694,059.49	$	696,056.13

CALL ORDER: 001 PROPOSAL ID: T3437 LETTING DATE: 03/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) COMMERCIAL INDUSTRIAL CORP. UNIT PRICE	 AMOUNT	(5) NORTH FLORIDA CONSTRUCTION, UNIT PRICE	 AMOUNT	(6) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT
SECTION 0001 STRUCTURES							
0005 0110 3 REMOVAL OF EXISTING STRUCTURE 42719715201	411.000 LS	14550.00000	14550.00	11000.00000	11000.00	43440.57000	43440.57
0010 0400 2 4 CONC CLASS II, SUPERSTRUCTURE	67.700 CY	803.00000	54363.10	720.00000	48744.00	595.61000	40322.80
0015 0400 2 5 CONCRETE CLASS II, SUBSTRUCTURE	40.000 CY	800.00000	32000.00	1000.00000	40000.00	1386.73000	55469.20
0020 0400 2 10 CONCRETE CLASS II, APPROACH SLABS	42.100 CY	373.35000	15718.04	550.00000	23155.00	412.64000	17372.14
0025 0400 7 BRIDGE DECK GROOVING, LESS THAN 8.5"	96.000 SY	55.00000	5280.00	20.00000	1920.00	30.88000	2964.48
0030 0415 1 4 REINFORCING STEEL - SUPERSTRUCTURE	11844.000 LB	0.97000	11488.68	1.50000	17766.00	1.06000	12554.64
0035 0415 1 5 REINFORCING STEEL- SUBSTRUCTURE	3942.000 LB	1.80000	7095.60	1.75000	6898.50	1.18000	4651.56
0040 0415 1 9 REINFORCING STEEL- APPROACH SLABS	8316.000 LB	0.97000	8066.52	1.50000	12474.00	1.06000	8814.96
0045 0455 34 3 PRESTRESSED CONCRETE PILING, 18" SQ	360.000 LF	144.01000	51843.60	160.00000	57600.00	154.57000	55645.20
0050 0455133 3 SHEET PILING STEEL, F&I PERMANENT	6132.000 SF	34.25000	210021.00	55.00000	337260.00	24.63000	151031.16
0055 0455143 3 TEST PILES-PRESTRESSED CONCRETE,18" SQ	150.000 LF	165.03000	24754.50	200.00000	30000.00	244.74000	36711.00
0060 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	51.000 LF	79.07000	4032.57	140.00000	7140.00	50.03000	2551.53
0065 0521 5 1 CONCRETE TRAFFIC RAILING, BRIDGE 32" F - SHAPE	154.000 LF	109.16000	16810.64	155.00000	23870.00	139.20000	21436.80
SECTION 0001 TOTALS		$	456,024.25	$	617,827.50	$	452,966.04
SECTION 0002 ROADWAY							
0070 0101 1 MOBILIZATION 42719715201	LUMP	94515.00000	94515.00	25000.00000	25000.00	189399.55000	189399.55

CALL ORDER: 001 PROPOSAL ID: T3437 LETTING DATE: 03/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) COMMERCIAL INDUSTRIAL CORP. UNIT PRICE	 AMOUNT	(5) NORTH FLORIDA CONSTRUCTION, UNIT PRICE	 AMOUNT	(6) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT
0075 0102 1 MAINTENANCE OF TRAFFIC 42719715201	100.000 LS	6215.00000	6215.00	12000.00000	12000.00	19418.33000	19418.33
0080 0102 60 WORK ZONE SIGN	8600.000 ED	0.55000	4730.00	1.00000	8600.00	0.54000	4644.00
0085 0102 74 2 BARRICADE, TEMPORARY, TYPE III, 6'	600.000 ED	0.55000	330.00	1.00000	600.00	0.54000	324.00
0090 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	1700.000 ED	0.55000	935.00	1.00000	1700.00	0.54000	918.00
0095 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	342.000 ED	21.90000	7489.80	25.00000	8550.00	21.45000	7335.90
0100 0104 1 ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	782.000 SY	1.79000	1399.78	3.00000	2346.00	3.42000	2674.44
0105 0104 10 3 SEDIMENT BARRIER	839.000 LF	1.11000	931.29	4.00000	3356.00	4.12000	3456.68
0110 0104 11 FLOATING TURBIDITY BARRIER	174.000 LF	10.35000	1800.90	15.00000	2610.00	19.59000	3408.66
0115 0110 1 1 CLEARING & GRUBBING 42719715201	0.490 LS	13411.00000	13411.00	15000.00000	15000.00	13459.20000	13459.20
0120 0120 1 REGULAR EXCAVATION	126.000 CY	6.86000	864.36	10.00000	1260.00	14.15000	1782.90
0125 0120 2 2 BORROW EXCAVATION, TRUCK MEASURE	504.000 CY	23.46000	11823.84	18.00000	9072.00	54.67000	27553.68
0130 0120 5 CHANNEL EXCAVATION	68.000 CY	14.31000	973.08	23.00000	1564.00	110.76000	7531.68
0135 0160 4 TYPE B STABILIZATION	647.000 SY	8.02000	5188.94	5.00000	3235.00	23.60000	15269.20
0140 0162 1 11 PREPARED SOIL LAYER, FINISH SOIL LAYER, 6"	569.000 SY	2.66000	1513.54	2.50000	1422.50	3.13000	1780.97
0145 0285702 OPTIONAL BASE, BASE GROUP 02	115.000 SY	16.90000	1943.50	19.00000	2185.00	64.15000	7377.25
0150 0285706 OPTIONAL BASE, BASE GROUP 06	485.000 SY	54.74000	26548.90	21.00000	10185.00	41.35000	20054.75
0155 0334 1 12 SUPERPAVE ASPHALTIC CONC, TRAFFIC B	56.800 TN	261.00000	14824.80	220.00000	12496.00	248.87000	14135.82

CALL ORDER: 001 PROPOSAL ID: T3437 LETTING DATE: 03/26/14 10:30 A.M. DISTRICT: 03

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(4) COMMERCIAL INDUSTRIAL CORP. UNIT PRICE	 AMOUNT	(5) NORTH FLORIDA CONSTRUCTION, UNIT PRICE	 AMOUNT	(6) ANDERSON COLUMBIA CO., INC. UNIT PRICE	 AMOUNT
0160 0339 1 MISCELLANEOUS ASPHALT PAVEMENT	17.400 TN	365.00000	6351.00	250.00000	4350.00	207.86000	3616.76
0165 0430174218 PIPE CULVERT, OPTIONAL MATERIAL, OTHER SHAPE - ELLIP/ARCH, 18"SD	23.000 LF	82.33000	1893.59	90.00000	2070.00	105.50000	2426.50
0170 0430984625 MITERED END SECT, OPTIONAL - ELLIPTICAL / ARCH, 18" SD	2.000 EA	1308.00000	2616.00	1400.00000	2800.00	1000.68000	2001.36
0175 0530 3 4 RIPRAP, RUBBLE, F&I, DITCH LINING	154.000 TN	115.00000	17710.00	130.00000	20020.00	103.70000	15969.80
0180 0536 1 1 GUARDRAIL -ROADWAY	163.000 LF	31.00000	5053.00	35.00000	5705.00	30.38000	4951.94
0185 0536 8 1 GUARDRAIL, BRIDGE ANCHORAGE ASSEMBLY, INSTALL	2.000 EA	2676.00000	5352.00	3000.00000	6000.00	2620.99000	5241.98
0190 0536 85 25 GUARDRAIL END ANCHORAGE ASSEMBLY- TYPE II	2.000 EA	851.00000	1702.00	1000.00000	2000.00	833.95000	1667.90
0195 0570 1 2 PERFORMANCE TURF, SOD	569.000 SY	4.14000	2355.66	3.50000	1991.50	4.77000	2714.13
SECTION 0002 TOTALS		$	238,471.98	$	166,118.00	$	379,115.38
SECTION 0003 SIGNING							
0200 0700 1 60 SINGLE POST SIGN, REMOVE	2.000 AS	60.82000	121.64	200.00000	400.00	29.79000	59.58
0205 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42719715201	LUMP	3735.00000	3735.00	6900.00000	6900.00	11913.61000	11913.61
SECTION 0003 TOTALS		$	3,856.64	$	7,300.00	$	11,973.19
CONTRACT TOTALS		$	698,352.87	$	791,245.50	$	844,054.61

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.