VENDOR RANKING

CALL ORDER : 029 PROPOSAL ID : T1622 PROPOSAL DESC :
LETTING DATE : 05/20/15 10:30 A.M. DISTRICT : 01 The improvements under this contract consist of milling and
SET-ASIDE : U/R CODE : resurfacing, widening, base work, shoulder treatment,
CONTRACT TIME : 80 WORKING DAYS (AVAILABLE DAYS) drainage improvements, curb and gutters, sidewalks and
signing and pavement marking on SR 25 (US 27).

FINPROJ(S) : 43576915201 (*) F.A. NO. : N/A COUNTIES : GLADES

LOCAL NAME : SR 25 (US 27) AT BRONSON ROAD ROAD NAME : SR 25
PROJ LIMITS :

RANK	VENDOR NAME	BID TYPE	BID STATUS	TOTAL BID	% OVER LOW BID
1	WEEKLEY ASPHALT PAVING, INC.	Responsive	Winning bid	$ 820,360.48	0.00%
2	COMMUNITY ASPHALT CORP.	Responsive	Non-Winning Bid	$ 889,374.00	8.41%
3	AJAX PAVING INDUSTRIES OF FLORIDA LLC	Responsive	Non-Winning Bid	$ 941,924.72	14.81%

CALL ORDER : 029
LETTING DATE : 05/20/15 10:30 A.M.
SET-ASIDE :
CONTRACT TIME : 80 WORKING DAYS (AVAILABLE DAYS)

PROPOSAL ID : T1622
DISTRICT : 01
U/R CODE :

PROPOSAL DESC :
The improvements under this contract consist of milling and resurfacing, widening, base work, shoulder treatment, drainage improvements, curb and gutters, sidewalks and signing and pavement marking on SR 25 (US 27).

FINPROJ(S) : 43576915201 (*)
F.A. NO. : N/A
COUNTIES : GLADES

LOCAL NAME : SR 25 (US 27) AT BRONSON ROAD
PROJ LIMITS :
ROAD NAME : SR 25

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(3) AJAX PAVING INDUSTRIES OF FLORI UNIT PRICE	 AMOUNT
SECTION 0001 ROADWAY							
0005 0101 1 MOBILIZATION 43576915201	LUMP	54430.00000	54430.00	77010.01000	77010.01	103500.00000	103500.00
0010 0102 1 MAINTENANCE OF TRAFFIC 43576915201	80.000 LS	76645.00000	76645.00	110890.00000	110890.00	102500.00000	102500.00
0015 0102 60 WORK ZONE SIGN	2880.000 ED	0.30000	864.00	0.35000	1008.00	0.35000	1008.00
0020 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	6720.000 ED	0.15000	1008.00	0.15000	1008.00	0.17000	1142.40
0025 0102 76 ARROW BOARD / ADVANCE WARNING ARROW PANEL	80.000 ED	8.00000	640.00	8.90000	712.00	9.23000	738.40
0030 0102 77 HIGH INTENSITY FLASHING LIGHTS, TEMP, TYPE B	640.000 ED	0.35000	224.00	0.40000	256.00	0.40000	256.00
0035 0104 10 3 SEDIMENT BARRIER	1129.000 LF	1.62000	1828.98	2.10000	2370.90	1.70000	1919.30
0040 0104 12 STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	41.000 LF	4.20000	172.20	4.20000	172.20	4.33000	177.53
0045 0104 18 INLET PROTECTION SYSTEM	1.000 EA	130.00000	130.00	128.00000	128.00	132.65000	132.65
0050 0107 1 LITTER REMOVAL	26.370 AC	20.00000	527.40	83.60000	2204.53	39.22000	1034.23
0055 0107 2 MOWING	26.370 AC	30.00000	791.10	83.60000	2204.53	39.22000	1034.23

CALL ORDER: 029 PROPOSAL ID: T1622 LETTING DATE: 05/20/15 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(3) AJAX PAVING INDUSTRIES OF FLORI UNIT PRICE	 AMOUNT
0060 0110 1 1 CLEARING & GRUBBING 43576915201	2.500 LS	39890.00000	39890.00	72300.00000	72300.00	30250.00000	30250.00
0065 0120 1 REGULAR EXCAVATION	2043.000 CY	19.65000	40144.95	12.70000	25946.10	20.10000	41064.30
0070 0120 6 EMBANKMENT	1435.000 CY	9.50000	13632.50	7.10000	10188.50	16.90000	24251.50
0075 0160 4 TYPE B STABILIZATION	7584.000 SY	4.90000	37161.60	5.60000	42470.40	9.90000	75081.60
0080 0285701 OPTIONAL BASE, BASE GROUP 01	327.000 SY	10.98000	3590.46	10.90000	3564.30	34.25000	11199.75
0085 0285711 OPTIONAL BASE, BASE GROUP 11	6003.000 SY	22.00000	132066.00	17.50000	105052.50	22.00000	132066.00
0090 0327 70 11 MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH	2178.000 SY	3.00000	6534.00	7.60000	16552.80	4.75000	10345.50
0095 0334 1 14 SUPERPAVE ASPHALTIC CONC, TRAFFIC D	1297.300 TN	118.00000	153081.40	117.00000	151784.10	117.55000	152497.62
0100 0334 1 24 SUPERPAVE ASPH CONC, TRAFFIC D, PG76-22 PMA	691.200 TN	150.00000	103680.00	139.00000	96076.80	128.55000	88853.76
0105 0337 7 22 ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22, PMA	335.200 TN	150.00000	50280.00	202.00000	67710.40	175.25000	58743.80
0110 0425 1521 INLETS, DT BOT, TYPE C,<10'	1.000 EA	5468.00000	5468.00	6899.43000	6899.43	2135.00000	2135.00
0115 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	18.000 LF	230.85000	4155.30	251.00000	4518.00	231.00000	4158.00
0120 0430610123 U-ENDWALL, STD 261, 1:4 SLOPE, 15"PIPE	1.000 EA	4225.00000	4225.00	3290.00000	3290.00	1155.00000	1155.00
0125 0520 1 7 CONCRETE CURB & GUTTER, TYPE E	625.000 LF	22.75000	14218.75	19.00000	11875.00	19.60000	12250.00
0130 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	15.000 SY	145.00000	2175.00	60.20000	903.00	62.30000	934.50
0135 0570 1 2 PERFORMANCE TURF, SOD	6235.000 SY	1.98000	12345.30	2.10000	13093.50	3.75000	23381.25
0136 0710 11111 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1.192 NM	900.00000	1072.80	1120.00000	1335.04	1155.00000	1376.76

CALL ORDER: 029 PROPOSAL ID: T1622 LETTING DATE: 05/20/15 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(3) AJAX PAVING INDUSTRIES OF FLORI UNIT PRICE	 AMOUNT
0137 0710 11112 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 8"	0.292 NM	1000.00000	292.00	1490.00000	435.08	1540.00000	449.68
0138 0710 11125 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	194.000 LF	4.50000	873.00	1.60000	310.40	1.60000	310.40
0139 0710 11131 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	0.258 GM	700.00000	180.60	418.00000	107.84	433.00000	111.71
0140 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 43576915201	LUMP	34375.00000	34375.00	34375.00000	34375.00	34375.00000	34375.00
0141 0710 11151 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	208.000 LF	0.16000	33.28	1.10000	228.80	1.15000	239.20
0142 0710 11170 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	44.000 EA	30.00000	1320.00	27.90000	1227.60	28.85000	1269.40
0143 0710 11211 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	0.998 NM	900.00000	898.20	1120.00000	1117.76	1155.00000	1152.69
0144 0710 11251 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, DOTTED/ GUIDELINE/6-10 GAP EXTENSION, 6"	36.000 LF	0.16000	5.76	1.10000	39.60	1.15000	41.40
0146 0710 11224 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	214.000 LF	1.00000	214.00	1.50000	321.00	1.50000	321.00
SECTION 0001 TOTALS		$	799,173.58	$	869,687.12	$	921,457.56
SECTION 0002 SIGNING							
0145 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	7.000 AS	350.00000	2450.00	271.00000	1897.00	280.00000	1960.00

CALL ORDER: 029 PROPOSAL ID: T1622 LETTING DATE: 05/20/15 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(3) AJAX PAVING INDUSTRIES OF FLORI UNIT PRICE	 AMOUNT
0155 0700 1 13 SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	1.000 AS	1500.00000	1500.00	1870.00000	1870.00	1933.00000	1933.00
0160 0700 1 50 SINGLE POST SIGN, RELOCATE	4.000 AS	250.00000	1000.00	223.00000	892.00	230.70000	922.80
0165 0700 1 60 SINGLE POST SIGN, REMOVE	3.000 AS	50.00000	150.00	22.30000	66.90	23.10000	69.30
0175 0705 10 2 OBJECT MARKER, TYPE 2	2.000 EA	100.00000	200.00	167.00000	334.00	173.00000	346.00
0180 0705 11 1 DELINEATOR, FLEXIBLE TUBULAR	1.000 EA	100.00000	100.00	167.00000	167.00	173.00000	173.00
0185 0705 11 2 DELINEATOR, NON-FLEXIBLE	4.000 EA	100.00000	400.00	145.00000	580.00	150.00000	600.00
0190 0706 3 RETRO-REFLECTIVE PAVEMENT MARKERS	153.000 EA	5.00000	765.00	5.60000	856.80	5.75000	879.75
0195 0710 11190 PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	79.000 SF	2.00000	158.00	2.20000	173.80	2.30000	181.70
0200 0710 11290 PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	148.000 SF	2.00000	296.00	2.20000	325.60	2.30000	340.40
0205 0711 11124 THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	254.000 LF	5.00000	1270.00	4.20000	1066.80	4.35000	1104.90
0210 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	97.000 LF	6.00000	582.00	5.60000	543.20	5.80000	562.60
0215 0711 11151 THERMOPLASTIC, STANDARD, WHITE, DOTTED/GUIDELINE/ 6-10 GAP EXTENSION, 6"	104.000 LF	3.00000	312.00	0.85000	88.40	0.90000	93.60
0220 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW	22.000 EA	75.00000	1650.00	63.60000	1399.20	65.75000	1446.50
0225 0711 11224 THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	107.000 LF	5.00000	535.00	4.20000	449.40	4.35000	465.45
0230 0711 11251 THERMOPLASTIC, STANDARD, YELLOW, DOTTED / GUIDELINE /6-10 GAP EXTENSION, 6"	18.000 LF	3.00000	54.00	0.85000	15.30	0.90000	16.20

CALL ORDER: 029 PROPOSAL ID: T1622 LETTING DATE: 05/20/15 10:30 A.M. DISTRICT: 01

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(1) WEEKLEY ASPHALT PAVING, INC UNIT PRICE	 AMOUNT	(2) COMMUNITY ASPHALT CORP. UNIT PRICE	 AMOUNT	(3) AJAX PAVING INDUSTRIES OF FLORI UNIT PRICE	 AMOUNT
0235 0711 14160 THERMOPLASTIC, PREFORMED, WHITE, MESSAG	2.000 EA	250.00000	500.00	223.00000	446.00	230.70000	461.40
0240 0711 14170 THERMOPLASTIC, PREFORMED, WHITE, ARROWS	2.000 EA	150.00000	300.00	112.00000	224.00	115.35000	230.70
0245 0711 15111 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	0.596 NM	5000.00000	2980.00	4460.00000	2658.16	4615.00000	2750.54
0250 0711 15112 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	0.146 NM	6000.00000	876.00	5950.00000	868.70	6155.00000	898.63
0255 0711 15131 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	0.129 GM	1700.00000	219.30	1120.00000	144.48	1155.00000	149.00
0260 0711 15211 THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	0.499 NM	5000.00000	2495.00	4460.00000	2225.54	4615.00000	2302.89
0261 0711 17 THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS	1842.000 SF	1.30000	2394.60	1.30000	2394.60	1.40000	2578.80
SECTION 0002 TOTALS			$ 21,186.90		$ 19,686.88		$ 20,467.16
CONTRACT TOTALS			$ 820,360.48		$ 889,374.00		$ 941,924.72

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.