Vendor Ranking

Letting: CT160928 September 28, 2016 10:30 AM **Call Order:** 010 **Contract:** T4443

District: District 4 **Counties:** MARTIN **Fed Aid No:** N/A

Contract Time: 120 AVAILABLE DAYS **Project(s):** 43427515201 (*)

Contract Desc: SR 76 (KANNER HWY)

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	LYNCH PAVING & CONSTRUCTION CO.	Responsive	Winning bid	$1,312,213.59	100.00%
2	RANGER CONSTRUCTION INDUSTRIES, INC.	Responsive	Non-Winning Bid	$1,515,568.76	115.50%
3	COMMUNITY ASPHALT CORP.	Responsive	Non-Winning Bid	$1,585,391.85	120.82%
4	MANCIL'S TRACTOR SERVICE, INC.	Responsive	Non-Winning Bid	$1,767,126.15	134.67%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

District: District 4 **Counties:** MARTIN **Fed Aid No:** N/A

Contract Time: 120 AVAILABLE DAYS **Project(s):** 43427515201 (*)

Contract Descr: SR 76 (KANNER HWY)

The improvements under this contract consist of milling and resurfacing, signing and pavement markings including rumble striping, shoulder widening, intersection and driveway paving, new guardrail and guardrail repair along SR 76 (Kanner Hwy.).

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Roadway						
0005 0101 1 MOBILIZATION 43427515201 (1.000) LS	71,709.07000	71,709.07	161,393.96000	161,393.96	57,560.00000	57,560.00
0010 0102 1 MAINTENANCE OF TRAFFIC 43427515201 (120.000) DA (LS)	41,008.00000	41,008.00	95,333.21000	95,333.21	121,830.00000	121,830.00
0015 0102 60 WORK ZONE SIGN 1,980.000 ED	0.55000	1,089.00	0.41000	811.80	0.30000	594.00
0020 0102 71 14 BARRIER WALL, TEMPORARY, F&I, TYPE K 1,188.000 LF	25.00000	29,700.00	31.72000	37,683.36	29.70000	35,283.60
0025 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 17,040.000 ED	0.20000	3,408.00	0.18000	3,067.20	0.15000	2,556.00
0030 0102 78 TEMPORARY RETROREFLECTIVE PAVEMENT MARKER 400.000 EA	4.25000	1,700.00	3.53000	1,412.00	3.10000	1,240.00
0035 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION 2.000 LO	1,000.00000	2,000.00	2,640.09000	5,280.18	1,030.00000	2,060.00

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Roadway						
0040 0102 99 360.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	15.00000	5,400.00	14.12000	5,083.20	14.40000	5,184.00
0045 0102909 240.000 DA TEMPORARY RAISED RUMBLE STRIPS-PER DAY, INCLUDES ALL SETS AND RELOCATIONS	50.00000	12,000.00	94.12000	22,588.80	49.40000	11,856.00
0050 0104 10 3 4,050.000 LF SEDIMENT BARRIER	1.20000	4,860.00	2.07000	8,383.50	0.80000	3,240.00
0055 0104 18 3.000 EA INLET PROTECTION SYSTEM	85.00000	255.00	94.12000	282.36	77.20000	231.60
0060 0107 1 80.380 AC LITTER REMOVAL	120.00000	9,645.60	65.20000	5,240.78	47.00000	3,777.86
0065 0107 2 68.860 AC MOWING	60.00000	4,131.60	124.86000	8,597.86	98.30000	6,768.94
0070 0110 1 1 (1.020) AC (LS) CLEARING & GRUBBING 43427515201	5,000.00000	5,000.00	7,054.39000	7,054.39	91,470.00000	91,470.00
0075 0120 1 337.200 CY REGULAR EXCAVATION	24.50000	8,261.40	29.19000	9,842.87	29.90000	10,082.28

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0080 0120 6 1,178.900 CY EMBANKMENT	13.50000	15,915.15	16.24000	19,145.34	28.80000	33,952.32
0085 0285705 2,268.000 SY OPTIONAL BASE, BASE GROUP 05	27.75000	62,937.00	26.97000	61,167.96	31.30000	70,988.40
0090 0327 70 4 26,690.000 SY MILLING EXIST ASPH PAVT, 3" AVG DEPTH	1.45000	38,700.50	3.46000	92,347.40	2.70000	72,063.00
0095 0327 70 6 11,708.000 SY MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	1.45000	16,976.60	2.36000	27,630.88	2.10000	24,586.80
0100 0334 1 13 1,243.200 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	110.30000	137,124.96	94.89000	117,967.25	107.00000	133,022.40
0105 0339 1 14.100 TN MISCELLANEOUS ASPHALT PAVEMENT	290.00000	4,089.00	224.95000	3,171.80	267.00000	3,764.70
0110 0536 1 1 188.000 LF GUARDRAIL -ROADWAY, GENERAL TL-3	31.00000	5,828.00	32.65000	6,138.20	28.60000	5,376.80
0115 0536 73 177.000 LF GUARDRAIL REMOVAL	6.00000	1,062.00	5.88000	1,040.76	5.20000	920.40
0120 0536 85 22 2.000 EA GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	2,860.00000	5,720.00	3,058.82000	6,117.64	2,680.00000	5,360.00

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0125 0570 1 2 — 2,714.000 SY PERFORMANCE TURF, SOD	2.65000	7,192.10	5.55000	15,062.70	3.00000	8,142.00
0130 0710 11101 — 11.139 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	1,140.00000	12,698.46	905.15000	10,082.47	793.00000	8,833.23
0135 0710 11125 — 348.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	2.10000	730.80	0.64000	222.72	0.55000	191.40
0140 0710 11160 — 6.000 EA PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	60.00000	360.00	52.94000	317.64	46.30000	277.80
0145 0710 11201 — 3.555 GM PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	1,140.00000	4,052.70	904.61000	3,215.89	793.00000	2,819.12
0150 0710 11231 — 4.251 GM PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	420.00000	1,785.42	411.67000	1,750.01	360.00000	1,530.36
0155 0914334 2 — 2,038.400 TN SUPERPAVE ASPHALT CONCRETE, TRAFFIC C, PG 76-22, HIGH POLYMER	113.40000	231,154.56	107.57000	219,270.69	134.00000	273,145.60
0160 0914337 4 — 3,524.400 TN ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC 12.5, PG 76-22, HIGH POLYMER	113.60000	400,371.84	113.08000	398,539.15	127.00000	447,598.80

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0002 Signing						
0165 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 43427515201	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0001 Roadway Section Totals:		**$1,196,866.76**		**$1,405,243.97**		**$1,496,307.41**
SECTION: 0002 Signing						
0170 0546 72 52 1.226 GM RUMBLE STRIPS, GROUND-IN, 16" CENTERLINE USED WITH RUMBLE STRIPE	2,350.00000	2,881.10	3,675.55000	4,506.22	2,180.00000	2,672.68
0175 0546 72 53 2.392 GM RUMBLE STRIPS, GROUND-IN, 8" EDGELINE USED WITH RUMBLE STRIPE	2,050.00000	4,903.60	2,789.45000	6,672.36	1,900.00000	4,544.80
0180 0700 1 11 100.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	360.00000	36,000.00	386.20000	38,620.00	339.00000	33,900.00
0185 0700 1 12 14.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	1,345.00000	18,830.00	1,319.93000	18,479.02	1,160.00000	16,240.00
0190 0700 1 50 1.000 AS SINGLE POST SIGN, RELOCATE	310.00000	310.00	329.97000	329.97	289.00000	289.00
0195 0700 1 60 92.000 AS SINGLE POST SIGN, REMOVE	25.00000	2,300.00	19.61000	1,804.12	17.20000	1,582.40

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0002 Signing						
0200 0700 2 14 — 1.000 AS MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	4,230.00000	4,230.00	4,521.59000	4,521.59	3,960.00000	3,960.00
0205 0705 10 1 — 1.000 EA OBJECT MARKER, TYPE 1	135.00000	135.00	142.07000	142.07	124.00000	124.00
0210 0705 10 2 — 6.000 EA OBJECT MARKER, TYPE 2	120.00000	720.00	121.26000	727.56	106.00000	636.00
0215 0705 11 2 — 79.000 EA DELINEATOR, NON-FLEXIBLE	50.00000	3,950.00	51.94000	4,103.26	45.50000	3,594.50
0220 0710 90 — (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43427515201	13,390.00000	13,390.00	13,210.66000	13,210.66	6,440.00000	6,440.00
0225 0711 11125 — 116.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	5.00000	580.00	2.99000	346.84	2.60000	301.60
0230 0711 11141 — 0.027 GM THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	3,490.00000	94.23	718.89000	19.41	849.00000	22.92
0235 0711 11160 — 2.000 EA THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	365.00000	730.00	76.47000	152.94	66.90000	133.80

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) LYNCH PAVING & CONSTRUCTION CO.		(2) RANGER CONSTRUCTION INDUSTRIES, INC.		(3) COMMUNITY ASPHALT CORP.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Roadway						
0240 0711 11170 1.000 EA THERMOPLASTIC, STANDARD, WHITE, ARROW	150.00000	150.00	64.71000	64.71	56.60000	56.60
0245 0711 16101 3.691 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	4,920.00000	18,159.72	3,116.80000	11,504.11	2,730.00000	10,076.43
0250 0711 16102 0.022 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	9,300.00000	204.60	4,053.64000	89.18	3,900.00000	85.80
0255 0711 16201 1.185 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	4,920.00000	5,830.20	3,104.49000	3,678.82	2,730.00000	3,235.05
0260 0711 16231 1.417 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	1,375.00000	1,948.38	954.09000	1,351.95	839.00000	1,188.86
0002 Signing Section Totals:		**$115,346.83**		**$110,324.79**		**$89,084.44**
Contract Grand Totals:		**$1,312,213.59**		**$1,515,568.76**		**1,585,391.85**

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Roadway						

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0005 0101 1 (1.000) LS MOBILIZATION 43427515201	98,500.00000	98,500.00				
0010 0102 1 (120.000) DA (LS) MAINTENANCE OF TRAFFIC 43427515201	50,000.00000	50,000.00				
0015 0102 60 1,980.000 ED WORK ZONE SIGN	0.33000	653.40				
0020 0102 71 14 1,188.000 LF BARRIER WALL, TEMPORARY, F&I, TYPE K	24.55000	29,165.40				
0025 0102 74 1 17,040.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.18000	3,067.20				
0030 0102 78 400.000 EA TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	4.24000	1,696.00				
0035 0102 89 1 2.000 LO TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	990.00000	1,980.00				
0040 0102 99 360.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	15.40000	5,544.00				

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) MANCIL'S TRACTOR SERVICE, INC.					
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0045 0102909 TEMPORARY RAISED RUMBLE STRIPS-PER DAY, INCLUDES ALL SETS AND RELOCATIONS 240.000 DA	52.80000	12,672.00				
0050 0104 10 3 SEDIMENT BARRIER 4,050.000 LF	1.50000	6,075.00				
0055 0104 18 INLET PROTECTION SYSTEM 3.000 EA	175.00000	525.00				
0060 0107 1 LITTER REMOVAL 80.380 AC	75.00000	6,028.50				
0065 0107 2 MOWING 68.860 AC	75.00000	5,164.50				
0070 0110 1 1 CLEARING & GRUBBING 43427515201 (1.020) AC (LS)	7,500.00000	7,500.00				
0075 0120 1 REGULAR EXCAVATION 337.200 CY	5.00000	1,686.00				
0080 0120 6 EMBANKMENT 1,178.900 CY	12.50000	14,736.25				

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0085 0285705 2,268.000 SY OPTIONAL BASE, BASE GROUP 05	124.50000	282,366.00				
0090 0327 70 4 26,690.000 SY MILLING EXIST ASPH PAVT, 3" AVG DEPTH	3.00000	80,070.00				
0095 0327 70 6 11,708.000 SY MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	2.25000	26,343.00				
0100 0334 1 13 1,243.200 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	108.50000	134,887.20				
0105 0339 1 14.100 TN MISCELLANEOUS ASPHALT PAVEMENT	175.00000	2,467.50				
0110 0536 1 1 188.000 LF GUARDRAIL -ROADWAY, GENERAL TL-3	30.55000	5,743.40				
0115 0536 73 177.000 LF GUARDRAIL REMOVAL	5.50000	973.50				
0120 0536 85 22 2.000 EA GUARDRAIL END ANCHORAGE ASSEMBLY- FLARED	2,860.00000	5,720.00				
0125 0570 1 2 2,714.000 SY PERFORMANCE TURF, SOD	4.00000	10,856.00				

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Roadway						
0130 0710 11101	11.139	1,138.50000	12,681.75			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM					
0135 0710 11125	348.000	2.09000	727.32			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF					
0140 0710 11160	6.000	60.50000	363.00			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA					
0145 0710 11201	3.555	1,138.50000	4,047.37			
PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM					
0150 0710 11231	4.251	418.00000	1,776.92			
PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM					
0155 0914334 2	2,038.400	130.00000	264,992.00			
SUPERPAVE ASPHALT CONCRETE, TRAFFIC C, PG 76-22, HIGH POLYMER	TN					
0160 0914337 4	3,524.400	147.13000	518,544.97			
ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC 12.5, PG 76-22, HIGH POLYMER	TN					
0165 0999 25	(1.000)	50,000.00000	50,000.00			
INITIAL CONTINGENCY AMOUNT, DO NOT BID 43427515201	LS					

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
0001 Roadway Section Totals:		**$1,647,553.18**				
SECTION: 0002 Signing						
0170 0546 72 52 RUMBLE STRIPS, GROUND-IN, 16" CENTERLINE USED WITH RUMBLE STRIPE	1.226 GM	4,750.00000	5,823.50			
0175 0546 72 53 RUMBLE STRIPS, GROUND-IN, 8" EDGELINE USED WITH RUMBLE STRIPE	2.392 GM	4,100.00000	9,807.20			
0180 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	100.000 AS	317.90000	31,790.00			
0185 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	14.000 AS	1,402.50000	19,635.00			
0190 0700 1 50 SINGLE POST SIGN, RELOCATE	1.000 AS	275.00000	275.00			
0195 0700 1 60 SINGLE POST SIGN, REMOVE	92.000 AS	5.50000	506.00			
0200 0700 2 14 MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	1.000 AS	4,397.80000	4,397.80			

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0205 0705 10 1 OBJECT MARKER, TYPE 1 1.000 EA	165.00000	165.00				
0210 0705 10 2 OBJECT MARKER, TYPE 2 6.000 EA	148.50000	891.00				
0215 0705 11 2 DELINEATOR, NON-FLEXIBLE 79.000 EA	66.00000	5,214.00				
0220 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43427515201 (1.000) LS	13,384.80000	13,384.80				
0225 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 116.000 LF	5.06000	586.96				
0230 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.027 GM	3,484.80000	94.09				
0235 0711 11160 THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL 2.000 EA	363.00000	726.00				
0240 0711 11170 THERMOPLASTIC, STANDARD, WHITE, ARROW 1.000 EA	148.50000	148.50				

Letting: CT160928 September 28, 2016 **Call Order:** 010 **Contract:** T4443

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) MANCIL'S TRACTOR SERVICE, INC.					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Signing						
0245 0711 16101 3.691 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	4,917.00000	18,148.65				
0250 0711 16102 0.022 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	9,292.80000	204.44				
0255 0711 16201 1.185 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	4,917.00000	5,826.65				
0260 0711 16231 1.417 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	1,375.00000	1,948.38				
0002 Signing Section Totals:		**$119,572.97**				
Contract Grand Totals:		**$1,767,126.15**				

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.