Vendor Ranking

Letting: CT190130 January 30, 2019 10:30 AM **Call Order:** 015 **Contract:** T6445
District: District 6 **Counties:** MIAMI-DADE **Fed Aid No:** D618073B
Contract Time: 300 AVAILABLE DAYS **Project(s):** 42611315201 (*) 42611315601
Contract Desc: NW 34TH AVE

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	CONDOTTE AMERICA, INC.	Responsive	Winning bid	$1,196,727.45	100.00%
2	HALLEY ENGINEERING CONTRACTORS, INC.	Responsive	Non-Winning Bid	$1,232,167.68	102.96%
3	ANZAC CONTRACTORS, INC.	Responsive	Non-Winning Bid	$1,293,710.95	108.10%
4	LEAD ENGINEERING CONTRACTORS, LLC	Responsive	Non-Winning Bid	$1,595,327.18	133.31%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

District: District 6 **Counties:** MIAMI-DADE **Fed Aid No:** D618073B

Contract Time: 300 AVAILABLE DAYS **Project(s):** 42611315201 (*) 42611315601

Contract Descr: NW 34TH AVE

The improvements under this contract consist of Bridge Replacement along NW 34th Ave.

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (865.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 42611315201 876420	70,000.00000	70,000.00	50,000.00000	50,000.00	50,050.00000	50,050.00
0010 0400 2 4 20.400 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	700.00000	14,280.00	1,030.00000	21,012.00	2,931.99000	59,812.60
0015 0400 2 10 75.600 CY CONCRETE CLASS II, APPROACH SLABS	350.00000	26,460.00	625.00000	47,250.00	455.44000	34,431.26
0020 0400 2 47 74.900 CY CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	890.00000	66,661.00	1,300.00000	97,370.00	988.38000	74,029.66
0025 0400 4 5 61.600 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	965.00000	59,444.00	1,010.00000	62,216.00	2,982.86000	183,744.18
0030 0400 7 151.000 SY BRIDGE DECK GROOVING, LESS THAN 8.5"	42.00000	6,342.00	50.00000	7,550.00	45.86000	6,924.86
0035 0400148 4.200 CF PLAIN NEOPRENE BEARING PADS	950.00000	3,990.00	2,500.00000	10,500.00	1,257.14000	5,279.99

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0040 0415 1 4 REINFORCING STEEL - BRIDGE SUPERSTRUCTURE 13,091.000 LB	1.10000	14,400.10	1.15000	15,054.65	1.09000	14,269.19
0045 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 5,366.000 LB	1.10000	5,902.60	1.21000	6,492.86	1.09000	5,848.94
0050 0415 1 9 REINFORCING STEEL- APPROACH SLABS 14,466.000 LB	1.10000	15,912.60	1.21000	17,503.86	1.09000	15,767.94
0055 0450 8 13 PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 55-57" 387.000 LF	270.00000	104,490.00	270.00000	104,490.00	250.93000	97,109.91
0060 0455 34304 PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING- PROJECT 426113-1-52-01, SIZE 14" 1,040.000 LF	75.00000	78,000.00	125.00000	130,000.00	149.64000	155,625.60
0065 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD 98.000 LF	35.00000	3,430.00	100.00000	9,800.00	39.96000	3,916.08
0070 0515 4 1 BULLET RAIL, SINGLE RAIL 120.000 LF	55.00000	6,600.00	52.00000	6,240.00	69.30000	8,316.00
0075 0521 5 4 CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE 120.000 LF	180.00000	21,600.00	163.00000	19,560.00	154.46000	18,535.20

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**	**Unit Price**	**Ext Amount**
SECTION: 0001 Structures						
0001 Structures Section Totals:		**$497,512.30**		**$605,039.37**		**$733,661.41**
SECTION: 0002 Roadway						
0080 0101 1 (1.000) LS MOBILIZATION 42611315201	118,000.00000	118,000.00	135,000.00000	135,000.00	116,446.00000	116,446.00
0085 0102 1 (300.000) DA (LS) MAINTENANCE OF TRAFFIC 42611315201	90,000.00000	90,000.00	70,000.00000	70,000.00	19,294.00000	19,294.00
0090 0102 2 1 (1.000) LS SPECIAL DETOUR 1 42611315201	110,000.00000	110,000.00	100.00000	100.00	94,325.00000	94,325.00
0095 0102 3 1.700 CY COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	750.00000	1,275.00	100.00000	170.00	380.47000	646.80
0100 0102 60 18,900.000 ED WORK ZONE SIGN	0.25000	4,725.00	0.33000	6,237.00	0.24000	4,536.00
0105 0102 71 16 170.000 LF TEMPORARY BARRIER, F&I, FREE STANDING	20.00000	3,400.00	0.01000	1.70	30.61000	5,203.70
0110 0102 71 26 170.000 LF TEMPORARY BARRIER, RELOCATE, FREE STANDING	12.00000	2,040.00	0.01000	1.70	7.70000	1,309.00

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0115 0102 74 1 1,995.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.30000	598.50	0.20000	399.00	0.13000	259.35
0120 0102 74 2 2,250.000 ED CHANNELIZING DEVICE, TYPE III, 6'	0.50000	1,125.00	0.50000	1,125.00	0.33000	742.50
0125 0102 74 7 157.000 LF CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	9.00000	1,413.00	5.00000	785.00	8.80000	1,381.60
0130 0102 89 1 4.000 LO TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	1,200.00000	4,800.00	0.01000	0.04	1,017.50000	4,070.00
0135 0102 99 418.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	12.00000	5,016.00	15.00000	6,270.00	12.10000	5,057.80
0140 0104 10 3 477.000 LF SEDIMENT BARRIER	2.00000	954.00	5.00000	2,385.00	2.20000	1,049.40
0145 0104 11 118.000 LF FLOATING TURBIDITY BARRIER	10.00000	1,180.00	25.00000	2,950.00	13.98000	1,649.64
0150 0104 18 4.000 EA INLET PROTECTION SYSTEM	30.00000	120.00	50.00000	200.00	220.00000	880.00

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0155 0107 1 LITTER REMOVAL 0.460 AC	30.00000	13.80	0.01000	0.00	239.30000	110.08
0160 0107 2 MOWING 0.100 AC	200.00000	20.00	0.01000	0.00	1,100.00000	110.00
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 42611315201 (1.000) LS	15,000.00000	15,000.00	10,000.00000	10,000.00	17,600.00000	17,600.00
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 42611315201 (1.000) LS	15,000.00000	15,000.00	18,000.00000	18,000.00	11,220.00000	11,220.00
0175 0110 1 1 CLEARING & GRUBBING 42611315201 (0.210) AC (LS)	40,000.00000	40,000.00	130,000.00000	130,000.00	15,796.00000	15,796.00
0180 0110 2 2 SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN 0.010 AC	500,000.00000	5,000.00	10,000.00000	100.00	255,200.00000	2,552.00
0185 0110 4 10 REMOVAL OF EXISTING CONCRETE 418.000 SY	88.00000	36,784.00	32.00000	13,376.00	11.00000	4,598.00
0190 0120 1 REGULAR EXCAVATION 191.000 CY	52.50000	10,027.50	55.00000	10,505.00	16.50000	3,151.50

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0195 0120 5 CHANNEL EXCAVATION 173.000 CY	80.00000	13,840.00	35.00000	6,055.00	40.06000	6,930.38
0200 0120 6 EMBANKMENT 25.000 CY	110.00000	2,750.00	100.00000	2,500.00	110.00000	2,750.00
0205 0160 4 TYPE B STABILIZATION 187.000 SY	15.00000	2,805.00	0.01000	1.87	16.50000	3,085.50
0210 0285709 OPTIONAL BASE, BASE GROUP 09 177.000 SY	32.50000	5,752.50	65.00000	11,505.00	148.50000	26,284.50
0215 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH 631.000 SY	11.00000	6,941.00	10.00000	6,310.00	10.54000	6,650.74
0220 0334 1 52 SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22 19.400 TN	530.00000	10,282.00	500.00000	9,700.00	276.70000	5,367.98
0225 0337 7 80 ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22 49.800 TN	425.00000	21,165.00	400.00000	19,920.00	231.04000	11,505.79
0230 0339 1 MISCELLANEOUS ASPHALT PAVEMENT 0.200 TN	1,000.00000	200.00	1,000.00000	200.00	9,900.00000	1,980.00
0235 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 135.000 SY	40.00000	5,400.00	50.00000	6,750.00	49.50000	6,682.50

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0240 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 41.000 SY	140.00000	5,740.00	150.00000	6,150.00	175.59000	7,199.19
0245 0526 1 1 PAVERS, ARCHITECTURAL, ROADWAY 199.000 SY	80.00000	15,920.00	100.00000	19,900.00	105.00000	20,895.00
0250 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK 35.000 SY	100.00000	3,500.00	100.00000	3,500.00	156.51000	5,477.85
0255 0527 2 DETECTABLE WARNINGS 61.000 SF	30.00000	1,830.00	25.00000	1,525.00	39.31000	2,397.91
0260 0530 4 6 ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6" 239.000 SY	160.00000	38,240.00	150.00000	35,850.00	133.27000	31,851.53
0265 0550 10210 FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES 609.000 LF	23.00000	14,007.00	21.00000	12,789.00	24.20000	14,737.80
0270 0550 10232 FENCING, TYPE B, 6.1-7.0, W/ VINYL COATING 43.000 LF	52.00000	2,236.00	55.00000	2,365.00	30.80000	1,324.40
0275 0550 10918 FENCING, SPECIAL TYPE, 0.0-5.0', RESET EXISTING 94.000 LF	20.00000	1,880.00	17.00000	1,598.00	157.51000	14,805.94
0280 0550 60211 FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING 1.000 EA	1,000.00000	1,000.00	1,650.00000	1,650.00	1,045.00000	1,045.00

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0285 0550 60212 2.000 EA FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING	1,800.00000	3,600.00	2,100.00000	4,200.00	1,375.00000	2,750.00
0290 0570 1 2 51.000 SY PERFORMANCE TURF, SOD	8.00000	408.00	10.00000	510.00	21.78000	1,110.78
0295 0710 11101 0.066 GM PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	750.00000	49.50	700.00000	46.20	935.00000	61.71
0300 0710 11123 602.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	0.75000	451.50	0.60000	361.20	0.66000	397.32
0305 0710 11125 14.000 LF PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	1.20000	16.80	1.10000	15.40	2.20000	30.80
0310 0710 11201 0.070 GM PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	800.00000	56.00	700.00000	49.00	935.00000	65.45
0315 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 42611315201	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0002 Roadway Section Totals:		**$674,562.10**		**$611,056.11**		**$537,376.44**

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0320 0700 1 11 — 3.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	600.00000	1,800.00	465.00000	1,395.00	605.00000	1,815.00
0325 0700 1 12 — 1.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	850.00000	850.00	1,215.00000	1,215.00	880.00000	880.00
0330 0700 1 60 — 4.000 AS SINGLE POST SIGN, REMOVE	125.00000	500.00	30.00000	120.00	110.00000	440.00
0335 0700 3501 — 4.000 EA SIGN PANEL, RELOCATE, UP TO 12 SF	85.00000	340.00	215.00000	860.00	88.00000	352.00
0340 0710 90 — (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42611315201	1,200.00000	1,200.00	900.00000	900.00	395.00000	395.00
0345 0711 11123 — 297.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	1.75000	519.75	1.60000	475.20	1.76000	522.72
0350 0711 11125 — 62.000 LF THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	3.50000	217.00	3.15000	195.30	3.30000	204.60
0355 0711 16101 — 0.054 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	3,000.00000	162.00	3,100.00000	167.40	4,125.00000	222.75

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0360 0711 16201 0.053 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" GM	3,100.00000	164.30	3,100.00000	164.30	4,125.00000	218.63
0365 0713103101 0.030 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES GM	24,000.00000	720.00	22,000.00000	660.00	29,040.00000	871.20
0370 0713103201 0.030 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES GM	24,000.00000	720.00	22,000.00000	660.00	29,040.00000	871.20
0003 Signing Section Totals:		**$7,193.05**		**$6,812.20**		**$6,793.10**
SECTION: 0004 Landscape / Peripheral						
0375 0580 1 2 (1.000) LANDSCAPE COMPLETE- LARGE PLANTS 42611315201 LS	6,000.00000	6,000.00	5,000.00000	5,000.00	9,020.00000	9,020.00
0004 Landscape / Peripheral Section Totals:		**$6,000.00**		**$5,000.00**		**$9,020.00**
SECTION: 0005 Utilities						
0380 0999 25 (1.000) INITIAL CONTINGENCY AMOUNT, DO NOT BID 42611315601 LS	260.00000	260.00	260.00000	260.00	260.00000	260.00
0385 1060 15 2.000 UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY EA	3,200.00000	6,400.00	1,000.00000	2,000.00	2,200.00000	4,400.00

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) CONDOTTE AMERICA, INC.		(2) HALLEY ENGINEERING CONTRACTORS, INC.		(3) ANZAC CONTRACTORS, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0005 Utilities						
0390 1080 24500 4.000 EA UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	1,200.00000	4,800.00	500.00000	2,000.00	550.00000	2,200.00
0005 Utilities Section Totals:		**$11,460.00**		**$4,260.00**		**$6,860.00**
Contract Grand Totals:		**$1,196,727.45**		**$1,232,167.68**		**1,293,710.95**

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (865.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 42611315201 876420	98,000.00000	98,000.00				
0010 0400 2 4 20.400 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	900.00000	18,360.00				
0015 0400 2 10 75.600 CY CONCRETE CLASS II, APPROACH SLABS	600.00000	45,360.00				
0020 0400 2 47 74.900 CY CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	600.00000	44,940.00				
0025 0400 4 5 61.600 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	2,400.00000	147,840.00				
0030 0400 7 151.000 SY BRIDGE DECK GROOVING, LESS THAN 8.5"	10.00000	1,510.00				
0035 0400148 4.200 CF PLAIN NEOPRENE BEARING PADS	640.00000	2,688.00				
0040 0415 1 4 13,091.000 LB REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	0.80000	10,472.80				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0045 0415 1 5 — 5,366.000 LB REINFORCING STEEL- BRIDGE SUBSTRUCTURE	1.00000	5,366.00				
0050 0415 1 9 — 14,466.000 LB REINFORCING STEEL- APPROACH SLABS	0.80000	11,572.80				
0055 0450 8 13 — 387.000 LF PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 55-57"	600.00000	232,200.00				
0060 0455 34304 — 1,040.000 LF PRESTRESSED CONCRETE PILING, INCLUDES 100% DYNAMIC TESTING- PROJECT 426113-1-52-01, SIZE 14"	300.00000	312,000.00				
0065 0458 1 11 — 98.000 LF BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	60.00000	5,880.00				
0070 0515 4 1 — 120.000 LF BULLET RAIL, SINGLE RAIL	47.00000	5,640.00				
0075 0521 5 4 — 120.000 LF CONCRETE TRAFFIC RAILING- BRIDGE, 32" VERTICAL FACE	165.00000	19,800.00				
0001 Structures Section Totals:		**$961,629.60**				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0080 0101 1 (1.000) LS MOBILIZATION 42611315201	150,000.00000	150,000.00				
0085 0102 1 (300.000) DA (LS) MAINTENANCE OF TRAFFIC 42611315201	12,773.00000	12,773.00				
0090 0102 2 1 (1.000) LS SPECIAL DETOUR 1 42611315201	125,000.00000	125,000.00				
0095 0102 3 1.700 CY COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	1,500.00000	2,550.00				
0100 0102 60 18,900.000 ED WORK ZONE SIGN	0.25000	4,725.00				
0105 0102 71 16 170.000 LF TEMPORARY BARRIER, F&I, FREE STANDING	23.00000	3,910.00				
0110 0102 71 26 170.000 LF TEMPORARY BARRIER, RELOCATE, FREE STANDING	8.60000	1,462.00				
0115 0102 74 1 1,995.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.13000	259.35				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0120 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6' 2,250.000 ED	0.35000	787.50				
0125 0102 74 7 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) 157.000 LF	9.00000	1,413.00				
0130 0102 89 1 TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION 4.000 LO	1,040.00000	4,160.00				
0135 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 418.000 ED	12.50000	5,225.00				
0140 0104 10 3 SEDIMENT BARRIER 477.000 LF	2.50000	1,192.50				
0145 0104 11 FLOATING TURBIDITY BARRIER 118.000 LF	18.00000	2,124.00				
0150 0104 18 INLET PROTECTION SYSTEM 4.000 EA	128.00000	512.00				
0155 0107 1 LITTER REMOVAL 0.460 AC	2,800.00000	1,288.00				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0160 0107 2 MOWING	0.100 AC	13,000.00000	1,300.00			
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 42611315201	(1.000) LS	7,520.00000	7,520.00			
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 42611315201	(1.000) LS	10,000.00000	10,000.00			
0175 0110 1 1 CLEARING & GRUBBING 42611315201	(0.210) AC (LS)	5,500.00000	5,500.00			
0180 0110 2 2 SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	0.010 AC	100,000.00000	1,000.00			
0185 0110 4 10 REMOVAL OF EXISTING CONCRETE	418.000 SY	31.00000	12,958.00			
0190 0120 1 REGULAR EXCAVATION	191.000 CY	22.00000	4,202.00			
0195 0120 5 CHANNEL EXCAVATION	173.000 CY	60.00000	10,380.00			

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0200 0120 6 EMBANKMENT 25.000 CY	30.00000	750.00				
0205 0160 4 TYPE B STABILIZATION 187.000 SY	18.00000	3,366.00				
0210 0285709 OPTIONAL BASE, BASE GROUP 09 177.000 SY	100.00000	17,700.00				
0215 0327 70 1 MILLING EXIST ASPH PAVT, 1" AVG DEPTH 631.000 SY	12.50000	7,887.50				
0220 0334 1 52 SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22 19.400 TN	550.00000	10,670.00				
0225 0337 7 80 ASPHALT CONCRETE FRICTION COURSE,TRAFFIC B, FC-9.5, PG 76-22 49.800 TN	512.00000	25,497.60				
0230 0339 1 MISCELLANEOUS ASPHALT PAVEMENT 0.200 TN	550.00000	110.00				
0235 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 135.000 SY	42.00000	5,670.00				
0240 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 41.000 SY	140.00000	5,740.00				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0245 0526 1 1 PAVERS, ARCHITECTURAL, ROADWAY 199.000 SY	160.00000	31,840.00				
0250 0526 1 2 PAVERS, ARCHITECTURAL, SIDEWALK 35.000 SY	106.00000	3,710.00				
0255 0527 2 DETECTABLE WARNINGS 61.000 SF	25.00000	1,525.00				
0260 0530 4 6 ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6" 239.000 SY	211.99000	50,665.61				
0265 0550 10210 FENCING, TYPE B, 0.0-5.0', STANDARD FEATURES 609.000 LF	23.00000	14,007.00				
0270 0550 10232 FENCING, TYPE B, 6.1-7.0, W/ VINYL COATING 43.000 LF	23.00000	989.00				
0275 0550 10918 FENCING, SPECIAL TYPE, 0.0-5.0', RESET EXISTING 94.000 LF	32.00000	3,008.00				
0280 0550 60211 FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING 1.000 EA	23.00000	23.00				
0285 0550 60212 FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING 2.000 EA	23.00000	46.00				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0290 0570 1 2	51.000	2.00000	102.00			
PERFORMANCE TURF, SOD	SY					
0295 0710 11101	0.066	1,330.00000	87.78			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM					
0300 0710 11123	602.000	1.00000	602.00			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF					
0305 0710 11125	14.000	2.00000	28.00			
PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF					
0310 0710 11201	0.070	1,260.00000	88.20			
PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM					
0315 0999 25	(1.000)	50,000.00000	50,000.00			
INITIAL CONTINGENCY AMOUNT, DO NOT BID 42611315201	LS					
0002 Roadway Section Totals:			**$604,354.04**			
SECTION: 0003 Signing						
0320 0700 1 11	3.000	555.00000	1,665.00			
SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS					

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0325 0700 1 12 SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF 1.000 AS	800.00000	800.00				
0330 0700 1 60 SINGLE POST SIGN, REMOVE 4.000 AS	100.00000	400.00				
0335 0700 3501 SIGN PANEL, RELOCATE, UP TO 12 SF 4.000 EA	80.00000	320.00				
0340 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 42611315201 (1.000) LS	1,500.00000	1,500.00				
0345 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT 297.000 LF	3.00000	891.00				
0350 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 62.000 LF	6.00000	372.00				
0355 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.054 GM	5,160.00000	278.64				
0360 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 0.053 GM	5,300.00000	280.90				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) LEAD ENGINEERING CONTRACTORS, LLC					
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0365 0713103101 0.030 GM PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	39,600.00000	1,188.00				
0370 0713103201 0.030 GM PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	39,600.00000	1,188.00				
0003 Signing Section Totals:		**$8,883.54**				
SECTION: 0004 Landscape / Peripheral						
0375 0580 1 2 (1.000) LS LANDSCAPE COMPLETE- LARGE PLANTS 42611315201	4,200.00000	4,200.00				
0004 Landscape / Peripheral Section Totals:		**$4,200.00**				
SECTION: 0005 Utilities						
0380 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 42611315601	260.00000	260.00				
0385 1060 15 2.000 EA UTILITY STRUCTURE, BELOW GROUND, ADJUST/MODIFY	1,400.00000	2,800.00				
0390 1080 24500 4.000 EA UTILITY FIXTURE, VALVE ASSEMBLY, ADJUST/MODIFY	3,300.00000	13,200.00				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

Line No / Item ID Item Description *( ) indicates item is bid as Lump Sum*	Alternate	Quantity Units	(4) LEAD ENGINEERING CONTRACTORS, LLC Unit Price	 Ext Amount	 Unit Price	 Ext Amount	 Unit Price	 Ext Amount
SECTION: 0005 Utilities								
0005 Utilities Section Totals:				**$16,260.00**				
Contract Grand Totals:				**$1,595,327.18**				

Letting: CT190130 January 30, 2019 **Call Order:** 015 **Contract:** T6445

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

Manager, Contracts Administration Office