Vendor Ranking

Letting: CT190925 September 25, 2019 10:30 AM
Call Order: 011
Contract: T4526
District: District 4
Counties: PALM BEACH
Fed Aid No: D419052B
Contract Time: 360 AVAILABLE DAYS
Project(s): 43689425201 (*)
Contract Desc: EL CLAIR RANCH RD

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	EBSARY FOUNDATION COMPANY	Responsive	Winning bid	$2,010,551.54	100.00%
2	CONE & GRAHAM, INC.	Responsive	Non-Winning Bid	$2,069,481.95	102.93%
3	CONDOTTE AMERICA, INC.	Responsive	Non-Winning Bid	$2,105,270.89	104.71%
4	ANZAC CONTRACTORS, INC.	Responsive	Non-Winning Bid	$2,269,978.69	112.90%
5	RUSSELL ENGINEERING, INC.	Responsive	Non-Winning Bid	$2,358,952.56	117.33%
6	LEAD ENGINEERING CONTRACTORS, LLC	Responsive	Non-Winning Bid	$2,382,856.28	118.52%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

District: District 4 **Counties:** PALM BEACH **Fed Aid No:** D419052B

Contract Time: 360 AVAILABLE DAYS **Project(s):** 43689425201 (*)

Contract Descr: EL CLAIR RANCH RD

The improvements under this contract consist of replacing the existing bridge #934419 with a 3 span bridge accommodating sidewalks and bike lanes. The proposed Typical Section Package will include two-12 foot lanes of travel, 5 foot designated bike lanes on both sides of roadway and a minimum of 6 foot sidewalks on both sides of roadway, raised from the roadway by at least 6 inches of curb. Sidewalks and bike paths shall not extend past the begin/end bridge. By request of the MPO, El Clair Ranch Rd. Bridge will be raised to meet Florida Greenbook (FG) navigational criteria.

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (5700.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 43689425201	211,000.00000	211,000.00	235,000.00000	235,000.00	232,000.00000	232,000.00
0010 0400 2 4 35.700 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	1,085.00000	38,734.50	1,000.00000	35,700.00	700.00000	24,990.00
0015 0400 2 10 77.200 CY CONCRETE CLASS II, APPROACH SLABS	610.00000	47,092.00	500.00000	38,600.00	500.00000	38,600.00
0020 0400 2 47 151.800 CY CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	660.00000	100,188.00	700.00000	106,260.00	800.00000	121,440.00
0025 0400 4 5 82.100 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	1,950.00000	160,095.00	950.00000	77,995.00	1,100.00000	90,310.00
0030 0400 9 600.000 SY BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER	17.00000	10,200.00	25.00000	15,000.00	25.00000	15,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0035 0400148 12.800 CF PLAIN NEOPRENE BEARING PADS	1,260.00000	16,128.00	800.00000	10,240.00	700.00000	8,960.00
0040 0415 1 4 35,322.000 LB REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	0.87000	30,730.14	1.50000	52,983.00	1.00000	35,322.00
0045 0415 1 5 9,850.000 LB REINFORCING STEEL- BRIDGE SUBSTRUCTURE	0.87000	8,569.50	1.50000	14,775.00	1.00000	9,850.00
0050 0415 1 9 15,015.000 LB REINFORCING STEEL- APPROACH SLABS	0.86000	12,912.90	1.50000	22,522.50	1.00000	15,015.00
0055 0450 8 14 1,135.000 LF PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 58-60"	248.00000	281,480.00	325.00000	368,875.00	220.00000	249,700.00
0060 0455 34 3 1,415.000 LF PRESTRESSED CONCRETE PILING, 18" SQ	120.00000	169,800.00	60.00000	84,900.00	100.00000	141,500.00
0065 0455137 1 24.000 EA LOAD TEST (DYNAMIC), INTERNAL GAUGES	2,545.00000	61,080.00	1,500.00000	36,000.00	1,800.00000	43,200.00
0070 0455143103 315.000 LF TEST PILES-PRESTRESSED CONCRETE, 100% DYNAMIC TESTING WITH INTERNAL GAUGES, 18" SQ	139.00000	43,785.00	300.00000	94,500.00	240.00000	75,600.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0075 0458 1 11 — 196.000 LF — BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	51.00000	9,996.00	50.00000	9,800.00	40.00000	7,840.00
0080 0521 5 5 — 312.000 LF — CONCRETE TRAFFIC RAILING- BRIDGE, 42" VERTICAL FACE	140.00000	43,680.00	100.00000	31,200.00	125.00000	39,000.00
0085 0530 1 — 30.000 CY — RIPRAP, SAND-CEMENT	815.00000	24,450.00	400.00000	12,000.00	825.00000	24,750.00
0090 0530 3 3 — 1,276.600 TN — RIPRAP- RUBBLE, BANK AND SHORE	90.00000	114,894.00	130.00000	165,958.00	90.00000	114,894.00
0095 0530 74 — 551.700 TN — BEDDING STONE	130.00000	71,721.00	140.00000	77,238.00	90.00000	49,653.00
0001 Structures Section Totals:		**$1,456,536.04**		**$1,489,546.50**		**$1,337,624.00**
SECTION: 0002 Roadway						
0100 0101 1 — (1.000) LS — MOBILIZATION 43689425201	50,000.00000	50,000.00	200,000.00000	200,000.00	200,000.00000	200,000.00
0105 0102 1 — (360.000) DA (LS) — MAINTENANCE OF TRAFFIC 43689425201	3,000.00000	3,000.00	5,000.00000	5,000.00	100,000.00000	100,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0110 0102 3 COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE 58.100 CY	145.00000	8,424.50	50.00000	2,905.00	110.00000	6,391.00
0115 0102 4 PEDESTRIAN SPECIAL DETOUR 43689425201 (118.000) SY (LS)	16,000.00000	16,000.00	2,000.00000	2,000.00	10,000.00000	10,000.00
0120 0102 60 WORK ZONE SIGN 51,840.000 ED	0.25000	12,960.00	0.15000	7,776.00	0.22000	11,404.80
0125 0102 71 16 TEMPORARY BARRIER, F&I, FREE STANDING 75.000 LF	55.00000	4,125.00	25.00000	1,875.00	40.00000	3,000.00
0130 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 7,200.000 ED	0.12000	864.00	0.15000	1,080.00	0.11000	792.00
0135 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6' 1,440.000 ED	0.25000	360.00	0.20000	288.00	0.20000	288.00
0140 0102 74 7 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) 216.000 LF	5.00000	1,080.00	4.00000	864.00	5.00000	1,080.00
0145 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 748.000 ED	11.00000	8,228.00	8.00000	5,984.00	10.00000	7,480.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0150 0104 10 3 SEDIMENT BARRIER 794.000 LF	4.00000	3,176.00	10.00000	7,940.00	2.20000	1,746.80
0155 0104 11 FLOATING TURBIDITY BARRIER 165.000 LF	33.00000	5,445.00	30.00000	4,950.00	17.00000	2,805.00
0160 0104 18 INLET PROTECTION SYSTEM 2.000 EA	1,300.00000	2,600.00	300.00000	600.00	165.00000	330.00
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 43689425201 (1.000) LS	5,500.00000	5,500.00	2,000.00000	2,000.00	10,000.00000	10,000.00
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 43689425201 (1.000) LS	9,500.00000	9,500.00	5,000.00000	5,000.00	15,000.00000	15,000.00
0175 0110 1 1 CLEARING & GRUBBING 43689425201 (0.850) AC (LS)	20,000.00000	20,000.00	40,000.00000	40,000.00	100,000.00000	100,000.00
0180 0110 4 10 REMOVAL OF EXISTING CONCRETE 465.000 SY	31.00000	14,415.00	50.00000	23,250.00	23.00000	10,695.00
0185 0120 1 REGULAR EXCAVATION 295.500 CY	44.00000	13,002.00	25.00000	7,387.50	14.00000	4,137.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0190 0120 5 1,452.800 CY CHANNEL EXCAVATION	60.00000	87,168.00	25.00000	36,320.00	18.00000	26,150.40
0195 0120 6 403.300 CY EMBANKMENT	50.00000	20,165.00	10.50000	4,234.65	32.00000	12,905.60
0200 0160 4 2,081.000 SY TYPE B STABILIZATION	5.00000	10,405.00	17.00000	35,377.00	4.00000	8,324.00
0205 0285701 451.000 SY OPTIONAL BASE, BASE GROUP 01	25.00000	11,275.00	28.00000	12,628.00	19.00000	8,569.00
0210 0285707 1,202.000 SY OPTIONAL BASE, BASE GROUP 07	33.00000	39,666.00	8.00000	9,616.00	23.00000	27,646.00
0215 0286 1 319.000 SY TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	33.00000	10,527.00	40.00000	12,760.00	45.00000	14,355.00
0220 0334 1 13 105.300 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	250.00000	26,325.00	175.00000	18,427.50	195.00000	20,533.50
0225 0337 7 82 84.900 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	250.00000	21,225.00	220.00000	18,678.00	285.00000	24,196.50
0230 0339 1 6.000 TN MISCELLANEOUS ASPHALT PAVEMENT	1,000.00000	6,000.00	500.00000	3,000.00	870.00000	5,220.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0235 0521 72 40 SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT 26.000 LF	160.00000	4,160.00	440.00000	11,440.00	700.00000	18,200.00
0240 0522 1 CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK 97.000 SY	54.00000	5,238.00	70.00000	6,790.00	40.00000	3,880.00
0245 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 26.000 SY	60.00000	1,560.00	85.00000	2,210.00	59.00000	1,534.00
0250 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 145.000 LF	72.00000	10,440.00	14.50000	2,102.50	18.00000	2,610.00
0255 0536 7 3 SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT 3.000 EA	230.00000	690.00	95.00000	285.00	260.00000	780.00
0260 0536 73 GUARDRAIL REMOVAL 208.000 LF	10.00000	2,080.00	2.10000	436.80	5.00000	1,040.00
0265 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 2.000 EA	2,000.00000	4,000.00	975.00000	1,950.00	1,400.00000	2,800.00
0270 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 2.000 EA	4,500.00000	9,000.00	2,600.00000	5,200.00	3,200.00000	6,400.00
0275 0546 71 1 RAISED RUMBLE STRIP SET-PERMANENT 1.000 EA	9,000.00000	9,000.00	1,060.00000	1,060.00	1,070.00000	1,070.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0280 0550 10220 52.000 LF FENCING, TYPE B, 5.1-6.0', STANDARD	90.00000	4,680.00	40.00000	2,080.00	22.00000	1,144.00
0285 0570 1 2 2,063.000 SY PERFORMANCE TURF, SOD	9.00000	18,567.00	5.50000	11,346.50	4.00000	8,252.00
0290 0999 16 (1.000) LS PARTNERING, DO NOT BID 43689425201	6,000.00000	6,000.00	6,000.00000	6,000.00	6,000.00000	6,000.00
0295 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 43689425201	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0002 Roadway Section Totals:		**$536,850.50**		**$570,841.45**		**$736,759.60**
SECTION: 0003 Signing						
0300 0700 1 11 5.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	110.00000	550.00	415.00000	2,075.00	435.00000	2,175.00
0305 0700 1 60 5.000 AS SINGLE POST SIGN, REMOVE	330.00000	1,650.00	31.00000	155.00	55.00000	275.00
0310 0710 90 (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43689425201	5,100.00000	5,100.00	1,500.00000	1,500.00	20,000.00000	20,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) EBSARY FOUNDATION COMPANY		(2) CONE & GRAHAM, INC.		(3) CONDOTTE AMERICA, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0315 0711 11141 — 0.049 GM THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	34,000.00000	1,666.00	2,400.00000	117.60	3,490.00000	171.01
0320 0711 16101 — 0.161 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	13,000.00000	2,093.00	6,400.00000	1,030.40	10,620.00000	1,709.82
0325 0711 16201 — 0.147 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	14,000.00000	2,058.00	6,400.00000	940.80	10,180.00000	1,496.46
0330 0713103101 — 0.046 GM PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	44,000.00000	2,024.00	35,600.00000	1,637.60	55,000.00000	2,530.00
0335 0713103201 — 0.046 GM PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	44,000.00000	2,024.00	35,600.00000	1,637.60	55,000.00000	2,530.00
0003 Signing Section Totals:		**$17,165.00**		**$9,094.00**		**$30,887.29**
Contract Grand Totals:		**$2,010,551.54**		**$2,069,481.95**		**2,105,270.89**

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (5700.000) REMOVAL OF EXISTING STRUCTURES/BRIDGES 43689425201 SF (LS)	95,480.00000	95,480.00	92,700.00000	92,700.00	400,000.00000	400,000.00
0010 0400 2 4 35.700 CONC CLASS II, BRIDGE SUPERSTRUCTURE CY	907.73000	32,405.96	900.00000	32,130.00	600.00000	21,420.00
0015 0400 2 10 77.200 CONCRETE CLASS II, APPROACH SLABS CY	442.99000	34,198.83	413.00000	31,883.60	620.00000	47,864.00
0020 0400 2 47 151.800 CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE CY	1,053.19000	159,874.24	635.00000	96,393.00	900.00000	136,620.00
0025 0400 4 5 82.100 CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE CY	1,311.69000	107,689.75	913.00000	74,957.30	1,300.00000	106,730.00
0030 0400 9 600.000 BRIDGE DECK GROOVING & PLANING, DECK 8.5" AND GREATER SY	27.35000	16,410.00	50.00000	30,000.00	12.11000	7,266.00
0035 0400148 12.800 PLAIN NEOPRENE BEARING PADS CF	644.53000	8,249.98	1,355.00000	17,344.00	650.00000	8,320.00
0040 0415 1 4 35,322.000 REINFORCING STEEL - BRIDGE SUPERSTRUCTURE LB	0.97000	34,262.34	0.85000	30,023.70	0.85000	30,023.70

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0045 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 9,850.000 LB	0.97000	9,554.50	0.95000	9,357.50	1.10000	10,835.00
0050 0415 1 9 REINFORCING STEEL- APPROACH SLABS 15,015.000 LB	0.97000	14,564.55	0.85000	12,762.75	0.80000	12,012.00
0055 0450 8 14 PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 58-60" 1,135.000 LF	254.41000	288,755.35	285.00000	323,475.00	220.00000	249,700.00
0060 0455 34 3 PRESTRESSED CONCRETE PILING, 18" SQ 1,415.000 LF	139.82000	197,845.30	96.00000	135,840.00	200.00000	283,000.00
0065 0455137 1 LOAD TEST (DYNAMIC), INTERNAL GAUGES 24.000 EA	3,006.67000	72,160.08	2,050.00000	49,200.00	520.00000	12,480.00
0070 0455143103 TEST PILES-PRESTRESSED CONCRETE, 100% DYNAMIC TESTING WITH INTERNAL GAUGES, 18" SQ 315.000 LF	332.44000	104,718.60	285.00000	89,775.00	300.00000	94,500.00
0075 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD 196.000 LF	96.67000	18,947.32	40.00000	7,840.00	40.00000	7,840.00
0080 0521 5 5 CONCRETE TRAFFIC RAILING- BRIDGE, 42" VERTICAL FACE 312.000 LF	143.85000	44,881.20	68.00000	21,216.00	100.00000	31,200.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0085 0530 1 RIPRAP, SAND-CEMENT 30.000 CY	898.33000	26,949.90	555.00000	16,650.00	1,450.00000	43,500.00
0090 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE 1,276.600 TN	103.07000	131,579.16	145.00000	185,107.00	100.00000	127,660.00
0095 0530 74 BEDDING STONE 551.700 TN	55.00000	30,343.50	130.00000	71,721.00	160.00000	88,272.00
0001 Structures Section Totals:		**$1,428,870.56**		**$1,328,375.85**		**$1,719,242.70**
SECTION: 0002 Roadway						
0100 0101 1 MOBILIZATION 43689425201 (1.000) LS	203,461.50000	203,461.50	230,055.00000	230,055.00	213,000.00000	213,000.00
0105 0102 1 MAINTENANCE OF TRAFFIC 43689425201 (360.000) DA (LS)	110,269.50000	110,269.50	413,055.00000	413,055.00	20,000.00000	20,000.00
0110 0102 3 COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE 58.100 CY	69.30000	4,026.33	0.01000	0.58	60.00000	3,486.00
0115 0102 4 PEDESTRIAN SPECIAL DETOUR 43689425201 (118.000) SY (LS)	14,630.00000	14,630.00	13,055.00000	13,055.00	6,000.00000	6,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0120 0102 60 WORK ZONE SIGN 51,840.000 ED	0.28000	14,515.20	0.20000	10,368.00	0.20000	10,368.00
0125 0102 71 16 TEMPORARY BARRIER, F&I, FREE STANDING 75.000 LF	38.50000	2,887.50	100.00000	7,500.00	24.00000	1,800.00
0130 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 7,200.000 ED	0.28000	2,016.00	0.35000	2,520.00	0.10000	720.00
0135 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6' 1,440.000 ED	0.55000	792.00	0.35000	504.00	0.18000	259.20
0140 0102 74 7 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) 216.000 LF	7.70000	1,663.20	10.00000	2,160.00	4.00000	864.00
0145 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 748.000 ED	11.00000	8,228.00	9.00000	6,732.00	9.00000	6,732.00
0150 0104 10 3 SEDIMENT BARRIER 794.000 LF	2.20000	1,746.80	2.00000	1,588.00	7.00000	5,558.00
0155 0104 11 FLOATING TURBIDITY BARRIER 165.000 LF	20.00000	3,300.00	20.00000	3,300.00	40.00000	6,600.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0160 0104 18 INLET PROTECTION SYSTEM 2.000 EA	550.00000	1,100.00	75.00000	150.00	200.00000	400.00
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 43689425201 (1.000) LS	13,200.00000	13,200.00	1,355.00000	1,355.00	5,550.00000	5,550.00
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 43689425201 (1.000) LS	32,945.00000	32,945.00	5,513.00000	5,513.00	5,350.00000	5,350.00
0175 0110 1 1 CLEARING & GRUBBING 43689425201 (0.850) AC (LS)	33,550.00000	33,550.00	55,413.00000	55,413.00	50,000.00000	50,000.00
0180 0110 4 10 REMOVAL OF EXISTING CONCRETE 465.000 SY	33.00000	15,345.00	13.55000	6,300.75	40.00000	18,600.00
0185 0120 1 REGULAR EXCAVATION 295.500 CY	55.00000	16,252.50	5.00000	1,477.50	30.00000	8,865.00
0190 0120 5 CHANNEL EXCAVATION 1,452.800 CY	35.28000	51,254.78	30.00000	43,584.00	25.00000	36,320.00
0195 0120 6 EMBANKMENT 403.300 CY	41.80000	16,857.94	20.00000	8,066.00	55.00000	22,181.50

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0200 0160 4 2,081.000 SY TYPE B STABILIZATION	8.80000	18,312.80	7.50000	15,607.50	18.00000	37,458.00
0205 0285701 451.000 SY OPTIONAL BASE, BASE GROUP 01	20.90000	9,425.90	25.00000	11,275.00	27.00000	12,177.00
0210 0285707 1,202.000 SY OPTIONAL BASE, BASE GROUP 07	35.20000	42,310.40	25.00000	30,050.00	30.00000	36,060.00
0215 0286 1 319.000 SY TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	71.50000	22,808.50	25.00000	7,975.00	28.00000	8,932.00
0220 0334 1 13 105.300 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	313.50000	33,011.55	165.00000	17,374.50	185.00000	19,480.50
0225 0337 7 82 84.900 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	357.50000	30,351.75	205.00000	17,404.50	237.00000	20,121.30
0230 0339 1 6.000 TN MISCELLANEOUS ASPHALT PAVEMENT	440.00000	2,640.00	600.00000	3,600.00	600.00000	3,600.00
0235 0521 72 40 26.000 LF SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	595.48000	15,482.48	400.00000	10,400.00	190.00000	4,940.00
0240 0522 1 97.000 SY CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	104.50000	10,136.50	55.00000	5,335.00	40.00000	3,880.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0245 0522 2 CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK 26.000 SY	165.00000	4,290.00	113.00000	2,938.00	43.00000	1,118.00
0250 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 145.000 LF	22.00000	3,190.00	15.00000	2,175.00	16.00000	2,320.00
0255 0536 7 3 SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT 3.000 EA	220.00000	660.00	100.00000	300.00	110.00000	330.00
0260 0536 73 GUARDRAIL REMOVAL 208.000 LF	5.50000	1,144.00	2.00000	416.00	2.20000	457.60
0265 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 2.000 EA	1,320.00000	2,640.00	950.00000	1,900.00	1,040.00000	2,080.00
0270 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 2.000 EA	3,300.00000	6,600.00	2,650.00000	5,300.00	2,900.00000	5,800.00
0275 0546 71 1 RAISED RUMBLE STRIP SET-PERMANENT 1.000 EA	1,100.00000	1,100.00	748.00000	748.00	4,220.00000	4,220.00
0280 0550 10220 FENCING, TYPE B, 5.1-6.0', STANDARD 52.000 LF	82.50000	4,290.00	35.00000	1,820.00	23.00000	1,196.00
0285 0570 1 2 PERFORMANCE TURF, SOD 2,063.000 SY	6.30000	12,996.90	10.00000	20,630.00	4.00000	8,252.00

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0290 0999 16 (1.000) LS PARTNERING, DO NOT BID 43689425201	6,000.00000	6,000.00	6,000.00000	6,000.00	6,000.00000	6,000.00
0295 0999 25 (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 43689425201	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0002 Roadway Section Totals:		**$825,432.03**		**$1,023,945.33**		**$651,076.10**
SECTION: 0003 Signing						
0300 0700 1 11 5.000 AS SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	550.00000	2,750.00	375.00000	1,875.00	420.00000	2,100.00
0305 0700 1 60 5.000 AS SINGLE POST SIGN, REMOVE	82.50000	412.50	5.00000	25.00	30.00000	150.00
0310 0710 90 (1.000) LS PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43689425201	3,850.00000	3,850.00	900.00000	900.00	8,500.00000	8,500.00
0315 0711 11141 0.049 GM THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	4,400.00000	215.60	1,225.00000	60.03	1,180.00000	57.82
0320 0711 16101 0.161 GM THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	11,000.00000	1,771.00	4,355.00000	701.16	4,200.00000	676.20

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) ANZAC CONTRACTORS, INC.		(5) RUSSELL ENGINEERING, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0325 0711 16201 0.147 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" GM	11,000.00000	1,617.00	4,355.00000	640.19	4,300.00000	632.10
0330 0713103101 0.046 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES GM	55,000.00000	2,530.00	26,413.00000	1,215.00	4,580.00000	210.68
0335 0713103201 0.046 PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES GM	55,000.00000	2,530.00	26,413.00000	1,215.00	4,580.00000	210.68
0003 Signing Section Totals:		**$15,676.10**		**$6,631.38**		**$12,537.48**
Contract Grand Totals:		**$2,269,978.69**		**$2,358,952.56**		**2,382,856.28**

Letting: CT190925 September 25, 2019 **Call Order:** 011 **Contract:** T4526

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

Manager, Contracts Administration Office