Vendor Ranking

Letting: CT190925 September 25, 2019 10:30 AM **Call Order:** 012 **Contract:** T4527

District: District 4 **Counties:** PALM BEACH **Fed Aid No:** D419053B

Contract Time: 323 AVAILABLE DAYS **Project(s):** 43689445201 (*)

Contract Desc: SEMINOLE DR

Rank	Vendor	Bid Type	Bid Status	Total Bid	Percent Of Low Bid
1	AMERICAN EMPIRE BUILDERS, INC.	Responsive	Winning bid	$1,334,387.85	100.00%
2	EBSARY FOUNDATION COMPANY	Responsive	Non-Winning Bid	$1,614,858.43	121.02%
3	CONE & GRAHAM, INC.	Responsive	Non-Winning Bid	$1,687,217.30	126.44%
4	CONDOTTE AMERICA, INC.	Responsive	Non-Winning Bid	$1,794,092.10	134.45%
5	ANZAC CONTRACTORS, INC.	Responsive	Non-Winning Bid	$1,991,295.00	149.23%
6	LEAD ENGINEERING CONTRACTORS, LLC	Responsive	Non-Winning Bid	$2,175,039.12	163.00%

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

District: District 4 **Counties:** PALM BEACH **Fed Aid No:** D419053B

Contract Time: 323 AVAILABLE DAYS **Project(s):** 43689445201 (*)

Contract Descr: SEMINOLE DR

The improvements under this contract consist of replacing the bridge on Seminole with a single span bridge accommodating sidewalks and bike lanes. The proposed Typical Section Package will include two-12 foot lanes of travel, 5 foot designated bike lanes on both sides of roadway and a minimum of 6 foot sidewalks on both sides of roadway, raised from the roadway by at least 6 inches of curb. Sidewalks and bike paths shall not extend past the begin/end bridge.

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (2653.000) SF (LS) REMOVAL OF EXISTING STRUCTURES/BRIDGES 43689445201	113,502.72000	113,502.72	195,000.00000	195,000.00	234,000.00000	234,000.00
0010 0400 2 4 10.500 CY CONC CLASS II, BRIDGE SUPERSTRUCTURE	911.42000	9,569.91	1,057.00000	11,098.50	2,000.00000	21,000.00
0015 0400 2 10 29.900 CY CONCRETE CLASS II, APPROACH SLABS	874.19000	26,138.28	900.00000	26,910.00	2,000.00000	59,800.00
0020 0400 2 47 45.700 CY CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE	1,568.77000	71,692.79	1,450.00000	66,265.00	2,000.00000	91,400.00
0025 0400 4 5 67.300 CY CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	1,099.48000	73,995.00	1,165.00000	78,404.50	2,000.00000	134,600.00
0030 0400 7 176.000 SY BRIDGE DECK GROOVING, LESS THAN 8.5"	17.00000	2,992.00	37.00000	6,512.00	20.00000	3,520.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0035 0400148 4.300 CF PLAIN NEOPRENE BEARING PADS	1,413.00000	6,075.90	1,620.00000	6,966.00	1,000.00000	4,300.00
0040 0415 1 4 10,439.000 LB REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	1.05000	10,960.95	1.35000	14,092.65	2.50000	26,097.50
0045 0415 1 5 5,872.000 LB REINFORCING STEEL- BRIDGE SUBSTRUCTURE	1.05000	6,165.60	1.35000	7,927.20	2.50000	14,680.00
0050 0415 1 9 5,384.000 LB REINFORCING STEEL- APPROACH SLABS	1.05000	5,653.20	1.35000	7,268.40	2.50000	13,460.00
0055 0450 8 14 331.000 LF PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 58-60"	355.83000	117,779.73	312.00000	103,272.00	520.00000	172,120.00
0060 0455111 84.000 LF CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION	22.00000	1,848.00	53.00000	4,452.00	40.00000	3,360.00
0065 0455112101 1,158.000 LF AUGER GROUTED PILE, 24" DIAMETER, PROJECT 436894-4-52-01	142.49000	165,003.42	219.36000	254,018.88	70.00000	81,060.00
0070 0455119103 1.000 EA LOAD TEST-STATIC, COMPRESSION,101-600 TONS	77,000.00000	77,000.00	88,000.00000	88,000.00	75,000.00000	75,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0075 0455148901 THERMAL INTEGRITY TESTING FOR AUGER CAST PILES, PROJECT 436894-4-52-01 15.000 EA	3,300.00000	49,500.00	8,300.00000	124,500.00	4,000.00000	60,000.00
0080 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD 98.000 LF	35.00000	3,430.00	39.00000	3,822.00	50.00000	4,900.00
0085 0521 5 5 CONCRETE TRAFFIC RAILING- BRIDGE, 42" VERTICAL FACE 98.000 LF	175.19000	17,168.62	204.00000	19,992.00	150.00000	14,700.00
0090 0530 1 RIPRAP, SAND-CEMENT 30.000 CY	715.00000	21,450.00	860.00000	25,800.00	500.00000	15,000.00
0095 0530 3 3 RIPRAP- RUBBLE, BANK AND SHORE 330.200 TN	143.00000	47,218.60	99.00000	32,689.80	140.00000	46,228.00
0100 0530 74 BEDDING STONE 208.600 TN	93.50000	19,504.10	142.00000	29,621.20	155.00000	32,333.00
0001 Structures Section Totals:		**$846,648.82**		**$1,106,612.13**		**$1,107,558.50**
SECTION: 0002 Roadway						
0105 0101 1 MOBILIZATION 43689445201 (1.000) LS	116,000.00000	116,000.00	113,000.00000	113,000.00	220,000.00000	220,000.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0110 0102 1 (323.000) DA (LS) MAINTENANCE OF TRAFFIC 43689445201	98,483.00000	98,483.00	6,000.00000	6,000.00	10,000.00000	10,000.00
0115 0102 3 36.100 CY COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	107.80000	3,891.58	55.00000	1,985.50	50.00000	1,805.00
0120 0102 60 28,101.000 ED WORK ZONE SIGN	0.22000	6,182.22	0.26000	7,306.26	0.15000	4,215.15
0125 0102 71 16 138.000 LF TEMPORARY BARRIER, F&I, FREE STANDING	17.60000	2,428.80	30.00000	4,140.00	25.00000	3,450.00
0130 0102 74 1 6,460.000 ED CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	0.18000	1,162.80	0.21000	1,356.60	0.15000	969.00
0135 0102 74 2 1,292.000 ED CHANNELIZING DEVICE, TYPE III, 6'	0.31000	400.52	0.37000	478.04	0.20000	258.40
0140 0102 74 7 178.000 LF CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	6.60000	1,174.80	8.00000	1,424.00	4.00000	712.00
0145 0102 99 674.000 ED PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	11.00000	7,414.00	13.00000	8,762.00	8.00000	5,392.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0150 0104 10 3 SEDIMENT BARRIER 419.000 LF	2.50000	1,047.50	3.00000	1,257.00	10.00000	4,190.00
0155 0104 11 FLOATING TURBIDITY BARRIER 50.000 LF	100.00000	5,000.00	13.00000	650.00	30.00000	1,500.00
0160 0104 18 INLET PROTECTION SYSTEM 3.000 EA	165.00000	495.00	147.00000	441.00	300.00000	900.00
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 43689445201 (1.000) LS	4,290.00000	4,290.00	8,000.00000	8,000.00	5,000.00000	5,000.00
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 43689445201 (1.000) LS	7,865.00000	7,865.00	5,500.00000	5,500.00	10,000.00000	10,000.00
0175 0110 1 1 CLEARING & GRUBBING 43689445201 (0.500) AC (LS)	7,700.00000	7,700.00	6,000.00000	6,000.00	30,000.00000	30,000.00
0180 0110 2 2 SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN 0.030 AC	1,980.00000	59.40	308,000.00000	9,240.00	110,000.00000	3,300.00
0185 0110 4 10 REMOVAL OF EXISTING CONCRETE 139.000 SY	27.50000	3,822.50	50.00000	6,950.00	50.00000	6,950.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0190 0110 7 1 MAILBOX, F&I SINGLE 2.000 EA	209.00000	418.00	850.00000	1,700.00	200.00000	400.00
0195 0120 1 REGULAR EXCAVATION 353.500 CY	38.50000	13,609.75	48.00000	16,968.00	25.00000	8,837.50
0200 0120 5 CHANNEL EXCAVATION 278.500 CY	41.80000	11,641.30	80.00000	22,280.00	50.00000	13,925.00
0205 0120 6 EMBANKMENT 588.100 CY	22.00000	12,938.20	52.00000	30,581.20	10.50000	6,175.05
0210 0160 4 TYPE B STABILIZATION 1,520.000 SY	8.80000	13,376.00	4.00000	6,080.00	17.00000	25,840.00
0215 0285701 OPTIONAL BASE, BASE GROUP 01 274.000 SY	18.70000	5,123.80	28.00000	7,672.00	28.00000	7,672.00
0220 0285707 OPTIONAL BASE, BASE GROUP 07 878.000 SY	22.00000	19,316.00	36.00000	31,608.00	28.00000	24,584.00
0225 0286 1 TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS 221.000 SY	27.50000	6,077.50	36.00000	7,956.00	50.00000	11,050.00
0230 0334 1 13 SUPERPAVE ASPHALTIC CONC, TRAFFIC C 80.300 TN	126.50000	10,157.95	277.00000	22,243.10	205.00000	16,461.50

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0235 0337 7 82 — 60.100 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	137.50000	8,263.75	277.00000	16,647.70	280.00000	16,828.00
0240 0339 1 — 8.200 TN MISCELLANEOUS ASPHALT PAVEMENT	242.00000	1,984.40	277.00000	2,271.40	450.00000	3,690.00
0245 0400 1 2 — 3.500 CY CONCRETE CLASS I, ENDWALLS	1,650.00000	5,775.00	5,000.00000	17,500.00	1,700.00000	5,950.00
0250 0425 1523 — 2.000 EA INLETS, DT BOT, TYPE C,JBOT, <10'	6,820.00000	13,640.00	5,500.00000	11,000.00	7,850.00000	15,700.00
0255 0430175115 — 49.000 LF PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	137.50000	6,737.50	190.00000	9,310.00	290.00000	14,210.00
0260 0430175124 — 24.000 LF PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	214.50000	5,148.00	245.00000	5,880.00	440.00000	10,560.00
0265 0521 72 40 — 13.000 LF SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	280.00000	3,640.00	925.00000	12,025.00	440.00000	5,720.00
0270 0536 1 0 — 208.000 LF GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	16.50000	3,432.00	43.00000	8,944.00	14.50000	3,016.00
0275 0536 7 3 — 4.000 EA SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT	110.00000	440.00	185.00000	740.00	95.00000	380.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0280 0536 8 12 — 3.000 EA APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2	2,530.00000	7,590.00	3,075.00000	9,225.00	2,300.00000	6,900.00
0285 0536 73 — 54.000 LF GUARDRAIL REMOVAL	2.20000	118.80	12.00000	648.00	2.10000	113.40
0290 0536 85 20 — 1.000 EA GUARDRAIL END TREATMENT-TRAILING ANCHORAGE	1,045.00000	1,045.00	1,220.00000	1,220.00	975.00000	975.00
0295 0536 85 24 — 2.000 EA GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL	2,915.00000	5,830.00	3,300.00000	6,600.00	2,600.00000	5,200.00
0300 0570 1 2 — 707.000 SY PERFORMANCE TURF, SOD	3.58000	2,531.06	6.00000	4,242.00	5.50000	3,888.50
0305 0999 16 — (1.000) LS PARTNERING, DO NOT BID 43689445201	6,000.00000	6,000.00	6,000.00000	6,000.00	6,000.00000	6,000.00
0310 0999 25 — (1.000) LS INITIAL CONTINGENCY AMOUNT, DO NOT BID 43689445201	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0002 Roadway Section Totals:		**$482,251.13**		**$491,831.80**		**$572,717.50**

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0315 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF 6.000 AS	385.00000	2,310.00	526.00000	3,156.00	415.00000	2,490.00
0320 0700 1 60 SINGLE POST SIGN, REMOVE 6.000 AS	22.00000	132.00	40.00000	240.00	31.00000	186.00
0325 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43689445201 (1.000) LS	1,153.90000	1,153.90	5,000.00000	5,000.00	1,500.00000	1,500.00
0330 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT 50.000 LF	1.82000	91.00	7.00000	350.00	4.75000	237.50
0335 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 26.000 LF	3.63000	94.38	14.00000	364.00	13.50000	351.00
0340 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.022 GM	1,485.00000	32.67	31,000.00000	682.00	4,800.00000	105.60
0345 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.099 GM	4,290.00000	424.71	7,500.00000	742.50	6,400.00000	633.60
0350 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 0.080 GM	4,290.00000	343.20	15,000.00000	1,200.00	6,400.00000	512.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(1) AMERICAN EMPIRE BUILDERS, INC.		(2) EBSARY FOUNDATION COMPANY		(3) CONE & GRAHAM, INC.	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0355 0713103101 0.013 GM PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	34,848.00000	453.02	180,000.00000	2,340.00	35,600.00000	462.80
0360 0713103201 0.013 GM PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	34,848.00000	453.02	180,000.00000	2,340.00	35,600.00000	462.80
0003 Signing Section Totals:		**$5,487.90**		**$16,414.50**		**$6,941.30**
Contract Grand Totals:		**$1,334,387.85**		**$1,614,858.43**		**1,687,217.30**

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0005 0110 3 (2653.000) REMOVAL OF EXISTING STRUCTURES/BRIDGES 43689445201 SF (LS)	185,000.00000	185,000.00	110,000.00000	110,000.00	300,000.00000	300,000.00
0010 0400 2 4 10.500 CONC CLASS II, BRIDGE SUPERSTRUCTURE CY	960.00000	10,080.00	1,666.00000	17,493.00	1,100.00000	11,550.00
0015 0400 2 10 29.900 CONCRETE CLASS II, APPROACH SLABS CY	560.00000	16,744.00	673.00000	20,122.70	510.00000	15,249.00
0020 0400 2 47 45.700 CONCRETE CLASS II, CAST-IN-PLACE TOPPING WITH SHRINKAGE REDUCING ADMIXTURE CY	960.00000	43,872.00	1,834.00000	83,813.80	1,100.00000	50,270.00
0025 0400 4 5 67.300 CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE CY	640.00000	43,072.00	1,491.00000	100,344.30	1,800.00000	121,140.00
0030 0400 7 176.000 BRIDGE DECK GROOVING, LESS THAN 8.5" SY	35.00000	6,160.00	70.00000	12,320.00	25.61000	4,507.36
0035 0400148 4.300 PLAIN NEOPRENE BEARING PADS CF	1,150.00000	4,945.00	1,151.00000	4,949.30	1,500.00000	6,450.00
0040 0415 1 4 10,439.000 REINFORCING STEEL - BRIDGE SUPERSTRUCTURE LB	1.10000	11,482.90	1.00000	10,439.00	1.70000	17,746.30

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0045 0415 1 5 REINFORCING STEEL- BRIDGE SUBSTRUCTURE 5,872.000 LB	1.10000	6,459.20	1.00000	5,872.00	1.75000	10,276.00
0050 0415 1 9 REINFORCING STEEL- APPROACH SLABS 5,384.000 LB	1.10000	5,922.40	1.00000	5,384.00	1.60000	8,614.40
0055 0450 8 14 PRESTRESSED BEAM: FLORIDA SLAB BEAM, BEAM DEPTH 12", WIDTH 58-60" 331.000 LF	257.50000	85,232.50	336.00000	111,216.00	250.00000	82,750.00
0060 0455111 CORE-PILOT HOLE, DRILLED SHAFT EXCAVATION 84.000 LF	98.00000	8,232.00	66.00000	5,544.00	1,285.00000	107,940.00
0065 0455112101 AUGER GROUTED PILE, 24" DIAMETER, PROJECT 436894-4-52-01 1,158.000 LF	195.00000	225,810.00	132.00000	152,856.00	350.00000	405,300.00
0070 0455119103 LOAD TEST-STATIC, COMPRESSION,101-600 TONS 1.000 EA	162,100.00000	162,100.00	307,725.00000	307,725.00	2,500.00000	2,500.00
0075 0455148901 THERMAL INTEGRITY TESTING FOR AUGER CAST PILES, PROJECT 436894-4-52-01 15.000 EA	9,725.00000	145,875.00	6,600.00000	99,000.00	2,500.00000	37,500.00
0080 0458 1 11 BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD 98.000 LF	41.00000	4,018.00	139.00000	13,622.00	170.00000	16,660.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 Structures						
0085 0521 5 5 98.000 LF CONCRETE TRAFFIC RAILING- BRIDGE, 42" VERTICAL FACE	180.00000	17,640.00	217.00000	21,266.00	62.00000	6,076.00
0090 0530 1 30.000 CY RIPRAP, SAND-CEMENT	823.00000	24,690.00	898.00000	26,940.00	2,200.00000	66,000.00
0095 0530 3 3 330.200 TN RIPRAP- RUBBLE, BANK AND SHORE	96.50000	31,864.30	121.00000	39,954.20	195.00000	64,389.00
0100 0530 74 208.600 TN BEDDING STONE	89.00000	18,565.40	60.00000	12,516.00	360.00000	75,096.00
0001 Structures Section Totals:		**$1,057,764.70**		**$1,161,377.30**		**$1,410,014.06**
SECTION: 0002 Roadway						
0105 0101 1 (1.000) LS MOBILIZATION 43689445201	175,000.00000	175,000.00	181,000.00000	181,000.00	219,000.00000	219,000.00
0110 0102 1 (323.000) DA (LS) MAINTENANCE OF TRAFFIC 43689445201	110,000.00000	110,000.00	124,740.00000	124,740.00	43,300.00000	43,300.00
0115 0102 3 36.100 CY COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	110.00000	3,971.00	77.00000	2,779.70	260.00000	9,386.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0120 0102 60 WORK ZONE SIGN 28,101.000 ED	0.25000	7,025.25	0.28000	7,868.28	0.20000	5,620.20
0125 0102 71 16 TEMPORARY BARRIER, F&I, FREE STANDING 138.000 LF	41.50000	5,727.00	26.00000	3,588.00	24.00000	3,312.00
0130 0102 74 1 CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD 6,460.000 ED	0.15000	969.00	0.22000	1,421.20	0.10000	646.00
0135 0102 74 2 CHANNELIZING DEVICE, TYPE III, 6' 1,292.000 ED	0.20000	258.40	1.10000	1,421.20	0.20000	258.40
0140 0102 74 7 CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) 178.000 LF	4.50000	801.00	8.80000	1,566.40	4.00000	712.00
0145 0102 99 PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY 674.000 ED	10.00000	6,740.00	12.10000	8,155.40	9.00000	6,066.00
0150 0104 10 3 SEDIMENT BARRIER 419.000 LF	2.25000	942.75	2.20000	921.80	7.00000	2,933.00
0155 0104 11 FLOATING TURBIDITY BARRIER 50.000 LF	18.00000	900.00	16.50000	825.00	115.00000	5,750.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0160 0104 18 INLET PROTECTION SYSTEM 3.000 EA	165.00000	495.00	550.00000	1,650.00	400.00000	1,200.00
0165 0108 1 MONITOR EXISTING STRUCTURES-INSPECTION AND SETTLEMENT MONITORING 43689445201 (1.000) LS	5,500.00000	5,500.00	13,200.00000	13,200.00	5,000.00000	5,000.00
0170 0108 2 MONITOR EXISTING STRUCTURES-VIBRATION MONITORING 43689445201 (1.000) LS	10,850.00000	10,850.00	41,745.00000	41,745.00	10,000.00000	10,000.00
0175 0110 1 1 CLEARING & GRUBBING 43689445201 (0.500) AC (LS)	125,000.00000	125,000.00	36,300.00000	36,300.00	150,000.00000	150,000.00
0180 0110 2 2 SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN 0.030 AC	145,000.00000	4,350.00	88,000.00000	2,640.00	50,610.00000	1,518.30
0185 0110 4 10 REMOVAL OF EXISTING CONCRETE 139.000 SY	52.10000	7,241.90	33.00000	4,587.00	200.00000	27,800.00
0190 0110 7 1 MAILBOX, F&I SINGLE 2.000 EA	275.00000	550.00	550.00000	1,100.00	150.00000	300.00
0195 0120 1 REGULAR EXCAVATION 353.500 CY	15.00000	5,302.50	47.00000	16,614.50	15.00000	5,302.50

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0200 0120 5 278.500 CY CHANNEL EXCAVATION	22.50000	6,266.25	164.00000	45,674.00	210.00000	58,485.00
0205 0120 6 588.100 CY EMBANKMENT	28.00000	16,466.80	44.00000	25,876.40	30.00000	17,643.00
0210 0160 4 1,520.000 SY TYPE B STABILIZATION	4.55000	6,916.00	8.80000	13,376.00	10.00000	15,200.00
0215 0285701 274.000 SY OPTIONAL BASE, BASE GROUP 01	22.20000	6,082.80	38.50000	10,549.00	15.00000	4,110.00
0220 0285707 878.000 SY OPTIONAL BASE, BASE GROUP 07	22.20000	19,491.60	38.50000	33,803.00	15.00000	13,170.00
0225 0286 1 221.000 SY TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	45.50000	10,055.50	71.50000	15,801.50	30.00000	6,630.00
0230 0334 1 13 80.300 TN SUPERPAVE ASPHALTIC CONC, TRAFFIC C	235.00000	18,870.50	330.00000	26,499.00	205.00000	16,461.50
0235 0337 7 82 60.100 TN ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-9.5, PG 76-22	342.00000	20,554.20	385.00000	23,138.50	280.00000	16,828.00
0240 0339 1 8.200 TN MISCELLANEOUS ASPHALT PAVEMENT	665.00000	5,453.00	440.00000	3,608.00	500.00000	4,100.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0245 0400 1 2 CONCRETE CLASS I, ENDWALLS 3.500 CY	1,750.00000	6,125.00	6,050.00000	21,175.00	1,500.00000	5,250.00
0250 0425 1523 INLETS, DT BOT, TYPE C,JBOT, <10' 2.000 EA	8,000.00000	16,000.00	11,550.00000	23,100.00	3,200.00000	6,400.00
0255 0430175115 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD 49.000 LF	290.00000	14,210.00	385.00000	18,865.00	140.00000	6,860.00
0260 0430175124 PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD 24.000 LF	450.00000	10,800.00	385.00000	9,240.00	140.00000	3,360.00
0265 0521 72 40 SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT 13.000 LF	815.00000	10,595.00	898.00000	11,674.00	245.00000	3,185.00
0270 0536 1 0 GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2 208.000 LF	17.50000	3,640.00	22.00000	4,576.00	17.00000	3,536.00
0275 0536 7 3 SPECIAL GUARDRAIL POST- ENCASED POST FOR SHALLOW MOUNT 4.000 EA	260.00000	1,040.00	165.00000	660.00	107.28000	429.12
0280 0536 8 12 APPROACH TRANSITION CONNECTION TO RIGID BARRIER, FURNISH AND INSTALL, TL-2 3.000 EA	2,350.00000	7,050.00	2,750.00000	8,250.00	2,500.00000	7,500.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0002 Roadway						
0285 0536 73 GUARDRAIL REMOVAL 54.000 LF	7.50000	405.00	11.00000	594.00	2.50000	135.00
0290 0536 85 20 GUARDRAIL END TREATMENT-TRAILING ANCHORAGE 1.000 EA	1,380.00000	1,380.00	1,320.00000	1,320.00	880.00000	880.00
0295 0536 85 24 GUARDRAIL END TREATMENT-PARALLEL APPROACH TERMINAL 2.000 EA	3,200.00000	6,400.00	3,300.00000	6,600.00	2,700.00000	5,400.00
0300 0570 1 2 PERFORMANCE TURF, SOD 707.000 SY	5.45000	3,853.15	8.16000	5,769.12	5.00000	3,535.00
0305 0999 16 PARTNERING, DO NOT BID 43689445201 (1.000) LS	6,000.00000	6,000.00	6,000.00000	6,000.00	6,000.00000	6,000.00
0310 0999 25 INITIAL CONTINGENCY AMOUNT, DO NOT BID 43689445201 (1.000) LS	50,000.00000	50,000.00	50,000.00000	50,000.00	50,000.00000	50,000.00
0002 Roadway Section Totals:		**$719,278.60**		**$818,272.00**		**$753,202.02**
SECTION: 0003 Signing						
0315 0700 1 11 SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF 6.000 AS	500.00000	3,000.00	550.00000	3,300.00	330.00000	1,980.00

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units *( ) indicates item is bid as Lump Sum*	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0320 0700 1 60 SINGLE POST SIGN, REMOVE 6.000 AS	75.00000	450.00	110.00000	660.00	10.00000	60.00
0325 0710 90 PAINTED PAVEMENT MARKINGS, FINAL SURFACE 43689445201 (1.000) LS	7,500.00000	7,500.00	3,300.00000	3,300.00	8,500.00000	8,500.00
0330 0711 11123 THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT 50.000 LF	8.20000	410.00	11.00000	550.00	3.83000	191.50
0335 0711 11125 THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK 26.000 LF	16.40000	426.40	11.00000	286.00	8.29000	215.54
0340 0711 11141 THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" 0.022 GM	6,500.00000	143.00	4,400.00000	96.80	1,050.00000	23.10
0345 0711 16101 THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" 0.099 GM	18,600.00000	1,841.40	12,100.00000	1,197.90	4,300.00000	425.70
0350 0711 16201 THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" 0.080 GM	20,500.00000	1,640.00	12,100.00000	968.00	4,300.00000	344.00
0355 0713103101 PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES 0.013 GM	63,000.00000	819.00	49,500.00000	643.50	3,200.00000	41.60

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

Line No / Item ID / Item Description / Alternate / Quantity / Units	(4) CONDOTTE AMERICA, INC.		(5) ANZAC CONTRACTORS, INC.		(6) LEAD ENGINEERING CONTRACTORS, LLC	
( ) indicates item is bid as Lump Sum	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0003 Signing						
0360 0713103201 0.013 GM PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	63,000.00000	819.00	49,500.00000	643.50	3,200.00000	41.60
0003 Signing Section Totals:		**$17,048.80**		**$11,645.70**		**$11,823.04**
Contract Grand Totals:		**$1,794,092.10**		**$1,991,295.00**		**2,175,039.12**

Letting: CT190925 September 25, 2019 **Call Order:** 012 **Contract:** T4527

NOTE: Failure to file a protest within the time prescribed in section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under chapter 120, Florida Statutes.

Certified in accordance with Code of Federal Regulations Title 23, Chapter 1, Subchapter G, Subsection 635.113(b).

Manager, Contracts Administration Office