FED. ROAD DIVN. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
3	FLA.	1354-150			

Prop Haul Route

Sta. 188+25 ℄ 20' Graded Sand Rd.

Drain R/W Line

℄ Pit Drain

Drain R/W Line

P.I. Sta. 1+22.12
Δ=46°00'

END DRAIN R/W
STA. 1+79.46

400'

Avg. 48' Top Ditch

All Pit Angles = 90°

400'

BEGIN JOB
STA. 198+00.0

190

195

Cultivated Field

P.I. Sta. 200+75.07
Δ=6°00' LT.
D=4°00'
T=75.07'
L=150.00'
P.C. Sta. 200+00.00
P.T. Sta. 201+50.00
R=1432.40'

N.W. Cor. Sec. 15
T 35 S, R. 18 E
6x6 Conc. Mon.

200

205

Dense Under-Growth

BRADEN R.

℄ SURVEY

N 88°45' E (Mag.)

R/W Line

S.R. 10

N 88°45' E (Mag.)

N 82°48' E

℄ of Water Main

Sta. 189+23.46

15' Asphalt

21.8' 18" Conc. & V.C.P.

Cultivated Field

Rock & Mortar in W.S.

Cone. Hdwl.

Avg. 28' Shell & Clay Road

Cabb. Palm

Fence Made from Old Piling

18" Span Timb. Br. Conc. Piers, 14" Treated Timb. Pilings, 3"x6" Decking, 10"x10" Caps, 4"x16" Stringers

14" Oak

1 Sty Blk. Bldg.

Swimming Pool

P.I. Sta. 204+09.77
Δ=6°00' RT.
D=4°00'
T=75.07'
L=150.00', R=1432.40
P.C. Sta. 203+34.70
P.T. Sta. 204+84.70

P.I. Sta. 211+91.25
Δ=6°00' RT.
D=4°00'
T=75.07'
L=150.00', R=1432.40
P.C. Sta. 211+16.18
P.T. Sta. 212+66.18

P.I. Sta. 215+25.95
Δ=6°00' LT.
D=4°00'
T=75.07'
L=150.00', R=1432.40
P.C. Sta. 214+50.88
P.T. Sta. 216+00.88

N.E. Cor. N.W. ¼ Sec. 15
T 35 S, R. 18 E
Corner Falls in River
No. Marker

1991.66

Tide Flats

BRADEN R.

215

220

Cemetery

3" Stock Mt. 1.5' Drb. Inc. (Good)

Palmetto & Scattered Pine

Avg. 28' Shell & Clay Road

N 88°45' E (Mag.)

R/W Line

Palmetto & Scattered Pine

Tide Flats

14" Sty. Brk. Inc. (Good)

END JOB
STA. 220+00.0

Sta. 214+91.11

OWNER	UTILITIES
Power	[illegible] Power & Light Co.
Tele.	[illegible]nsular Tele. Co.
Water	[illegible]y of Bradenton

Trash & Dump Area

+25-f Graded Sand Rd.

Prop. Haul Route

Row of Houses

All pit Angles Are 90°

400'

N 11°17' W (Mag.)

S 88°43' W (Mag.)

51°17' E (Mag.)

Pit Drain R/W Line

BEG. DRAIN R/W
STA. 0+00

℄ Pit Drain

Cabb. Over Pines & Palmetto

Lt. Pt. Bank Braden R.

END DRAIN R/W
STA. 1+79.46

To Braden R.

Sta. 188+23.46

℄ Survey

℄ Asphalt

BORROW PIT
LT. STA. 189+23.42
DRAIN R/W REQ'D.: STA. 0+00 To 1+79.46, 15', 15'

R/W WIDTHS REQUIRED
STA. 198+00.0 TO STA. 220+00.0, 40' RT., 40' LT.

SKETCH SHOWING LOCATION OF JOB No. 1354-150 S.R. No. 70 MANATEE Co.

June 1, 1959

SAMOSET

ELWOOD PARK

ONECO

T 34 S
T 35 S

RIVER

BEG. JOB
STA. 198+00.0

END JOB
STA. 220+00.0

STATE OF FLORIDA
STATE ROAD DEPARTMENT

RIGHT OF WAY MAP

SECTION No. 1354-150

ROAD No. 70 — MANATEE COUNTY

	NAMES	DATES
SCALE 1"		
DRAWN		
TRACED		
INDEXED		
REVIEWED		
REVISED		

APPROVED BY